

Application No: A.13-12-013xxx
Exhibit No.: _____
Witness: David Buczkowski

_____)
Application of Southern California Gas Company)
(U 904 G) and San Diego Gas & Electric Company)
(U 902 G) For Authority To Recover North-South)
Project Revenue Requirement In Customer Rates)
And For Approval Of Related Cost Allocation And)
Rate Design Proposals)
_____)

A.13-12-013xxx
(Filed December 20, 2013)

UPDATED DIRECT TESTIMONY OF

DAVID BUCZKOWSKI

SAN DIEGO GAS & ELECTRIC COMPANY

AND

SOUTHERN CALIFORNIA GAS COMPANY

BEFORE THE PUBLIC UTILITIES COMMISSION
OF THE STATE OF CALIFORNIA

November 12, 2014~~December 20, 2013~~

TABLE OF CONTENTS

I.	PURPOSE & OVERVIEW	1
II.	PROJECT SCOPE	7
A.	Adelanto-Moreno Pipeline	8
B.	Adelanto Compressor Station.....	8
III.	<u>COST ESTIMATES.....</u>	<u>10</u>
A.	<u>Adelanto-Moreno Pipeline</u>	<u>10</u>
B.	<u>Adelanto Compressor Station.....</u>	<u>13</u>
C.	<u>Company Labor</u>	<u>16</u>
D.	<u>Contingency</u>	<u>16</u>
E.	<u>O & M Costs.....</u>	<u>20</u>
IV.	<u>PROJECT SCHEDULE</u>	<u>21</u>
V.	<u>PHYSICAL ALTERNATIVES.....</u>	<u>22</u>
VI.	<u>QUALIFICATIONS.....</u>	<u>24</u>
	<u>Appendix A – Adelanto-Moreno Pipeline Direct Cost Detail</u>	<u>26</u>
	<u>Appendix B – Adelanto Compressor Station Direct Cost Detail.....</u>	<u>33</u>
	<u>C. —Moreno-Whitewater Pipeline</u>	<u>9</u>
III.	<u>COST ESTIMATES.....</u>	<u>10</u>
A.	<u>Adelanto-Moreno Pipeline</u>	<u>10</u>
B.	<u>Adelanto Compressor Station.....</u>	<u>13</u>
C.	<u>Moreno-Whitewater Pipeline</u>	<u>15</u>
D.	<u>Company Labor.....</u>	<u>16</u>
E.	<u>Contingency.....</u>	<u>16</u>
F.	<u>O & M Costs.....</u>	<u>20</u>
IV.	<u>PROJECT SCHEDULE</u>	<u>21</u>

V.—PHYSICAL ALTERNATIVES.....	22
VI.—QUALIFICATIONS.....	24
Appendix A—Adelanto-Moreno Pipeline Direct Cost Detail.....	26
Appendix B—Adelanto Compressor Station Direct Cost Detail.....	33
Appendix C—Moreno-Whitewater Pipeline Direct Cost Detail	38

1 **UPDATED DIRECT TESTIMONY OF DAVID BUCZKOWSKI**

2 **I. NOVEMBER 2014 UPDATE**

3 The North-South Project described in our Application consisted of three elements: (1) a
4 new 36-inch diameter pipeline approximately 60 miles long, from Adelanto Compressor Station
5 to the Moreno Pressure Limiting Station, (2) rebuilding of the existing Adelanto Compressor
6 Station with approximately 30,000 HP of compression, and (3) an additional 31 miles of new
7 pipeline from Whitewater Station to Moreno. As explained by Ms. Marelli in her Updated
8 Direct Testimony, SoCalGas has reduced the scope of the proposed North-South Project.
9 SoCalGas is continuing to pursue the first two elements of the project, namely the Adelanto-to-
10 Moreno pipeline and the Adelanto Compressor Station upgrade. SoCalGas will no longer be
11 moving forward with the proposed 31-mile Moreno-to-Whitewater pipeline portion of the
12 project. My updated direct testimony reflects this scope reduction.

13 By eliminating over \$186 million in forecasted expenditures, this scope reduction will
14 substantially reduce the cost of the project. Although the Moreno-to-Whitewater pipeline was
15 originally estimated to cost \$186.1 million, this estimate was provided before SoCalGas refined
16 route and cost inputs, as we have now done for the remaining portions of the project. An
17 updated estimated for the Moreno-to-Whitewater portion of the project would be well above
18 \$186.1 million. In addition, this scope reduction should also simplify environmental review,
19 permitting, and land acquisition, and reduce project risks.

20 Since filing the Application SoCalGas has continued to move forward on project
21 activities: pipeline route refinement, planning, engineering, design and environmental approval
22 processes, CEQA and NEPA. This work built off of the effort made by SoCalGas and their
23 consultant, TRC, in 2013 that was summarized in the report attached to my supplemental

1 testimony filed on March 28, 2014. During 2014 SoCalGas has performed extensive field
2 review and has met with federal, state and local agencies. These efforts have resulted in the
3 refinement of North-South Project scope and increased the level of project definition, degree of
4 completeness of deliverables, and improved accuracy of the cost estimate. As a result of this
5 work, we are also providing up-to-date detailed cost information for the Adelanto to Moreno
6 pipeline and Adelanto Compressor Station upgrade.

7 Estimated direct costs for the Adelanto-to-Moreno pipeline have increased from \$331.8
8 million (in 2013 dollars) to \$484.5 million (in 2014 dollars). The primary drivers for this
9 increase (see Table 1) are attributed to changes in construction, engineering, environmental and
10 material costs along with updates to other project execution costs identified.

11 *Table 1*
12 *Adelanto to Moreno Pipeline Costs Changes*

<u>Direct Capital Cost Increases</u>	<u>Total</u>
<u>Materials</u>	<u>\$8.1</u>
<u>Construction</u>	<u>\$90.3</u>
<u>Engineering</u>	<u>\$7.9</u>
<u>Environmental</u>	<u>\$22.3</u>
<u>Pressure Limiting Stations¹</u>	<u>\$12.7</u>
<u>Other Project Execution Activities</u>	<u>\$11.4</u>
<u>Total Increase</u>	<u>\$152.7</u>

13
14 The Adelanto-to-Moreno pipeline route alignment adjustments resulted in an increase in
15 mileage from approximately 60 miles to approximately 63 miles and increased footage in paved
16 roads as opposed to previously planned in dirt roads. The basis for valve spacing has also been

¹ Three new pressure limiting stations at Whitewater, Shaver Summit, and Desert Center were previously planned as
part of the Moreno to Whitewater cost estimates (\$ 5.7 million in 2013 direct dollars). Included are updates for the
three new PLSs (\$2.6 million) and cost increases for Moreno PLS (\$4.4 million)

1 refined resulting in an increase in mainline and other valves. These alignment and others
2 changes increased the costs estimates for materials, engineering and construction.

3 Additional research and discussions with local agencies have improved our understanding
4 of terrain and soil conditions, specifically sandy soil, historic road construction practices² and
5 ground water, resulting in better definition of the requirement to shore trenches with plywood,
6 trench through multiple layers of asphalt and concrete, and dewater trenches. The United States
7 Forest Service has provided guidance on construction access and construction related restoration.
8 These challenges and guidance have driven up the per foot cost estimates of construction along
9 with increasing engineering cost estimates. Furthermore, pipeline construction costs have
10 increased over 5% in 2014 and going forward skilled pipeline construction trades are
11 commanding wage and per diem premiums as pipeline construction takes off across the country
12 further driving costs. As a result of these and other construction challenges and risks, we have
13 increased our construction cost contingencies to 16%.

14 Environmental cost estimates have been updated based on more extensive field studies
15 and input from state and federal agencies. Increases include costs required by state and federal
16 agencies for consultants to prepare CEQA and NEPA environmental reports and studies,
17 construction monitoring and mitigation.

18 Other project execution activities that have cost estimate increases include, land
19 acquisition, outside legal services, Company labor and outreach activities.

20 Estimated direct costs for the Adelanto Compressor Station upgrade have increased from
21 \$110.7 million to \$136.8 million. The major drivers for the \$26.1 million increase in the
22 estimated direct cost of the Adelanto Compressor Station upgrade include: pipe and fittings;

² Historic practice of building new roads on top of old roads was identified along the proposed route and not
previously anticipated.

1 updated compressor equipment cost estimates; additional environmental costs; and an increase in
2 Adelanto Compressor Station project contingency to 15%.

3 The new total estimated direct cost of the North-South Project, taking into account these
4 estimated cost increases for the Adelanto-to-Moreno pipeline and the Adelanto Compressor
5 Station upgrade as well as elimination of the Moreno-to-Whitewater pipeline portion of the
6 project, is now reduced to \$621.3 million from our original estimate of \$628.6 million.

7 As a result of a more mature project scope definition, degree of completion of
8 deliverables, and execution plan development, our estimate is within a Class 3 range of accuracy
9 as defined by the Association for the Advancement of Cost Engineers International (AACE). A
10 Class 3 estimate as applied for the Building and General Construction Industries, most relevant
11 to pipeline construction, is defined as:

- 12 • Having a maturity level of project definition deliverables between 10% and 40%
- 13 • An end usage of design development, budget authorization, feasibility
- 14 • Based on a methodology of semi-detailed unit costs with assembly level line items
- 15 • An expected accuracy range of -5% to -15% and +10% to +20%

16 The only variance between the Class 3 estimate above and as applied for the Process
17 Industries, most applicable to compressor station construction, is a higher range of expected
18 accuracy of +30%. It should be noted that in concert with better definition of the project scope
19 and requirements resulting in more accurate cost estimates, the contingency applied to various
20 project expenditures has also been updated based on this improved understanding of the project
21 challenges and risks. This update of the contingency percentages better reflects the risk profile
22 of the project and has resulted in a higher contingency percentage as compared to the original
23 cost estimate.

In addition to updating project cost estimates, SoCalGas has updated ongoing O&M cost estimates based on revised scope and updated the factored cost estimates for River Route and Cross Desert alternatives to reflect the updated cost per mile and updated cost per horsepower on the North-South Project.

II. PURPOSE & OVERVIEW

The purpose of my direct testimony on behalf of Southern California Gas Company (SoCalGas) and San Diego Gas & Electric Company (SDG&E) is to present the estimated direct project costs, and schedule for the North-South Project. ~~This project consists of three major components: Adelanto Moreno Pipeline, Adelanto Compressor Station, and Moreno Whitewater Pipeline. The estimated project direct costs are summarized as follows in Table 1:~~

This project consists of two major components: Adelanto-Moreno Pipeline and Adelanto Compressor Station. The estimated project direct costs are summarized as follows in Table 2:

Table 2
Estimated North - South Project Direct Costs
(In Millions of Dollars)

Direct Capital Costs	Total
<u>Adelanto-Moreno Pipeline</u>	<u>\$484.5</u>
<u>Adelanto Compressor Station</u>	<u>\$136.8</u>
<u>Total</u>	<u>\$621.3</u>

Adelanto-Moreno Pipeline	\$331.8
Adelanto Compressor Station	\$110.7
Moreno-Whitewater Pipeline	\$186.1

Total	\$628.6
-------	---------

1 The costs described in this chapter are direct costs (in ~~2014 direct~~~~2013-unloaded~~ dollars) and
2 cover anticipated project elements, including, engineering, environmental review, permitting,
3 mitigation, land and right-of-way acquisition, equipment and materials, construction labor,
4 construction management, consultant costs, and internal company labor.

5 The overall project schedule is estimated to encompass six years from commencing work
6 until the new assets are placed in service. The estimated annual capital expenditures are
7 summarized as follows in ~~Table 32~~:

8
9
10
11
12
13
14

~~Table 2~~Table 3

Estimated North - South Project Annual Direct Capital Expenditures
(In Millions of Dollars)

2014	2015	2016	2017	2018	2019	2020 (Labor Only)	2020- 2039 ³	Total
\$3.4	\$11.0	\$22.1	\$169.8	\$135.6	\$276.0	\$1.2	\$2.2	\$621.3
7.4	10.2	17.9	188.0	229.8	174.2		1.1	628.6

H.III. PROJECT SCOPE

The North-South Project scope includes the design and construction of approximately ~~6360~~ miles of new pipeline from Adelanto to our Moreno pressure limiting station (Moreno PLS) ~~and~~; upgrades to the compressor station in Adelanto, ~~and approximately 31 miles of new pipeline from Moreno to Whitewater. SoCalGas and SDG&E utilized the assistance of a third party firm, TRC Companies, Inc. (TRC), specializing in engineering services and construction management to support development of the project scope and cost estimates for this application.~~

Based on the preliminary engineering and design work completed to date and the project experience of SoCalGas, SDG&E, and ~~consultants⁴TRC~~, the overall scope of work presented below is feasible and constructible. SoCalGas and SDG&E have evaluated this proposed project scope against other possible project alternatives, as discussed in the updated testimony of Ms. ~~MarelliMusich~~ and Mr. Bisi. High-level cost estimates for two of the most feasible project alternatives are presented in Section ~~VIV~~ below.

This project is anticipated to require an extensive environmental review and involve monitoring and mitigation activities throughout the construction phase. For purposes of

~~³Accounts for post construction environmental monitoring that will occur after the assets are placed in service.~~

⁴ These consultants include ARB Construction (ARB), Spec Services, BonTerra Psomas, and URS. Information about each of these firms can be found at the following websites: ARB - <http://www.arbinc.com/> Spec Services - <http://www.specservices.com/> BonTerra Psomas - <http://www.psomas.com/> URS - <http://www.urs.com/>

1 determining the environmental activities and costs associated with this project, SoCalGas and
2 SDG&E assume that the project ~~is will be~~ subject to the requirements of the National
3 Environmental Policy Act and the California Environmental Quality Act as well as ~~discretionary~~
4 permits from various federal, state and local agencies.

5 **A. Adelanto-Moreno Pipeline**

6 The Adelanto-Moreno pipeline is a new 36” diameter pipeline that originates at
7 SoCalGas’ Adelanto Compressor Station and traverses approximately ~~6360~~ miles in a
8 southeasterly direction, terminating at the Moreno PLS. The new pipeline will traverse both
9 undeveloped and urban locations in San Bernardino and Riverside counties, and will pass
10 through private and public land. SoCalGas project management, environmental, land services,
11 and operations personnel, developed the proposed pipeline alignment.

12 SoCalGas and SDG&E ~~conducted field investigations; provided this alignment to TRC for~~
13 ~~their review and analysis and to aid in their support of the cost estimation effort. TRC~~ obtained
14 publicly available GIS, topography, land ownership, and fault data to use in ~~our~~~~their~~ review and
15 analysis of the pipeline route. ~~We~~~~TRC~~ identified several challenges along the route, including
16 traversing the Cajon Pass and crossings of multiple highways, earthquake faults, the California
17 Aqueduct, Santa Ana River, and flood control channels.

18 ~~The Adelanto-Moreno Pipeline scope also includes the installation of pressure control~~
19 ~~equipment at Moreno PLS and on three SoCalGas pipelines at Whitewater, Shaver Summit, and~~
20 ~~Desert Center Stations. Three new pressure control stations (PLSs) are required to flow gas east~~
21 ~~from Moreno to Blythe and were originally included in the Moreno – Whitewater Pipeline cost~~
22 ~~estimate.~~

23 **B. Adelanto Compressor Station**

1 The project scope for this application also includes an upgrade of the existing Adelanto
2 Compressor Station. SoCalGas and SDG&E determined the operational requirements for the
3 station (e.g., minimum and maximum station throughput, minimum inlet pressure, maximum
4 outlet pressure), and URS Corporation, a consultant with compression station expertise, was
5 contracted to further develop the engineering and design and provide a detailed estimate based
6 on TRC used their expertise in conjunction with input from equipment manufacturers.⁵ ~~to~~
7 ~~determine the overall station horsepower requirement and develop the preliminary design for the~~
8 ~~station upgrade.~~

9 The current station consists of a single gas-turbine driven compressor installed in the
10 early 1970's. The total horsepower of this existing unit is inadequate to provide the necessary
11 throughput for the North-South Project at the required design conditions. Without the ability to
12 move the required volume of gas through the Adelanto Compressor Station, the minimum flow
13 requirements on the Southern System described in the updated testimonies of Ms. Marelli Musieh
14 and Mr. Bisi could not be met through this project. As such, the aforementioned station
15 upgrades are required. Since the existing turbine-driven compressor is no longer in commercial
16 production, and ongoing maintenance and procurement of replacement parts is difficult and
17 costly, it will be retired.⁶

18 ~~C. Moreno-Whitewater Pipeline~~

19 ~~The Moreno-Whitewater pipeline is a new 36" diameter pipeline that originates at~~
20 ~~SoCalGas' Moreno PLS and traverses approximately 31 miles eastward, terminating in~~

⁵ Please note that the initial work on this topic was prepared by outside consultant TRC. SoCalGas and URS used this initial work as a starting point for our analyses and estimates, but the revised estimates in this updated testimony are the product of the detailed work done by SoCalGas and URS.

⁶ The same type of gas turbine-driven compressor (GE LM 1500) is also being replaced through a different project at the Aliso Canyon Storage facility. See Decision 13-11-023.

1 ~~Whitewater. The pipeline will follow the I-10 corridor near the towns of Whitewater, Cabazon,~~
2 ~~Banning and Beaumont in Riverside County.~~

3 ~~SoCalGas initially considered replacement of a portion of Line 5000 with the new~~
4 ~~Moreno-Whitewater pipeline. However, this approach would entail significant cost for the~~
5 ~~abandonment and removal of this portion of the Line 5000, which happens to be a 1980's vintage~~
6 ~~segment. As such, we determined that building an additional pipeline from Moreno to~~
7 ~~Whitewater and leaving Line 5000 intact would be the better approach to this project.~~

8 **III-IV. COST ESTIMATES**

9 SoCalGas and SDG&E developed direct cost estimates to implement the above scope of
10 work, including costs associated with project management, engineering and design,
11 environmental permitting, land acquisition, material and equipment procurement, and
12 construction. ~~Various consultants~~TRC provided support for this effort. -All cost information and
13 vendor quotes gathered by ~~contractors~~TRC were reviewed by experienced SoCalGas project and
14 construction management personnel.

15 **A. Adelanto-Moreno Pipeline**

16 The installation of approximately ~~6360~~ miles of new 36" diameter pipeline from
17 Adelanto Compressor Station to Moreno is estimated to cost \$~~484.5331.8~~ million (direct costs).

18 The estimated pipeline costs are summarized as follows in the Table 4 below:

19
20 ~~Table 4~~**Table 3**⁷
21 **Estimated Adelanto-Moreno Pipeline Direct Costs**
22 *(In Millions of Dollars)*

Direct Capital Costs	Total
<u>Materials</u>	<u>\$92.8</u>

⁷ See Appendix A for Adelanto-Moreno Pipeline Direct Cost Detail.

<u>Construction</u>	<u>\$270.4</u>
<u>Other</u> ⁸	<u>\$121.5</u>
<u>Total</u>	<u>\$484.7</u>
Materials	\$84.7
Construction	\$180.1
Other	\$66.9
Total	\$331.8 ⁹

1 SoCalGas and SDG&E consulted with vendors to determine current material costs for
2 pipe and valves. The new pipeline will allow passage of commonly available in-line inspection
3 tools. Costs are included for a launcher/receiver at each end of the new pipeline. The project
4 scope includes ~~approximately 20~~ nine main line valves for the Adelanto-Moreno pipeline route.
5 The main line valves installed as part of this project will be capable of operating in automatic
6 shut-off and remote control modes, and the cost estimates include the controls and actuators
7 necessary to permit such operation.

8 ~~SoCalGasTRC~~ obtained estimates for the construction costs from ~~ARB which has two~~
9 ~~pipeline contractors, each with~~ extensive experience constructing large diameter natural gas
10 transmission pipelines. The estimates account for type of terrain traversed during construction
11 and the effect of the terrain on such factors as type of construction methods employed and rate of
12 construction progress. ~~The estimates were~~ Each estimate was reviewed by ~~TRC and~~ experienced
13 SoCalGas project management personnel ~~and each was~~ considered to be technically acceptable
14 and complete with respect to scope and schedule. ~~The estimates are~~ The superior of the two
15 ~~estimates in terms of overall cost and proposed execution, particularly in the more populated city~~

⁸ See Table III in Appendix A for a breakdown of “Other” costs for Adelanto-Moreno Pipeline.

⁹ ~~Some of the numbers in the tables in this testimony do not add due to rounding.~~

1 ~~areas, is~~ incorporated into the direct costs presented in Table ~~43~~ above. ~~Third TRC also provided~~
2 ~~anticipated third~~ party construction management man hours were developed based upon the
3 construction schedule, number of construction crews, and work hours ~~and used a labor rate~~
4 provided by ARB. Labor rates for construction management ~~knowledgeable and experienced~~
5 SoCalGas personnel were obtained from current vendors. ~~to develop the cost estimate for this~~
6 ~~activity.~~

7 Land costs include acquisition of additional land for PLSs, ~~both~~ temporary work space,
8 and permanent easements along the proposed Adelanto-Moreno pipeline route. After
9 construction is completed, our scope and estimate basis is that the sections of the pipeline outside
10 dedicated roads and highways will have a 50 foot right-of-way. Temporary work space during
11 construction will vary in open terrain. ~~An~~ ~~require an~~ additional 50 feet is required to establish a
12 100-foot work strip in open land and mountainous terrain. In urban in- ~~in~~ areas along paved
13 roadways, temporary work space will be utilized where space is available and necessary.

14 SoCalGas and consultants TRC combined analysis of aerial images and U.S. Geological
15 Survey maps with multiple site visits to develop our ~~inform their~~ engineering and construction
16 cost estimates. The engineering cost estimate incorporates anticipated man hours and estimated
17 labor rates for activities related to site investigation, project coordination, survey, pipeline and
18 traffic control design drawings and review for permitting from local municipalities, preparation
19 of bid specifications and coordination with vendors, construction support, review of right-of-way
20 documents, and project closeout.

21 SoCalGas environmental staff provided anticipated man-hours and labor rates in order to
22 develop estimated costs for environmental data collection surveys (including cultural resources,
23 natural resources, water resources, soils, geology and hazardous materials), geotechnical support,

1 and permitting activities, as well as preconstruction surveys, mitigation compliance, and
2 construction monitoring. Costs for mitigation are based on estimated acreage impacts and fees to
3 available mitigation banks, as well as ~~standard~~ costs per acre for restoration of specific habitat
4 types.

5 Other items covered in the cost estimate are legal support services, an allowance for
6 public relations activities and community outreach, and installation of fiber optic right-of-way
7 monitoring and methane detection devices along the pipeline route.

8 **B. Adelanto Compressor Station**

9 Compressor station upgrades at Adelanto adding approximately 30,000 horsepower of
10 compression are estimated to cost \$~~136.8~~~~110.7~~ million (2014 direct dollars).

11
12 ***Table 4¹⁰***
13 ***Estimated Adelanto Compressor Station Direct Costs***
14 ***(In Millions of Dollars)***

Direct Capital Costs	Total
Equipment and Materials	\$ 80.5 67.5
Construction	\$ 30.4 30.8
Other ¹¹	\$ 26.0 12.5
Total	\$136.8110.7

15 This estimate assumes the 30,000 horsepower of compression is provided by ~~four~~~~three~~
16 natural gas turbine-driven compressors. It is assumed that this ~~four~~~~three~~-unit configuration will
17 allow for the required operational flexibility. ~~URSTRC~~ consulted with a reputable compressor
18 manufacturer to obtain pricing for the compressors and related equipment. As the project design
19 moves forward, additional engineering is required to thoroughly evaluate the horsepower and

¹⁰ See Appendix B for Adelanto Compressor Station Direct Cost Detail.

¹¹ See Table III in Appendix B for breakdown of "Other" costs for Adelanto Compressor Station.

1 flow rate requirements of the station. If further engineering and design suggests an alternate
2 configuration of type and quantity of compressors is better suited for this project, it is assumed
3 the resultant change will be within the accuracy of the cost estimate.

4 Construction of the station upgrades is assumed to take place just outside the fence line of
5 the existing Adelanto Compressor Station. The total parcel of land owned by SoCalGas is
6 approximately 560 ft. x 875 ft., with the existing Adelanto Station covering much less than half
7 of the entire parcel. This provides sufficient room to install the new compressor station on the
8 SoCalGas parcel, outside the existing fence line and due south of the existing station. -This will
9 reduce/avoid land acquisition costs for the new compression equipment installation, however
10 additional land acquisition is assumed to be required for ancillary facilities. In addition,
11 executing the construction in this manner will eliminate the need for any immediate demolition
12 of the existing compressor and will not impact system operation and remote control of critical
13 valves while the new station is being built. The current turbine driven compressor will remain in
14 service until the new units are installed and commissioned. The direct costs for the Adelanto
15 Compressor Station do not include demolition of the existing unit. As stated in Mr. Yee's
16 testimony, those costs are accounted for in authorized depreciation rates.

17 In order to meet regional air quality requirements, emissions controls and continuous
18 emissions monitoring equipment will be required. The compressor station will be subject to
19 Federal Operating Permit (Title V) requirements due to its potential to emit emissions in excess
20 of federal major source thresholds. As a federal major source, the facility will meet the Lowest
21 Achievable Emission Rate (LAER). The capital costs for procurement and installation of this
22 equipment are included in the project estimate. The emission reduction credits cost estimate are
23 based on ERC costs per ton of a recent transaction in the Mojave Desert Air Quality

1 ~~Management District provided by an emissions broker and validated by the air district. Internal~~
2 ~~estimates were developed for the anticipated costs of emission reduction credits.~~ These
3 emissions offset costs and other air permit related fees necessary to construct the station
4 upgrades are also included towards the total cost of the compressor station.

5 SoCalGas and SDG&E evaluated natural gas driven compression as the basis for the
6 project scope and cost estimates in this application. As stated in Mr. Bisi's testimony, SoCalGas
7 and SDG&E believe that this new compression should be gas-driven for a number of reasons.

8 ~~C. — Moreno-Whitewater Pipeline~~

9 ~~The installation of approximately 31 miles of 36" diameter pipeline from the Moreno~~
10 ~~PLS to Whitewater is estimated to cost \$186.1 million (direct). The project scope includes six~~
11 ~~main line valves along the Moreno-Whitewater pipeline route. Similar assumptions and cost~~
12 ~~estimating methodologies as described above in the Adelanto Moreno Pipeline section for~~
13 ~~materials, construction, and several other costs are used for the Moreno-Whitewater Pipeline.~~
14 ~~On a per-mile basis, the only cost that is substantially different between the Adelanto Moreno~~
15 ~~pipeline and the Moreno-Whitewater pipeline is the land and right-of-way acquisition cost due to~~
16 ~~differences in land values and proportion of the anticipated routes in franchise, as opposed to~~
17 ~~non-franchise areas for which additional right-of-way will have to be purchased.~~

18 *Table 5¹²*
19 *Estimated Moreno-Whitewater Direct Costs*
20 *(In Millions of Dollars)*
21

Direct Capital Costs	Total
Materials	\$43.1
Construction	\$95.2

¹² See Appendix C for Moreno-Whitewater Pipeline Direct Cost Detail.

Other	\$47.7
Total	\$186.1

~~In addition to the pipeline costs, the overall estimate for this portion of the project includes building three pressure limiting stations.~~

D.C. Company Labor

SoCalGas will use company resources to perform various functions over the course of the project. In particular, SoCalGas will be responsible for overall project and construction management, environmental management, project controls, and various other support functions. All third party contractor and consultant activity, including but not limited to environmental surveys and monitoring, procurement, engineering/design, land and right-of-way acquisition, construction management, and legal services will be overseen by company resources. SoCalGas developed a preliminary staffing plan for the functions that will be supporting the project. It is estimated that the number of SoCalGas full-time equivalent employees working on this project will range from roughly ~~714~~ in the early stages of the project to approximately ~~3924~~ during the peak construction activities. The total direct costs for company labor are estimated to be approximately ~~\$22.1~~ ~~15.1~~ million.

E.D. Contingency

The estimated project costs in this application include contingencies that, in aggregate, amount to ~~13.8%~~ ~~between 8% and 9%~~ of the total direct cost. Contingency is a direct cost to the project and will be spent over the course of engineering, design, procurement, and construction. Per the Association for the Advancement of Cost Engineering (AACE), contingency is defined as “a cost element of the estimate used to cover the uncertainty and variability associated with a

1 | cost estimate, and unforeseeable elements of cost within the defined project scope.”¹³ -The risk
2 | of these unknown elements within the defined scope, and their associated costs materializing, is
3 | always present on construction projects like the North-South Project. Including a contingency
4 | allows for these costs to be budgeted, even though the exact contingency-related expenditures
5 | and unforeseen events are unknown at the current level of project definition. To calculate
6 | contingency for the Adelanto to Moreno pipeline, we analyzed each cost component¹⁴,
7 | considered the risks related to the component that fall within the defined project scope, and
8 | established a contingency percentage.¹⁵ For the Adelanto Compressor Station, we determined
9 | contingency at the project level. This is a common process for calculating contingency. For
10 | example, in D.09-03-026, the Commission authorized PG&E's smart meter Program Upgrade.
11 | The approved authorized cost of that project included a risk based allowance (i.e., contingency)
12 | of 12.9%. In another example, in D.06-07-027 the Commission authorized PG&E’s Advanced
13 | Metering Infrastructure project with an 8.0% contingency included in the cost estimate. In D.09-
14 | 03-026, the Commission explains that “the analysis of risk for the Upgrade should consider the
15 | risk profiles specific to the Upgrade, rather than that of the original AMI project.”¹⁶ Consistent
16 | with good estimating practice, and these prior Commission precedents, SoCalGas and SDG&E
17 | have taken the approach of contemplating the risks specific to the North-South Project costs
18 | when determining a reasonable contingency to include in the cost estimate.

¹³ AACE International Recommended Practice, No. 34-R-05, TCM Framework: 7.3 - Cost Estimating and Budgeting, 2007, p. 4.

¹⁴ Project Management Institute (PMI) Project Management Body of Knowledge (PMBOK) in section 7.2.2.6 Reserve Analysis states, “contingency reserves can provide for a specific activity, for the whole project, or both”

¹⁵ AACE Recommended Practice NO. 40R-08 defines expert judgment as having a strong basis in experience and competency in risk management and analysis

¹⁶ D.09-03-026, mimeo., at 88.

1 At the project component level, we included contingency amounts that range from 0% to
2 3040% of the direct cost. Those project components where fewer issues are expected to arise
3 and the scope and cost estimates are more fully developed will have contingencies towards the
4 lower end of the aforementioned range. Project components where issues with greater cost
5 impact can arise and the scope and costs estimates are not as fully developed will have a higher
6 contingency applied. In aggregate, the contingency for the project is approximately \$75.454
7 million.

8 Even after accounting for the contingency in the direct cost estimate, there still may be
9 variability in the overall cost of the project. The amount of expected variability is related to
10 external, uncontrollable factors that impact skilled labor costs, material costs, etc. For example,
11 the best quality estimate would be a firm quote from a vendor to perform a specific task. While
12 many cost estimates for this project are based on input from vendors and contractors, no firm
13 quotations were obtained, as many of the project activities estimated will not be occurring for
14 several years.

15 It should be noted that there are risks outside of the defined project scope that are
16 excluded from the cost estimate and contingency. Examples of such risks include:

- 17 • Costs for skilled labor and qualified resources (e.g., engineers, contractors,
18 construction workers, specialty consultants), materials, or other commodities
19 increasing significantly over the project duration, beyond the escalation included in
20 the revenue requirement.
- 21 • Significant changes to the project scope as a result of the environmental and/or
22 regulatory review of the project.

1
2
3
4
5
6

- Significant delays in the project schedule as a result of the environmental and/or regulatory review, local community intervention, natural disaster, labor strike, etc.
- Changes to laws or regulations that would significantly affect project cost and/or schedule.
- Earthquakes, fires, natural disasters, strikes or other force majeure type events.

1 **F.E. O&M Costs**

2 **O&M Costs During Project Construction**

3 The costs discussed in the preceding sections of this testimony are all estimated capital
4 expenditures. In addition, we also expect that there will be O&M expenses incurred during
5 project execution, prior to placing the new pipelines and compressor equipment in service.
6 These expenses are anticipated to be primarily for office space and other office related costs.
7 The cost estimate includes office space for the project team, including company personnel and
8 key consultants. These costs are included in the revenue requirement discussed in Mr. Yee's
9 testimony.

10 **Table 6**
11 **Estimated North - South Project O&M Expenses**
12 **(In Millions of Dollars)**

2014	2015	2016	2017	2018	2019
\$0.50.2	<\$0.30.1	<\$0.30.1	<\$0.30.1	<\$0.10.2	<\$0.10.2

13 **Ongoing Post-Construction O&M Costs**

14 This project will also result in incremental ongoing O&M expenses for the pipelines and
15 compressor station after they are placed into service. Estimates of these costs are provided in
16 Table 7. Pipeline operations and compliance activities, including valve maintenance and
17 cathodic protection, will incur ongoing costs, as will activities related to right-of-way mitigation.
18 The compressor station will have associated O&M expenses (labor and non-labor) from such
19 activities as operating the station and maintaining the emissions monitoring equipment.
20 Emissions fees based on the amount of greenhouse gases generated through operation of the
21 compressors will also be an ongoing expense. Recovery of these ongoing O&M costs is not
22 included in the proposed revenue requirement for this application. However as discussed in the

1 testimony of Mr. Ahmed, these post-construction O&M costs will be recorded in the requested
2 memorandum account until they are addressed in SoCalGas' next GRC or other applicable
3 proceeding.

4 *Table 7¹⁷*
5 *Estimated Ongoing O&M Costs*
6 *(In Millions of Dollars Per Year)*

O&M Costs	Total
Pipeline Operations & Compliance	\$0.2
Right-of-Way	\$0. 68
Compressor Station	\$0. 87
Greenhouse Gas Emissions Fees ¹⁸	\$ 0.83.4
Total	\$ 2.45.1

7
8 **IV.V. PROJECT SCHEDULE**

9 SoCalGas and SDG&E estimate that it will take approximately six years to permit,
10 engineer/design, procure, construct, and place the new assets in service by the fourth quarter of
11 2019. The basis for the schedule, cost estimates, and revenue requirement is that all assets will
12 go into service at approximately the same time. We may be able to place certain project
13 components in service before the others are completed. If this ends up occurring, per Mr.
14 Ahmed's testimony, the capital-related costs of the assets in-service will be recorded in the
15 requested memorandum account until we are authorized to recover the revenue requirement in
16 rates.

¹⁷ One expense not included in Table 7 is the cost of catalyst replacement. It is assumed replacement of the catalyst will not occur prior to the next GRC or other applicable proceeding after the compressor station is placed in service.

¹⁸ The estimated cost presented in Table 7 assumes the compressors operate at approximately 30% load. Previous estimate was based on 100% load factor. Actual fees will be assessed based on actual compressor operation and greenhouse gas generation.

1 If SoCalGas and SDG&E ~~had waited~~~~wait~~ to commence work on the project until after
2 regulatory approval, the project ~~would have taken~~~~will take~~ the time needed for regulatory
3 approval plus approximately six years. In order to develop this project as quickly as possible,
4 SoCalGas and SDG&E ~~initiated~~~~plan on initiating~~ planning, engineering, design, and permitting
5 work in advance of Commission authorization, so these estimates reflect an in-service date in Q4
6 2019 rather than Q4 2021.

7 The environmental clearance process is also assumed to commence in parallel with the
8 regulatory approval phase of the project. By not waiting for final regulatory approval before
9 starting planning, engineering, design and permitting work, the overall schedule from the filing
10 of this application to placing the new assets in service can be compressed, potentially saving in
11 escalation costs that would otherwise be passed on to ratepayers.¹⁹

12 Since the environmental clearance process has the potential to impact the overall project
13 scope, it is assumed that material procurement (including long lead time valves and compression
14 equipment), land and right-of-way acquisition, and awarding of major construction contracts will
15 not occur until after SoCalGas and SDG&E receive the final environmental clearance for the
16 project. It is estimated that detailed engineering and design, procurement, and construction for
17 the project will be completed within roughly three years of receiving the final environmental
18 clearances.

19 V.VI. PHYSICAL ALTERNATIVES

21 High-level cost estimates have been evaluated for the two alternative projects described
22 in Mr. Bisi and Ms. ~~Marelli's~~~~Musich's~~ testimonies (River Route and Cross Desert). These

¹⁹ Escalation is discussed in the testimony of Mr. Yee.

1 projects involve similar components as the proposed North-South Project (i.e., pipeline and
2 compressor station equipment), though in different quantities. The pipeline material
3 specifications (diameter, wall thickness, and grade) for each alternative would be the same as the
4 proposed Adelanto to Moreno ~~pipeline and Moreno to Whitewater pipelines~~, for which we've
5 already obtained estimated costs. There may be lower construction costs in rural areas
6 (particularly on the River Route) where longer stretches of trench can be left open. However,
7 these same areas may also have higher costs to mitigate environmental impacts. Other costs for
8 activities such as engineering, survey, right-of-way acquisition, etc., should be comparable, on a
9 unit cost basis, to the estimates obtained for the Adelanto to Moreno ~~pipeline and Moreno to~~
10 ~~Whitewater pipelines~~. The compressor station required for the Cross Desert alternative would
11 have a higher total horsepower than the station proposed as part of the North-South Project, but it
12 would be comprised of similar equipment (i.e., gas turbine driven compressors, emissions
13 reduction and monitoring equipment, compressor building, gas cooling, etc.) and would be
14 subject to the same emissions requirements.

15 As such, we determined that applying overall per mile costs obtained for the Adelanto-
16 Moreno ~~pipeline and Moreno-Whitewater pipelines~~ and overall per horsepower costs obtained for
17 the proposed Adelanto Compressor Station to the project alternatives would provide sufficient
18 preliminary estimates that can be used for comparison. While construction cost of these facilities
19 is an important consideration, it should be noted that the other benefits of the North-South
20 Project discussed in the testimonies of Mr. Bisi and Ms. Musich were the primary drivers for
21 determining the best option to address long-term Southern System reliability.

22 *Table 8*
23 *Preliminary Direct Costs for Project Alternatives*
24 *(In Millions of Dollars)*

Direct Capital Costs	Total
----------------------	-------

River Route	\$ 769.0560
Cross Desert	\$1, 538.1250

1 The costs above assume \$~~7.75-6~~ million/mile for the 100 miles of pipeline in the River
2 Route and 200 miles of pipeline in the Cross Desert option, and approximately
3 ~~\$4\$3~~,500/horsepower for the 35,000 horsepower compressor station required for the Cross
4 Desert option.

5 **VI.VII. QUALIFICATIONS**

6 My name is David L. Buczkowski. I am employed by SoCalGas as the Senior Director of
7 Major Projects. My business address is 555 West Fifth Street, Los Angeles, California 90013-
8 1011.

9 I graduated from the University of Illinois in 1989 with a Bachelor of Science degree in
10 Mechanical Engineering. I have over 23 years of domestic and international experience in
11 various energy industries.

12 I have been employed by SoCalGas as the Director and then Senior Director of Major
13 Projects since May of 2011. In these positionsthis position, my responsibilities include
14 overseeing the project management and project execution of major capital and expense gas
15 infrastructure projects for SoCalGas and SDG&E.

16 Prior to joining SoCalGas, I served as a project manager on several multi-billion dollar
17 mega-projects. Through my career my roles have included project management, engineering
18 management, start-up, and O&M engineering for projects in refineries, oil and gas processing
19 facilities, biofuels, and petrochemical plants. Project scopes included conceptual engineering,
20 basic engineering, front-end engineering, program management, and detailed engineering and
21 design, procurement and construction efforts. From 2001 to 2011, I worked for Fluor in various

1 project management positions of increasing responsibility, ultimately serving in the role of
2 Project Director. In that role, I had overall responsibility for project cost, schedule, and
3 execution, including engineering/design, procurement, contracts, and construction of large
4 capital projects.

5 From 1997 to 2001, I was employed by Parsons Corporation, first as a Project Engineer,
6 then in various project management positions of increasing responsibility. From 1990 to 1995, I
7 was employed by Shell Oil Company, first as an Operations Support Engineer and subsequently
8 in various roles of increasing responsibility, including project management of major refinery
9 projects and ultimately ascended to the position of Start-Up Engineer for the Shell Refinery
10 Expansion and Clean Fuels megaproject.

11 I have previously testified before the California Public Utilities Commission.

12 This concludes my updated prepared direct testimony.

Appendix A – Adelanto-Moreno Pipeline Direct Cost Detail

1

I. Material Costs -

Cost Element	Direct Costs (\$ Million)
Pipe & Coating	\$58.8
Pipe Delivery	\$10.8
Ells	\$4.8
Valves	\$3.8
Other Materials	\$5.1
Freight (other than Pipe)	\$1.2
Filter / Separator For Pipeline	\$1.4
Odorization	\$0.2
Tax	\$6.6
TOTAL MATERIAL	\$92.8

2

<i>Cost Element</i>	<i>Direct Cost (\$ millions)</i>
<i>Pipe & Coating</i>	<i>\$59.9</i>
<i>Pipe Delivery</i>	<i>\$9.3</i>
<i>Ells</i>	<i>\$5.2</i>
<i>Valves</i>	<i>\$1.0</i>
<i>Other Materials</i>	<i>\$2.2</i>
<i>Freight</i>	<i>\$0.6</i>
<i>Filter / Separator For Pipeline</i>	<i>\$0.5</i>
<i>Odorization</i>	<i>\$0.2</i>
<i>Tax</i>	<i>\$5.9</i>
Total	\$84.7

3

II. Construction Costs

Cost Element	Direct Costs (\$ Million)
Mobilization	\$0.5
Unload –Stockpile Pipe	\$0.4
Load Pipe – Haul to right-of-way	\$1.5
Unpaved Rural Road	\$14.9
Two lane Paved	\$39.2
Low Roll	\$11.2
Steep terrain	\$5.3
Roll Chop Sidecut	\$14.9
US 66 Paved	\$19.8
Primary Paved Road	\$114.9

1
2
3

Additional footage, elevation gains -5%	\$5.3
HDD Bores	\$1.9
Silt Fence	\$1.4
Tier 4 emissions equipment	\$8.4
Restore ROW/Seed, Stabilize	\$1.0
Temporary By=Pass Road on two lane	\$0.6
Security Fencing	\$0.4
Conventional Bores	\$6.7
Mainline Valves	\$4.3
Launcher/receiver	\$0.4
Caliper Survey	\$0.1
X-Ray Services	\$2.5
Hydro Testing and Drying	\$2.5
Casing Wax	\$1.2
Demobilization	\$0.3
Construction Management	\$10.8
TOTAL CONSTRUCTION LABOR	\$270.4

1
2
3
4
5
6
7
8

<i>Cost Element</i>	<i>Direct-Cost (\$ millions)</i>
Mobilization	-\$0.6
Unload—Stockpile Pipe	-\$0.8
Load Pipe—Haul to right of way	-\$0.8
County Paved Roads	-\$15.4
County Dirt Roads	-\$31.6
Light Residential—Paved	-\$17.5
City Street Paved	-\$52.2
SB National Forest	-\$8.4
Cajon Pass Cross-Country	-\$16.1
HDD Bores	-\$2.1
Cross-Country	-\$14.3
Short bores	-\$1.7
Conventional Bores	-\$4.5
Mainline Valves	-\$2.1
Launcher/receiver	-\$0.1
Caliper Survey	-\$0.2
X-Ray Services	-\$1.5
Hydro-Testing and Drying	-\$1.4
Demobilization	-\$0.3
Construction Management	\$8.3
Total	\$180.1

1

III. Other Costs

Cost Element	Direct Costs (\$ Million)
ROW Acquisition	\$17.8
Legal Services	\$8.0
Public Relations	\$2.7
Environmental Permitting	\$38.1
Geotechnical Investigation	\$0.4
Ministerial Permits	\$1.2
Engineering	\$14.3
SCADA	\$2.8
ROW Intrusion Monitoring	\$5.9
Methane Detection	\$0.1
PLS's	\$12.7
Company Labor	\$17.5
TOTAL OTHER COSTS	\$121.5

<i>Cost Element</i>	<i>Direct Cost (\$ millions)</i>
<i>ROW Acquisition</i>	<i>\$16.0</i>
<i>Legal Services</i>	<i>\$5.6</i>

Public Relations	\$1.1
Environmental Permitting	\$15.8
Geotechnical Investigation	\$0.4
Survey	\$3.6
Ministerial Permits	\$1.2
Engineering	\$7.4
As-built	\$0.8
SCADA	\$0.9
ROW Intrusion Monitoring	\$5.6
Methane Detection	\$0.1
Moreno PLS	\$2.4
Company Labor	\$5.9
Total	\$66.9

Appendix B – Adelanto Compressor Station Direct Cost Detail

1

I. Material Costs -

Cost Element	Direct Costs (\$ Million)
Turbine-driven Compressors	\$36.3
Buildings	\$4.5
Gas Cooling	\$1.1
Selective Catalytic Reduction System	\$5.5
Continuous Emissions Monitoring Systems	\$0.9
Aqueous Unit (Ammonia)	\$4.0
Major Piping and Fittings + Valves	\$12.6
Major Electrical Equipment	\$3.3
Concrete and Foundations	\$0.7
Other Process Equipment	\$1.8
Misc Process Equipment List	\$0.5
Vendor Reps	\$0.2
Auxiliary Generator	\$2.3
Tax	\$6.6
TOTAL MATERIAL	\$80.5

2

3

<i>Cost Element</i>	<i>Direct Cost (\$ millions)</i>
Turbine-driven Compressors	-\$31.7
Buildings	-\$2.5
Gas Cooling	-\$3.8
Major Piping and Fittings	-\$1.1
Valves	-\$2.1
Major Electrical Equipment	-\$1.1

Concrete and Foundations	-\$0.2
Misc. Materials	-\$4.2
Auxiliary Generator	-\$6.6
Selective Catalytic Reduction System/ Oxidation Catalyst	-\$4.0
Continuous Emissions Monitoring Systems	-\$0.8
Aqueous Unit (Ammonia)	-\$3.9
Maintenance Parts	\$0.2
Tax	\$3.7
Freight	\$1.7
Total	\$67.5

1 II. Construction Costs

Cost Element	Direct Costs (\$ Million)
Construction Labor	\$27.4
Construction Management	\$3.0
TOTAL CONSTRUCTION	\$30.4

<i>Cost Element</i>	<i>Direct Cost (\$ millions)</i>
Construction Labor	\$26.5
Block Wall	\$1.4
Electrical Upgrade—Construction	\$0.3
Construction Management	\$2.5
Total	\$30.8

1

III. Other Costs

Cost Element	Direct Costs (\$ Million)
Public Relations	\$0.2
Legal Services	\$0.0
ROW Acquisiton	\$0.1
Maintenance Parts	\$0.4
Environmental Permitting	\$10.3
Survey	\$0.4
Ministerial Permits	\$0.1
Engineering	\$3.3
As-built	\$0.2
SCADA	\$0.4
Company Labor	\$4.6
Freight	\$5.9
TOTAL OTHER COSTS	\$26.0

2

<i>Cost-Element</i>	<i>Direct-Cost (\$-millions)</i>
<i>Public-Relations</i>	<i>\$0.2</i>
<i>Environmental-Permitting</i>	<i>\$5.8</i>
<i>Survey</i>	<i>\$0.4</i>
<i>Ministerial-Permits</i>	<i>\$0.1</i>
<i>Engineering</i>	<i>\$1.8</i>
<i>As-built</i>	<i>\$0.1</i>
<i>SCADA</i>	<i>\$0.4</i>
<i>Company-Labor</i>	<i>\$3.7</i>
<i>Total</i>	<i>\$12.5</i>

|



Appendix C – Moreno-Whitewater Pipeline Direct Cost Detail

1

I.—Material Costs—

<i>Cost Element</i>	<i>Direct Cost (\$ millions)</i>
Pipe & Coating	-\$31.4
Pipe Delivery	-\$4.8
Ells	-\$0.6
Valves	-\$0.8
Other Materials	-\$1.9
Freight	-\$0.6
Odorization	-\$0.1
Tax	-\$3.0
Total	\$43.1

2

II.—Construction Costs

<i>Cost Element</i>	<i>Direct Cost (\$ millions)</i>
Mobilization	-\$0.3
Unload—Stockpile Pipe	-\$0.4
Load Pipe—Haul to right of way	-\$0.4
County Paved Roads	-\$24.9
Narrow Right of Way	-\$21.2
Mountain Terrain	-\$31.6
Cross-Country	-\$2.4
Conventional Bores	-\$3.3
HDD Bores	-\$2.8
Mainline Valves	-\$1.4
Launcher/receiver	-\$0.1
Caliper Survey	-\$0.2
X-Ray Services	-\$0.8
Hydro Testing and Drying	-\$0.7
Demobilization	-\$0.2

Construction Management	\$4.5
Total	\$95.2

1

III. Other Costs

<i>Cost Element</i>	<i>Direct Cost (\$ millions)</i>
ROW Acquisition	\$16.3
Legal Services	\$3.0
Public Relations	\$0.8
Environmental Permitting	\$6.4
Geotechnical Investigation	-\$0.2
Survey	-\$1.8
Ministerial Permits	-\$0.5
Engineering	-\$3.7
SCADA	\$0.6
As-built	-\$0.4
ROW Intrusion Monitoring	-\$2.8
Methane Detection	-\$0.0
Pressure Limiting Stations	\$5.8
Company Labor	\$5.4
Total	\$47.7