

Company: San Diego Gas & Electric Company (U 902 M)
Proceeding: 2024 General Rate Case
Application: A.22-05-015_016
Exhibit No: (SDGE-36-WP-S)

SUPPLEMENTAL
WORKPAPERS TO
PREPARED DIRECT TESTIMONY
OF DANE A. WATSON
ON BEHALF OF SAN DIEGO GAS & ELECTRIC COMPANY
VOLUME 13
BEFORE THE PUBLIC UTILITIES COMMISSION
OF THE STATE OF CALIFORNIA
AUGUST 2022



SDG&E BESS Decommissioning



SDG&E

Battery Energy Storage System

Decommissioning Plans and Study

January 2022

Table of Contents

| | |
|---|----|
| 1. Executive Summary..... | 4 |
| 2. Project Details | 4 |
| 2.1. Battery Container | 6 |
| 2.2. Battery Pack..... | 6 |
| 2.3. HVAC System | 6 |
| 2.4. Fire Suppression System | 7 |
| 2.5. Power Conversion System | 7 |
| 2.6. Additional Equipment | 7 |
| 3. Applicable Regulations, Certifications & Training..... | 7 |
| 3.1. Arizona Environmental Quality & US DOT Regulations | 7 |
| 3.2. Municipal Codes..... | 8 |
| 3.3. Certifications & Training | 8 |
| 4. Decommissioning Activities | 8 |
| 4.1. State of charge at decommissioning..... | 9 |
| 4.2. System shutdown and disconnection | 9 |
| 4.2.1. General Lockout/Tagout Procedures and Sequence | 9 |
| 4.3. Battery removal | 10 |
| 4.4. HVAC System | 11 |
| 4.5. Fire Suppression System | 11 |
| 4.6. BESS Containers | 13 |
| 4.7. Power Conversion System | 13 |
| 4.8. Transformers..... | 13 |
| 4.9. Additional Equipment | 13 |
| 4.10. Electric Conductor Removal | 13 |
| 4.11. Fencing removal..... | 14 |
| 4.12. Foundation Removal | 14 |
| 5. Site Restoration Process Description | 14 |
| 6. Environmental Effects..... | 14 |
| 7. Damaged Batteries..... | 14 |
| 7.1. Mechanical Damage..... | 15 |
| 7.2. Electrical Damage | 15 |
| 7.3. Thermal Damage | 16 |
| 7.3.1. High Internal Temperatures during Operation | 16 |
| 7.3.2. High Ambient Temperatures during Storage | 16 |

7.4. Leaking Cells 16

7.5. Packaging for Shipment 17

 7.5.1. Preparing Battery Modules for Shipment..... 18

 7.5.2. Package Labeling & Marking..... 19

 7.5.3. Record Retention 19

APPENDIX 1 – Typical Division of Responsibilities

APPENDIX 2 – Project Schedules

APPENDIX 3 – Project Details

APPENDIX 4 – Project Cost Estimates

1. Executive Summary

The purpose of this document is to provide an overall plan and cost estimate for activities that will occur during the decommissioning phase of SDG&E Battery Energy Storage System (BESS) for the following projects:

- Borrego Microgrid 1 (Parker/Saft), 2100 Borrego Valley Road, Borrego Springs, CA 92004
- Borrego Microgrid 2 (ABB/Saft), 2100 Borrego Valley Road, Borrego Springs, CA 92004
- Escondido BESS, 571 Enterprise St, Escondido, CA 92029
- Eastern BESS, 904 W. Main St, El Cajon, CA 92020
- Top Gun Energy Storage, 6875 Consolidated Way, San Diego, CA 92121

Activities related to the restoration of land, the management of materials and waste will be considered in this document including:

- Permits, Certifications & Training
- Equipment Dismantling and Removal
- Removal and Recycling of the Battery Energy Storage Modules
- Removal of the Ancillary Electrical Systems
- Removal of Equipment Pads, Supports, Gravel and Perimeter Fence
- Site Restoration
- Environment Impacts

This plan is based on current best management practices and procedures. It will be updated as necessary based on new information and developments at the time of decommissioning.

A typical division of responsibility (DOR) for a BESS decommissioning project is provided in Appendix 1. Overall project schedule for completing the BESS decommissioning project is provided in Appendix 2. Overall project details for each ESS decommissioning project can be found in Appendix 3. Cost estimates for each BESS decommissioning project can be found in Appendix 4.

2. Project Details and Cost Estimating

The details required to plan and estimate a BESS Decommissioning Project are provided in Figure 1. In addition to these inputs the applicable local county codes and standards as well as state and federal regulations will need to be considered.

Figure 1 – Plan Detail Inputs

| Input Data | |
|-------------------|---|
| Battery | Battery Make/Model |
| | Battery Chemistry |
| | Battery module weight (lbs) |
| | Battery Module Length (in) |
| | Battery Module Width (in) |
| | Battery Module CATL Liquid Cooled? |
| | Number of battery racks per container |
| | Number of battery modules per rack |
| Enclosure | Number of battery enclosures (EOL) |
| | Estimated weight of battery enclosure without battery modules (lbs) |
| | Battery enclosures HVAC cooled (wall or roof mount)? |
| | Number of HVAC/Chiller Units per battery enclosure |
| | Clean agent fire suppression installed in enclosure? |
| Inverter/PCS | Are Inverters/PCS pad mounted? |
| | Number Inverters/PCS to be decommissioned |
| | Is isolation transformer integrated with PCS? |
| | Estimated weight of inverter/PCS (lbs) |
| | Inverter/PCS width (in) |
| | Inverter/PCS length (in) |
| | Are inverters/PCS liquid or air cooled? |
| Transformer | Number of isolation transformers (pad mounted or integrated) |
| | Estimated weight of empty transformer (lbs) |
| | Are there oil filled transformers? |
| | Gallons of oil per transformer |
| Labor | Average Site Labor Cost (\$/hr) |
| Logistics | Shipping distance from site to battery recycling facility (miles) |
| Schedule | Estimating Year |
| | Decommissioning Year |
| | Escalation (average ECI value since 2002) |

The layout of the major equipment and access to the site are also important factors in determining final costs. These estimates assume there is adequate access to all sites and no obstructions need to be removed.

Labor cost estimate is based on a fully burdened rate for a qualified union electrician hired by a General Contractor. The rate assumes some overtime will applied during the decommissioning project.

Since these projects do not require a supply of new materials, the majority of the costs is due to the labor component. Therefore, the Employment Cost Index is used for price escalation. Using the following data one can determine the ECI for construction workers to be 2.5% on average for the last 20 years. For this study, the next 20 years will be assumed to follow a similar trend.



Source: U.S. Bureau of Labor Statistics [Release: Employment Cost Index](#)

Units: Index Dec 2005=100, Not Seasonally Adjusted

Frequency: Quarterly

Includes wages, salaries, and employer costs for employee benefits.

Suggested Citation:

U.S. Bureau of Labor Statistics, Employment Cost Index: Total compensation for Private industry workers in Construction [CIU20123000000001], retrieved from FRED, Federal Reserve Bank of St. Louis; <https://fred.stlouisfed.org/series/CIU20123000000001>, November 15, 2021.

2.1. Battery Container

All of the systems in this study are composed of containerized batteries in various types of enclosure designs. All of the enclosure are assumed to be within standard shipping dimensions

2.2. Battery Pack

The fundamental unit of a battery pack is the battery cell, where potential electrical energy is stored as chemical energy. The battery pack cells wired in series. The battery cells utilize lithium-ion based chemistry. Each battery pack contains a battery pack controller, which collects voltage and temperature data from the battery cells and reports to the string controller. The battery pack controller is comprised of power supplies, power resistors, heat sinks and various other electronic circuits for controlling battery performance.

2.3. HVAC System

Battery container thermal management is provided by an HVAC system composed of one or more vertical wall-mounted air conditioning units. The HVAC units utilize R-410a refrigerant. Refrigerant 410A is not RCRA listed hazardous wastes but is subject to U.S. Environmental Protection Agency Clean Air Act Regulations Section 608 in 40 CFR Part 82 regarding refrigerant recycling.

2.4. Fire Suppression System

Fire suppression units are assumed to be a dry agent. The cannisters of dry agent will need to be removed and disposed of per manufacturer's instructions and applicable regulations

2.5. Power Conversion System

The PCS/Inverters vary in size and configuration for all projects in this study. The inverters may be skid mounted units installed on concrete foundations or housed in the battery containers. Some inverter types may use forced air cooling systems which utilize R449A refrigerant, or equivalent. Refrigerant R449A is not RCRA listed hazardous wastes but is subject to U.S. Environmental Protection Agency Clean Air Act Regulations Section 608 in 40 CFR Part 82 regarding refrigerant recycling.

2.6. Additional Equipment

Additional balance of plant equipment on site include oil-filled pad mount isolation transformers, control equipment enclosures, switchgear, dry-type transformers, and automatic transfer switches. At end of life, the transformers offer the potential for refurbishment and reuse, while the balance of equipment is electronic waste that will be managed appropriately.

3. Applicable Regulations, Certifications & Training

Decommissioning and restoration activities will adhere to the requirements of appropriate governing authorities, and will be in accordance with applicable federal, state, and local permits.

3.1. Environmental Quality & US DOT Regulations

California Administrative Code adopts the US EPA Universal Waste rule in its entirety. Batteries in the decommissioned system destined for recycling are considered by the US EPA Resource Conservation and Recovery Act (Code of Federal Regulations, Title 40, Part 273) as Universal Waste.

The Project Owner will obtain an EPA ID number in advance of decommissioning the system as more than 5000 kg of universal waste will be accumulated (Code of Federal Regulations, 40 CFR 273.32).

Lithium-ion batteries are classified by the US Department of Transportation (DOT) as Class 9 hazardous materials. All requirements related to the packaging, labelling and transportation contained in the Code of Federal Regulations, Title 49, Subchapter C, Parts 171-180, will be followed.

3.2. Municipal Codes

The Projects reside in multiple counties in CA. Most have adopted the International Building Code with Amendments. Per the building code, a building permit must be obtained for any construction, alteration, repair, demolition, or change to the use or occupancy of a building. Accordingly, a building permit may be required prior to decommissioning of some sites. Notification of decommissioning to the AHJ/Fire Marshal may also be required during permit processing.

County ordinances regulating Stormwater Quality Management and the Discharge of Stormwater mandates post-construction stormwater measures and practices must be evaluated and planned for. A stormwater management permit may be required at project initiation to comply with the Ordinance. This permit requires the landowner to maintain any and all storm water measures and practices identified in the construction plan that were intended to remain in place after construction activities have been completed. It is not expected significant ground-disturbing activities will occur during decommissioning; therefore, a revised permit may not be required.

Because the decommissioning is expected to occur at a later date, the permitting requirements listed above will be reviewed and updated based on current local, state, and federal regulations at the time.

3.3. Certifications & Training

The handling of lithium-ion batteries will be performed by employees who have completed hazmat training applicable to their function (Code of Federal Regulations 49 CFR 172.704).

All workers who perform electrical work, including lockout/tagout and electrical disconnection, will be NFPA 70E electrical safety certified.

All hazardous wastes will be transported using appropriate waste manifests by certified waste carriers to a US EPA certified Treatment, Storage or Destination Facility.

4. Decommissioning Activities

At the time of decommissioning the installed equipment will be removed, repurposed, disposed of and recycled where possible. The facility will be restored to a state similar to its preconstruction condition. The removal of equipment and material will be done in accordance with the applicable regulations and manufacturer recommendations.

Prior to decommissioning, the facility will be deenergized and disconnected from the grid in coordination with all applicable parties. Generally, the decommissioning of the facility proceeds in reverse order of the original installation as follows.

4.1. State of charge at decommissioning

The battery energy storage system should be discharged to a state of charge as low as reasonably achievable. Although there is currently no restriction on the state of charge for ground transportation of lithium-ion batteries, the generally accepted practice is to reduce it as low as possible to minimize the hazard during handling and transport. If the batteries will be reused, follow manufacturer's instructions regarding depth of discharge to prevent cell damage.

4.2. System shutdown and disconnection

Before the system can be dismantled or removed, it will need to be shut down and disconnected from the utility system in accordance with the manufacturer's/integrator's procedures. This will include a final inspection of the system, system shut-down, and physical disconnection of the systems electrical components.

4.2.1. General Lockout/Tagout Procedures and Sequence

A general lockout/tagout (LOTO) sequence for isolating the BESS is provided below. Original Equipment Manufacturers provide equipment-specific LOTO procedures that will be used for equipment decommissioning. These LOTO procedures provide safe work processes and procedures compliant with OSHA standards 29 CFR 1910.147 and 29 CFR 1910.333 for the control of hazardous energy and the protection of employees working on electric circuits and equipment.

BESS Mains and DC Power LOTO

Discharge battery modules to minimum SOC prior to starting LOTO.

Open and Lockout BESS Feeder Breaker to de-energize AC Mains to BESS Feeder

Maintain Aux Feeder Breaker closed to maintain HVAC/FSS systems operational until battery modules are removed.

Turn inverter OFF and open and lockout DC or AC input breakers.

Open and lockout DC disconnect in each battery enclosure to the associated inverter.

Open and lockout AC breaker supplying power to battery switchgear inside of each the battery enclosure LV power distribution panel.

Remove DC battery string power cables (NOTE: Only Electrically qualified Electricians can perform this operation. This is an arc flash hazard requiring HRC3 or greater PPE).

Remove battery modules and package for shipment.

Auxiliary Power LOTO

- Open and lockout Aux Feeder Breaker and any associated Load Break Switches
- Disconnect and Remove 125VDC power batteries
- Disconnect and remove UPS battery in Control Room
- Disconnect and remove Fire Control Panel backup batteries in each battery enclosure
- Turn off and disconnect backup generator
- Disconnect and remove all power and control cables and prepare equipment for removal

12/12.47KV Power LOTO

- Open and lockout Substation BESS Main Feeder breaker.
- Remove Utility supplied equipment and meters and connections
- Remove MV switchgear and associated power and control cables

4.3. Battery removal

Battery modules will be removed from their racks and packaged as described below. Occupational Safety and Health Administration (OSHA) standards for safe lifting of heavy loads will be strictly followed. Multiple workers will be used as needed to safely remove the battery modules.

Lithium-ion batteries will be packaged in a manner to prevent short circuits, movement within the outer package, and accidental activation of the equipment.

The batteries will be palletized and packaged in accordance with the requirements of 49 CFR 173.24 and 173.24a. The packages containing the batteries will be marked and labelled in accordance with 49 CFR 173.185, Subparts D and E. Considerations for damaged batteries are provided in Section 7.0.

Battery recycling will be completed using a hydrometallurgical process. Large battery packs first go through a manual disassembly process where technicians will carefully dismantle the pack, separating assembly pieces and circuitry from the battery cells. The separated cells are then fed by conveyor to an automated crusher. This crusher, which operates under a liquid solution to prevent fugitive emissions and to reduce the reactivity of processed batteries, produces three types of materials: metal solids, metal-enriched liquid, and plastic fluff. The metal solids and metal-enriched liquid contain materials that can all be used as raw materials in new products.

4.4. HVAC System

Refrigerant R410a is not RCRA listed hazardous wastes but is subject to U.S. Environmental Protection Agency Clean Air Act Regulations Section 608 in 40 CFR Part 82 regarding refrigerant recycling. The refrigerant will be removed by a certified technician who will ensure that the refrigerants are not exposed to atmosphere while decommissioning the chiller and safe disposal of refrigerants comply with EPA regulations 40 CFR part 82, Subpart F.

HVAC units will be removed from the containers per OEM procedures and sent to a metal recycler separately, or they will be sent with the container to an off-site metal recycler/reclamation facility.

4.5. Fire Suppression System

The fire suppression cannisters are generally units that may be connected via piping to centralized tanks or self contains . Typically fire suppression systems used FM200, Novec 1230, or Stat-X. For FM200 and Novec 1230 system cannisters are removed and sent back to qualified fire equipment installers for disposal/re-use.

Before disposing Stat-X canisters to landfill, they need to be processed to deactivate the materials. Per the Manufacturer the following methods shall be used to deactivate Stat-X canisters.


Note: Stat-X fixed aerosol fire suppression units are UN Class 1.4S devices (or Class 9 safety devices with US DOT special permit DOT-SP 20600) sealed in a stainless and insulated container of double wall tube construction. Orifice holes are hermetically sealed with a metalized polyester film.

Stat-X aerosol forming molded pellet compounds are blended and pressed mixtures of dry potassium nitrate, dicyandiamide, and organic resin. These chemicals are more soluble in hot water than cold water, and dissolves most rapidly in boiling water (100°C/212°F). The electric initiator also includes a silicon capsule filled with crushed and ground aerosol forming compound. This mixture is also soluble in hot water.

The following steps must be performed to safely decommission Stat-X aerosol generators:

1. Prior to performing the following steps ensure that the generator flying leads are grounded together (copper leads are twisted together). **GENERATORS THAT ARE LIVE MUST HAVE INITIATOR LEADS KEPT AWAY FROM ANY LIVE ELECTRICAL SOURCES.** Subjecting leads to any electrical current or voltage source may cause the generator to discharge.
2. Safely place the generator in a securing device such as a belt or rubber grip table vice with the discharge ports pointed upward.

3. Using a Phillips tipped screwdriver or other such device puncture the membrane seal in each of the discharge ports as pictured below. Be sure each port is completely opened.



4. Fill a waterproof container such as a 5 gallon pail (or larger drum for 8" diameter generators) with hot or boiling or continuously heated water. Remove the generator from the securing device and submerge it in the water filled container. Allow water to enter the generator through the open discharge ports.

Repeat steps 1, 2 and 3 with other generators always placing them in the water filled container in horizontal or orifice facing upward. However, keep in mind that all generators must be fully submerged during the decommissioning process. Beware of scolding hot water and hot container.

5. Leave the generator(s) submerged in hot water for no less than 24 hours allowing the water to penetrate the generator and soak the internal components. During this process the water will dissolve the generator aerosol forming pellet compound. Drain and replace with fresh hot or boiling water as practical.

Warning: Always wear water proof gloves and eyewear protection when handling units in water solutions with dissolved chemicals. Avoid chemical solution contact with eyes or skin. Wash hands following operation.

6. Remove the now inert unit(s) from the water filled container.
7. Dispose of each unit and waste water by following local waste disposal regulations.

4.6. BESS Containers

All external additions such as stairs or railings will be removed and shipped separately as necessary to meet standard ISO container shipping dimensions. All loose components will be removed and anchoring will be removed to permit container to be lifted from the site. The container will be lifted by crane onto a flatbed or standard ISO container chassis for shipment to recycler/reclamation facility.

4.7. Power Conversion System

PCS units or portions of it can potentially be returned to the manufacturer or for secondary use in other projects. Alternatively, the PCS units will be sent to an R2-certified waste electronics salvage facility, where they will be able to remove the IGBTs and other power electronics for metal recovery. The R449A refrigerant in the PCS forced air cooling system will be removed by a certified technician who will ensure that the refrigerants are not exposed to atmosphere while decommissioning the chiller and safe disposal of refrigerants comply with EPA regulations 40 CFR part 82, Subpart F.

4.8. Transformers

Oil-filled transformers of this type typically have potential resale value, which will be pursued as the preferred outlet for this material. Should resale not be possible, transformer oil will be drained and sent to a waste oil processing facility for proper management. The transformer will be sent to a metal recycler or metal smelting facility for further processing and reclamation.

4.9. Additional Equipment

Control enclosures, automatic transfer switches, dry-type transformers and switchgear all considered electronic waste at end of life. Metal structures that can be easily separated will be sent to metal recyclers for reclamation. The balance of the electronic equipment will be sent to a certified R2-certified electronic waste recycler for proper management.

4.10. Electric Conductor Removal

Electrical conductors/wiring will be removed from above ground and underground locations. Underground conduit, pull boxes, trenches, and duct banks will be plugged/filled and abandoned in place. All electrical conductors removed will be recycled. All above grade conduits will be sent to metal recycler.

4.11. Fencing removal

Fencing material will be broken down into manageable units, removed from facility sent to an approved recycler. All posts driven into the ground will be pulled and removed.

4.12. Foundation Removal

Augured foundations and concrete slabs used as equipment pads will be broken and removed to grade. Clean concrete will be crushed and disposed of off-site and/or recycled and reused either on or off-site. Equipment foundations poured over existing pavement will be removed to existing pavement surface. Holes in existing pavement will be filled/patched.

5. Site Restoration Process Description

Following decommissioning activities, additional grade material will be applied. The affected areas will be inspected, thoroughly cleaned, and all construction-related debris removed. No reseeding of disturbed areas has been assumed.

6. Environmental Effects

Decommissioning activities have a similar risk of environmental impacts as those associated with construction phase. For example, decommissioning activities may result in the disturbance of soil, and erosion prevention measures will be put in place, so nearby watercourses or other natural features are not impacted. A Sediment and Erosion Control Plan, like that used during construction will be employed. The sediment and erosion control measures will remain in place until the site is stabilized to mitigate stormwater runoff and soil erosion. Temporary impact to roadway traffic similar to those during construction will accompany the decommissioning process. Noise levels similar to those during construction may be heard in the surrounding area while the decommissioning is taking place.

7. Damaged Batteries

Guidelines for safely handling batteries that have been subjected to abnormal conditions during installation or operation are provided below. In some cases, these abnormal conditions may require special care and specific packaging, storage and/or shipment requirements. Such abnormal conditions include:

1. Mechanical damage
2. Electrical damage
3. Thermal damage
4. Leaking electrolyte (resulting from either mechanical, electrical damage)

7.1. Mechanical Damage

Mechanical damage to battery modules can occur during handling and the damage may range from superficial scratches to more significant damage (e.g., dents, broken hardware, etc.). In severe cases, mechanical damage of the battery module resulting from severe shocks (e.g., dropping a battery module) can create a flaw in the cell that results in an internal cell fault much later (i.e., after the cell has undergone numerous cycles).

If mechanical damage is evident, or if the battery module is believed to have been subjected to severe shocks (i.e., dropped), take the following actions:

- Quarantine and monitor battery modules that have suffered mechanical damage. Mechanically damaged battery modules should be recycled rather than placed back into service.
- If the mechanical damage is severe, check for any signs of leaking electrolyte. If found, following the guidance provided in Section 7.4 below.
- Battery modules that have been mechanically damaged should be packaged and shipped per the guidance provided in Section 7.5 below.

7.2. Electrical Damage

Electrical damage may result from improper operation of the battery module, such as over-discharge, or may result from an internal or external short circuit. Over discharge may occur when the battery module has been fully discharged to the point that overall voltage is too low, or the voltage of individual batteries is much lower than its normal working voltage range. A short circuit could be caused by external means such as improper handling that permits results in the battery terminals shorting together, or from severe mechanical damage that results in an internal short between cells.

In the event of known or suspected electrical damage, take the following actions:

- If the battery module is in operation, shut off the relevant power source and electrical equipment. Shut off the connection between battery and system immediately.
- Quarantine and monitor battery modules that have suffered electrical damage. Electrically damaged battery modules should be recycled rather than placed back into service.
- Check for any signs of leaking electrolyte. If found, following the guidance provided in Section 7.4 below.

- Battery modules that have been electrically damaged should be packaged and shipped per the guidance provided in Section 7.5 below.

7.3. Thermal Damage

Thermal damage may occur due to a variety of conditions, including high internal temperatures that may result during operation that cannot be dissipated by the battery cooling system or high ambient temperature during storage that exceed manufacturer's recommendations.

7.3.1. High Internal Temperatures during Operation

Under normal circumstances, when the battery of the battery pack is over-temperature, the heat-removal system of the battery pack will automatically conduct the heat dissipation to make the battery pack cool down to the optimal working temperature range. When the battery pack cannot cool down to the target temperature within the specified time or the temperature of the battery pack exceeds the upper limit of safe use, notify OEM technical personnel to conduct a comprehensive inspection. If the evaluation determines that the excess temperatures may have damaged the battery module, it should be treated as a damaged battery and recycled following the guidance provided in Section 7.5 below.

7.3.2. High Ambient Temperatures during Storage

The battery manufacturer publishes specifications for proper storage of lithium-ion batteries, including ambient temperature ranges. Exceeding the ambient temperature specification can cause battery performance degradation. If it is believed that ambient storage temperatures exceeded manufacturer's specifications, notify OEM technical personnel to conduct an evaluation. If the evaluation determines that the excess temperatures may have damaged the battery module, it should be treated as a damaged battery and recycled following the guidance provided in Section 7.5 below.

7.4. Leaking Cells

The above sections provide recommendations on how to safely manage battery modules that have been subjected to mechanical, electrical, or thermal damage. Any of these scenarios could cause significant damage to the extent that permit electrolyte to leak from the battery cells. Should this occur, the following actions should be taken:

- Evacuate personnel from the area.

- If indoor, provide adequate ventilation until after the cell is removed from the area.
- If the cell vented because of excessive heating, it must be allowed to cool to ambient temperature before handling.
- Put on appropriate PPE including lab coat, rubber gloves, safety glasses and respirator.
- Place the battery in a container of sand or another chemically inert cushioning material like vermiculite
- Absorb and/or neutralize spilled electrolyte with an absorbent material or baking soda.
- Sweep contaminated baking soda or absorbent material into a sealable plastic bag for disposal.
- Clean the area with copious amounts of water or an ammonia- based cleaner.
- The resulting waste may be hazardous and subject to specific local, state, and federal hazardous waste disposal regulations.

7.5. Packaging for Shipment


This procedure is limited to batteries that remain classified as Universal Waste despite the damage, such as blunt force damage to battery module casing, loose parts, swollen cells, evidence of short circuit, etc. This procedure does not apply to damaged batteries with leaking cells. Such batteries must be shipped as a fully regulated hazardous waste.

Before handling battery modules, the following requirements must be observed:

- Wear personal protective equipment including eye protection and nonconductive gloves
- Handle all damaged, defective, or recalled batteries with the same responsible care as a new battery to avoid any further damage.
- Do not drop batteries into the packaging or onto the shipping skid/pallet. Set them down carefully. Use lifting and handling fixtures as needed.
- If multiple damaged are being shipped, they may be palletized and stacked provided the overall weight does not exceed the capacity of the pallet.

7.5.1. Preparing Battery Modules for Shipment

- Damaged, defective, or recalled batteries must be placed in UN specification packaging, which is specially designed and tested packaging that has been demonstrated to withstand the forces typically expected to be encountered during shipment.
- Any battery module or cell that is damaged must be packaged individually. Multiple batteries in the same packaging are prohibited unless such packaging is accompanied by a Special Permit issued by the US DOT Pipeline & Hazardous Material Safety Administration (PHMSA).
- Battery module dimensions vary significantly by OEM and model. UN specification packaging must be procured that is suitable for the size and weight of the battery module to be shipped.
- The UN specification Packaging must be constructed of metal, plastic, or wood. Corrugated/fiberboard packaging is specifically prohibited.
- Terminals must be electrically insulated using electrical tape or other appropriate means.
- The battery module must be placed inside a non-metallic inner packaging that completely encloses the cell or battery. An anti-static plastic bag is suitable for this purpose.
- The battery module enclosed in the inner packaging must be placed inside the outer UN specification packaging and surrounded by cushioning material that is non-combustible, non-conductive, and absorbent (CellBlockEx or Vermiculite are suitable for this purpose). Refer to Figure 3 for a depiction of a properly prepared damaged battery.
- The battery modules should be set on the skid/pallet in the same orientation they were installed in the battery racks.



7.5.2. Package Labeling & Marking

- Each container must have the correct labeling to meet DOT regulations prior to shipment. This is considered a Universal Waste shipment and must be marked as such.
- Affix DOT Class 9 and UN3480 on at least 2 sides.
- Affix a Universal Waste label or clearly write the words “UNIVERSAL WASTE BATTERY” on the package
- Label the package with the Consignor and Consignee Name and Address.
- Write “DAMAGED/DEFECTIVE LITHIUM-ION BATTERY” with black marker on at least one side.
- Do not overlap any markings or labels.
- Do not bend markings or labels around corners of packaging
- Do not put labels on the bottom of the package
- For shipments involving multiple damaged batteries, apply multiple layers of 75-gauge, clear stretch wrap around all four sides of the battery modules.
- Ensure all hazard markings, labels and UN Specification markings are clearly visible after shrink wrapping. If they are not visible, duplicate hazard markings and labels on the outside of the shrink wrap

7.5.3. Record Retention

A large quantity handler of universal waste must keep a record of each shipment of universal waste sent from the handler to other facilities. The record may take the form of a log, invoice, manifest, bill of lading, movement document or other shipping document. The record for each shipment of universal waste sent must include the following information:

- (1) The name and address of the universal waste handler, destination facility, or foreign destination to whom the universal waste was sent.
- (2) The quantity of each type of universal waste sent (e.g., batteries, pesticides, thermostats).

(3) The date the shipment of universal waste left the facility. A large quantity handler of universal waste must retain the records for at least three years from the date a shipment of universal waste left the facility.

A large quantity handler of universal waste must retain the records for at least three years from the date a shipment of universal waste left the facility.

APPENDIX 1 TYPICAL DIVISION OF RESPONSIBILITY

| | Activity | SDGE | Equipment Logistics and Recycling | Site Labor and Decommissioning Contractor |
|------------|---|---------|-----------------------------------|---|
| 1.0 | Project and Site Management | | | |
| 1 | Overall Project Management | | X | |
| 2 | Site Coordination/Site Management | | | X |
| 3 | Coordination Customer Internal Approvals | X | | |
| 4 | Coordination with Independent System Operators/Utility Company | X | | |
| 5 | Coordination with Geo-Tech Engineering if backfill/grading is required | | | X |
| 6 | Comply with existing Project Labor Agreements | | | |
| 7 | Payment of Fees including permits and Disposal of Equipment/Materials to Landfill | X (EPA) | | X(Demolition, Landfill) |
| 8 | Provide existing site drawings, equipment manuals, equipment quantities, and bill of materials | X | | |
| 9 | Provide material safety data sheets for all equipment/materials to be removed from site | X | | |
| 10 | Provide and maintain insurance for all site related activities per Owner requirements | | X | X |
| 2.0 | Pre-Mobilization Planning | | | |
| 1 | Obtain EPA Permit | X | | |
| 2 | Obtain Demolition Permit | | | X |
| 3 | Obtain Environmental Permits (e.g. AQMD Approvals) | X | | |
| 4 | Coordination and Notification of AHJs/Local Fire Authorities | X | | |
| 5 | Develop and Submit Overall Site Safety Plans (JHA Procedure, Fall Protection, Hot Work, Hearing Protection, Heat Illness Protection, etc.) | | | X |
| 6 | Develop and Submit Emergency Response/Evacuation Plan | | | X |
| 7 | Develop and Submit Site Access/Security Plan | | | X |
| 8 | Develop Environmental Plans per Customer Specifications (Dust Mitigation, Storm Water Pollution Plan, Spill Prevention Plan, Audible Noise Plan, Wildlife Protection Plans, Emission Plan) | | | X |
| 9 | Provide traffic and track-out control plan | | | X |
| 10 | Develop and Submit Laydown Area and Parking Plan | | | X |
| 11 | Provide equipment removal and dismantling procedures | | X | |
| 3.0 | Site Preparations and Mobilization | | | |
| 1 | Provide Temporary Office Space (if required) | | | X |
| 2 | Provide Temporary Site Lighting (if required) | | | X |
| 3 | Provide and Connect Temporary Power Source | | | X |
| 4 | Provide Temporary Fencing (if required) | | | X |
| 5 | Provide Site Signage, Access Control, and Security | | | X |
| 6 | Provide Waste Management Equipment (Dumpsters, Oil Drums, Storage Bins) | | | X |
| 7 | Provide Portable Restrooms and Potable Water | | | X |
| 8 | Provide First Aid/Emergency Response Equipment (Eyewash Station, Fire Extinguishers, Spill) | | | X |
| 9 | Perform Site Surveys to Locate Underground Utilities (Electrical/Gas/Water/Sewage) Prior to | | | X |
| 10 | Relocation of Existing Equipment/Overheads To Facilitate Access | X | | |
| 11 | Ensure all battery modules have been discharged to minimum SOC | X | | |
| 12 | Perform hazardous material samples and inspections (asbestos, lead, PCBs, mercury) | | X | |
| 13 | Perform hazardous material abatements if required | X | | |
| 4.0 | System De-energization and LOTO | | | |
| 1 | Develop AC Power De-energization/LOTO Plan with Utility Company at POC | X | | |
| 2 | Develop Med (12K-34K) Voltage AC Power De-energization/LOTO Plan | | X | X |
| 3 | Develop Site Low (120/240/480V) Voltage AC Power De-energization/LOTO Plan | | X | X |
| 4 | Develop Site DC Power De-energization/LOTO Plan | | X | X |
| 5 | Develop Turnover Plan | X | | |
| 6 | Perform MV De-Energization/LOTO Plan | | | X |
| 7 | Perform LV De-Energization/LOTO Plan | | | X |
| 8 | Perform DC De-Energization/LOTO Plan | | | X |
| 9 | Complete System/Equipment Turnover to Dismantling Team | X | | |

APPENDIX 1 (Cont.)

| | Activity | SDGE | Equipment Logistics and Recycling | Site Labor and Decommissioning Contractor |
|------------|---|------|-----------------------------------|---|
| 5.0 | Equipment Dismantling/Removal | | | |
| 1 | Provide all Tools/PPE for Safe Dismantling/Removal of Equipment | | | X |
| 2 | Disconnect Low Voltage AC Power Cables at Terminals | | | X |
| 3 | Disconnect DC Power Cables Including Battery String Cables at Terminals | | | X |
| 4 | Sample and analyze Isolation Transformer Oil | | | X |
| 5 | Remove Isolation Transformer (s) | | | X |
| 6 | Prepare and Remove Pad Mounted Inverter (s) | | | X |
| 7 | Depressurize and Collect Battery Enclosure HVAC Refrigerant, if required | | X | |
| 8 | Remove Battery Enclosure Fire Suppression Agent/Canisters, if required | | X | |
| 9 | Remove battery modules from racks | | | X |
| 10 | Remove AC/DC Cables between Battery Enclosure and Transformer/Auxiliary Equipment up to high side of BESS main breaker | | | X |
| 11 | Remove Aux transformer and Aux Distribution Panels/Equipment | | | X |
| 12 | Remove BESS controls/SCADA | | | X |
| 13 | Remove MV switchgear | | | X |
| 14 | Remove UPS and recycle UPS batteries | | | X |
| 15 | Remove above ground cable trays | | | X |
| 16 | Remove steel platforms and support structures | | | X |
| 17 | Remove Utility supplied equipment (meters, RTAC, switches, transformers) | X | | |
| 18 | Remove power and control connections Outside Fence line to Utility POC | X | | |
| 6.0 | Equipment Packaging and Loading | | | |
| 1 | Package all equipment/materials for shipment per DOT standards | | | X |
| 2 | Ensure Proper Labeling of Equipment/Materials | | | X |
| 3 | Provide crane and/or forklift for equipment loading | | | X |
| 7.0 | Equipment/Materials Transport | | | |
| 1 | Coordinate pickup of battery modules | | X | |
| 2 | Coordinate pickup of all equipment/materials to be disposed to landfill or recycled by local scrap metal company | | | X |
| 3 | Recycle damaged Battery Modules with unbreached cells (Universal Waste) | | X | |
| 4 | Recycle damaged Battery Modules with breached cells (Hazardous Waste) | | X | |
| 5 | Recycle/Scrap Battery Enclosure/Racks/HVAC | | X | |
| 6 | Recycle/Scrap Inverter Enclosure/Power Electronics Inside Enclosure | | X | |
| 7 | Recycle/Resell Isolation Transformer | | X | |
| 8 | Recycle/Scrap Power and Control Cabling Outside Enclosure | | | X |
| 9 | Prepare Bill of Lading and Shipping Documents for respective shipments | | X | |
| 10 | Load equipment/materials onto trucks for shipment | | | X |
| 11 | Provide 24/7 emergency contact coverage during transport and storage required by 49 CFR | | X | |
| 12 | Ensure all equipment/materials have been delivered to recycler(s) | | X | |
| 13 | Manage recordkeeping and certifications | | X | |
| 8.0 | Site Demolition/Cleanup | | | |
| 1 | Inspection and Off Haul of Non -Contaminated Soils/Concrete | | | X |
| 2 | Inspection and Off Haul of Contaminated Soils (Not included) | X | | |
| 3 | Removal of Equipment Foundations to grade or existing pavement | | | X |
| 4 | Removal of below grade material (Trenches, Conduit, Manholes, Pull Boxes, Ground Grid Equipment, Concrete Encasements, Duct Banks) - NOT INCLUDED | | | NA |
| 5 | Supply Backfill for Restore Grade per Geo-Tech Engineering Requirements - NOT | | | NA |
| 6 | Remove and Dispose of Existing Site Fencing | | | X |
| 7 | Restoration of roadways to pre-Decommissioning conditions-NOT INCLUDED | | | NA |
| 8 | Ensure all permit inspections have been completed | | | X |
| 9.0 | Demobilization/Project Closeout | | | |
| 1 | Remove all temporary equipment from site | | | X |
| 2 | Submit completed final turnover document package to Owner | | | X |

APPENDIX 2 Decommissioning Project Schedule-Borrego Microgrid 1

| Decommissioning Plan and Sequence | Task | Week 1 | Week 2 | Week 3 | Week 4 | Week 5 | Week 6 | Week 7 |
|---|--|--------|--------|--------|--------|--------|--------|--------|
| Pre-Mobilization Planning | Develop De-energization plans with Customer, including PPE requirements | | | | | | | |
| | Develop equipment lifting and handling plan | | | | | | | |
| | Prepare materials needed at site (tools, pallets, packaging , labels) | | | | | | | |
| | Develop and approve site environmental and safety plans | | | | | | | |
| | Develop and approve security and site access plans (equipment access, gates, doors, staging area, parking) | | | | | | | |
| | Develop loading/pickup plans for batteries, scrap metal | | | | | | | |
| | Complete draft of BOL for hazardous materials | | | | | | | |
| | Obtain Utility agreement on de-energization plan and schedule | | | | | | | |
| | Complete site restoration and drainage plans | | | | | | | |
| | Obtain permits as needed | | | | | | | |
| | Physical obstacle to perform work have been removed. | | | | | | | |
| Mobilization | Setup site security and temporary facilities | | | | | | | |
| | Discuss site specific hazards and safety protocols | | | | | | | |
| | Perform job hazard assessments with Customer and perform work setup | | | | | | | |
| | Confirm laydown/temporary storage areas with Customer | | | | | | | |
| | Confirm emergency response procedures and contacts for fire or injury | | | | | | | |
| | Deliver metal scrap bins and packaging materials | | | | | | | |
| | Deliver forklift and handling equipment to site | | | | | | | |
| BESS AC Mains and DC Power LOTO | De-energize/LOTO AC side (mains) and DC power (Battery to Inverter) of Energy Storage System | | | | | | | |
| | De-energize/LOTO auxiliary power to battery switchgear | | | | | | | |
| | Set up limited approach boundary | | | | | | | |
| | Inspect and outfit in PPE. Minimum HRC3/PPE CAT 3 required during battery string power cable disconnects | | | | | | | |
| | Using insulated tools, remove battery module string power cables. (Note: After all string cables are removed PPE Cat 0 can be used.) | | | | | | | |
| Battery Module Removal and Shipment | Disconnect battery string power and communication cables | | | | | | | |
| | Remove Battery Modules and palletize for shipment | | | | | | | |
| | Ship battery modules to recycler | | | | | | | |
| Auxiliary Power LOTO | Disconnect and lockout Aux power supply from Medium Voltage Switchgear | | | | | | | |
| | Disconnect UPS and 125 VDC power | | | | | | | |
| | Disconnect Fire Control Panel backup batteries | | | | | | | |
| | Disconnect back up generator | | | | | | | |
| Utility Disconnect and LOTO | Disconnect and LOTO 12.47 KV power at Utility POC | | | | | | | |
| | Remove all utility company supplied meters, RTACs, CTs, SCADA equipment and ship to utility company | | | | | | | |
| Equipment Disassembly - Prep for Shipment | Drain and collect battery container AC refrigerant | | | | | | | |
| | Drain and collect inverter AC refrigerant | | | | | | | |
| | Remove and process Stat-X canisters for disposal | | | | | | | |
| | Remove control house AC refrigerant | | | | | | | |
| | Drain and collect transformer oil | | | | | | | |
| | Remove and package UPS/125 VDC lead acid batteries for shipment/recycling | | | | | | | |
| | Remove exterior hoods, steps, hold down bolts from battery enclosures | | | | | | | |
| | Disconnect and remove all power and control cables between equipment | | | | | | | |
| | Mobilize crane | | | | | | | |
| Loading and Shipment | Load battery containers onto trucks for shipment to recycler | | | | | | | |
| | Load Inverter and transformers onto truck for shipment | | | | | | | |
| | Load control enclosure | | | | | | | |
| | Load MV switchgear | | | | | | | |
| | De-mobilize crane | | | | | | | |
| | Ship scrap metal (cables, metal structures, panels) to recycler | | | | | | | |
| | Shipped drained oil to processing facility | | | | | | | |
| | Shipped lead acid batteries to recycler | | | | | | | |
| De-mobilization | Backfill and recompact | | | | | | | |
| | Remove and dispose of fencing | | | | | | | |
| | Final Patch and Grade per plan | | | | | | | |
| | Ensure all tools and equipment are removed. | | | | | | | |
| | Final site cleanup | | | | | | | |
| | Submit final reports and documentation | | | | | | | |

APPENDIX 2, continued Decommissioning Project Schedule-Borrego Microgrid 2

| Decommissioning Plan and Sequence | Task | Week 1 | Week 2 | Week 3 | Week 4 | Week 5 | Week 6 | Week 7 |
|---|--|--------|--------|--------|--------|--------|--------|--------|
| Pre-Mobilization Planning | Develop De-energization plans with Customer, including PPE requirements | | | | | | | |
| | Develop equipment lifting and handling plan | | | | | | | |
| | Prepare materials needed at site (tools, pallets, packaging , labels) | | | | | | | |
| | Develop and approve site environmental and safety plans | | | | | | | |
| | Develop and approve security and site access plans (equipment access, gates, doors, staging area, parking) | | | | | | | |
| | Develop loading/pickup plans for batteries, scrap metal | | | | | | | |
| | Complete draft of BOL for hazardous materials | | | | | | | |
| | Obtain Utility agreement on de-energization plan and schedule | | | | | | | |
| | Complete site restoration and drainage plans | | | | | | | |
| | Obtain permits as needed | | | | | | | |
| Mobilization | Physical obstacle to perform work have been removed. | | | | | | | |
| | Setup site security and temporary facilities | | | | | | | |
| | Discuss site specific hazards and safety protocols | | | | | | | |
| | Perform job hazard assessments with Customer and perform work setup | | | | | | | |
| | Confirm laydown/temporary storage areas with Customer | | | | | | | |
| | Confirm emergency response procedures and contacts for fire or injury | | | | | | | |
| BESS AC Mains and DC Power LOTO | Deliver metal scrap bins and packaging materials | | | | | | | |
| | Deliver forklift and handling equipment to site | | | | | | | |
| | De-energize/LOTO AC side (mains) and DC power (Battery to Inverter) of Energy Storage System | | | | | | | |
| | De-energize/LOTO auxiliary power to battery switchgear | | | | | | | |
| | Set up limited approach boundary | | | | | | | |
| Battery Module Removal and Shipment | Inspect and outfit in PPE. Minimum HRC3/PPE CAT 3 required during battery string power cable disconnects | | | | | | | |
| | Using insulated tools, remove battery module string power cables. (Note: After all string cables are removed PPE Cat 0 can be used.) | | | | | | | |
| | Disconnect battery string power and communication cables | | | | | | | |
| Auxiliary Power LOTO | Remove Battery Modules and palletize for shipment | | | | | | | |
| | Ship battery modules to recycler | | | | | | | |
| | Disconnect and lockout Aux power supply from Medium Voltage Switchgear | | | | | | | |
| | Disconnect UPS and 125 VDC power | | | | | | | |
| Utility Disconnect and LOTO | Disconnect Fire Control Panel backup batteries | | | | | | | |
| | Disconnect back up generator | | | | | | | |
| | Disconnect and LOTO 12.47 KV power at Utility POC | | | | | | | |
| Equipment Disassembly - Prep for Shipment | Remove all utility company supplied meters, RTACs, CTs, SCADA equipment and ship to utility company | | | | | | | |
| | Drain and collect battery container AC refrigerant | | | | | | | |
| | Drain and collect inverter AC refrigerant | | | | | | | |
| | Remove and process Stat-X canisters for disposal | | | | | | | |
| | Remove control house AC refrigerant | | | | | | | |
| | Drain and collect transformer oil | | | | | | | |
| | Remove and package UPS/125 VDC lead acid batteries for shipment/recycling | | | | | | | |
| | Remove exterior hoods, steps, hold down bolts from battery enclosures | | | | | | | |
| Loading and Shipment | Disconnect and remove all power and control cables between equipment | | | | | | | |
| | Mobilize crane | | | | | | | |
| | Load battery containers onto trucks for shipment to recycler | | | | | | | |
| | Load Inverter and transformers onto truck for shipment | | | | | | | |
| | Load control enclosure | | | | | | | |
| | Load MV switchgear | | | | | | | |
| | De-mobilize crane | | | | | | | |
| | Ship scrap metal (cables, metal structures, panels) to recycler | | | | | | | |
| De-mobilization | Shipped drained oil to processing facility | | | | | | | |
| | Shipped lead acid batteries to recycler | | | | | | | |
| | Backfill and recompact | | | | | | | |
| | Remove and dispose of fencing | | | | | | | |
| De-mobilization | Final Patch and Grade per plan | | | | | | | |
| | Ensure all tools and equipment are removed. | | | | | | | |
| | Final site cleanup | | | | | | | |
| De-mobilization | Submit final reports and documentation | | | | | | | |

APPENDIX 2, continued Decommissioning Project Schedule-Top Gun Energy Storage

| Decommissioning Plan and Sequence | Task | Week 1 | Week 2 | Week 3 | Week 4 | Week 5 | Week 6 | Week 7 | Week 8 | Week 9 | Week 10 | Week 11 | Week 12 | Week 13 | Week 14 | Week 15 | |
|---|--|--|--------|--------|--------|--------|--------|--------|--------|--------|---------|---------|---------|---------|---------|---------|--|
| Pre-Mobilization Planning | Develop De-energization plans with Customer, including PPE requirements | | | | | | | | | | | | | | | | |
| | Develop equipment lifting and handling plan | | | | | | | | | | | | | | | | |
| | Prepare materials needed at site (tools, pallets, packaging , labels) | | | | | | | | | | | | | | | | |
| | Develop and approve site environmental and safety plans | | | | | | | | | | | | | | | | |
| | Develop and approve security and site access plans (equipment access, gates, doors, staging area, parking) | | | | | | | | | | | | | | | | |
| | Develop loading/pickup plans for batteries, scrap metal | | | | | | | | | | | | | | | | |
| | Complete draft of BOL for hazardous materials | | | | | | | | | | | | | | | | |
| | Obtain Utility agreement on de-energization plan and schedule | | | | | | | | | | | | | | | | |
| | Complete site restoration and drainage plans | | | | | | | | | | | | | | | | |
| | Obtain permits as needed | | | | | | | | | | | | | | | | |
| Mobilization | Physical obstacle to perform work have been removed. | | | | | | | | | | | | | | | | |
| | Setup site security and temporary facilities | | | | | | | | | | | | | | | | |
| | Discuss site specific hazards and safety protocols | | | | | | | | | | | | | | | | |
| | Perform job hazard assessments with Customer and perform work setup | | | | | | | | | | | | | | | | |
| | Confirm laydown/temporary storage areas with Customer | | | | | | | | | | | | | | | | |
| | Confirm emergency response procedures and contacts for fire or injury | | | | | | | | | | | | | | | | |
| | Deliver metal scrap bins and packaging materials | | | | | | | | | | | | | | | | |
| | Deliver forklift and handling equipment to site | | | | | | | | | | | | | | | | |
| | De-energize/LOTO AC side (mains) and DC power (Battery to Inverter) of Energy Storage System | | | | | | | | | | | | | | | | |
| | De-energize/LOTO auxiliary power to battery switchgear | | | | | | | | | | | | | | | | |
| BESS AC Mains and DC Power LOTO | Set up limited approach boundry | | | | | | | | | | | | | | | | |
| | Inspect and outfit in PPE. Minimum HRC3/PPE CAT 3 required during battery string power cable disconnects | | | | | | | | | | | | | | | | |
| | Using insulated tools, remove battery module string power cables. (Note: After all string cables are removed PPE Cat 0 can be used.) | | | | | | | | | | | | | | | | |
| | Disconnect battery string power and communication cables | | | | | | | | | | | | | | | | |
| | Remove Battery Modules and palletize for shipment | | | | | | | | | | | | | | | | |
| | Ship battery modules to recycler | | | | | | | | | | | | | | | | |
| | Auxiliary Power LOTO | Disconnect and lockout Aux power supply from Medium Voltage Switchgear | | | | | | | | | | | | | | | |
| | | Disconnect UPS and 125 VDC power | | | | | | | | | | | | | | | |
| | | Disconnect Fire Control Panel backup batteries | | | | | | | | | | | | | | | |
| | | Disconnect back up generator | | | | | | | | | | | | | | | |
| Utility Disconnect and LOTO | Disconnect and LOTO 12.47 KV power at Utility POC | | | | | | | | | | | | | | | | |
| | Remove all utility company supplied meters,RTACs, CTs, SCADA equipment and ship to utility company | | | | | | | | | | | | | | | | |
| Equipment Disassembly - Prep for Shipment | Drain and collect battery container AC refrigerant | | | | | | | | | | | | | | | | |
| | Drain and collect inverter AC refrigerant | | | | | | | | | | | | | | | | |
| | Remove and process fire suppression agent for disposal | | | | | | | | | | | | | | | | |
| | Remove control house AC refrigerant | | | | | | | | | | | | | | | | |
| | Drain and collect transformer oil | | | | | | | | | | | | | | | | |
| | Remove and package UPS/125 VDC lead acid batteries for shipment/recycling | | | | | | | | | | | | | | | | |
| | Remove exterior hoods, steps, hold down bolts from battery enclosures | | | | | | | | | | | | | | | | |
| | Disconnect and remove all power and control cables between equipment | | | | | | | | | | | | | | | | |
| Loading and Shipment | Mobilize crane | | | | | | | | | | | | | | | | |
| | Load battery containers onto trucks for shipment to recycler | | | | | | | | | | | | | | | | |
| | Load inverter and/or transformers onto truck for shipment | | | | | | | | | | | | | | | | |
| | Load control enclosure | | | | | | | | | | | | | | | | |
| | Load MV switchgear | | | | | | | | | | | | | | | | |
| | De-mobilize crane | | | | | | | | | | | | | | | | |
| | Ship scrap metal (cables, metal structures, panels) to recycler | | | | | | | | | | | | | | | | |
| | Shipped drained oil to processing facility | | | | | | | | | | | | | | | | |
| | Shipped lead acid batteries to recycler | | | | | | | | | | | | | | | | |
| | Site Restoration | Backfill and recompact | | | | | | | | | | | | | | | |
| Remove and dispose of fencing | | | | | | | | | | | | | | | | | |
| Final Patch and Grade per plan | | | | | | | | | | | | | | | | | |
| De-mobilization | Ensure all tools and equipment are removed. | | | | | | | | | | | | | | | | |
| | Final site cleanup | | | | | | | | | | | | | | | | |
| | Submit final reports and documentation | | | | | | | | | | | | | | | | |

APPENDIX 2, continued
Decommissioning Project Schedule- Eastern BESS

| Task | Week 1 | Week 2 | Week 3 | Week 4 | Week 5 | Week 6 | Week 7 | Week 8 | Week 9 |
|--|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| Develop De-energization plans with Customer, including PPE requirements | | | | | | | | | |
| Develop equipment lifting and handling plan | | | | | | | | | |
| Prepare materials needed at site (tools, pallets, packaging , labels) | | | | | | | | | |
| Develop and approve site environmental and safety plans | | | | | | | | | |
| Develop and approve security and site access plans (equipment access, gates, doors, staging area, parking) | | | | | | | | | |
| Develop loading/pickup plans for batteries, scrap metal | | | | | | | | | |
| Complete draft of BOL for hazardous materials | | | | | | | | | |
| Obtain Utility agreement on de-energization plan and schedule | | | | | | | | | |
| Complete site restoration and drainage plans | | | | | | | | | |
| Obtain permits as needed | | | | | | | | | |
| Physical obstacle to perform work have been removed. | | | | | | | | | |
| Setup site security and temporary facilities | | | | | | | | | |
| Discuss site specific hazards and safety protocols | | | | | | | | | |
| Perform job hazard assessments with Customer and perform work setup | | | | | | | | | |
| Confirm laydown/temporary storage areas with Customer | | | | | | | | | |
| Confirm emergency response procedures and contacts for fire or injury | | | | | | | | | |
| Deliver metal scrap bins and packaging materials | | | | | | | | | |
| Deliver forklift and handling equipment to site | | | | | | | | | |
| De-energize/LOTO AC side (mains) and DC power (Battery to Inverter) of Energy Storage System | | | | | | | | | |
| De-energize/LOTO auxiliary power to battery switchgear | | | | | | | | | |
| Set up limited approach boundary | | | | | | | | | |
| Inspect and outfit in PPE. Minimum HRC3/PPE CAT 3 required during battery string power cable disconnects | | | | | | | | | |
| Using insulated tools, remove battery module string power cables. (Note: After all string cables are removed PPE Cat 0 can be used.) | | | | | | | | | |
| Disconnect battery string power and communication cables | | | | | | | | | |
| Remove Battery Modules and palletize for shipment | | | | | | | | | |
| Ship battery modules to recycler | | | | | | | | | |
| Disconnect and lockout Aux power supply from Medium Voltage Switchgear | | | | | | | | | |
| Disconnect UPS and 125 VDC power | | | | | | | | | |
| Disconnect Fire Control Panel backup batteries | | | | | | | | | |
| Disconnect back up generator | | | | | | | | | |
| Disconnect and LOTO 12.47 KV power at Utility POC | | | | | | | | | |
| Remove all utility company supplied meters, RTACs, CTs, SCADA equipment and ship to utility company | | | | | | | | | |
| Drain and collect battery container AC refrigerant | | | | | | | | | |
| Drain and collect inverter AC refrigerant | | | | | | | | | |
| Remove and process fire suppression agent for disposal | | | | | | | | | |
| Remove control house AC refrigerant | | | | | | | | | |
| Drain and collect transformer oil | | | | | | | | | |
| Remove and package UPS/125 VDC lead acid batteries for shipment/recycling | | | | | | | | | |
| Remove exterior hoods, steps, hold down bolts from battery enclosures | | | | | | | | | |
| Disconnect and remove all power and control cables between equipment | | | | | | | | | |
| Mobilize crane | | | | | | | | | |
| Load battery containers onto trucks for shipment to recycler | | | | | | | | | |
| Load Inverter and/or transformers onto truck for shipment | | | | | | | | | |
| Load control enclosure | | | | | | | | | |
| Load MV switchgear | | | | | | | | | |
| De-mobilize crane | | | | | | | | | |
| Ship scrap metal (cables, metal structures, panels) to recycler | | | | | | | | | |
| Shipped drained oil to processing facility | | | | | | | | | |
| Shipped lead acid batteries to recycler | | | | | | | | | |
| Backfill and recompact | | | | | | | | | |
| Remove and dispose of fencing | | | | | | | | | |
| Final Patch and Grade per plan | | | | | | | | | |
| Ensure all tools and equipment are removed. | | | | | | | | | |
| Final site cleanup | | | | | | | | | |
| Submit final reports and documentation | | | | | | | | | |

APPENDIX 2, continued Decommissioning Project Schedule-Escondido BESS

| Decommissioning Plan and Sequence | Task | Week 1 | Week 2 | Week 3 | Week 4 | Week 5 | Week 6 | Week 7 | Week 8 | Week 9 | Week 10 | Week 11 | Week 12 | Week 13 | Week 14 | Week 15 |
|--|--|--------|--------|--------|--------|--------|--------|--------|--------|--------|---------|---------|---------|---------|---------|---------|
| Pre-Mobilization Planning | Develop De-energization plans with Customer, including PPE requirements | | | | | | | | | | | | | | | |
| | Develop equipment lifting and handling plan | | | | | | | | | | | | | | | |
| | Prepare materials needed at site (tools, pallets, packaging , labels) | | | | | | | | | | | | | | | |
| | Develop and approve site environmental and safety plans | | | | | | | | | | | | | | | |
| | Develop and approve security and site access plans (equipment access, gates, doors, staging area, parking) | | | | | | | | | | | | | | | |
| | Develop loading/pickup plans for batteries, scrap metal | | | | | | | | | | | | | | | |
| | Complete draft of BOL for hazardous materials | | | | | | | | | | | | | | | |
| | Obtain Utility agreement on de-energization plan and schedule | | | | | | | | | | | | | | | |
| | Complete site restoration and drainage plans | | | | | | | | | | | | | | | |
| | Obtain permits as needed | | | | | | | | | | | | | | | |
| Physical obstacle to perform work have been removed. | | | | | | | | | | | | | | | | |
| Mobilization | Setup site security and temporary facilities | | | | | | | | | | | | | | | |
| | Discuss site specific hazards and safety protocols | | | | | | | | | | | | | | | |
| | Perform job hazard assessments with Customer and perform work setup | | | | | | | | | | | | | | | |
| | Confirm laydown/temporary storage areas with Customer | | | | | | | | | | | | | | | |
| | Confirm emergency response procedures and contacts for fire or injury | | | | | | | | | | | | | | | |
| | Deliver metal scrap bins and packaging materials | | | | | | | | | | | | | | | |
| BESS AC Mains and DC Power LOTO | Deliver forklift and handling equipment to site | | | | | | | | | | | | | | | |
| | De-energize/LOTO AC side (mains) and DC power (Battery to Inverter) of Energy Storage System | | | | | | | | | | | | | | | |
| | De-energize/LOTO auxiliary power to battery switchgear | | | | | | | | | | | | | | | |
| | Set up limited approach boundary | | | | | | | | | | | | | | | |
| | Inspect and outfit in PPE. Minimum HRC3/PPE CAT 3 required during battery string power cable disconnects | | | | | | | | | | | | | | | |
| Battery Module Removal and Shipment | Using insulated tools, remove battery module string power cables. (Note: After all string cables are removed PPE Cat 0 can be used.) | | | | | | | | | | | | | | | |
| | Disconnect battery string power and communication cables | | | | | | | | | | | | | | | |
| | Remove Battery Modules and palletize for shipment | | | | | | | | | | | | | | | |
| Auxiliary Power LOTO | Ship battery modules to recycler | | | | | | | | | | | | | | | |
| | Disconnect and lockout Aux power supply from Medium Voltage Switchgear | | | | | | | | | | | | | | | |
| | Disconnect UPS and 125 VDC power | | | | | | | | | | | | | | | |
| | Disconnect Fire Control Panel backup batteries | | | | | | | | | | | | | | | |
| Utility Disconnect and LOTO | Disconnect back up generator | | | | | | | | | | | | | | | |
| | Disconnect and LOTO 12.47 KV power at Utility POC | | | | | | | | | | | | | | | |
| Equipment Disassembly - Prep for Shipment | Remove all utility company supplied meters, RTACs, CTs, SCADA equipment and ship to utility company | | | | | | | | | | | | | | | |
| | Drain and collect battery container AC refrigerant | | | | | | | | | | | | | | | |
| | Drain and collect inverter AC refrigerant | | | | | | | | | | | | | | | |
| | Remove and process fire suppression agent for disposal | | | | | | | | | | | | | | | |
| | Remove control house AC refrigerant | | | | | | | | | | | | | | | |
| | Drain and collect transformer oil | | | | | | | | | | | | | | | |
| | Remove and package UPS/125 VDC lead acid batteries for shipment/recycling | | | | | | | | | | | | | | | |
| | Remove exterior hoods, steps, hold down bolts from battery enclosures | | | | | | | | | | | | | | | |
| Loading and Shipment | Disconnect and remove all power and control cables between equipment | | | | | | | | | | | | | | | |
| | Mobilize crane | | | | | | | | | | | | | | | |
| | Load battery containers onto trucks for shipment to recycler | | | | | | | | | | | | | | | |
| | Load Inverter and/or transformers onto truck for shipment | | | | | | | | | | | | | | | |
| | Load control enclosure | | | | | | | | | | | | | | | |
| | Load MV switchgear | | | | | | | | | | | | | | | |
| | De-mobilize crane | | | | | | | | | | | | | | | |
| Site Restoration | Ship scrap metal (cables, metal structures, panels) to recycler | | | | | | | | | | | | | | | |
| | Shipped drained oil to processing facility | | | | | | | | | | | | | | | |
| | Shipped lead acid batteries to recycler | | | | | | | | | | | | | | | |
| De-mobilization | Backfill and recompact | | | | | | | | | | | | | | | |
| | Remove and dispose of fencing | | | | | | | | | | | | | | | |
| | Final Patch and Grade per plan | | | | | | | | | | | | | | | |
| | Ensure all tools and equipment are removed. | | | | | | | | | | | | | | | |
| | Final site cleanup | | | | | | | | | | | | | | | |
| | Submit final reports and documentation | | | | | | | | | | | | | | | |

APPENDIX 3
Project Details-Borrego Microgrid 1
500 KW, 1500 KWH

| Input Data | | |
|-------------------|---|----------|
| Battery | Battery Make/Model | SAFT 24P |
| | Battery Chemistry | NMC |
| | Battery module weight (lbs) | 42 |
| | Battery Module Length (in) | 18 |
| | Battery Module Width (in) | 12 |
| | Battery Module CATL Liquid Cooled? | NO |
| | Number of battery racks per container | 10 |
| | Number of battery modules per rack | 15 |
| Enclosure | Number of battery enclosures (EOL) | 3 |
| | Estimated weight of battery enclosure without battery modules (lbs) | 32000 |
| | Battery enclosures HVAC cooled (wall or roof mount)? | YES |
| | Number of HVAC/Chiller Units per battery enclosure | 1 |
| | Clean agent fire suppression installed in enclosure? | YES |
| Inverter/PCS | Are Inverters/PCS pad mounted? | NO |
| | Is isolation transformer integrated with PCS? | NO |
| | Are inverters/PCS liquid or air cooled? | AIR |
| Transformer | Number of isolation transformers (pad mounted or integrated) | 4 |
| | Estimated weight of empty transformer (lbs) | 8000 |
| | Are there oil filled transformers? | YES |
| | Gallons of oil per transformer | 166 |
| Labor | Average Site Labor Cost (\$/hr) | \$110 |
| Logistics | Shipping distance from site to battery recycling facility (miles) | 2600 |
| Schedule | Estimating Year | 2021 |
| | Decommissioning Year | 2025 |
| | Escalation (average ECI value since 2002) | 1.025 |

APPENDIX 3, continued
Project Details-Borrogo Microgrid 2
1000 KW, 3144 KWH

| Input Data | | |
|-------------------|---|----------|
| Battery | Battery Make/Model | SAFT 24E |
| | Battery Chemistry | NMC |
| | Battery module weight (lbs) | 42 |
| | Battery Module Length (in) | 18 |
| | Battery Module Width (in) | 12 |
| | Battery Module CATL Liquid Cooled? | NO |
| | Number of battery racks per container | 10 |
| | Number of battery modules per rack | 15 |
| Enclosure | Number of battery enclosures (EOL) | 4 |
| | Estimated weight of battery enclosure without battery modules (lbs) | 32000 |
| | Battery enclosures HVAC cooled (wall or roof mount)? | YES |
| | Number of HVAC/Chiller Units per battery enclosure | 1 |
| | Clean agent fire suppression installed in enclosure? | YES |
| Inverter/PCS | Are Inverters/PCS pad mounted? | NO |
| | Is isolation transformer integrated with PCS? | NO |
| | Are inverters/PCS liquid or air cooled? | AIR |
| Transformer | Number of isolation transformers (pad mounted or integrated) | 2 |
| | Estimated weight of empty transformer (lbs) | 8000 |
| | Are there oil filled transformers? | YES |
| | Gallons of oil per transformer | 166 |
| Labor | Average Site Labor Cost (\$/hr) | \$110 |
| Logistics | Shipping distance from site to battery recycling facility (miles) | 2600 |
| Schedule | Estimating Year | 2021 |
| | Decommissioning Year | 2025 |
| | Labor Escalation (average ECI value since 2002) | 1.025 |

APPENDIX 3, continued
Project Details-Top Gun Energy Storage
30 MW , 120 MWH

| Input Data | | |
|-------------------|---|------------|
| Battery | Battery Make/Model | Samsung E3 |
| | Battery Chemistry | NMC |
| | Battery module weight (lbs) | 125 |
| | Battery Module Length (in) | 25 |
| | Battery Module Width (in) | 15 |
| | Battery Module CATL Liquid Cooled? | NO |
| | Number of battery racks per container | 24 |
| | Number of battery modules per rack | 25 |
| Enclosure | Number of battery enclosures (EOL) | 36 |
| | Estimated weight of battery enclosure without battery modules (lbs) | 50000 |
| | Battery enclosures HVAC cooled (wall or roof mount)? | YES |
| | Number of HVAC/Chiller Units per battery enclosure | 2 |
| | Clean agent fire suppression installed in enclosure? | YES |
| Inverter/PCS | Are Inverters/PCS pad mounted? | YES |
| | Number Inverters/PCS to be decommissioned | 36 |
| | Is isolation transformer integrated with PCS? | NO |
| | Estimated weight of inverter/PCS (lbs) | 15500 |
| | Inverter/PCS width (in) | 244 |
| | Inverter/PCS length (in) | 84 |
| | Are inverters/PCS liquid or air cooled? | LIQUID |
| Transformer | Number of isolation transformers (pad mounted or integrated) | 36 |
| | Estimated weight of empty transformer (lbs) | 12000 |
| | Are there oil filled transformers? | YES |
| | Gallons of oil per transformer | 600 |
| Labor | Average Site Labor Cost (\$/hr) | \$110 |
| Logistics | Shipping distance from site to battery recycling facility (miles) | 2600 |
| Schedule | Estimating Year | 2021 |
| | Decommissioning Year | 2041 |
| | Escalation (average ECI value since 2002) | 1.025 |

APPENDIX 3, continued
Project Details-Eastern BESS
7.5 MW, 30 MWH

| Input Data | | |
|-------------------|---|---------------|
| Battery | Battery Make/Model | Samsung (APS) |
| | Battery Chemistry | NMC |
| | Battery module weight (lbs) | 110 |
| | Battery Module Length (in) | 21 |
| | Battery Module Width (in) | 18 |
| | Battery Module CATL Liquid Cooled? | NO |
| | Number of battery racks per container | 50 |
| | Number of battery modules per rack | 16 |
| Enclosure | Number of battery enclosures (EOL) | 6 |
| | Estimated weight of battery enclosure without battery modules (lbs) | 175000 |
| | Battery enclosures HVAC cooled (wall or roof mount)? | YES |
| | Number of HVAC/Chiller Units per battery enclosure | 2 |
| | Clean agent fire suppression installed in enclosure? | YES |
| Inverter/PCS | Are Inverters/PCS pad mounted? | NO |
| | Number Inverters/PCS to be decommissioned | 0 |
| | Is isolation transformer integrated with PCS? | NO |
| | Estimated weight of inverter/PCS (lbs) | 0 |
| | Inverter/PCS width (in) | 0 |
| | Inverter/PCS length (in) | 0 |
| | Are inverters/PCS liquid or air cooled? | AIR |
| Transformer | Number of isolation transformers (pad mounted or integrated) | 3 |
| | Estimated weight of empty transformer (lbs) | 12000 |
| | Are there oil filled transformers? | YES |
| | Gallons of oil per transformer | 460 |
| Labor | Average Site Labor Cost (\$/hr) | \$110 |
| Logistics | Shipping distance from site to battery recycling facility (miles) | 2600 |
| Schedule | Estimating Year | 2021 |
| | Decommissioning Year | 2027 |
| | Escalation (average ECI value since 2002) | 1.025 |

APPENDIX 3, continued
Project Details-Escondido BESS
30MW, 120MWH

| Input Data | | |
|-------------------|---|---------------|
| Battery | Battery Make/Model | Samsung (APS) |
| | Battery Chemistry | NMC |
| | Battery module weight (lbs) | 110 |
| | Battery Module Length (in) | 21 |
| | Battery Module Width (in) | 18 |
| | Battery Module CATL Liquid Cooled? | NO |
| | Number of battery racks per container | 50 |
| | Number of battery modules per rack | 16 |
| Enclosure | Number of battery enclosures (EOL) | 24 |
| | Estimated weight of battery enclosure without battery modules (lbs) | 175000 |
| | Battery enclosures HVAC cooled (wall or roof mount)? | YES |
| | Number of HVAC/Chiller Units per battery enclosure | 2 |
| | Clean agent fire suppression installed in enclosure? | YES |
| Inverter/PCS | Are Inverters/PCS pad mounted? | NO |
| | Number Inverters/PCS to be decommissioned | 0 |
| | Is isolation transformer integrated with PCS? | NO |
| | Estimated weight of inverter/PCS (lbs) | 0 |
| | Inverter/PCS width (in) | 0 |
| | Inverter/PCS length (in) | 0 |
| | Are inverters/PCS liquid or air cooled? | AIR |
| Transformer | Number of isolation transformers (pad mounted or integrated) | 12 |
| | Estimated weight of empty transformer (lbs) | 12000 |
| | Are there oil filled transformers? | YES |
| | Gallons of oil per transformer | 460 |
| Labor | Average Site Labor Cost (\$/hr) | \$110 |
| Logistics | Shipping distance from site to battery recycling facility (miles) | 2600 |
| Schedule | Estimating Year | 2021 |
| | Decommissioning Year | 2027 |
| | Escalation (average ECI value since 2002) | 1.025 |

APPENDIX4 Decommissioning Project Cost Estimates

Pricing Assumptions

In addition to Appendix 3 the following are the cost estimate assumptions used to determine overall project decommissioning costs:

- Battery recycling : Renewance works with all the recyclers in North America and has established recycling rates with them. Renewance selects the recycler based on the lowest cost option for the customer depending on the battery model, chemistry, recycling rates, location and other factors. The rates listed are assuming that the company who is doing the decommissioning adds on a 30% margin to the recyclers recycling rates
 - Battery Recycling (LFP) - \$0.72/lb
 - Battery Recycling (NMC<50000 lbs) - \$0.125/lb
 - Battery Recycling (NMC>50000 lbs) - \$0.00/lb
- Battery Removal Labor = 15 man-minutes/module
 - The batteries have to be removed from the container and packaged before shipping to the recycler. The estimate is based on Renewance's experience decommissioning battery containers with similar battery types (weight & dimensions)
- Scrap Metal/E-Metal Recycle Credit (enclosures, PCS, panels) - \$0.03/lb
 - Renewance's estimate based on BESS decom projects in California
- Transformers : Transformers typically have a long life and there is a strong secondary market for used transformers. The assumptions are based on Renewance's experience in selling used transformers in 2020 & 2021
 - Isolation Transformers Recycle Credit = \$0.04/lb
 - Isolation Transformer Oil Recycling = \$0.21/gallon
- Transportation : Batteries are considered Hazardous material and have to be shipped accordingly. Below assumptions are based on transportation rates obtained from Renewance's preferred freight forwarders who have transported batteries in the past
 - Hazmat Transportation = \$5.50 per mile
 - Standard Transportation = \$0.05/lb
 - Oversize Shipment (custom enclosures) = \$0.10/lb
- Equipment Rental is based on typical rental rates from equipment rental companies in California
 - Crane Rental = \$6500/day
 - Forklift Rental = \$700/day
- Demolition and Site Restoration = 25-35% of total site labor+disposal+recycle
 - Site restoration for BESS decom projects varies drastically depending on how the site is supposed to look post decom. Usually the contract between the BESS owner & the landlord specifies the condition that the site should be left post decommissioning. Site restoration could be as simple as basic clean up to something complicated like completely restoring the site to original condition which could involve things like concrete or road removal, underground cable removal & extensive landscaping. After discussions with the SDGE team and reviewing the sites, this study assumes minimal site restoration which essentially is basic clean up, patching and repairing any cracks/holes left at the site after equipment removal
- Contingencies = 15% on Labor, Rentals, and Logistics. No contingency on battery recycling cost
- T&L (assumes local labor used) = \$0

Decommissioning Project Cost Estimate -Borrego Microgrid 1 Details

| | Item | Units | Labor Cost | Material/Rental/Logistics Cost | Disposal Cost | Recycling Cost/Credits |
|---|--|---------|------------|--------------------------------|---------------|------------------------|
| Battery | Number of Battery Modules (EOL) | 450 | | | | |
| | Total Battery Module Weight (lbs) | 18,900 | | | | |
| | Battery Module Recycling Cost | | | | | \$2,363 |
| | Battery Module Disassembly Prior Recycling Cost | | | | | \$0 |
| | Battery Modules per 40 x 48 Pallet | 21 | | | | |
| | Number of Pallets | 22 | | | | |
| | Number of Truck Loads | 1 | | | | |
| | Hazardous Material Shipping Cost (\$/mi) | \$5.50 | | | | |
| | Battery Logistic Cost | | | | \$14,300 | |
| Battery Module Removal and Packaging Cost (Labor and Materials) | | | \$12,375 | \$550 | | |
| Enclosure | Refrigerant Recovery and Preparation | | | | \$900 | |
| | Fire Suppression System Decommissioning/Agent Recovery | | | | \$1,350 | |
| | Battery Enclosure Prep for Shipment Labor Cost | | \$2,640 | | | |
| | Battery enclosure logistic costs | | | \$4,800 | | |
| | Battery enclosure recycle credit | | | | | (\$2,880) |
| Inverter/PCS | Inverter/PCS Coolant Disposal | | | | \$0 | |
| | Pad mounted Inverter/PCS Prep for Ship Labor Cost | | \$0 | | | |
| | Pad mounted Inverter/PCS logistics cost | | | \$0 | | |
| | Pad mounted Inverter/PCS recycle credit | | | | | \$0 |
| Transformer | Pad mounted transformer prep for ship labor cost | | \$2,200 | | | |
| | Pad mounted transformer logistics cost | | | \$1,600 | | |
| | Pad mounted transformer recycle credit | | | | | (\$1,280) |
| | Transformer Oil recycling cost (\$/gallon) | \$0.21 | | | | \$139 |
| | Oil collection/transport cost per transformer | \$500 | | | \$2,000 | |
| Crane/Forklift | Crane Rental Days | 2 | | | | |
| | Crane Rental Cost /Day | \$6,500 | | | | |
| | Crane Rental Cost | | | \$13,000 | | |
| | Forklift Rental Days | 4.5 | | | | |
| | Forklift Rental Cost /Day | \$700 | | | | |
| | Forklift Rental Cost | | | \$3,150 | | |
| Schedule/Other | Total Project Duration | 28.5 | | | | |
| | Total Onsite Duration | 6.5 | | | | |
| | Mobilization/LOTO | 2 | \$7,040 | | | |
| | Loading and Handling | 3 | | | | |
| | Demobilization | 1 | \$3,520 | | | |
| | Site Mangement | | \$8,125 | | | |
| Project/Logisitcs Management | | \$7,125 | | | | |
| Estimates | Total Cost Estimate (2021 dollars) | | \$43,025 | \$37,400 | \$4,250 | (\$1,658) |
| | Total Cost Estimate in Decommissiong Year | | \$47,492 | \$41,283 | \$4,691 | (\$1,658) |
| | Labor Escalation 1.025 (average ECI value since 2002) | 1.025 | | | | |

\$83,017
\$91,807

NOTES:

All cost estimates in USD

Demolition and Site Cleanu \$11,404.24

No change in recycling cost estimate with time. Increased recycling volume will offset inflation costs.

**Decommissioning Project Cost Estimate -Borrego Microgrid 1
Summary**

| Estimating Year | 2021 | 2025 |
|---|-------------|-------------|
| Project / Site Management, Preparation & Mobilization | \$ 14,165 | \$ 15,636 |
| Site Services (Electrical work, Labor for battery removal, Equipment Rental) | \$ 49,399 | \$ 54,528 |
| Battery Recycling | \$ 2,363 | \$ 2,608 |
| Transportation & Logistics | \$ 15,490 | \$ 17,098 |
| Site Restoration (Foundation Removal, Patch, Grade, Cleanup) | \$ 11,404 | \$ 12,588 |
| Contingency | \$ 13,569 | \$ 14,977 |
| Total | \$ 106,390 | \$ 117,435 |

Decommissioning Project Cost Estimate -Borrego Microgrid 2 Details

| | Item | Units | Labor Cost | Material/Rental/Logistics Cost | Disposal Cost | Recycling Cost/Credits |
|-----------------------|---|---------|------------|--------------------------------|---------------|------------------------|
| Battery | Number of Battery Modules (EOL) | 600 | | | | |
| | Total Battery Module Weight (lbs) | 25,200 | | | | |
| | Battery Module Recycling Cost | | | | | \$3,150 |
| | Battery Module Disassembly Prior Recycling Cost | | | | | \$0 |
| | Battery Modules per 40 x 48 Pallet | 21 | | | | |
| | Number of Pallets | 29 | | | | |
| | Number of Truck Loads | 1.2 | | | | |
| | Hazardous Material Shipping Cost (\$/mi) | \$5.50 | | | | |
| | Battery Logistic Cost | | | | \$17,160 | |
| | Battery Module Removal and Packaging Cost (Labor and Materials) | | | \$16,500 | \$725 | |
| Enclosure | Refrigerant Recovery and Preparation | | | | \$1,200 | |
| | Fire Suppression System Decommissioning/Agent Recovery | | | | \$1,800 | |
| | Battery Enclosure Prep for Shipment Labor Cost | | \$3,520 | | | |
| | Battery enclosure logistic costs | | | \$6,400 | | |
| | Battery enclosure recycle credit | | | | | (\$3,840) |
| Inverter/PCS | Inverter/PCS Coolant Disposal | | | | \$0 | |
| | Pad mounted Inverter/PCS Prep for Ship Labor Cost | | \$0 | | | |
| | Pad mounted Inverter/PCS logistics cost | | | \$0 | | |
| | Pad mounted Inverter/PCS recycle credit | | | | | \$0 |
| Transformer | Pad mounted transformer prep for ship labor cost | | \$1,100 | | | |
| | Pad mounted transformer logistics cost | | | \$800 | | |
| | Pad mounted transformer recycle credit | | | | | (\$640) |
| | Transformer Oil recycling cost (\$/gallon) | \$0.21 | | | | \$70 |
| | Oil collection/transport cost per transformer | \$500 | | | \$1,000 | |
| Crane/Forklift | Crane Rental Days | 2.4 | | | | |
| | Crane Rental Cost /Day | \$6,500 | | | | |
| | Crane Rental Cost | | | \$15,600 | | |
| | Forklift Rental Days | 5.4 | | | | |
| | Forklift Rental Cost /Day | \$700 | | | | |
| | Forklift Rental Cost | | | \$3,780 | | |
| Schedule/Other | Total Project Duration | 29.4 | | | | |
| | Total Onsite Duration | 7.4 | | | | |
| | Mobilization/LOTO | 2 | \$7,040 | | | |
| | Loading and Handling | 3 | | | | |
| | Demobilization | 1 | \$3,520 | | | |
| | Site Mangement | | \$9,250 | | | |
| | Project/Logisitics Management | | \$7,350 | | | |
| Estimates | Total Cost Estimate (2021 dollars) | | \$48,280 | \$44,465 | \$4,000 | (\$1,260) |
| | Total Cost Estimate in Decommissioning Year | | \$53,292 | \$49,081 | \$4,415 | (\$1,260) |
| | Labor Escalation 1.025 (average ECI value since 2002) | 1.025 | | | | |

\$95,485
\$105,528

NOTES:

All cost estimates in USD

No change in recycling cost estimate with time. Increased recycling volume will offset inflation costs.

Demolition and Site Cleanup (2021)

\$12,754.93

**Decommissioning Project Cost Estimate -Borrego Microgrid 2
Summary**

| Year | 2021 | 2025 |
|---|-------------|-------------|
| Project / Site Management, Preparation & Mobilization | \$ 14,390 | \$ 15,884 |
| Site Services (Electrical work, Labor for battery removal, Equipment Rental) | \$ 57,340 | \$ 63,292 |
| Battery Recycling | \$ 3,150 | \$ 3,477 |
| Transportation & Logistics | \$ 19,805 | \$ 21,861 |
| Site Restoration (Foundation Removal, Patch, Grade, Cleanup) | \$ 12,755 | \$ 14,079 |
| Contingency | \$ 15,643 | \$ 17,267 |
| Total | \$ 123,083 | \$ 135,861 |

Decommissioning Project Cost Estimate – Top Gun Energy Storage Details

| | Item | Units | Labor Cost | Material/Rental/Logistics Cost | Disposal Cost | Recycling Cost/Credits |
|-----------------------|---|-----------|-------------|--------------------------------|---------------|------------------------|
| Battery | Number of Battery Modules (EOL) | 21,600 | | | | |
| | Total Battery Module Weight (lbs) | 2,700,000 | | | | |
| | Battery Module Recycling Cost | | | | | \$0 |
| | Battery Module Disassembly Prior Recycling Cost | | | | | \$0 |
| | Battery Modules per 40 x 48 Pallet | 12 | | | | |
| | Number of Pallets | 1800 | | | | |
| | Number of Truck Loads | 72 | | | | |
| | Hazardous Material Shipping Cost (\$/mi) | \$5.50 | | | | |
| | Battery Logistic Cost | | | | \$1,029,600 | |
| | Battery Module Removal and Packaging Cost (Labor and Materials) | | | \$594,000 | \$45,000 | |
| Enclosure | Refrigerant Recovery and Preparation | | | | \$21,600 | |
| | Fire Suppression System Decommissioning/Agent Recovery | | | | \$16,200 | |
| | Battery Enclosure Prep for Shipment Labor Cost | | \$31,680 | | | |
| | Battery enclosure logistic costs | | | \$90,000 | | |
| | Battery enclosure recycle credit | | | | | (\$54,000) |
| Inverter/PCS | Inverter/PCS Coolant Disposal | | | | \$10,620 | |
| | Pad mounted Inverter/PCS Prep for Ship Labor Cost | | \$19,800 | | | |
| | Pad mounted Inverter/PCS logistics cost | | | \$27,900 | | |
| | Pad mounted Inverter/PCS recycle credit | | | | | (\$16,740) |
| Transformer | Pad mounted transformer prep for ship labor cost | | \$19,800 | | | |
| | Pad mounted transformer logistics cost | | | \$21,600 | | |
| | Pad mounted transformer recycle credit | | | | | (\$17,280) |
| | Transformer Oil recycling cost (\$/gallon) | \$0.21 | | | | \$4,536 |
| | Oil collection/transport cost per transformer | \$500 | | | \$18,000 | |
| Crane/Forklift | Crane Rental Days | 13 | | | | |
| | Crane Rental Cost /Day | \$6,500 | | | | |
| | Crane Rental Cost | | | \$84,500 | | |
| | Forklift Rental Days | 32 | | | | |
| | Forklift Rental Cost /Day | \$700 | | | | |
| | Forklift Rental Cost | | | \$22,400 | | |
| Schedule/Other | Total Project Duration | 56 | | | | |
| | Total Onsite Duration | 34 | | | | |
| | Mobilization/LOTO | 2 | \$7,040 | | | |
| | Loading and Handling | 37 | | | | |
| | Demobilization | 1 | \$3,520 | | | |
| | Site Mangement | | \$42,500 | | | |
| | Project/Logisitcs Management | | \$14,000 | | | |
| Estimates | Total Cost Estimate (2021 dollars) | | \$732,340 | \$1,321,000 | \$66,420 | (\$83,484) |
| | Total Cost Estimate in Decommissioning Year | | \$1,200,024 | \$2,164,612 | \$108,837 | (\$83,484) |
| | Labor Escalation 1.025 (average ECI value since 2002) | 1.025 | | | | |

\$2,036,276
\$3,389,990

NOTES:

All cost estimates in USD

No change in recycling cost estimate with time. Increased recycling volume will offset inflation costs.

Demolition and Site Cleanu \$178,819.00

**Decommissioning Project Cost Estimate – Top Gun Energy Storage
Summary**

| Estimating Year | 2021 | 2041 |
|---|--------------|--------------|
| Project / Site Management, Preparation & Mobilization | \$ 21,040 | \$ 34,476 |
| Site Services (Electrical work, Labor for battery removal, Equipment Rental) | \$ 858,736 | \$ 1,407,139 |
| Battery Recycling | \$ - | \$ - |
| Transportation & Logistics | \$ 1,093,320 | \$ 1,791,532 |
| Site Restoration (Foundation Removal, Patch, Grade, Cleanup) | \$ 178,819 | \$ 293,016 |
| Contingency | \$ 322,787 | \$ 528,924 |
| Total | \$ 2,474,702 | \$ 4,055,088 |

Decommissioning Project Cost Estimate – Eastern BESS Details

| | Item | Units | Labor Cost | Material/Rental/Logistics Cost | Disposal Cost | Recycling Cost/Credits |
|-----------------------|---|---------|------------|--------------------------------|---------------|------------------------|
| Battery | Number of Battery Modules (EOL) | 4,800 | | | | |
| | Total Battery Module Weight (lbs) | 528,000 | | | | |
| | Battery Module Recycling Cost | | | | | \$0 |
| | Battery Module Disassembly Prior Recycling Cost | | | | | \$0 |
| | Battery Modules per 40 x 48 Pallet | 12 | | | | |
| | Number of Pallets | 400 | | | | |
| | Number of Truck Loads | 16 | | | | |
| | Hazardous Material Shipping Cost (\$/mi) | \$5.50 | | | | |
| | Battery Logistic Cost | | | | \$228,800 | |
| | Battery Module Removal and Packaging Cost (Labor and Materials) | | | \$132,000 | \$10,000 | |
| Enclosure | Refrigerant Recovery and Preparation (added labor to remove HVAC) | | \$10,560 | | \$3,600 | |
| | Fire Suppression System Decommissioning/Agent Recovery | | | | \$2,700 | |
| | Battery Enclosure Prep for Shipment Labor Cost (oversized) | | \$7,920 | | | |
| | Battery enclosure logistic costs (heavy/oversize load) | | | \$105,000 | | |
| | Battery enclosure recycle credit | | | | | (\$31,500) |
| Inverter/PCS | Inverter/PCS Coolant Disposal | | | | \$0 | |
| | Pad mounted Inverter/PCS Prep for Ship Labor Cost | | \$0 | | | |
| | Pad mounted Inverter/PCS logistics cost | | | \$0 | | |
| | Pad mounted Inverter/PCS recycle credit | | | | | \$0 |
| Transformer | Pad mounted transformer prep for ship labor cost | | \$1,650 | | | |
| | Pad mounted transformer logistics cost | | | \$1,800 | | |
| | Pad mounted transformer recycle credit | | | | | (\$1,440) |
| | Transformer Oil recycling cost (\$/gallon) | \$0.21 | | | | \$290 |
| | Oil collection/transport cost per transformer | \$500 | | | \$1,500 | |
| Crane/Forklift | Crane Rental Days | 3 | | | | |
| | Crane Rental Cost /Day | \$6,500 | | | | |
| | Crane Rental Cost (2x to include load and unload) | | | | \$39,000 | |
| | Forklift Rental Days | 7 | | | | |
| | Forklift Rental Cost /Day | \$700 | | | | |
| | Forklift Rental Cost | | | | \$4,900 | |
| Schedule/Other | Total Project Duration | 31 | | | | |
| | Total Onsite Duration | 9 | | | | |
| | Mobilization/LOTO | 2 | \$7,040 | | | |
| | Loading and Handling | 9 | | | | |
| | Demobilization | 1 | \$3,520 | | | |
| | Site Mangement | | \$11,250 | | | |
| | Project/Logisitcs Management | | \$31,000 | | | |
| Estimates | Total Cost Estimate (2021 dollars) | | \$204,940 | \$389,500 | \$7,800 | (\$32,650) |
| | Total Cost Estimate in Decommissioning Year | | \$237,668 | \$451,701 | \$9,046 | (\$32,650) |
| | Labor Escalation 1.025 (average ECI value since 2002) | 1.025 | | | | |

\$569,590
\$665,764

NOTES:

All cost estimates in USD

No change in recycling cost estimate with time. Increased recycling volume will offset inflation costs.

Demolition and Site Cleanu \$63,031.43

**Decommissioning Project Cost Estimate – Eastern BESS
Summary**

| Estimating Year | 2021 | 2027 |
|---|-------------|-------------|
| Project / Site Management, Preparation & Mobilization | \$ 38,040 | \$ 44,115 |
| Site Services (Electrical work, Labor for battery removal, Equipment Rental) | \$ 208,330 | \$ 241,599 |
| Battery Recycling | \$ - | \$ - |
| Transportation & Logistics | \$ 310,860 | \$ 360,502 |
| Site Restoration (Foundation Removal, Patch, Grade, Cleanup) | \$ 63,031 | \$ 73,097 |
| Contingency | \$ 93,039 | \$ 107,897 |
| Total | \$ 713,300 | \$ 827,210 |

Decommissioning Project Cost Estimate – Escondido BESS Details

| | Item | Units | Labor Cost | Material/Rental/Logistics Cost | Disposal Cost | Recycling Cost/Credits |
|-----------------------|---|-----------|------------|--------------------------------|---------------|------------------------|
| Battery | Number of Battery Modules (EOL) | 19,200 | | | | |
| | Total Battery Module Weight (lbs) | 2,112,000 | | | | |
| | Battery Module Recycling Cost | | | | | \$0 |
| | Battery Module Disassembly Prior Recycling Cost | | | | | \$0 |
| | Battery Modules per 40 x 48 Pallet | 12 | | | | |
| | Number of Pallets | 1600 | | | | |
| | Number of Truck Loads | 64 | | | | |
| | Hazardous Material Shipping Cost (\$/mi) | \$5.50 | | | | |
| | Battery Logistic Cost | | | | \$915,200 | |
| | Battery Module Removal and Packaging Cost (Labor and Materials) | | | \$528,000 | \$40,000 | |
| Enclosure | Refrigerant Recovery and Preparation (added labor to remove HVAC) | | \$42,240 | | \$14,400 | |
| | Fire Suppression System Decommissioning/Agent Recovery | | | | \$10,800 | |
| | Battery Enclosure Prep for Shipment Labor Cost (oversized) | | \$31,680 | | | |
| | Battery enclosure logistic costs (heavy/oversize load) | | | \$420,000 | | |
| | Battery enclosure recycle credit | | | | | (\$126,000) |
| Inverter/PCS | Inverter/PCS Coolant Disposal | | | | \$0 | |
| | Pad mounted Inverter/PCS Prep for Ship Labor Cost | | \$0 | | | |
| | Pad mounted Inverter/PCS logistics cost | | | \$0 | | |
| | Pad mounted Inverter/PCS recycle credit | | | | | \$0 |
| Transformer | Pad mounted transformer prep for ship labor cost | | \$6,600 | | | |
| | Pad mounted transformer logistics cost | | | \$7,200 | | |
| | Pad mounted transformer recycle credit | | | | | (\$5,760) |
| | Transformer Oil recycling cost (\$/gallon) | \$0.21 | | | | \$1,159 |
| | Oil collection/transport cost per transformer | \$500 | | | \$6,000 | |
| Crane/Forklift | Crane Rental Days | 9 | | | | |
| | Crane Rental Cost /Day | \$6,500 | | | | |
| | Crane Rental Cost (2x to include load and unload) | | | \$117,000 | | |
| | Forklift Rental Days | 22 | | | | |
| | Forklift Rental Cost /Day | \$700 | | | | |
| | Forklift Rental Cost | | | \$15,400 | | |
| Schedule/Other | Total Project Duration | 46 | | | | |
| | Total Onsite Duration | 24 | | | | |
| | Mobilization/LOTO | 2 | \$7,040 | | | |
| | Loading and Handling | 31 | | | | |
| | Demobilization | 1 | \$3,520 | | | |
| | Site Mangement | | \$30,000 | | | |
| | Project/Logisitics Management | | \$46,000 | | | |
| Estimates | Total Cost Estimate (2021 dollars) | | \$695,080 | \$1,514,800 | \$31,200 | (\$130,601) |
| | Total Cost Estimate in Decommissioning Year | | \$806,080 | \$1,756,704 | \$36,182 | (\$130,601) |
| | Labor Escalation 1.025 (average ECI value since 2002) | 1.025 | | | | |

\$2,110,479
\$2,468,365

NOTES:

All cost estimates in USD

No change in recycling cost estimate with time. Increased recycling volume will offset inflation costs.

Demolition and Site Cleanu \$208,487.72

**Decommissioning Project Cost Estimate – Escondido BESS
Summary**

| Estimating Year | 2021 | 2027 |
|---|--------------|--------------|
| Project / Site Management, Preparation & Mobilization | \$ 53,040 | \$ 61,510 |
| Site Services (Electrical work, Labor for battery removal, Equipment Rental) | \$ 764,559 | \$ 886,654 |
| Battery Recycling | \$ - | \$ - |
| Transportation & Logistics | \$ 1,243,440 | \$ 1,442,009 |
| Site Restoration (Foundation Removal, Patch, Grade, Cleanup) | \$ 208,488 | \$ 241,782 |
| Contingency | \$ 340,429 | \$ 394,793 |
| Total | \$ 2,609,956 | \$ 3,026,749 |

SL-016628.A_SDGE Decom(Palomar)

Decommissioning Study

**Prepared for
San Diego Gas & Electric Company
Palomar Energy Center**

Prepared by Sargent & Lundy

LEGAL NOTICE

This deliverable was prepared by Sargent & Lundy, L.L.C. (S&L) expressly for the sole use of San Diego Gas & Electric Company (Client) in accordance with the contract agreement between S&L and Client. This deliverable was prepared using the degree of skill and care ordinarily exercised by engineers practicing under similar circumstances. Client acknowledges: (1) S&L prepared this deliverable subject to the particular scope limitations, budgetary and time constraints, and business objectives of Client; (2) information and data provided by others, including Client, may not have been independently verified by S&L; and (3) the information and data contained in this deliverable are time-sensitive and changes in the data, applicable codes, standards, and acceptable engineering practices may invalidate the findings of this deliverable. Any use or reliance upon this deliverable by third parties shall be at their sole risk.

Sargent & Lundy is one of the oldest and most experienced full-service architect engineering firms in the world. Founded in 1891, the firm is a global leader in power and energy with expertise in grid modernization, renewable energy, energy storage, nuclear power, and fossil fuels. Sargent & Lundy delivers comprehensive project services—from consulting, design, and implementation to construction management, commissioning, and operations/maintenance—with an emphasis on quality and safety. The firm serves public and private sector clients in the power and energy, gas distribution, industrial, and government sectors.

55 East Monroe Street • Chicago, IL 60603-5780 USA • 312-269-2000

VERSION LOG

| Version | Issue Date | Sections Modified |
|----------|------------------|-------------------|
| Draft v0 | December 1, 2021 | Initial Issue |
| Final | April 4, 2022 | Section 1.3 |

ISSUE SUMMARY AND APPROVAL PAGE

This is to certify that this document has been prepared, reviewed, and approved in accordance with Sargent & Lundy's Standard Operating Procedure SOP-0405, which is based on ANSI/ISO/ASSQC Q9001 Quality Management Systems.

Contributors

Prepared by:

| Name | Title | Section(s) Prepared | Signature | Date |
|----------------|---------------------------|---|-----------|----------|
| Kyle E. Folken | Energy Consultant | Section ES, Section 1, Section 2, Section 4 | | 4/4/2022 |
| Gregory Amen | Cost Information Division | Section 3, Appendix A | | 4/4/2022 |

Reviewed by:

| Name | Title | Section(s) Reviewed | Signature | Date |
|--------------------|---|-----------------------|-----------|----------|
| Borko Andric | Manager | Section 3, Appendix A | | 4/4/2022 |
| Craig Gitchell | Senior Energy Consultant | All | | 4/4/2022 |
| Robert. P. Charles | Senior Principal Consultant & Project Manager | All | | 4/4/2022 |

Approved by:

| | |
|--|--------------------------------|
| _____ Kevin C. Hopkins Principal Consultant & Project Manager | April 4, 2022 _____ Date |
|--|--------------------------------|

TABLE OF CONTENTS

| | |
|--|----------|
| EXECUTIVE SUMMARY | I |
| METHODOLOGY | I |
| CONCEPTUAL COST ESTIMATE | I |
| SERVICE LIFE BENCHMARKING | II |
| 1. INTRODUCTION | 1 |
| 1.1. SCOPE OF WORK | 1 |
| 1.2. SARGENT & LUNDY BACKGROUND | 1 |
| 1.3. FACILITY DESCRIPTION..... | 2 |
| 2. COST ESTIMATE | 3 |
| 2.1. METHODOLOGY | 3 |
| 2.2. COST ESTIMATE SUMMARY..... | 4 |
| 3. BASIS OF ESTIMATE | 6 |
| 4. SERVICE LIFE BENCHMARKING EVALUATION | 8 |
| 4.1. DESCRIPTION OF FACILITY..... | 8 |
| 4.2. SERVICE-LIFE BENCHMARKING ANALYSIS | 8 |
| 4.3. CONCLUSION | 8 |
| 5. REFERENCES | 9 |

TABLES

| | |
|---|----|
| TABLE ES-1 — PALOMAR COST ESTIMATE SUMMARY..... | II |
| TABLE ES-2 — PALOMAR COST ESTIMATE SUMMARY BY FERC ACCOUNT | II |
| TABLE 2-1 — PALOMAR COST ESTIMATE SUMMARY..... | 4 |
| TABLE 2-2 — PALOMAR COST ESTIMATE SUMMARY BY FERC ACCOUNT | 4 |
| TABLE 3-1 — SCRAP VALUE..... | 7 |
| TABLE 3-2 — SDG&E INTERNAL COSTS IN SUPPORT OF DECOMMISSIONING..... | 7 |
| TABLE 4-1 — LIST OF EQUIPMENT | 8 |
| TABLE 4-2 — PALOMAR BENCHMARKING PEER GROUP 1 CRITERIA..... | 8 |

APPENDIXES

| |
|--|
| APPENDIX A. CONCEPTUAL ESTIMATE OF COST TO DISMANTLE PALOMAR ENERGY CENTER |
| APPENDIX B. CONCEPTUAL COST ESTIMATE — FERC ACCOUNTS |
| APPENDIX C. EXPLANATION OF VARIANCE FROM THE PREVIOUS COST STUDY |

ACRONYMS AND ABBREVIATIONS

| Acronym/Abbreviation | Definition/Clarification |
|----------------------|--------------------------------------|
| CT | combustion turbine |
| FERC | Federal Energy Regulatory Commission |
| G&A | general and administrative |
| GE | General Electric |
| GSU | generator step-up transformer |
| HRSG | heat recovery steam generator |
| Owner | San Diego Gas & Electric Company |
| Palomar | Palomar Energy Center |
| PCB | polychlorinated biphenyl |
| S&L | Sargent & Lundy, L.L.C. |
| SCR | selective catalytic reduction |
| SDG&E | San Diego Gas & Electric Company |
| ST | steam turbine |

EXECUTIVE SUMMARY

Sargent & Lundy (S&L) was contracted by San Diego Gas & Electric Company (“SDG&E” or the “Owner”) to perform an independent conceptual cost estimate for the dismantlement of Palomar Energy Center (Palomar) and estimate the average service life of the facility’s peer group. Palomar is a 2x1 natural gas-fired, combined-cycle project (588 MW) in Escondido, California. The work scope included updating the 2016 conceptual demolition cost estimate and report as well as conducting a benchmarking analysis for the facility.

METHODOLOGY

The S&L methodology for developing the cost estimate consist of three elements: (1) S&L experience in developing plant demolition costs and the existing S&L database for numerous other projects; (2) use of the unit cost factor methodology; and (3) quotes from previous projects for similar activities. The cost estimate was developed based on the drawings, documents, and data provided by SDG&E. These drawings and documents were used to estimate the building foundation sizes, building volumes, and quantities of steel, piping, valves, and other equipment. A site walkdown was performed to conduct a review of the site for dismantlement and determine any specific site-unique requirements. This site walkdown was performed in 2016; however, recent discussions with the Owner and facility management confirmed that no significant modifications have occurred since that time. This information was used with unit cost factors developed by S&L based on industry data and S&L experience. Unit cost factors for concrete removal, steel removal, cutting costs, etc. were developed from labor and material cost information. S&L estimated the quantities of recoverable metals that could be recovered and sold for scrap. The estimate includes the value of scrap metals; however, equipment is assumed to have no resale or other salvage value besides the value of scrap metal at the end of its life.

The benchmarking analysis considers publicly available data to determine the average service life of similar facilities.

CONCEPTUAL COST ESTIMATE

The summary of the cost estimate for decommissioning Palomar is shown in Table ES-1. The cost estimate broken into FERC accounts is shown in Table ES-2. All costs are in 2021 U.S. dollars, and the total is the same in both tables: \$12,014,670. The decommissioning costs are expected to increase by the end of the service life of the asset due to escalation and other factors.

Table ES-1 — Palomar Cost Estimate Summary

| Description | Total Cost | Subtotal |
|--|----------------------|-------------|
| Demolition Cost | \$7,754,704 | – |
| Labor | – | \$5,180,119 |
| Subcontracts | – | \$372,500 |
| Equipment | – | \$1,440,078 |
| Material | – | \$762,007 |
| General Condition (Decommissioning Contractor Indirect) Costs | \$3,195,069 | – |
| Scrap Value | (\$1,880,519) | – |
| Subtotal Demolition Contractor Costs | \$9,069,254 | – |
| Project Indirect Costs | \$1,133,000 | – |
| Engineering | – | \$231,000 |
| SDG&E Internal Costs | – | \$902,000 |
| Contingency Cost | \$1,812,416 | – |
| Total Project Cost | \$12,014,670 | – |

Table ES-2 — Palomar Cost Estimate Summary by FERC Account

| FERC No. | Description | Total Cost |
|----------|---|---------------------|
| 311 | Other Production – Structures & Improvements | \$1,926,247 |
| 312 | Boiler Plant Equipment | \$3,334,916 |
| 314 | Turbo Generator Units | \$3,052,089 |
| 315 | Accessory Electrical Equipment | \$484,650 |
| 316 | Miscellaneous Power Plant Equipment | \$165,083 |
| 341 | Other Production – Structures and Improvements | \$636,144 |
| 342 | Other Production – Fuel Holders, Producers, and Accessories | \$346,465 |
| 344 | Other Production – Generators | \$1,732,669 |
| 345 | Other Production – Accessory Electric Equipment | \$336,407 |
| – | General Conditions | Included Above |
| – | Engineering | Included Above |
| – | Contingency | Included Above |
| – | Total Project Cost | \$12,014,670 |

1. INTRODUCTION

1.1. SCOPE OF WORK

Sargent & Lundy (S&L) was contracted by San Diego Gas & Electric Company (“SDG&E” or the “Owner”) to perform a conceptual cost estimate for the dismantlement of the Palomar Energy Center (Palomar) in Escondido, California and estimate the average service life of the facility’s peer group. The work scope included updating the 2016 conceptual demolition cost estimate report and performing a benchmarking analysis.

1.2. SARGENT & LUNDY BACKGROUND

S&L has been dedicated to providing complete engineering and environmental services exclusively to the power industry since 1891. Through work with various utilities, lending institutions, and developers over the years, the Sargent & Lundy Consulting Group has become one of the premier power project consultants in the power industry. This commitment to quality is proven by the successful completion of the ISO 9001 certification audit. S&L’s experience encompasses independent engineer services—including decommissioning cost estimation and average service life evaluation—for both global and domestic electric power assets.

S&L has extensive decommissioning and related services experience, including power plant dismantling, demolition, and layup for fossil fuel, renewable energy, and nuclear plants. This includes decommissioning cost estimates, decommissioning studies, and related services for 18 clients at more than 70 stations. S&L also has extensive experience providing clients with testimony services.

Having engineered over 958 power plant units, S&L has both the benefit of extensive design experience—supported with feedback from operating plants—and individuals with extensive plant operations experience to support consulting services such as those performed for Palomar.

1.3. FACILITY DESCRIPTION

Palomar, located in northern San Diego County, Escondido, California, consists of two GE Frame 7FA (PG7241FA) combustion turbine (CT) generators and a single steam turbine (ST) generator. Each CT exhausts into a separate heat recovery steam generator (HRSG), each of which has a selective catalytic reduction (SCR) system for NO_x reduction and an oxidation catalyst to reduce volatile organic compounds (VOCs) and carbon monoxide (CO). Each HRSG is also provided with natural gas-fired duct burners that provide additional steam production to increase the net plant generating output during peak load periods. The steam produced by the two HRSGs is supplied to a single ST generator. The turbine exhaust steam is condensed in a steam surface condenser by transferring the heat to the circulating cooling water. The heat in the circulating water is then rejected to the atmosphere in an evaporative cooling tower.

The nameplate rating (i.e., the full-load continuous rating of a generator under specified conditions as designated by the manufacturer) of Palomar is 588 MW following an uprate. Palomar is configured so that it may operate using either of the CTs alone or one CT with the ST. The CTs were up-rated to 176 MW nominal each, and the steam turbine was up-rated to 236 MW nominal. This gives Palomar operational flexibility to respond to a varying load demand while optimizing efficiency. With two CTs feeding two HRSGs feeding one steam turbine, this configuration is referred to as a 2x1 combined-cycle plant and is typical of modern high-efficiency plant installations of this capacity in use by utilities and merchant generators throughout the United States and abroad.

The CTs are capable of producing more power, and are more efficient, with colder inlet temperatures. As such, Palomar is equipped with a chiller system that can reduce the turbine inlet temperature to approximately 50°F. This reduction in temperature allows the plant to increase output on hot summer days when the system electrical demand is the highest.

2. COST ESTIMATE

2.1. METHODOLOGY

The methodology used for developing the cost estimate includes a combination of stochastic and deterministic methods. Deterministic methods were used based on the quantity and size of equipment (e.g., the number of foundations, linear feet of piping, equipment, etc.). Stochastic methods were also used if quantitative information (e.g., fire lines and hydrants, miscellaneous electrical equipment, etc.) was unavailable.

The cost estimate was developed based on drawings, documents, and data provided by the Owner. These drawings and documents were used to estimate the building foundation sizes, building volumes, steel quantities, and the quantity of piping, valves, and other equipment.

The S&L methodology for developing the cost estimate consist of three elements: (1) S&L experience in developing plant demolition cost and the existing S&L database for numerous other projects; (2) use of the unit cost factor methodology; and (3) quotes for previous projects for similar activities.

Cost estimates were created using the S&L cost model format and the S&L cost database. The estimates include both summaries and details for each type of work performed, indirect costs, and contingencies. The cost estimate database report lists costs by buildings, plant systems, and several other categories.

An inventory of plant piping, valves, equipment, HVAC ducts, concrete, galleries, cable tray, and other equipment was developed based on a review of drawings and a site walkdown to conduct a review for dismantlement and determine any specific site-unique requirements. This information was used with unit cost factors developed by S&L based on industry data and S&L experience. Unit cost factors for concrete removal, steel removal, cutting costs, and other tasks were developed from labor and material cost information. S&L also estimated the quantities of recoverable metals that could be recovered and sold for scrap. The estimate includes the value of scrap metals; however, equipment is assumed to have no resale or other salvage value besides the value of scrap metal at the end of its life.

S&L worked from site general arrangement drawings and company documentation for the facilities, including information about any existing metal cleaning storage ponds, asbestos inventories, biphenyl (PCB) inventories, or sludge ponds. S&L relied on SDG&E to identify the location of environmental issues that need to be considered in the estimates, since S&L's scope of work excludes doing a detailed survey and testing program to identify such problems.

2.2. COST ESTIMATE SUMMARY

The summary of the cost estimate for decommissioning Palomar is shown in Table 2-1. The commercial and technical basis for the estimate is described in Section 0. The detailed estimate is included in Appendix A. The summary breakdown into FERC accounts is shown in Table 2-2, and the detailed allocation of FERC accounts is shown in Appendix B. All costs are in 2021 U.S. dollars. The decommissioning costs are expected to increase by the end of the service life of the asset due to escalation and other factors.

The 2021 cost estimate format was changed to be consistent with S&L's current standards. The variance between the 2021 and 2016 cost estimate is shown in Appendix C.

Table 2-1 — Palomar Cost Estimate Summary

| Description | Total Cost | Subtotal |
|--|----------------------|-------------|
| Demolition Cost | \$7,754,704 | – |
| Labor | – | \$5,180,119 |
| Subcontracts | – | \$372,500 |
| Equipment | – | \$1,440,078 |
| Material | – | \$762,007 |
| General Condition (Decommissioning Contractor Indirect) Costs | \$3,195,069 | – |
| Scrap Value | (\$1,880,519) | – |
| Subtotal Demolition Contractor Costs | \$9,069,254 | – |
| Project Indirect Costs | \$1,133,000 | – |
| Engineering | – | \$231,000 |
| SDG&E Internal Costs | – | \$902,000 |
| Contingency Cost | \$1,812,416 | – |
| Total Project Cost | \$12,014,670 | – |

Table 2-2 — Palomar Cost Estimate Summary by FERC Account

| FERC No. | Description | Total Cost |
|----------|--|-------------|
| 311 | Other Production – Structures & Improvements | \$1,926,247 |
| 312 | Boiler Plant Equipment | \$3,334,916 |
| 314 | Turbo Generator Units | \$3,052,089 |
| 315 | Accessory Electrical Equipment | \$484,650 |
| 316 | Miscellaneous Power Plant Equipment | \$165,083 |
| 341 | Other Production – Structures and Improvements | \$636,144 |

| FERC No. | Description | Total Cost |
|----------|---|---------------------|
| 342 | Other Production – Fuel Holders, Producers, and Accessories | \$346,465 |
| 344 | Other Production – Generators | \$1,732,669 |
| 345 | Other Production – Accessory Electric Equipment | \$336,407 |
| – | General Conditions | Included Above |
| – | Engineering | Included Above |
| – | Contingency | Included Above |
| – | Total Project Cost | \$12,014,670 |

3. BASIS OF ESTIMATE

The basis for the cost estimate is as follows:

1. Construction Labor Wages

Craft labor rates (or craft hourly rates) for the cost estimate are based on the prevailing wages for San Diego, California as published in *R.S. Means Labor Rates for the Construction Industry* (2021). These prevailing rates are representative of union or non-union rates, whichever is prevailing in the area. Costs have been added to cover social security, workmen's compensation, and federal and state unemployment insurance. The resulting burdened craft rates were then used to develop typical crew rates applicable to the task being performed.

2. Labor Work Schedule and Incentives

- The labor estimate is based on a 40-hour workweek with no per diem or other labor incentives.
- An allowance for arrival time is included if workers arrive and are then sent home.

3. Quantity Sources

Quantities of pieces of equipment and/or bulk material commodities used in this cost estimate were developed from supplied engineering information from the sites and the S&L database.

4. General Conditions Cost

Allowances were included for the decommissioning contractor indirect costs in the cost estimate for the following:

- Labor supervision (additional compensation for labor foreman/supervisors)
- Construction management
- Field office expenses
- Safety
- Temporary facilities
- Mobilization/demobilization
- Legal expenses/claims
- Small tools and consumables
- General liability insurance
- Construction equipment mobilization/demobilization
- Freight on material
- Contractor general and administrative costs (7% of labor [direct labor, additional labor cost, site overheads, and other construction indirect cost], material [direct material cost and freight cost], and equipment)

- Contractor's profit (10% of labor [direct labor, additional labor cost, site overheads, and other construction indirect cost], material [direct material cost and freight cost], and equipment)

5. Scrap

Scrap metals are a globally traded commodity and part of the larger metals industry. The value of scrap metal is subject to constantly changing economic conditions, as such the price of mixed steel, stainless steel, copper, and aluminum can vary greatly over time as a result of global supply and demand. The value of scrap for this study was determined by a 12-month average from *Scrap Metals MarketWatch*¹ (November 2020–October 2021) for the West Coast (Zone 1) of the United States. The values obtained are delivered prices to the recycler. Transportation cost to the recycler is estimated at \$30/ton, resulting in the values shown in Table 3-1:

Table 3-1 — Scrap Value

| Commodity | Scrap Value (\$/ton) |
|--------------------------|----------------------|
| Carbon Steel | 175 |
| #2 Copper | 6,145 |
| #2 Insulated Copper Wire | 2,440 |

Note: 1 ton = 2000 lbs.

6. Project Schedule

Palomar has an 18-month construction schedule.

7. Indirect Expenses

- Engineering is included to cover preparation of the decommissioning work specification, the engineering required to place the plant in a safe shutdown, and any unique engineering required during demolition.
- SDG&E internal costs are included to cover costs in support of decommissioning the facility.

Table 3-2 — SDG&E Internal Costs in Support of Decommissioning

| Activity | Estimated Cost |
|--|------------------|
| Labor to prepare the site for demolition, including drain oils, drain reagents, de-energization of the power buses, etc. | \$602,000 |
| Site security | \$80,000 |
| Subcontracts to remove chemicals, oils, and reagents from the site | \$100,000 |
| SDG&E project management, permitting, and procurement | \$120,000 |
| Total | \$902,000 |

¹ www.americanrecycler.com

8. Escalation Rates

Escalation rates were excluded from the estimates.

9. Sales and Use Taxes

Sales and use taxes were excluded from the estimates.

10. Contingency

- A 15% contingency is applied for labor, material, equipment, subcontracting, and indirect costs. General conditions (indirect demolition contractor costs) are allocated across labor, material, and equipment.
- There is no contingency on scrap value.

11. Contract Basis for Estimate

The contracting strategy is a multiple lump sum for the estimate.

12. Assumptions

- The facility will be in safe-shutdown mode and ready for a decommissioning contractor to start work.
- All chemicals and lubricating oils will be removed from the facilities to be demolished by the utility before demolition.
- No extraordinary environmental costs for demolition will be needed.
- There will be no PCBs on site at the time of demolition.
- Switchyards within the plant boundaries are not part of the scope, nor are access roads to these facilities.
- All items above grade and to a depth of one foot will be demolished. Any other items buried more than one foot deep will remain in place.
- Underground piping will be abandoned in place.
- Underground piping larger than four feet in diameter will be filled with sand or slurry and capped at the ends to prevent collapse (none noted at this site). Non-metal pipe will be collapsed.
- All demolished materials are considered debris, except for organic combustibles and non-embedded metals which have scrap value.
- The basis for salvage estimating is for scrap value only. No resale of equipment or material is included.
- Handling onsite and offsite disposal of hazardous materials will be performed in compliance with methods approved by SDG&E's Environmental Services Department.
- All borrow (fill) material is assumed to be from offsite sources.
- Catalyst is assumed to be removed and returned to the original equipment manufacturer before demolition.

4. REFERENCES

1. Sargent & Lundy Cost Data Base
2. RSMeans Cost Data, 2021.
3. Engineering Drawings, Equipment Lists, O&M Records and other information provided by the San Diego Gas & Electric.
4. 2020 Form EIA-860 Data – Schedule 3, “Generator Data” (Retired & Canceled Units Only)
5. *Scrap Metals MarketWatch*, West Coast (Zone 1), www.americanrecycler.com

**APPENDIX A. CONCEPTUAL ESTIMATE OF COST
TO DISMANTLE PALOMAR ENERGY CENTER**

**SAN DIEGO GAS & ELECTRIC
PALOMAR ENERGY CENTER
DECOMMISSIONING STUDY**

| | |
|-------------------------|------------|
| Estimator | GA |
| Labor rate table | 21CASAN |
| Project No. | A14520.001 |
| Estimate Date | 11/30/21 |
| Reviewed By | BA |
| Approved By | BA |
| Estimate No. | 30611C |

**SAN DIEGO GAS & ELECTRIC
 PALOMAR ENERGY CENTER
 DECOMMISSIONING STUDY**



| Group | Description | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|----------|------------------------|------------------|--------------------|----------------|---------------|------------------|------------------|------------------|
| 10.00.00 | WHOLE PLANT DEMOLITION | | | | 57,055 | 4,734,896 | 1,314,594 | 6,049,490 |
| 18.00.00 | SCRAP VALUE | | (1,880,519) | | 0 | | | (1,880,519) |
| 21.00.00 | CIVIL WORK | 372,500 | | 334,807 | 4,169 | 310,245 | 102,647 | 1,120,198 |
| 22.00.00 | CONCRETE | | | 427,200 | 1,780 | 134,977 | 22,837 | 585,015 |
| | TOTAL DIRECT | 372,500 | (1,880,519) | 762,007 | 63,004 | 5,180,119 | 1,440,078 | 5,874,185 |

**SAN DIEGO GAS & ELECTRIC
 PALOMAR ENERGY CENTER
 DECOMMISSIONG STUDY**



Estimate Totals

| Description | Amount | Totals | Hours |
|-------------------------------------|--------------------|-------------------|------------|
| Labor | 5,180,119 | | 63,004 hrs |
| Material | 762,007 | | |
| Subcontract | 372,500 | | |
| Construction Equipment | 1,440,078 | | hrs |
| Scrap Value | <u>(1,880,519)</u> | | |
| | 5,874,185 | 5,874,185 | |
| General Conditions | | | |
| Additional Labor Costs | | | |
| 90-1 Labor Supervision | 310,807 | | |
| 90-2 Show-up Time | 103,602 | | |
| 90-3 Cost Due To OT 5-10's | | | |
| 90-4 Cost Due To OT 6-10's | | | |
| 90-5 Per Diem | | | |
| Site Overheads | | | |
| 91-1 Construction Management | 559,453 | | |
| 91-2 Field Office Expenses | 123,080 | | |
| 91-3 Material&Quality Control | | | |
| 91-4 Site Services | | | |
| 91-5 Safety | 110,520 | | |
| 91-6 Temporary Facilities | 84,086 | | |
| 91-7 Temporary Utilities | | | |
| 91-8 Mobilization/Demob. | 88,617 | | |
| 91-9 Legal Expenses/Claims | 13,091 | | |
| Other Construction Indirects | | | |
| 92-1 Small Tools & Consumables | 55,945 | | |
| 92-2 Scaffolding | | | |
| 92-3 General Liability Insur. | 55,945 | | |
| 92-4 Constr. Equip. Mob/Demob | 144,008 | | |
| 92-5 Freight on Material | 38,100 | | |
| 92-6 Freight on Scrap | | | |
| 92-7 Sales Tax | | | |
| 92-8 Contractors G&A | 620,864 | | |
| 92-9 Contractors Profit | <u>886,951</u> | | |
| | 3,195,069 | 9,069,254 | |
| Project Indirect Costs | | | |
| 93-1 Engineering Services | 231,000 | | |
| 93-2 CM Support | | | |
| 93-3 Start-Up/Commissioning | | | |
| 93-4 Start-Up/Spare Parts | | | |
| 93-5 Excess Liability Insur. | | | |
| 93-6 Sales Tax On Indirects | | | |
| 93-7 SDG&E Internal Costs | 902,000 | | |
| 93-8 EPC Fee | <u></u> | | |
| | 1,133,000 | 10,202,254 | |
| Contingency | | | |
| 94-1 Contingency on Const Eq | 274,335 | | |
| 94-3 Contingency on Material | 140,419 | | |
| 94-4 Contingency on Labor | 1,171,837 | | |
| 94-5 Contingency on Subcontr. | 55,875 | | |
| 94-6 Contingency on Scrap | | | |
| 94-7 Contingency on Indirect | <u>169,950</u> | | |
| | 1,812,416 | 12,014,670 | |
| Escalation | | | |
| 96-1 Escalation on Const Equip | | | |
| 96-3 Escalation on Material | | | |
| 96-4 Escalation on Labor | | | |
| 96-5 Escalation on Subcontract | | | |
| 96-6 Escalation on Scrap | | | |
| 96-7 Escalation on Indirects | | 12,014,670 | |
| 98 Interest During Constr | | 12,014,670 | |
| Total | | 12,014,670 | |

**SAN DIEGO GAS & ELECTRIC
 PALOMAR ENERGY CENTER
 DECOMMISSIONING STUDY**



| Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|-----------------|-----------------|---|--|-------------|------------------|-------------|---------------|---------------|------------------|----------------|------------------|
| 10.00.00 | | WHOLE PLANT DEMOLITION | | | | | | | | | |
| | 10.21.00 | CIVIL WORK | | | | | | | | | |
| | | PAVED SURFACES, 6 IN THICK | STEAM PLANT | 3,744.00 SY | - | - | | 449 | 39,919 | 20,748 | 60,666 |
| | | PAVED SURFACES, 6 IN THICK | OTHER PRODUCTION | 3,744.00 SY | - | - | | 449 | 39,919 | 20,748 | 60,666 |
| | | CIVIL WORK | | | | | | 899 | 79,837 | 41,496 | 121,333 |
| | 10.22.00 | CONCRETE | | | | | | | | | |
| | | COMBUSTION TURBINE AREA MAT @ NORTH END | U-1, 2004-005-SF-005 | 33.00 CY | - | - | | 37 | 3,313 | 816 | 4,129 |
| | | COMBUSTION TURBINE AREA MAT @ NORTH END | U-2, 2004-005-SF-005 | 30.00 CY | - | - | | 34 | 3,012 | 742 | 3,754 |
| | | PEECC & ACCESSORY MODULE FDN | U-1, 2004-005-SF-006 | 389.00 CY | - | - | | 438 | 39,054 | 9,623 | 48,677 |
| | | COMBUSTION TURBINE AREA MAT AT EAST END | U-1, 2004-005-SF-007A | 63.00 CY | - | - | | 71 | 6,325 | 1,559 | 7,883 |
| | | COMBUSTION TURBINE AREA MAT AT EAST END | U-2, 2004-005-SF-007B | 121.00 CY | - | - | | 136 | 12,148 | 2,993 | 15,141 |
| | | STEAM TURBINE GEN FDN BASE MAT | U-3, 2004-005-SF-009 | 1,322.00 CY | - | - | | 1,487 | 132,722 | 32,705 | 165,427 |
| | | COOLING TOWER FDN | U-3, 2004-005-SF-021A | 1,544.00 CY | - | - | | 1,737 | 155,010 | 38,197 | 193,207 |
| | | HRSG / STACK FDN | U-1, 2004-005-SF-025 | 948.00 CY | - | - | | 1,067 | 95,174 | 23,452 | 118,627 |
| | | HRSG / STACK FDN | U-2, 2004-005-SF-025 | 948.00 CY | - | - | | 1,067 | 95,174 | 23,452 | 118,627 |
| | | HRSG EAST AREA MAT | U-1, 2004-005-SF-028 | 197.00 CY | - | - | | 222 | 19,778 | 4,874 | 24,651 |
| | | HRSG EAST AREA MAT | U-2, 2004-005-SF-028 | 160.00 CY | - | - | | 180 | 16,063 | 3,958 | 20,021 |
| | | CTG STEP-UP TRANSFORMER AND AUX TRNSFORMER FDNS | U-1, 2004-005-SF-029A | 250.00 CY | - | - | | 281 | 25,099 | 6,185 | 31,283 |
| | | CTG STEP-UP TRANSFORMER AND AUX TRNSFORMER FDNS | U-2, 2004-005-SF-029B | 241.00 CY | - | - | | 271 | 24,195 | 5,962 | 30,157 |
| | | STG ROTOR REMOVAL PLATFORM FDN | U-3, 2004-005-SF-030 | 35.00 CY | - | - | | 39 | 3,514 | 866 | 4,380 |
| | | STG STEP-UP TRANSFORMER AND AUX TRNSFORMER FDNS | U-3, 2004-005-SF-031 | 180.00 CY | - | - | | 203 | 18,071 | 4,453 | 22,524 |
| | | 5 KV SWITCHGEAR MODULE FDN | U-3, 2004-005-SF-033 | 116.00 CY | - | - | | 131 | 11,646 | 2,870 | 14,516 |
| | | EXCITATION XFMR & ISOLATION XFMR | U-2, 2004-005-SF-034 | 49.00 CY | - | - | | 55 | 4,919 | 1,212 | 6,132 |
| | | AQUEOUS AMMONIA STORAGE TANK AND UNLOADING AREA FDNS | U-2, 2004-005-SF-037 | 196.00 CY | - | - | | 221 | 19,677 | 4,849 | 24,526 |
| | | FUEL GAS COMPRESSOR FDN | U-0, 2004-005-SF-040 | 161.00 CY | - | - | | 181 | 16,164 | 3,983 | 20,147 |
| | | FINGER RACK AREA MAT | U-1, 2004-005-SF-047A | 248.00 CY | - | - | | 279 | 24,898 | 6,135 | 31,033 |
| | | FINGER RACK AREA MAT | U-2, 2004-005-SF-047B | 236.00 CY | - | - | | 266 | 23,893 | 5,838 | 29,532 |
| | | WEST AREA MAT @ TUR-CTG1-01 | U-1, 2004-005-SF-053 | 142.00 CY | - | - | | 160 | 14,256 | 3,513 | 17,769 |
| | | WEST AREA MAT @ TUR-CTG2-01 | U-2, 2004-005-SF-054 | 143.00 CY | - | - | | 161 | 14,356 | 3,538 | 17,894 |
| | | COOLING TOWER CHEMICAL FEED BLDG AND UNLOADING CONTAINMENT FDNS | U-2, 2004-005-SF-060A & B | 239.00 CY | - | - | | 269 | 23,994 | 5,913 | 29,907 |
| | | STG WEST AREA MAT | U-3, 2004-005-SF-061 | 49.00 CY | - | - | | 55 | 4,919 | 1,212 | 6,132 |
| | | TRAVELLING TOWER CONSTRUCTION CRANE FDN | U-0 2004-005-SF-078 | 117.00 CY | - | - | | 132 | 11,746 | 2,894 | 14,641 |
| | | STATIONARY TOWER CONSTRUCTION CRANE FDN | U-0 2004-005-SF-079 | 162.00 CY | - | - | | 182 | 16,264 | 4,008 | 20,272 |
| | | STG NORTH ARE MAT | U-0 2004-005-SF-080A | 341.00 CY | - | - | | 384 | 34,235 | 8,436 | 42,671 |
| | | RO PERMEATE STORAGE TANK FDN | U-0 2004-005-SF-082 | 25.00 CY | - | - | | 28 | 2,510 | 618 | 3,128 |
| | | RAW WATER STORAGE TANK FDN | U-0 2004-005-SF-089 | 57.00 CY | - | - | | 64 | 5,723 | 1,410 | 7,133 |
| | | DEMIN WATER STORAGE TANK FDN | U-0 2004-005-SF-090 | 52.00 CY | - | - | | 59 | 5,221 | 1,286 | 6,507 |
| | | THERMAL ENERGY STORAGE (TES) TANK FDN | U-0 2004-005-SF-090 | 364.00 CY | - | - | | 410 | 36,544 | 9,005 | 45,549 |
| | | MISC FDNS | U-0 2004-005-SF, 50% Steam Plant | 278.00 CY | - | - | | 313 | 27,910 | 6,877 | 34,787 |
| | | MISC FDNS | U-0 2004-005-SF, 50% Steam Plant | 278.00 CY | - | - | | 313 | 27,910 | 6,877 | 34,787 |
| | | ADMINISTRATION/WAREHOUSE/SHOP WT BLDG | U-0, 130'X34'X2'+100'X11'X2' - 50% Steam Plant | 205.00 CY | - | - | | 231 | 20,581 | 5,071 | 25,652 |
| | | ADMINISTRATION/WAREHOUSE/SHOP WT BLDG | U-0, 130'X34'X2'+100'X11'X2' - 50% Steam Plant | 205.00 CY | - | - | | 231 | 20,581 | 5,071 | 25,652 |
| | | CHILLER PREFAB FLDG | U-3, S200 | 467.00 CY | - | - | | 525 | 46,884 | 11,553 | 58,437 |
| | | TOOL STORAGE BLDG (#127) | 50% Steam Plant | 67.00 CY | - | - | | 75 | 6,726 | 1,658 | 8,384 |
| | | TOOL STORAGE BLDG (#127) | 50% Other Plant | 67.00 CY | - | - | | 75 | 6,726 | 1,658 | 8,384 |
| | | WATER LAB | U-0, 40'X35'X2' | 104.00 CY | - | - | | 117 | 10,441 | 2,573 | 13,014 |
| | | FAB SHOP | U-0, 20'X40'X2' | 59.00 CY | - | - | | 66 | 5,923 | 1,460 | 7,383 |
| | | SWITCHGEAR BUILDING | U-0, 5'X35'X2' | 13.00 CY | - | - | | 15 | 1,305 | 322 | 1,627 |
| | | NEW CT2 LCI W/PDC BUILDING | U-2, 12'X20'X2' | 17.00 CY | - | - | | 19 | 1,707 | 421 | 2,127 |
| | | DIESEL GENERATOR FDN | U-0, 12'X26'X1.5' | 18.00 CY | - | - | | 20 | 1,807 | 445 | 2,252 |
| | | GANTRY CRANE FDN | | 95.00 CY | - | - | | 107 | 9,538 | 2,350 | 11,888 |
| | | THERMAL ENERGY STORAGE (TES) TANK (#119) | U-0 3600000 GALLON, 120' DAI X 48' HIGH - CONCRETE | 1,052.00 CY | - | - | | 1,184 | 105,616 | 26,025 | 131,641 |
| | | TURBINE PEDESTAL | U-1, 2004-005-SF-001 | 742.00 CY | - | - | | 1,336 | 119,189 | 29,370 | 148,559 |
| | | TURBINE PEDESTAL | U-2, 2004-005-SF-001 | 742.00 CY | - | - | | 1,336 | 119,189 | 29,370 | 148,559 |
| | | STEAM TURBINE GEN COLUMNNS | U-3, 2004-005-SF-009 | 707.00 CY | - | - | | 1,273 | 113,567 | 27,984 | 141,551 |
| | | STEAM TURBINE ELEVATED SLAB | U-3, 2004-005-SF-011 | 778.00 CY | - | - | | 1,400 | 124,972 | 30,795 | 155,767 |
| | | CONCRETE | | | | | | 18,938 | 1,689,989 | 416,437 | 2,106,427 |

**SAN DIEGO GAS & ELECTRIC
 PALOMAR ENERGY CENTER
 DECOMMISSIONING STUDY**



| Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|-----------------|--------------------------------------|---|--|---------------|------------------|-------------|---------------|--------------|----------------|---------------|----------------|
| 10.24.00 | ARCHITECTURAL | | | | | | | | | | |
| | | ADMINISTRATION BUILDING | U-2, 70X90'X25' HIGH - 50% Steam Plant | 78,750.00 CF | - | - | | 236 | 19,663 | 6,551 | 26,214 |
| | | ADMINISTRATION BUILDING | U-2, 70X90'X25' HIGH - 50% Other Plant | 78,750.00 CF | - | - | | 236 | 19,663 | 6,551 | 26,214 |
| | | CHILLER BUILDING | U-0, 140'X45'X25' STEEL BLDG | 157,500.00 CF | - | - | | 473 | 39,326 | 13,102 | 52,429 |
| | | PROCESS BUILDING | U-0, 40'X90'X25' STEEL BLDG | 90,000.00 CF | - | - | | 270 | 22,472 | 7,487 | 29,959 |
| | | TOOL STORAGE BUILDING | U-0, 40'X90'X25' STEEL BLDG - 50% Steam Plant | 45,000.00 CF | - | - | | 135 | 11,236 | 3,744 | 14,980 |
| | | TOOL STORAGE BUILDING | U-0, 40'X90'X25' STEEL BLDG - 50% Other Plant | 45,000.00 CF | - | - | | 135 | 11,236 | 3,744 | 14,980 |
| | | ELECTRICAL EQUIPMENT / CONTROL BUILDING | U-0, 30'X90'X25' - 50% Steam Plant | 33,750.00 CF | - | - | | 101 | 8,427 | 2,808 | 11,235 |
| | | ELECTRICAL EQUIPMENT / CONTROL BUILDING | U-0, 30'X90'X25' - 50% Other Plant | 33,750.00 CF | - | - | | 101 | 8,427 | 2,808 | 11,235 |
| | | WATER LAB BUILDING | U-0, 40'X35'X25' | 35,000.00 CF | - | - | | 105 | 8,739 | 2,912 | 11,651 |
| | | FABRICATION SHOP BUILDING | U-0, 20'X40'X18' | 14,400.00 CF | - | - | | 43 | 3,596 | 1,198 | 4,793 |
| | | SWITCHGEAR BUILDING | U-0, 5'X35'X18' | 3,150.00 CF | - | - | | 9 | 787 | 262 | 1,049 |
| | | CT2 LCI W/PDC BUILDING | U-2, 12'X20'X9' | 2,200.00 CF | - | - | | 7 | 549 | 183 | 732 |
| | | ELEVATOR | | 1.00 EA | - | - | | 200 | 15,988 | 4,554 | 20,542 |
| | | ARCHITECTURAL | | | | | | 2,052 | 170,109 | 55,903 | 226,012 |
| 10.26.00 | MISCELLANEOUS STRUCTURAL ITEM | | | | | | | | | | |
| | | MISCELLANEOUS SMALL OBSTACLE REMOVAL FROM SITE | | 1.00 LT | - | - | | 500 | 39,970 | 11,385 | 51,355 |
| | | MISCELLANEOUS STRUCTURAL ITEM | | | | | | 500 | 39,970 | 11,385 | 51,355 |
| 10.31.00 | MECHANICAL EQUIPMENT | | | | | | | | | | |
| | | COMBUSTION TURBINE | U-1, GE PG7241FA C/T - NOMINAL 170 MW, FIRING NATURAL GAS ONLY, W DRY LOW NOX BURNERS, INLET AIR FILTERS SILENCING & EVAP COOLERS , 180'X75'X31' INLET CHILLER COILS | 854.00 TN | - | - | | 2,989 | 238,941 | 68,060 | 307,000 |
| | | COMBUSTION TURBINE | U-2, GE PG7241FA C/T - NOMINAL 170 MW, FIRING NATURAL GAS ONLY, W DRY LOW NOX BURNERS, INLET AIR FILTERS SILENCING & EVAP COOLERS , 180'X75'X31' INLET CHILLER COILS | 854.00 TN | - | - | | 2,989 | 238,941 | 68,060 | 307,000 |
| | | HEAT RECOVERY STEAM GENERATOR | U-1, 3-PRESS HRSG W/REHEAT SUPPLEMENTAL DUCT BURNERS INCL INTERGRAL DEAERATOR, SCR INC 110' STACK | 2,156.00 TN | - | - | | 7,546 | 603,227 | 171,822 | 775,050 |
| | | HEAT RECOVERY STEAM GENERATOR | U-2, 3-PRESS HRSG W/REHEAT SUPPLEMENTAL DUCT BURNERS INCL INTERGRAL DEAERATOR, SCR INC 110' STACK | 2,156.00 TN | - | - | | 7,546 | 603,227 | 171,822 | 775,050 |
| | | STEAM TURBINE GENERATOR | 235 MW CONDENSING REHEAT TURBINE W STANDARD ACCESSORIES | 465.00 TN | - | - | | 1,628 | 130,102 | 37,058 | 167,161 |
| | | CT INLET CHILLER | U-1 | 220.00 TN | - | - | | 446 | 35,613 | 10,144 | 45,757 |
| | | CT INLET CHILLER | U-2 | 220.00 TN | - | - | | 446 | 35,613 | 10,144 | 45,757 |
| | | AIR COMPRESSOR, CENTRIFUGAL | U-0, 2 @ 1335 SCFM STATION | 9.00 TN | - | - | | 18 | 1,457 | 415 | 1,872 |
| | | NATURAL GAS COMPRESSOR | U-0, 3 @ 2300 HP EA INCL VOLUME TANKS AND AFTERCOOLERS | 300.00 TN | - | - | | 608 | 48,564 | 13,833 | 62,396 |
| | | DEMIN WATER STORAGE TANK (#032) | U-0, 200000 GALLON, 38' DIA X 25' HIGH | 28.00 TN | - | - | | 76 | 6,043 | 1,721 | 7,765 |
| | | RAW/FIRE WATER STORAGE TANK (#034) | U-0 730000 GALLON, 58' DIA X 40' HIGH - 50% Steam Plant | 40.00 TN | - | - | | 108 | 8,634 | 2,459 | 11,093 |
| | | RAW/FIRE WATER STORAGE TANK (#034) | U-0 730000 GALLON, 58' DIA X 40' HIGH - 50% Other Plant | 40.00 TN | - | - | | 108 | 8,634 | 2,459 | 11,093 |
| | | RO PERMEATE STORAGE TANK (#674) | U-0, 60000 GALLON, 25' DIA X 18' HIGH | 11.00 TN | - | - | | 30 | 2,374 | 676 | 3,050 |
| | | AQUEOUS AMMONIA STORAGE TANK (#164) | U-0, 20000 GALLON, | 6.00 TN | - | - | | 16 | 1,295 | 369 | 1,664 |
| | | WATER TREATMENT DEMINERALIZATION & CHEMICAL TREATMENT EQUIPMENT | | 30.00 TN | - | - | | 61 | 4,856 | 1,383 | 6,240 |
| | | GANTRY CRANE | | 225.00 TN | - | - | | 608 | 48,564 | 13,833 | 62,396 |
| | | BRIDGE CRANE | | | - | - | | 621 | 49,643 | 14,140 | 63,783 |

**SAN DIEGO GAS & ELECTRIC
 PALOMAR ENERGY CENTER
 DECOMMISSIONING STUDY**



| Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|-------|-----------------|---|--|---------------|------------------|-------------|---------------|---------------|------------------|----------------|------------------|
| | 10.31.00 | MECHANICAL EQUIPMENT | | | | | | | | | |
| | | CONDENSATE PUMPS | U-0, 3 @ 1400 GPM & 625 TDH, 300 HP | 4.00 TN | - | - | - | 11 | 863 | 246 | 1,109 |
| | | CIRC WTR PUMPS | U-3, 2 @ 65000 GPM & 100' TDH, 1750 HP | 20.00 TN | - | - | - | 54 | 4,317 | 1,230 | 5,546 |
| | | CONDENSATE PUMPS | U-0, 3 @ 1400 GPM & 625 TDH, 300 HP | 4.50 TN | - | - | - | 12 | 971 | 277 | 1,248 |
| | | CT LUBE OIL SYSTEM INCL FIN FAN COOLER | U-1 | 3.00 TN | - | - | - | 12 | 959 | 273 | 1,233 |
| | | CT LUBE OIL SYSTEM INCL FIN FAN COOLER | U-2 | 3.00 TN | - | - | - | 12 | 959 | 273 | 1,233 |
| | | BOILER FEED PUMPS | U-1, 2 @ 1350 GPM FOR HRSGS, 2150 HP | 3.00 TN | - | - | - | 12 | 959 | 273 | 1,233 |
| | | BOILER FEED PUMPS | U-2, 2 @ 1350 GPM FOR HRSGS, 2150 HP | 5.00 TN | - | - | - | 20 | 1,599 | 455 | 2,054 |
| | | CLOSED COOLING WATER PUMPS | U-3, 2 @ 7000 GPM @ 213 TDH, 550 HP | 4.00 TN | - | - | - | 16 | 1,279 | 364 | 1,643 |
| | | 1.6 MW DIESEL GENERATOR | | 19.00 TN | - | - | - | 76 | 6,075 | 1,731 | 7,806 |
| | | CCW HEAT EXCHANGER | U-3, 2 EA SS PLATE & FRAMED DESIGN, 7000 GPM | 1.00 TN | - | - | - | 5 | 400 | 114 | 514 |
| | | FUEL GAS PREHEAT | U-3, 2 SHELL & TUBE HT EX | 1.00 TN | - | - | - | 5 | 400 | 114 | 514 |
| | | BACKUP CIRC WTR MAKEUP PUMP | U-3, 1, 40 HP | 0.20 TN | - | - | - | 1 | 80 | 23 | 103 |
| | | FIRE PUMPS | U-0, 2 @ 1500 GPM @ 125 PSI, 300 HP | 1.50 TN | - | - | - | 8 | 600 | 171 | 770 |
| | | AUX ILIARY COOLING WATER | U-3, 1 @ 2400GPM | 1.00 TN | - | - | - | 5 | 400 | 114 | 514 |
| | | COOLING TOWER MAKEUP | U-3, 1 @ 4550 GPM & 65' TDH | 1.00 TN | - | - | - | 5 | 400 | 114 | 514 |
| | | DEMIN WTR PUMPS | U-3, 2 @ 290 GPM & 90' TDH, 20 HP | 0.20 TN | - | - | - | 1 | 80 | 23 | 103 |
| | | EVAP COOLERS BLEND WATER PUMPS | U-3, 2 @ 125 GPM & 148 TDH | 1.00 TN | - | - | - | 5 | 400 | 114 | 514 |
| | | PUMPS, FUEL OIL UNLOADING, FORWARDING, DIRTY CLEAN OIL TRANSFER | NOT INCLUDED | TN | - | - | - | | | | |
| | | RAW WATER RO SUPPLY PUMPS | U-0, 3 @ 270 GPM & 180' TDH, 15 HP | 0.20 TN | - | - | - | 1 | 80 | 23 | 103 |
| | | HRSG BLOWDOWN SUMP PUMPS | U-1, 1 @ 500 GPM & 50' TDH VERTICAL, 20 HP | 0.20 TN | - | - | - | 1 | 80 | 23 | 103 |
| | | HRSG BLOWDOWN SUMP PUMPS | U-2, 1 @ 500 GPM & 50' TDH VERTICAL, 20 HP | 0.20 TN | - | - | - | 1 | 80 | 23 | 103 |
| | | WASTEWATER SUMP PUMPS | U-1, 1 @ 600 GPM & 46' TDH VERTICAL, 20HP | 0.20 TN | - | - | - | 1 | 80 | 23 | 103 |
| | | WASTEWATER SUMP PUMPS | U-2, 1 @ 600 GPM & 46' TDH VERTICAL, 20HP | 0.20 TN | - | - | - | 1 | 80 | 23 | 103 |
| | | SERVICE WATER PUMPS | U-0, 1 @ 300 GPM & 145' TDH, 25 HP | 0.20 TN | - | - | - | 1 | 80 | 23 | 103 |
| | | VACUUM PUMPS | U-0, 2 @ 75 HP | 0.60 TN | - | - | - | 3 | 240 | 68 | 308 |
| | | CONDENSER | U-3, SURFACE CONDENSER 2 PASS | 366.00 TN | - | - | - | 741 | 59,248 | 16,876 | 76,124 |
| | | COOLING TOWER | U-3, 7-CELL INLINE WET WOOD COUNTERFLOW, MARLEY | 897,600.00 CF | - | - | - | 1,795 | 143,508 | 40,877 | 184,385 |
| | | MECHANICAL EQUIPMENT | | | | | | 28,646 | 2,289,943 | 652,264 | 2,942,208 |
| | 10.35.00 | PIPING | | | | | | | | | |
| | | PIPING, VALVES AND HANGERS | U1, 14,000 LF/UNIT - 67% Steam Plant | 222.00 TN | - | - | - | 450 | 35,937 | 10,236 | 46,173 |
| | | PIPING, VALVES AND HANGERS | U1, 14,000 LF/UNIT - 33% Other Plant | 109.00 TN | - | - | - | 221 | 17,645 | 5,026 | 22,671 |
| | | PIPING, VALVES AND HANGERS | U2, 14,300 LF/UNIT - 67% Steam Plant | 236.00 TN | - | - | - | 478 | 38,203 | 10,882 | 49,085 |
| | | PIPING, VALVES AND HANGERS | U2, 14,300 LF/UNIT - 33% Other Plant | 116.00 TN | - | - | - | 235 | 18,778 | 5,349 | 24,127 |
| | | FIRE LINES & HYDRANTS | U-0, ABANDON UNDERGND LINES REMOVE HYDRANTS, 50% Steam Plant | 1.00 LT | - | - | - | 40 | 3,198 | 911 | 4,108 |
| | | FIRE LINES & HYDRANTS | U-0, ABANDON UNDERGND LINES REMOVE HYDRANTS, 50% Other Plant | 1.00 LT | - | - | - | 40 | 3,198 | 911 | 4,108 |
| | | PIPING | | | | | | 1,463 | 116,958 | 33,314 | 150,272 |
| | 10.41.00 | ELECTRICAL EQUIPMENT | | | | | | | | | |
| | | TRANSFORMERS | U-1, U-2, 67% Steam Plant | 261.00 TN | - | - | - | 697 | 49,354 | 15,880 | 65,234 |
| | | TRANSFORMERS | U-1, U-2, 33% Other Plant | 129.00 TN | - | - | - | 345 | 24,394 | 7,849 | 32,242 |
| | | MISC ELECT EQUIPMENT | U-1, U-2, 33% Other Plant | 60.00 TN | - | - | - | 160 | 11,346 | 3,650 | 14,996 |
| | | MISC ELECT EQUIPMENT | U-1, U-2, 67% Steam Plant | 122.00 TN | - | - | - | 326 | 23,070 | 7,423 | 30,493 |
| | | OUTDOOR LIGHT POLE / FIXTURE | U-0 | 1.00 LT | - | - | - | 150 | 10,616 | 3,416 | 14,031 |
| | | ELECTRICAL EQUIPMENT | U-0, CONTROL RM, 50% Steam Plant | 1.00 LT | - | - | - | 50 | 3,539 | 1,139 | 4,677 |
| | | ELECTRICAL EQUIPMENT | U-0, CONTROL RM, 50% Other Plant | 1.00 LT | - | - | - | 50 | 3,539 | 1,139 | 4,677 |
| | | ELECTRICAL EQUIPMENT | | | | | | 1,778 | 125,856 | 40,494 | 166,350 |
| | 10.42.00 | RACEWAY, CABLE TRAY, & CONDUIT | | | | | | | | | |

**SAN DIEGO GAS & ELECTRIC
 PALOMAR ENERGY CENTER
 DECOMMISSIONING STUDY**



| Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|--|-------|--|--|--------------|------------------|--------------------|---------------|---------------|------------------|------------------|--------------------|
| 10.42.00 RACEWAY, CABLE TRAY, & CONDUIT | | | | | | | | | | | |
| | | CONDUIT | Steam Plant 67% U-1 | 30,150.00 LF | - | - | | 302 | 24,102 | 6,865 | 30,967 |
| | | CONDUIT | Other Plant 33% U-1 | 14,850.00 LF | - | - | | 149 | 11,871 | 3,381 | 15,252 |
| | | CONDUIT | Steam Plant 67% U-2 | 30,150.00 LF | - | - | | 302 | 24,102 | 6,865 | 30,967 |
| | | CONDUIT | Other Plant 33% U-2 | 14,850.00 LF | - | - | | 149 | 11,871 | 3,381 | 15,252 |
| | | CABLE TRAY | Steam Plant 67% U-1 | 1,675.00 LF | - | - | | 67 | 5,356 | 1,526 | 6,882 |
| | | CABLE TRAY | Other Plant 33% U-1 | 825.00 LF | - | - | | 33 | 2,638 | 751 | 3,389 |
| | | CABLE TRAY | Steam Plant 67% U-2 | 1,675.00 LF | - | - | | 67 | 5,356 | 1,526 | 6,882 |
| | | CABLE TRAY | Other Plant 33% U-2 | 825.00 LF | - | - | | 33 | 2,638 | 751 | 3,389 |
| | | RACEWAY, CABLE TRAY, & CONDUIT | | | | | | 1,100 | 87,934 | 25,047 | 112,981 |
| 10.43.00 CABLE | | | | | | | | | | | |
| | | COPPER WIRE / CABLE - MEDIUM VOLTAGE | Steam Plant 67% U-1 | 19,430.00 LF | - | - | | 194 | 15,532 | 4,424 | 19,957 |
| | | COPPER WIRE / CABLE - MEDIUM VOLTAGE | Other Plant 33% U-1 | 9,570.00 LF | - | - | | 96 | 7,650 | 2,179 | 9,829 |
| | | COPPER WIRE / CABLE - MEDIUM VOLTAGE | Steam Plant 67% U-2 | 19,430.00 LF | - | - | | 194 | 15,532 | 4,424 | 19,957 |
| | | COPPER WIRE / CABLE - MEDIUM VOLTAGE | Other Plant 33% U-2 | 9,570.00 LF | - | - | | 96 | 7,650 | 2,179 | 9,829 |
| | | COPPER WIRE / CABLE - LOW VOLTAGE | Steam Plant 67% U-1 | 67,000.00 LF | - | - | | 335 | 26,780 | 7,628 | 34,408 |
| | | COPPER WIRE / CABLE - LOW VOLTAGE | Other Plant 33% U-1 | 33,000.00 LF | - | - | | 165 | 13,190 | 3,757 | 16,947 |
| | | COPPER WIRE / CABLE - LOW VOLTAGE | Steam Plant 67% U-2 | 67,000.00 LF | - | - | | 335 | 26,780 | 7,628 | 34,408 |
| | | COPPER WIRE / CABLE - LOW VOLTAGE | Other Plant 33% U-2 | 33,000.00 LF | - | - | | 165 | 13,190 | 3,757 | 16,947 |
| | | CABLE | | | | | | 1,580 | 126,305 | 35,977 | 162,282 |
| 10.44.00 CONTROL & INSTRUMENTATION | | | | | | | | | | | |
| | | CONTROL & INSTRUMENTATION | | 1.00 LT | - | - | | 100 | 7,994 | 2,277 | 10,271 |
| | | CONTROL & INSTRUMENTATION | | | | | | 100 | 7,994 | 2,277 | 10,271 |
| WHOLE PLANT DEMOLITION | | | | | | | | 57,055 | 4,734,896 | 1,314,594 | 6,049,490 |
| 18.00.00 SCRAP VALUE | | | | | | | | | | | |
| 18.10.00 MIXED STEEL | | | | | | | | | | | |
| | | CARBON STEEL | | -4,435.00 TN | - | (776,125) | - | | | | (776,125) |
| | | CARBON STEEL | CONDUIT, 1.5" DIA. AVG SIZE, 2.63 LBS/LF | -79.00 TN | - | (13,825) | - | | | | (13,825) |
| | | CARBON STEEL | CONDUIT, 1.5" DIA. AVG SIZE, 2.63 LBS/LF | -39.00 TN | - | (6,825) | - | | | | (6,825) |
| | | CARBON STEEL | CABLE TRAY, 6 LBS/LF | -10.06 TN | - | (1,760) | - | | | | (1,760) |
| | | CARBON STEEL | CABLE TRAY, 6 LBS/LF | -4.96 TN | - | (868) | - | | | | (868) |
| | | CARBON STEEL | | -1,325.00 TN | - | (231,875) | - | | | | (231,875) |
| | | CARBON STEEL | | -255.00 TN | - | (44,625) | - | | | | (44,625) |
| | | CARBON STEEL | COOLING TOWER | -350.00 TN | - | (61,250) | - | | | | (61,250) |
| | | CARBON STEEL | | -230.00 TN | - | (40,250) | - | | | | (40,250) |
| | | CARBON STEEL | | -782.00 TN | - | (136,850) | - | | | | (136,850) |
| | | CARBON STEEL | | -1,939.00 TN | - | (339,325) | - | | | | (339,325) |
| | | CARBON STEEL | BUILDINGS | -154.00 TN | - | (26,950) | - | | | | (26,950) |
| | | CARBON STEEL | BUILDINGS | -1.87 TN | - | (327) | - | | | | (327) |
| | | CARBON STEEL | BUILDINGS | -60.16 TN | - | (10,528) | - | | | | (10,528) |
| | | CARBON STEEL | MISC ELECT EQUIPMENT | -122.00 TN | - | (21,350) | - | | | | (21,350) |
| | | CARBON STEEL | MISC ELECT EQUIPMENT | -60.00 TN | - | (10,500) | - | | | | (10,500) |
| | | STEEL / COPPER MIX - LARGE TRANSFORMER > 100 KVA | | -261.00 TN | - | (91,350) | - | 0 | | | (91,350) |
| | | STEEL / COPPER MIX - LARGE TRANSFORMER > 100 KVA | | -129.00 TN | - | (45,150) | - | 0 | | | (45,150) |
| | | MIXED STEEL | | | | (1,859,734) | | 0 | | | (1,859,734) |
| 18.30.00 COPPER | | | | | | | | | | | |
| | | #2 SOLID COPPER / TUBING | BUS BAR | -0.67 TN | - | (4,117) | - | | | | (4,117) |
| | | #2 SOLID COPPER / TUBING | BUS BAR | -0.33 TN | - | (2,028) | - | | | | (2,028) |
| | | #2 INSULATED COPPER WIRE | | -4.00 TN | - | (9,760) | - | | | | (9,760) |
| | | #2 INSULATED COPPER WIRE | | -2.00 TN | - | (4,880) | - | | | | (4,880) |
| | | COPPER | | | | (20,785) | | | | | (20,785) |
| SCRAP VALUE | | | | | | (1,880,519) | | 0 | | | (1,880,519) |
| 21.00.00 CIVIL WORK | | | | | | | | | | | |
| 21.18.00 HAULING | | | | | | | | | | | |
| | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 713.00 CY | 14,260 | - | | | | | 14,260 |
| | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 713.00 CY | 14,260 | - | | | | | 14,260 |

**SAN DIEGO GAS & ELECTRIC
 PALOMAR ENERGY CENTER
 DECOMMISSIONING STUDY**



| Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|-----------------|-----------------|--|---|--------------|------------------|-------------|----------------|--------------|----------------|----------------|------------------|
| | 21.18.00 | HAULING | | | | | | | | | |
| | | HAULING TO RECYCLE FACILITY | DEBRIS IS RECYCLED. NO DISPOSAL FEE | 624.00 CY | 12,480 | - | | | | | 12,480 |
| | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 4,611.00 CY | 92,220 | - | | | | | 92,220 |
| | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 4,625.00 CY | 92,500 | - | | | | | 92,500 |
| | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 309.00 CY | 6,180 | - | | | | | 6,180 |
| | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 113.00 CY | 2,260 | - | | | | | 2,260 |
| | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 1,319.00 CY | 26,380 | - | | | | | 26,380 |
| | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 685.00 CY | 13,700 | - | | | | | 13,700 |
| | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 2,120.00 CY | 42,400 | - | | | | | 42,400 |
| | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 557.00 CY | 11,140 | - | | | | | 11,140 |
| | | HAULING TO RECYCLE FACILITY | CONCRETE PAVED SURFACES DEBRIS IS RECYCLED. NO DISPOSAL FEE | 624.00 CY | 12,480 | - | | | | | 12,480 |
| | | HAULING | | | 326,000 | | | | | | 326,000 |
| | 21.21.00 | MASS FILL | | | | | | | | | |
| | | MASS FILL, COMMON EARTH 6 INCHES THICK | COVER DISTURBED AREAS OF SITE | 12,907.00 CY | - | - | 296,861 | 452 | 41,163 | 43,358 | 381,382 |
| | | MASS FILL | | | | | 296,861 | 452 | 41,163 | 43,358 | 381,382 |
| | 21.47.00 | LANDSCAPING | | | | | | | | | |
| | | FINE GRADING, SEEDING & FERTILIZER | | 77,440.00 SY | - | - | 37,946 | 3,717 | 269,082 | 59,288 | 366,316 |
| | | LANDSCAPING | | | | | 37,946 | 3,717 | 269,082 | 59,288 | 366,316 |
| | 21.52.00 | WASTE DISPOSAL | | | | | | | | | |
| | | DISPOSAL AND TRANSPORTATION FEE | RUBBISH & TENANT DEBRIS | 1,550.00 CY | 46,500 | - | | | | | 46,500 |
| | | WASTE DISPOSAL | | | 46,500 | | | | | | 46,500 |
| | | CIVIL WORK | | | 372,500 | | 334,807 | 4,169 | 310,245 | 102,647 | 1,120,198 |
| 22.00.00 | | CONCRETE | | | | | | | | | |
| | 22.13.00 | CONCRETE | | | | | | | | | |
| | | FLOWABLE FILL, 1500 PSI | BURIED CIRCULATING WATER PIPES, 84" DIA X 2500LF | 3,560.00 CY | - | - | 427,200 | 1,780 | 134,977 | 22,837 | 585,015 |
| | | CONCRETE | | | | | 427,200 | 1,780 | 134,977 | 22,837 | 585,015 |
| | | CONCRETE | | | | | 427,200 | 1,780 | 134,977 | 22,837 | 585,015 |

**APPENDIX B. CONCEPTUAL COST ESTIMATE —
FERC ACCOUNTS**

**SAN DIEGO GAS & ELECTRIC
PALOMAR ENERGY CENTER
DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS**

| | |
|-------------------------|------------|
| Estimator | GA |
| Labor rate table | 21CASAN |
| Project No. | A14520.001 |
| Estimate Date | 11/30/21 |
| Reviewed By | BA |
| Approved By | BA |
| Estimate No. | 30611C |

SAN DIEGO GAS & ELECTRIC
 PALOMAR ENERGY CENTER
 DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS



| Area | Description | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|------|--|------------------|-------------|---------------|-----------|------------|--------------|------------|
| 311 | STRUCTURES AND IMPROVEMENTS | 92,941 | (26,950) | 521,949 | 6,933 | 1,044,589 | 293,718 | 1,926,247 |
| 312 | BOILER PLANT EQUIPMENT | 117,026 | (776,125) | | 20,604 | 3,244,452 | 749,563 | 3,334,916 |
| 314 | TURBO GENERATOR UNITS | 117,382 | (293,125) | 665,986 | 13,189 | 2,114,178 | 447,667 | 3,052,089 |
| 315 | ACCESSORY ELECTRIC EQUIPMENT | 7,842 | (142,490) | | 3,333 | 497,309 | 121,988 | 484,650 |
| 316 | MISCELLANEOUS POWER PLANT EQUIPMENT | 2,868 | (44,625) | | 1,079 | 167,391 | 39,449 | 165,083 |
| 341 | OTHER PRODUCTION - STRUCTURES & IMPROVEMENTS | 49,313 | (50,778) | | 3,067 | 506,211 | 131,398 | 636,144 |
| 342 | OTHER PRODUCTION - FUEL HOLDERS, PRODUCERS AND ACCESSORIES | 17,385 | (136,850) | | 2,389 | 379,225 | 86,704 | 346,465 |
| 344 | OTHER PRODUCTION - GENERATORS | 53,805 | (339,325) | | 10,344 | 1,642,844 | 375,345 | 1,732,669 |
| 345 | OTHER PRODUCTION - ACCESSORY ELECTRIC EQUIPMENT | 14,137 | (70,251) | | 2,066 | 317,493 | 75,029 | 336,407 |

SAN DIEGO GAS & ELECTRIC
 PALOMAR ENERGY CENTER
 DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS



Estimate Totals

| Description | Amount | Totals | Hours |
|-------------------------------------|--------------------|-------------------|--------|
| Labor | 9,913,692 | | 63,004 |
| Material | 1,187,936 | | |
| Subcontract | 472,699 | | |
| Construction Equipment | 2,320,861 | | |
| Scrap Value | <u>(1,880,519)</u> | | |
| | 12,014,669 | 12,014,669 | |
| General Conditions | | | |
| Additional Labor Costs | | | |
| Site Overheads | | | |
| Other Construction Indirects | | 12,014,669 | |
| Project Indirect Costs | | 12,014,669 | |
| Contingency | | 12,014,669 | |
| Escalation | | 12,014,669 | |
| Total | | 12,014,669 | |

General Conditions, Indirect Costs and Contingency are allocated in the line items above.

**SAN DIEGO GAS & ELECTRIC
 PALOMAR ENERGY CENTER
 DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS**



| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|------------|-----------------|-----------------|--|---|---------------|------------------|-----------------|----------------|--------------|------------------|----------------|------------------|
| 311 | | | STRUCTURES AND IMPROVEMENTS | | | | | | | | | |
| | 10.00.00 | | WHOLE PLANT DEMOLITION | | | | | | | | | |
| | | 10.21.00 | CIVIL WORK | | | | | | | | | |
| | | | PAVED SURFACES, 6 IN THICK | STEAM PLANT | 3,744.00 SY | - | - | | 449 | 76,396 | 33,438 | 109,833 |
| | | | CIVIL WORK | | | | | | 449 | 76,396 | 33,438 | 109,833 |
| | | 10.22.00 | CONCRETE | | | | | | | | | |
| | | | MISC FDNS | U-0 2004-005-SF, 50% Steam Plant | 278.00 CY | - | - | | 313 | 53,414 | 11,084 | 64,497 |
| | | | ADMINISTRATION/WAREHOUSE/SHOP WT BLDG | U-0, 130'X34'X2'+100'X11'X2' - 50% Steam Plant | 205.00 CY | - | - | | 231 | 39,388 | 8,173 | 47,561 |
| | | | TOOL STORAGE BLDG (#127) | 50% Steam Plant | 67.00 CY | - | - | | 75 | 12,873 | 2,671 | 15,544 |
| | | | WATER LAB | U-0, 40'X35'X2' | 104.00 CY | - | - | | 117 | 19,982 | 4,146 | 24,129 |
| | | | FAB SHOP | U-0, 20'X40'X2' | 59.00 CY | - | - | | 66 | 11,336 | 2,352 | 13,688 |
| | | | CONCRETE | | | | | | 802 | 136,993 | 28,427 | 165,420 |
| | | 10.24.00 | ARCHITECTURAL | | | | | | | | | |
| | | | ADMINISTRATION BUILDING | U-2, 70'X90'X25' HIGH - 50% Steam Plant | 78,750.00 CF | - | - | | 236 | 37,631 | 10,558 | 48,189 |
| | | | CHILLER BUILDING | U-0, 140'X45'X25' STEEL BLDG | 157,500.00 CF | - | - | | 473 | 75,262 | 21,116 | 96,378 |
| | | | PROCESS BUILDING | U-0, 40'X90'25' STEEL BLDG | 90,000.00 CF | - | - | | 270 | 43,007 | 12,066 | 55,073 |
| | | | TOOL STORAGE BUILDING | U-0, 40'X90'25' STEEL BLDG - 50% Steam Plant | 45,000.00 CF | - | - | | 135 | 21,503 | 6,033 | 27,537 |
| | | | ELECTRICAL EQUIPMENT / CONTROL BUILDING | U-0, 30'X90'X25' - 50% Steam Plant | 33,750.00 CF | - | - | | 101 | 16,128 | 4,525 | 20,653 |
| | | | WATER LAB BUILDING | U-0, 40'X35'X25' | 35,000.00 CF | - | - | | 105 | 16,725 | 4,692 | 21,417 |
| | | | FABRICATION SHOP BUILDING | U-0, 20'X40'X18' | 14,400.00 CF | - | - | | 43 | 6,881 | 1,931 | 8,812 |
| | | | ARCHITECTURAL | | | | | | 1,363 | 217,138 | 60,922 | 278,059 |
| | | 10.41.00 | ELECTRICAL EQUIPMENT | | | | | | | | | |
| | | | OUTDOOR LIGHT POLE / FIXTURE | U-0 | 1.00 LT | - | - | | 150 | 20,316 | 5,504 | 25,820 |
| | | | ELECTRICAL EQUIPMENT | | | | | | 150 | 20,316 | 5,504 | 25,820 |
| | | | WHOLE PLANT DEMOLITION | | | | | | 2,765 | 450,842 | 128,291 | 579,133 |
| | 18.00.00 | | SCRAP VALUE | | | | | | | | | |
| | | 18.10.00 | MIXED STEEL | | | | | | | | | |
| | | | CARBON STEEL | BUILDINGS | -154.00 TN | - | (26,950) | - | | | | (26,950) |
| | | | MIXED STEEL | | | | | | | | | (26,950) |
| | | | SCRAP VALUE | | | | | | | | | (26,950) |
| | 21.00.00 | | CIVIL WORK | | | | | | | | | |
| | | 21.18.00 | HAULING | | | | | | | | | |
| | | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 713.00 CY | 18,096 | - | | | | | 18,096 |
| | | | HAULING TO RECYCLE FACILITY | CONCRETE PAVED SURFACES DEBRIS IS RECYCLED. NO DISPOSAL FEE | 624.00 CY | 15,837 | - | | | | | 15,837 |
| | | | HAULING | | | 33,933 | | | | | | 33,933 |
| | | 21.21.00 | MASS FILL | | | | | | | | | |
| | | | MASS FILL, COMMON EARTH 6 INCHES THICK | COVER DISTURBED AREAS OF SITE | 12,907.00 CY | - | - | 462,794 | 452 | 78,778 | 69,878 | 611,449 |
| | | | MASS FILL | | | | | 462,794 | 452 | 78,778 | 69,878 | 611,449 |
| | | 21.47.00 | LANDSCAPING | | | | | | | | | |
| | | | FINE GRADING, SEEDING & FERTILIZER | | 77,440.00 SY | - | - | 59,156 | 3,717 | 514,969 | 95,550 | 669,674 |
| | | | LANDSCAPING | | | | | 59,156 | 3,717 | 514,969 | 95,550 | 669,674 |
| | | 21.52.00 | WASTE DISPOSAL | | | | | | | | | |
| | | | DISPOSAL AND TRANSPORTATION FEE | RUBBISH & TENANT DEBRIS | 1,550.00 CY | 59,008 | - | | | | | 59,008 |
| | | | WASTE DISPOSAL | | | 59,008 | | | | | | 59,008 |
| | | | CIVIL WORK | | | 92,941 | | 521,949 | 4,169 | 593,746 | 165,427 | 1,374,064 |
| | | | 311 STRUCTURES AND IMPROVEMENTS | | | 92,941 | (26,950) | 521,949 | 6,933 | 1,044,589 | 293,718 | 1,926,247 |
| 312 | | | BOILER PLANT EQUIPMENT | | | | | | | | | |
| | 10.00.00 | | WHOLE PLANT DEMOLITION | | | | | | | | | |
| | | 10.22.00 | CONCRETE | | | | | | | | | |
| | | | HRSG / STACK FDN | U-1, 2004-005-SF-025 | 948.00 CY | - | - | | 1,067 | 182,145 | 37,796 | 219,941 |
| | | | HRSG / STACK FDN | U-2, 2004-005-SF-025 | 948.00 CY | - | - | | 1,067 | 182,145 | 37,796 | 219,941 |
| | | | HRSG EAST AREA MAT | U-1, 2004-005-SF-028 | 197.00 CY | - | - | | 222 | 37,851 | 7,854 | 45,705 |
| | | | HRSG EAST AREA MAT | U-2, 2004-005-SF-028 | 160.00 CY | - | - | | 180 | 30,742 | 6,379 | 37,121 |
| | | | AQUEOUS AMMONIA STORAGE TANK AND UNLOADING AREA FDNS | U-2, 2004-005-SF-037 | 196.00 CY | - | - | | 221 | 37,659 | 7,814 | 45,473 |
| | | | STG WEST AREA MAT | U-3, 2004-005-SF-061 | 49.00 CY | - | - | | 55 | 9,415 | 1,954 | 11,368 |
| | | | TRAVELLING TOWER CONSTRUCTION CRANE FDN | U-0 2004-005-SF-061 | 132.00 CY | - | - | | 132 | 22,480 | 4,665 | 27,145 |

**SAN DIEGO GAS & ELECTRIC
 PALOMAR ENERGY CENTER
 DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS**



| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|----------|----------|----------|---|--|--------------|------------------|------------------|---------------|---------------|------------------|----------------|------------------|
| | | 10.22.00 | CONCRETE | | | | | | | | | |
| | | | STATIONARY TOWER CONSTRUCTION CRANE FDN | U-0 2004-005-SF-079 | 162.00 CY | - | - | - | 182 | 31,126 | 6,459 | 37,585 |
| | | | STG NORTH ARE MAT | U-0 2004-005-SF-080A | 341.00 CY | - | - | - | 384 | 65,518 | 13,595 | 79,114 |
| | | | RO PERMEATE STORAGE TANK FDN | U-0 2004-005-SF-082 | 25.00 CY | - | - | - | 28 | 4,803 | 997 | 5,800 |
| | | | DEMIN WATER STORAGE TANK FDN | U-0 2004-005-SF-090 | 52.00 CY | - | - | - | 59 | 9,991 | 2,073 | 12,064 |
| | | | THERMAL ENERGY STORAGE (TES) TANK FDN | U-0 2004-005-SF-090 | 364.00 CY | - | - | - | 410 | 69,937 | 14,513 | 84,450 |
| | | | THERMAL ENERGY STORAGE (TES) TANK (#119) | U-0 3600000 GALLON, 120' DIA X 48' HIGH - CONCRETE | 1,052.00 CY | - | - | - | 1,184 | 202,127 | 41,943 | 244,069 |
| | | | CONCRETE | | | | | | 5,187 | 885,937 | 183,838 | 1,069,775 |
| | | 10.31.00 | MECHANICAL EQUIPMENT | | | | | | | | | |
| | | | HEAT RECOVERY STEAM GENERATOR | U-1, 3-PRESS HRSG W/REHEAT SUPPLEMENTAL DUCT BURNERS INCL INTERGRAL DEAEERATOR, SCR INC 110' STACK | 2,156.00 TN | - | - | - | 7,546 | 1,154,454 | 276,913 | 1,431,367 |
| | | | HEAT RECOVERY STEAM GENERATOR | U-2, 3-PRESS HRSG W/REHEAT SUPPLEMENTAL DUCT BURNERS INCL INTERGRAL DEAEERATOR, SCR INC 110' STACK | 2,156.00 TN | - | - | - | 7,546 | 1,154,454 | 276,913 | 1,431,367 |
| | | | DEMIN WATER STORAGE TANK (#032) | U-0 200000 GALLON, 38' DIA X 25' HIGH | 28.00 TN | - | - | - | 76 | 11,566 | 2,774 | 14,340 |
| | | | RAW/FIRE WATER STORAGE TANK (#034) | U-0 730000 GALLON, 58' DIA X 40' HIGH - 50% Steam Plant | 40.00 TN | - | - | - | 108 | 16,523 | 3,963 | 20,486 |
| | | | RO PERMEATE STORAGE TANK (#674) | U-0, 60000 GALLON, 25' DIA X 18' HIGH | 11.00 TN | - | - | - | 30 | 4,544 | 1,090 | 5,634 |
| | | | AQUEOUS AMMONIA STORAGE TANK (#164) | U-0, 20000 GALLON, | 6.00 TN | - | - | - | 16 | 2,478 | 594 | 3,073 |
| | | | WATER TREATMENT DEMINERALIZATION & CHEMICAL TREATMENT EQUIPMENT | | 30.00 TN | - | - | - | 61 | 9,294 | 2,229 | 11,523 |
| | | | BOILER FEED PUMPS | U-1, 2 @ 1350 GPM FOR HRSGS, 2150 HP | 3.00 TN | - | - | - | 12 | 1,836 | 440 | 2,276 |
| | | | BOILER FEED PUMPS | U-2, 2 @ 1350 GPM FOR HRSGS, 2150 HP | 5.00 TN | - | - | - | 20 | 3,060 | 734 | 3,794 |
| | | | DEMIN WTR PUMPS | U-3, 2 @ 290 GPM & 90' TDH, 20 HP | 0.20 TN | - | - | - | 1 | 153 | 37 | 190 |
| | | | RAW WATER RO SUPPLY PUMPS | U-0, 3 @ 270 GPM & 180' TDH, 15 HP | 0.20 TN | - | - | - | 1 | 153 | 37 | 190 |
| | | | MECHANICAL EQUIPMENT | | | | | | 15,416 | 2,358,515 | 565,724 | 2,924,239 |
| | | | WHOLE PLANT DEMOLITION | | | | | | 20,604 | 3,244,452 | 749,563 | 3,994,014 |
| 18.00.00 | | | SCRAP VALUE | | | | | | | | | |
| | 18.10.00 | | MIXED STEEL | | | | | | | | | |
| | | | CARBON STEEL | | -4,435.00 TN | - | (776,125) | - | | | | (776,125) |
| | | | MIXED STEEL | | | | (776,125) | | | | | (776,125) |
| | | | SCRAP VALUE | | | | (776,125) | | | | | (776,125) |
| 21.00.00 | | | CIVIL WORK | | | | | | | | | |
| | 21.18.00 | | HAULING | | | | | | | | | |
| | | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 4,611.00 CY | 117,026 | - | - | | | | 117,026 |
| | | | HAULING | | | 117,026 | | | | | | 117,026 |
| | | | CIVIL WORK | | | 117,026 | | | | | | 117,026 |
| | | | 312 BOILER PLANT EQUIPMENT | | | 117,026 | (776,125) | | 20,604 | 3,244,452 | 749,563 | 3,334,916 |
| 314 | | | TURBO GENERATOR UNITS | | | | | | | | | |
| | 10.00.00 | | WHOLE PLANT DEMOLITION | | | | | | | | | |
| | | 10.22.00 | CONCRETE | | | | | | | | | |
| | | | STEAM TURBINE GEN FDN BASE MAT | U-3, 2004-005-SF-009 | 1,322.00 CY | - | - | - | 1,487 | 254,003 | 52,707 | 306,711 |
| | | | COOLING TOWER FDN | U-3, 2004-005-SF-021A | 1,544.00 CY | - | - | - | 1,737 | 296,657 | 61,559 | 358,216 |
| | | | STG ROTOR REMOVAL PLATFORM FDN | U-3, 2004-005-SF-030 | 35.00 CY | - | - | - | 39 | 6,725 | 1,395 | 8,120 |
| | | | COOLING TOWER CHEMICAL FEED BLDG AND UNLOADING CONTAINMENT FDN | U-2, 2004-005-SF-060A & B | 239.00 CY | - | - | - | 269 | 45,920 | 9,529 | 55,449 |
| | | | STEAM TURBINE GEN COLUMNS | U-3, 2004-005-SF-009 | 707.00 CY | - | - | - | 1,273 | 217,344 | 45,100 | 262,444 |
| | | | STEAM TURBINE ELEVATED SLAB | U-3, 2004-005-SF-011 | 778.00 CY | - | - | - | 1,400 | 239,170 | 49,630 | 288,800 |
| | | | CONCRETE | | | | | | 6,206 | 1,059,820 | 219,920 | 1,279,740 |
| | | 10.31.00 | MECHANICAL EQUIPMENT | | | | | | | | | |
| | | | STEAM TURBINE GENERATOR | 235 MW CONDENSING REHEAT TURBINE W STANDARD ACCESSORIES | 465.00 TN | - | - | - | 1,628 | 248,989 | 59,724 | 308,713 |
| | | | CONDENSATE PUMPS | U-0, 3 @ 1400 GPM & 625 TDH, 300 HP | 4.00 TN | - | - | - | 11 | 1,652 | 396 | 2,049 |
| | | | CIRC WTR PUMPS | U-3, 2 @ 65000 GPM & 100' TDH, 1750 HP | 20.00 TN | - | - | - | 54 | 8,261 | 1,982 | 10,243 |
| | | | CONDENSATE PUMPS | U-0, 3 @ 1400 GPM & 625 TDH, 300 HP | 4.50 TN | - | - | - | 12 | 1,859 | 446 | 2,305 |
| | | | CLOSED COOLING WATER PUMPS | U-3, 2 @ 7000 GPM @ 213 TDH, 550 HP | 4.00 TN | - | - | - | 16 | 2,448 | 587 | 3,035 |
| | | | CCW HEAT EXCHANGER | U-3, 2 EA SS PLATE & FRAMED DESIGN, 7000 GPM | 1.00 TN | - | - | - | 5 | 765 | 183 | 948 |
| | | | BACKUP CIRC WTR MAKEUP PUMP | U-3, 1, 40 HP | 0.20 TN | - | - | - | 1 | 153 | 37 | 190 |
| | | | AUX ILIARY COOLING WATER | U-3, 1 @ 2400GPM | 1.00 TN | - | - | - | 5 | 765 | 183 | 948 |
| | | | COOLING TOWER MAKEUP | U-3, 1 @ 4550 GPM & 65' TDH | 1.00 TN | - | - | - | 5 | 765 | 183 | 948 |
| | | | VACUUM PUMPS | U-0, 2 @ 1500 GPM | 2.00 TN | - | - | - | 3 | 459 | 110 | 569 |

SAN DIEGO GAS & ELECTRIC
 PALOMAR ENERGY CENTER
 DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS



| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|----------|-------|----------|---|--|---------------|------------------|------------------|----------------|---------------|------------------|----------------|------------------|
| | | 10.31.00 | MECHANICAL EQUIPMENT | | | | | | | | | |
| | | | CONDENSER | U-3, SURFACE CONDENSER 2 PASS | 366.00 TN | - | - | | 741 | 113,388 | 27,198 | 140,585 |
| | | | COOLING TOWER | U-3, 7-CELL INLINE WET WOOD COUNTERFLOW, MARLEY | 897,600.00 CF | - | - | | 1,795 | 274,646 | 65,878 | 340,523 |
| | | | MECHANICAL EQUIPMENT | | | | | | 4,276 | 654,150 | 156,907 | 811,057 |
| | | 10.35.00 | PIPING | | | | | | | | | |
| | | | PIPING, VALVES AND HANGERS | U1, 14,000 LF/UNIT - 67% Steam Plant | 222.00 TN | - | - | | 450 | 68,776 | 16,497 | 85,273 |
| | | | PIPING, VALVES AND HANGERS | U2, 14,300 LF/UNIT - 67% Steam Plant | 236.00 TN | - | - | | 478 | 73,113 | 17,537 | 90,651 |
| | | | PIPING | | | | | | 927 | 141,890 | 34,034 | 175,924 |
| | | | WHOLE PLANT DEMOLITION | | | | | | 11,409 | 1,855,859 | 410,862 | 2,266,721 |
| 18.00.00 | | | SCRAP VALUE | | | | | | | | | |
| | | 18.10.00 | MIXED STEEL | | | | | | | | | |
| | | | CARBON STEEL | | -1,325.00 TN | - | (231,875) | - | | | | (231,875) |
| | | | CARBON STEEL | COOLING TOWER | -350.00 TN | - | (61,250) | - | | | | (61,250) |
| | | | MIXED STEEL | | | | (293,125) | | | | | (293,125) |
| | | | SCRAP VALUE | | | | (293,125) | | | | | (293,125) |
| 21.00.00 | | | CIVIL WORK | | | | | | | | | |
| | | 21.18.00 | HAULING | | | | | | | | | |
| | | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 4,625.00 CY | 117,382 | - | | | | | 117,382 |
| | | | HAULING | | | 117,382 | | | | | | 117,382 |
| | | | CIVIL WORK | | | 117,382 | | | | | | 117,382 |
| 22.00.00 | | | CONCRETE | | | | | | | | | |
| | | 22.13.00 | CONCRETE | | | | | | | | | |
| | | | FLOWABLE FILL, 1500 PSI | BURIED CIRCULATING WATER PIPES, 84" DIA X 2500LF | 3,560.00 CY | - | - | 665,986 | 1,780 | 258,319 | 36,805 | 961,111 |
| | | | CONCRETE | | | | | 665,986 | 1,780 | 258,319 | 36,805 | 961,111 |
| | | | CONCRETE | | | | | 665,986 | 1,780 | 258,319 | 36,805 | 961,111 |
| | | | 314 TURBO GENERATOR UNITS | | | 117,382 | (293,125) | 665,986 | 13,189 | 2,114,178 | 447,667 | 3,052,089 |
| 315 | | | ACCESSORY ELECTRIC EQUIPMENT | | | | | | | | | |
| | | 10.00.00 | WHOLE PLANT DEMOLITION | | | | | | | | | |
| | | 10.22.00 | CONCRETE | | | | | | | | | |
| | | | STG STEP-UP TRANSFORMER AND AUX TRNSFORMER FDNS | U-3, 2004-005-SF-031 | 180.00 CY | - | - | | 203 | 34,584 | 7,177 | 41,761 |
| | | | 5 KV SWITCHGEAR MODULE FDN | U-3, 2004-005-SF-033 | 116.00 CY | - | - | | 131 | 22,288 | 4,625 | 26,913 |
| | | | SWITCHGEAR BUILDING | U-0, 5'X35'X2' | 13.00 CY | - | - | | 15 | 2,498 | 518 | 3,016 |
| | | | CONCRETE | | | | | | 348 | 59,370 | 12,320 | 71,690 |
| | | 10.24.00 | ARCHITECTURAL | | | | | | | | | |
| | | | SWITCHGEAR BUILDING | U-0, 5'X35'X18' | 3,150.00 CF | - | - | | 9 | 1,505 | 422 | 1,928 |
| | | | CT2 LCI W/PDC BUILDING | U-2, 12'X20'X9' | 2,200.00 CF | - | - | | 7 | 1,051 | 295 | 1,346 |
| | | | ARCHITECTURAL | | | | | | 16 | 2,557 | 717 | 3,274 |
| | | 10.41.00 | ELECTRICAL EQUIPMENT | | | | | | | | | |
| | | | TRANSFORMERS | U-1, U-2, 67% Steam Plant | 261.00 TN | - | - | | 697 | 94,454 | 25,592 | 120,046 |
| | | | MISC ELECT EQUIPMENT | U-1, U-2, 67% Steam Plant | 122.00 TN | - | - | | 326 | 44,151 | 11,963 | 56,114 |
| | | | ELECTRICAL EQUIPMENT | U-0, CONTROL RM, 50% Steam Plant | 1.00 LT | - | - | | 50 | 6,772 | 1,835 | 8,607 |
| | | | ELECTRICAL EQUIPMENT | | | | | | 1,073 | 145,377 | 39,389 | 184,767 |
| | | 10.42.00 | RACEWAY, CABLE TRAY, & CONDUIT | | | | | | | | | |
| | | | CONDUIT | Steam Plant 67% U-1 | 30,150.00 LF | - | - | | 302 | 46,126 | 11,064 | 57,190 |
| | | | CONDUIT | Steam Plant 67% U-2 | 30,150.00 LF | - | - | | 302 | 46,126 | 11,064 | 57,190 |
| | | | CABLE TRAY | Steam Plant 67% U-1 | 1,675.00 LF | - | - | | 67 | 10,250 | 2,459 | 12,709 |
| | | | CABLE TRAY | Steam Plant 67% U-2 | 1,675.00 LF | - | - | | 67 | 10,250 | 2,459 | 12,709 |
| | | | RACEWAY, CABLE TRAY, & CONDUIT | | | | | | 737 | 112,753 | 27,045 | 139,798 |
| | | 10.43.00 | CABLE | | | | | | | | | |
| | | | COPPER WIRE / CABLE - MEDIUM VOLTAGE | Steam Plant 67% U-1 | 19,430.00 LF | - | - | | 194 | 29,726 | 7,130 | 36,856 |
| | | | COPPER WIRE / CABLE - MEDIUM VOLTAGE | Steam Plant 67% U-2 | 19,430.00 LF | - | - | | 194 | 29,726 | 7,130 | 36,856 |
| | | | COPPER WIRE / CABLE - LOW VOLTAGE | Steam Plant 67% U-1 | 67,000.00 LF | - | - | | 335 | 51,251 | 12,293 | 63,545 |
| | | | COPPER WIRE / CABLE - LOW VOLTAGE | Steam Plant 67% U-2 | 67,000.00 LF | - | - | | 335 | 51,251 | 12,293 | 63,545 |
| | | | CABLE | | | | | | 1,059 | 161,954 | 38,847 | 200,801 |
| | | 10.44.00 | CONTROL & INSTRUMENTATION | | | | | | | | | |
| | | | CONTROL & INSTRUMENTATION | | | | | | 100 | 15,299 | 3,670 | 18,969 |

**SAN DIEGO GAS & ELECTRIC
 PALOMAR ENERGY CENTER
 DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS**



| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost | | | | |
|------------|-----------------|-----------------|--|--|------------|------------------|-------------|---------------|--------------|------------|------------------|----------------|------------------|----------------|----------------|----------------|
| | | | CONTROL & INSTRUMENTATION | | | | | | | | 100 | 15,299 | 3,670 | 18,969 | | |
| | | | WHOLE PLANT DEMOLITION | | | | | | | | 3,333 | 497,309 | 121,988 | 619,298 | | |
| | 18.00.00 | | SCRAP VALUE | | | | | | | | | | | | | |
| | | 18.10.00 | MIXED STEEL | | | | | | | | | | | | | |
| | | | CARBON STEEL | CONDUIT, 1.5" DIA. AVG SIZE, 2.63 LBS/LF | -79.00 TN | - | (13,825) | - | | | | (13,825) | | | | |
| | | | CARBON STEEL | CABLE TRAY, 6 LBS/LF | -10.06 TN | - | (1,760) | - | | | | (1,760) | | | | |
| | | | CARBON STEEL | BUILDINGS | -1.87 TN | - | (327) | - | | | | (327) | | | | |
| | | | CARBON STEEL | MISC ELECT EQUIPMENT | -122.00 TN | - | (21,350) | - | | | | (21,350) | | | | |
| | | | STEEL / COPPER MIX - LARGE TRANSFORMER > 100 KVA | | -261.00 TN | - | (91,350) | - | 0 | | | (91,350) | | | | |
| | | | MIXED STEEL | | | | | | | | 0 | | (128,613) | | | |
| | | 18.30.00 | COPPER | | | | | | | | | | | | | |
| | | | #2 SOLID COPPER / TUBING | BUS BAR | -0.67 TN | - | (4,117) | - | | | | (4,117) | | | | |
| | | | #2 INSULATED COPPER WIRE | | -4.00 TN | - | (9,780) | - | | | | (9,780) | | | | |
| | | | COPPER | | | | | | | | | | (13,877) | | | |
| | | | SCRAP VALUE | | | | | | | | 0 | | (142,490) | | | |
| | 21.00.00 | | CIVIL WORK | | | | | | | | | | | | | |
| | | 21.18.00 | HAULING | | | | | | | | | | | | | |
| | | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 309.00 CY | 7,842 | - | | | | | 7,842 | | | | |
| | | | HAULING | | | | | | | | | | 7,842 | | | |
| | | | CIVIL WORK | | | | | | | | | | 7,842 | | | |
| | | | 315 ACCESSORY ELECTRIC EQUIPMENT | | | | | | 7,842 | | (142,490) | | 3,333 | 497,309 | 121,988 | 484,650 |
| 316 | | | MISCELLANEOUS POWER PLANT EQUIPMENT | | | | | | | | | | | | | |
| | 10.00.00 | | WHOLE PLANT DEMOLITION | | | | | | | | | | | | | |
| | | 10.22.00 | CONCRETE | | | | | | | | | | | | | |
| | | | DIESEL GENERATOR FDN | U-0, 12'X26'X1.5' | 18.00 CY | - | - | - | 20 | 3,458 | 718 | 4,176 | | | | |
| | | | GANTRY CRANE FDN | | 95.00 CY | - | - | - | 107 | 18,253 | 3,788 | 22,041 | | | | |
| | | | CONCRETE | | | | | | | | 127 | 21,711 | 4,505 | 26,217 | | |
| | | 10.24.00 | ARCHITECTURAL | | | | | | | | | | | | | |
| | | | ELEVATOR | | 1.00 EA | - | - | - | 200 | 30,598 | 7,339 | 37,937 | | | | |
| | | | ARCHITECTURAL | | | | | | | | 200 | 30,598 | 7,339 | 37,937 | | |
| | | 10.31.00 | MECHANICAL EQUIPMENT | | | | | | | | | | | | | |
| | | | AIR COMPRESSOR, CENTRIFUGAL | U-0, 2 @ 1335 SCFM STATION | 9.00 TN | - | - | - | 18 | 2,788 | 669 | 3,457 | | | | |
| | | | GANTRY CRANE | | 225.00 TN | - | - | - | 608 | 92,941 | 22,293 | 115,234 | | | | |
| | | | 1.6 MW DIESEL GENERATOR | | 19.00 TN | - | - | - | 76 | 11,627 | 2,789 | 14,416 | | | | |
| | | | FIRE PUMPS | U-0, 2 @ 1500 GPM @ 125 PSI, 300 HP | 1.50 TN | - | - | - | 8 | 1,147 | 275 | 1,423 | | | | |
| | | | HRSG BLOWDOWN SUMP PUMPS | U-1, 1 @ 500 GPM & 50' TDH VERTICAL, 20 HP | 0.20 TN | - | - | - | 1 | 153 | 37 | 190 | | | | |
| | | | HRSG BLOWDOWN SUMP PUMPS | U-2, 1 @ 500 GPM & 50' TDH VERTICAL, 20 HP | 0.20 TN | - | - | - | 1 | 153 | 37 | 190 | | | | |
| | | | SERVICE WATER PUMPS | U-0, 1 @ 300 GPM & 145' TDH, 25 HP | 0.20 TN | - | - | - | 1 | 153 | 37 | 190 | | | | |
| | | | MECHANICAL EQUIPMENT | | | | | | | | 712 | 108,962 | 26,136 | 135,099 | | |
| | | 10.35.00 | PIPING | | | | | | | | | | | | | |
| | | | FIRE LINES & HYDRANTS | U-0, ABANDON UNDERGND LINES REMOVE HYDRANTS, 50% Steam Plant | 1.00 LT | - | - | - | 40 | 6,120 | 1,468 | 7,587 | | | | |
| | | | PIPING | | | | | | | | 40 | 6,120 | 1,468 | 7,587 | | |
| | | | WHOLE PLANT DEMOLITION | | | | | | | | 1,079 | 167,391 | 39,449 | 206,840 | | |
| | 18.00.00 | | SCRAP VALUE | | | | | | | | | | | | | |
| | | 18.10.00 | MIXED STEEL | | | | | | | | | | | | | |
| | | | CARBON STEEL | | -255.00 TN | - | (44,625) | - | | | | (44,625) | | | | |
| | | | MIXED STEEL | | | | | | | | | | (44,625) | | | |
| | | | SCRAP VALUE | | | | | | | | | | (44,625) | | | |
| | 21.00.00 | | CIVIL WORK | | | | | | | | | | | | | |
| | | 21.18.00 | HAULING | | | | | | | | | | | | | |
| | | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 113.00 CY | 2,868 | - | | | | | 2,868 | | | | |
| | | | HAULING | | | | | | | | | | 2,868 | | | |
| | | | CIVIL WORK | | | | | | | | | | 2,868 | | | |

SAN DIEGO GAS & ELECTRIC
 PALOMAR ENERGY CENTER
 DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS



| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|------------|-----------------|-----------------|---|--|--------------|------------------|-----------------|---------------|--------------|----------------|----------------|----------------|
| | | | 316 MISCELLANEOUS POWER PLANT EQUIPMENT | | | 2,868 | (44,625) | | 1,079 | 167,391 | 39,449 | 165,083 |
| 341 | | | OTHER PRODUCTION - STRUCTURES & IMPROVEMENTS | | | | | | | | | |
| | 10.00.00 | | WHOLE PLANT DEMOLITION | | | | | | | | | |
| | | 10.21.00 | CIVIL WORK | | | | | | | | | |
| | | | PAVED SURFACES, 6 IN THICK CIVIL WORK | OTHER PRODUCTION | 3,744.00 SY | - | - | - | 449 | 76,396 | 33,438 | 109,833 |
| | | | | | | | | | 449 | 76,396 | 33,438 | 109,833 |
| | | 10.22.00 | CONCRETE | | | | | | | | | |
| | | | FINGER RACK AREA MAT | U-1, 2004-005-SF-047A | 248.00 CY | - | - | - | 279 | 47,650 | 9,888 | 57,537 |
| | | | FINGER RACK AREA MAT | U-2, 2004-005-SF-047B | 236.00 CY | - | - | - | 266 | 45,344 | 9,409 | 54,753 |
| | | | WEST AREA MAT @ TUR-CTG1-01 | U-1, 2004-005-SF-053 | 142.00 CY | - | - | - | 160 | 27,283 | 5,661 | 32,945 |
| | | | WEST AREA MAT @ TUR-CTG2-01 | U-2, 2004-005-SF-054 | 143.00 CY | - | - | - | 161 | 27,475 | 5,701 | 33,177 |
| | | | MISC FDNS | U-0 2004-005-SF, 50% Steam Plant | 278.00 CY | - | - | - | 313 | 53,414 | 11,084 | 64,497 |
| | | | ADMINISTRATION/WAREHOUSE/SHOP WT BLDG | U-0, 130'X34'X2'+100'X11'X2' - 50% Steam Plant | 205.00 CY | - | - | - | 231 | 39,388 | 8,173 | 47,561 |
| | | | TOOL STORAGE BLDG (#127) CONCRETE | 50% Other Plant | 67.00 CY | - | - | - | 75 | 12,873 | 2,671 | 15,544 |
| | | | | | | | | | 1,484 | 253,427 | 52,588 | 306,015 |
| | | 10.24.00 | ARCHITECTURAL | | | | | | | | | |
| | | | ADMINISTRATION BUILDING | U-2, 70'X90'X25' HIGH - 50% Other Plant | 78,750.00 CF | - | - | - | 236 | 37,631 | 10,558 | 48,189 |
| | | | TOOL STORAGE BUILDING | U-0, 40'X90'25' STEEL BLDG - 50% Other Plant | 45,000.00 CF | - | - | - | 135 | 21,503 | 6,033 | 27,537 |
| | | | ELECTRICAL EQUIPMENT / CONTROL BUILDING ARCHITECTURAL | U-0, 30'X90'X25' - 50% Other Plant | 33,750.00 CF | - | - | - | 101 | 16,128 | 4,525 | 20,653 |
| | | | | | | | | | 473 | 75,262 | 21,116 | 96,378 |
| | | 10.31.00 | MECHANICAL EQUIPMENT | | | | | | | | | |
| | | | BRIDGE CRANE | | 230.00 TN | - | - | - | 621 | 95,006 | 22,789 | 117,795 |
| | | | MECHANICAL EQUIPMENT | | | | | | 621 | 95,006 | 22,789 | 117,795 |
| | | 10.35.00 | PIPING | | | | | | | | | |
| | | | FIRE LINES & HYDRANTS | U-0, ABANDON UNDERGND LINES REMOVE HYDRANTS, 50% Other Plant | 1.00 TN | - | - | - | 40 | 6,120 | 1,468 | 7,587 |
| | | | PIPING | | | | | | 40 | 6,120 | 1,468 | 7,587 |
| | | | WHOLE PLANT DEMOLITION | | | | | | 3,067 | 506,211 | 131,398 | 637,609 |
| | 18.00.00 | | SCRAP VALUE | | | | | | | | | |
| | | 18.10.00 | MIXED STEEL | | | | | | | | | |
| | | | CARBON STEEL | | -230.00 TN | - | (40,250) | - | | | | (40,250) |
| | | | CARBON STEEL | BUILDINGS | -60.16 TN | - | (10,528) | - | | | | (10,528) |
| | | | MIXED STEEL | | | | (50,778) | | | | | (50,778) |
| | | | SCRAP VALUE | | | | (50,778) | | | | | (50,778) |
| | 21.00.00 | | CIVIL WORK | | | | | | | | | |
| | | 21.18.00 | HAULING | | | | | | | | | |
| | | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 1,319.00 CY | 33,476 | - | - | | | | 33,476 |
| | | | HAULING TO RECYCLE FACILITY | CONCRETE PAVED SURFACES DEBRIS IS RECYCLED. NO DISPOSAL FEE | 624.00 CY | 15,837 | - | - | | | | 15,837 |
| | | | HAULING | | | 49,313 | | | | | | 49,313 |
| | | | CIVIL WORK | | | 49,313 | | | | | | 49,313 |
| | | | 341 OTHER PRODUCTION - STRUCTURES & IMPROVEMENTS | | | 49,313 | (50,778) | | 3,067 | 506,211 | 131,398 | 636,144 |
| 342 | | | OTHER PRODUCTION - FUEL HOLDERS, PRODUCERS AND ACCESSORIES | | | | | | | | | |
| | 10.00.00 | | WHOLE PLANT DEMOLITION | | | | | | | | | |
| | | 10.22.00 | CONCRETE | | | | | | | | | |
| | | | FUEL GAS COMPRESSOR FDN | U-0, 2004-005-SF-040 | 161.00 CY | - | - | - | 181 | 30,934 | 6,419 | 37,353 |
| | | | RAW WATER STORAGE TANK FDN | U-0 2004-005-SF-089 | 57.00 CY | - | - | - | 64 | 10,952 | 2,273 | 13,224 |
| | | | CHILLER PREFAB FLDG | U-3, S200 | 467.00 CY | - | - | - | 525 | 89,727 | 18,619 | 108,346 |
| | | | CONCRETE | | | | | | 771 | 131,613 | 27,311 | 158,924 |
| | | 10.31.00 | MECHANICAL EQUIPMENT | | | | | | | | | |
| | | | CT INLET CHILLER | U-1 | 220.00 TN | - | - | - | 446 | 68,157 | 16,348 | 84,505 |
| | | | CT INLET CHILLER | U-2 | 220.00 TN | - | - | - | 446 | 68,157 | 16,348 | 84,505 |
| | | | NATURAL GAS COMPRESSOR | U-0, 3 @ 2300 HP EA INCL VOLUME TANKS AND AFTERCOOLERS | 300.00 TN | - | - | - | 608 | 92,941 | 22,293 | 115,234 |

**SAN DIEGO GAS & ELECTRIC
 PALOMAR ENERGY CENTER
 DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS**



| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|----------|-------|----------|---|---|------------|------------------|------------------|---------------|---------------|------------------|----------------|------------------|
| | | 10.31.00 | MECHANICAL EQUIPMENT | | | | | | | | | |
| | | | RAW/FIRE WATER STORAGE TANK (#034) | U-0 730000 GALLON, 58' DIA X 40' HIGH - 50% Other Plant | 40.00 TN | - | - | | 108 | 16,523 | 3,963 | 20,486 |
| | | | FUEL GAS PREHEAT | U-3, 2 SHELL & TUBE HT EX | 1.00 TN | - | - | | 5 | 765 | 183 | 948 |
| | | | EVAP COOLERS BLEND WATER PUMPS | U-3, 2 @ 125 GPM & 148 TDH | 1.00 TN | - | - | | 5 | 765 | 183 | 948 |
| | | | PUMPS, FUEL OIL UNLOADING, FORWARDING, DIRTY CLEAN OIL TRANSFER | NOT INCLUDED | TN | - | - | | | | | |
| | | | WASTEWATER SUMP PUMPS | U-1, 1 @ 600 GPM & 46' TDH VERTICAL, 20HP | 0.20 TN | - | - | | 1 | 153 | 37 | 190 |
| | | | WASTEWATER SUMP PUMPS | U-2, 1 @ 600 GPM & 46' TDH VERTICAL, 20HP | 0.20 TN | - | - | | 1 | 153 | 37 | 190 |
| | | | MECHANICAL EQUIPMENT | | | | | | 1,619 | 247,612 | 59,394 | 307,006 |
| | | | WHOLE PLANT DEMOLITION | | | | | | 2,389 | 379,225 | 86,704 | 465,930 |
| 18.00.00 | | | SCRAP VALUE | | | | | | | | | |
| | | 18.10.00 | MIXED STEEL | | | | | | | | | |
| | | | CARBON STEEL | | -782.00 TN | - | (136,850) | - | | | | (136,850) |
| | | | MIXED STEEL | | | | | | | | | (136,850) |
| | | | SCRAP VALUE | | | | | | | | | (136,850) |
| 21.00.00 | | | CIVIL WORK | | | | | | | | | |
| | | 21.18.00 | HAULING | | | | | | | | | |
| | | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 685.00 CY | 17,385 | - | | | | | 17,385 |
| | | | HAULING | | | 17,385 | | | | | | 17,385 |
| | | | CIVIL WORK | | | 17,385 | | | | | | 17,385 |
| | | | 342 OTHER PRODUCTION - FUEL HOLDERS, PRODUCERS AND ACCESSORIES | | | 17,385 | (136,850) | | 2,389 | 379,225 | 86,704 | 346,465 |
| 344 | | | OTHER PRODUCTION - GENERATORS | | | | | | | | | |
| | | 10.00.00 | WHOLE PLANT DEMOLITION | | | | | | | | | |
| | | 10.22.00 | CONCRETE | | | | | | | | | |
| | | | COMBUSTION TURBINE AREA MAT @ NORTH END | U-1, 2004-005-SF-005 | 33.00 CY | - | - | | 37 | 6,340 | 1,316 | 7,656 |
| | | | COMBUSTION TURBINE AREA MAT @ NORTH END | U-2, 2004-005-SF-005 | 30.00 CY | - | - | | 34 | 5,764 | 1,196 | 6,960 |
| | | | PEECC & ACCESSORY MODULE FDN | U-1, 2004-005-SF-006 | 389.00 CY | - | - | | 438 | 74,741 | 15,509 | 90,250 |
| | | | COMBUSTION TURBINE AREA MAT AT EAST END | U-1, 2004-005-SF-007A | 63.00 CY | - | - | | 71 | 12,105 | 2,512 | 14,616 |
| | | | COMBUSTION TURBINE AREA MAT AT EAST END | U-2, 2004-005-SF-007B | 121.00 CY | - | - | | 136 | 23,248 | 4,824 | 28,073 |
| | | | TURBINE PEDESTAL | U-1, 2004-005-SF-001 | 742.00 CY | - | - | | 1,336 | 228,103 | 47,333 | 275,436 |
| | | | TURBINE PEDESTAL | U-2, 2004-005-SF-001 | 742.00 CY | - | - | | 1,336 | 228,103 | 47,333 | 275,436 |
| | | | CONCRETE | | | | | | 3,387 | 578,405 | 120,023 | 698,428 |
| | | 10.26.00 | MISCELLANEOUS STRUCTURAL ITEM | | | | | | | | | |
| | | | MISCELLANEOUS SMALL OBSTACLE REMOVAL FROM SITE | | 1.00 LT | - | - | | 500 | 76,494 | 18,348 | 94,843 |
| | | | MISCELLANEOUS STRUCTURAL ITEM | | | | | | 500 | 76,494 | 18,348 | 94,843 |
| | | 10.31.00 | MECHANICAL EQUIPMENT | | | | | | | | | |
| | | | COMBUSTION TURBINE | U-1, GE PG7241FA C/T - NOMINAL 170 MW, FIRING NATURAL GAS ONLY, W DRY LOW NOX BURNERS, INLET AIR FILTERS SILENCING & EVAP COOLERS, 180'X75'X31' INLET CHILLER COILS | 854.00 TN | - | - | | 2,989 | 457,284 | 109,686 | 566,970 |
| | | | COMBUSTION TURBINE | U-2, GE PG7241FA C/T - NOMINAL 170 MW, FIRING NATURAL GAS ONLY, W DRY LOW NOX BURNERS, INLET AIR FILTERS SILENCING & EVAP COOLERS, 180'X75'X31' INLET CHILLER COILS | 854.00 TN | - | - | | 2,989 | 457,284 | 109,686 | 566,970 |
| | | | CT LUBE OIL SYSTEM INCL FIN FAN COOLER | U-1 | 3.00 TN | - | - | | 12 | 1,836 | 440 | 2,276 |
| | | | CT LUBE OIL SYSTEM INCL FIN FAN COOLER | U-2 | 3.00 TN | - | - | | 12 | 1,836 | 440 | 2,276 |
| | | | MECHANICAL EQUIPMENT | | | | | | 6,002 | 918,239 | 220,253 | 1,138,492 |
| | | 10.35.00 | PIPING | | | | | | | | | |
| | | | PIPING, VALVES AND HANGERS | U1, 14,000 LF/UNIT - 33% Other Plant | 109.00 TN | - | - | | 221 | 33,768 | 8,100 | 41,868 |
| | | | PIPING, VALVES AND HANGERS | U2, 14,300 LF/UNIT - 33% Other Plant | 116.00 TN | - | - | | 235 | 35,937 | 8,620 | 44,557 |
| | | | PIPING | | | | | | 456 | 69,706 | 16,720 | 86,425 |
| | | | WHOLE PLANT DEMOLITION | | | | | | 10,344 | 1,642,844 | 375,345 | 2,018,189 |
| 18.00.00 | | | SCRAP VALUE | | | | | | | | | |
| | | 18.10.00 | MIXED STEEL | | | | | | | | | |

**SAN DIEGO GAS & ELECTRIC
 PALOMAR ENERGY CENTER
 DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS**



| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|------|----------|----------|--|--|--------------|------------------|------------------|---------------|---------------|------------------|----------------|------------------|
| | | 18.10.00 | MIXED STEEL CARBON STEEL | | -1,939.00 TN | - | (339,325) | - | | | | (339,325) |
| | | | MIXED STEEL | | | | (339,325) | | | | | (339,325) |
| | | | SCRAP VALUE | | | | (339,325) | | | | | (339,325) |
| | 21.00.00 | | CIVIL WORK | | | | | | | | | |
| | | 21.18.00 | HAULING HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 2,120.00 CY | 53,805 | - | | | | | 53,805 |
| | | | HAULING | | | 53,805 | | | | | | 53,805 |
| | | | CIVIL WORK | | | 53,805 | | | | | | 53,805 |
| | | | 344 OTHER PRODUCTION - GENERATORS | | | 53,805 | (339,325) | | 10,344 | 1,642,844 | 375,345 | 1,732,669 |
| 345 | | | OTHER PRODUCTION - ACCESSORY ELECTRIC EQUIPMENT | | | | | | | | | |
| | 10.00.00 | | WHOLE PLANT DEMOLITION | | | | | | | | | |
| | | 10.22.00 | CONCRETE CTG STEP-UP TRANSFORMER AND AUX TRNSFORMER FDNS | U-1, 2004-005-SF-029A | 250.00 CY | - | - | | 281 | 48,034 | 9,967 | 58,001 |
| | | | CTG STEP-UP TRANSFORMER AND AUX TRNSFORMER FDNS | U-2, 2004-005-SF-029B | 241.00 CY | - | - | | 271 | 46,305 | 9,609 | 55,913 |
| | | | EXCITATION XFMR & ISOLATION XFMR | U-2, 2004-005-SF-034 | 49.00 CY | - | - | | 55 | 9,415 | 1,954 | 11,368 |
| | | | NEW CT2 LCI W/PDC BUILDING | U-2, 12'X20'X2' | 17.00 CY | - | - | | 19 | 3,266 | 678 | 3,944 |
| | | | CONCRETE | | | | | | 627 | 107,020 | 22,207 | 129,227 |
| | | 10.41.00 | ELECTRICAL EQUIPMENT TRANSFORMERS | U-1, U-2, 33% Other Plant | 129.00 TN | - | - | | 345 | 46,684 | 12,649 | 59,333 |
| | | | MISC ELECT EQUIPMENT | U-1, U-2, 33% Other Plant | 60.00 TN | - | - | | 160 | 21,714 | 5,883 | 27,597 |
| | | | ELECTRICAL EQUIPMENT | U-0, CONTROL RM, 50% Other Plant | 1.00 LT | - | - | | 50 | 6,772 | 1,835 | 8,607 |
| | | | ELECTRICAL EQUIPMENT | | | | | | 555 | 75,170 | 20,367 | 95,537 |
| | | 10.42.00 | RACEWAY, CABLE TRAY, & CONDUIT CONDUIT | Other Plant 33% U-1 | 14,850.00 LF | - | - | | 149 | 22,719 | 5,449 | 28,168 |
| | | | CONDUIT | Other Plant 33% U-2 | 14,850.00 LF | - | - | | 149 | 22,719 | 5,449 | 28,168 |
| | | | CABLE TRAY | Other Plant 33% U-1 | 825.00 LF | - | - | | 33 | 5,049 | 1,211 | 6,260 |
| | | | CABLE TRAY | Other Plant 33% U-2 | 825.00 LF | - | - | | 33 | 5,049 | 1,211 | 6,260 |
| | | | RACEWAY, CABLE TRAY, & CONDUIT | | | | | | 363 | 55,535 | 13,321 | 68,856 |
| | | 10.43.00 | CABLE COPPER WIRE / CABLE - MEDIUM VOLTAGE | Other Plant 33% U-1 | 9,570.00 LF | - | - | | 96 | 14,641 | 3,512 | 18,153 |
| | | | COPPER WIRE / CABLE - MEDIUM VOLTAGE | Other Plant 33% U-2 | 9,570.00 LF | - | - | | 96 | 14,641 | 3,512 | 18,153 |
| | | | COPPER WIRE / CABLE - LOW VOLTAGE | Other Plant 33% U-1 | 33,000.00 LF | - | - | | 165 | 25,243 | 6,055 | 31,298 |
| | | | COPPER WIRE / CABLE - LOW VOLTAGE | Other Plant 33% U-2 | 33,000.00 LF | - | - | | 165 | 25,243 | 6,055 | 31,298 |
| | | | CABLE | | | | | | 521 | 79,768 | 19,134 | 98,902 |
| | | | WHOLE PLANT DEMOLITION | | | | | | 2,066 | 317,493 | 75,029 | 392,522 |
| | 18.00.00 | | SCRAP VALUE | | | | | | | | | |
| | | 18.10.00 | MIXED STEEL CARBON STEEL | CONDUIT, 1.5" DIA. AVG SIZE, 2.63 LBS/LF | -39.00 TN | - | (6,825) | - | | | | (6,825) |
| | | | CARBON STEEL | CABLE TRAY, 6 LBS/LF | -4.96 TN | - | (868) | - | | | | (868) |
| | | | CARBON STEEL | MISC ELECT EQUIPMENT | -60.00 TN | - | (10,500) | - | | | | (10,500) |
| | | | STEEL / COPPER MIX - LARGE TRANSFORMER > 100 KVA | | -129.00 TN | - | (45,150) | - | 0 | | | (45,150) |
| | | | MIXED STEEL | | | | (63,343) | | 0 | | | (63,343) |
| | | 18.30.00 | COPPER #2 SOLID COPPER / TUBING | BUS BAR | -0.33 TN | - | (2,028) | - | | | | (2,028) |
| | | | #2 INSULATED COPPER WIRE | | -2.00 TN | - | (4,880) | - | | | | (4,880) |
| | | | COPPER | | | | (6,908) | | | | | (6,908) |
| | | | SCRAP VALUE | | | | (70,251) | | 0 | | | (70,251) |
| | 21.00.00 | | CIVIL WORK | | | | | | | | | |
| | | 21.18.00 | HAULING HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 557.00 CY | 14,137 | - | | | | | 14,137 |
| | | | HAULING | | | 14,137 | | | | | | 14,137 |
| | | | CIVIL WORK | | | 14,137 | | | | | | 14,137 |
| | | | 345 OTHER PRODUCTION - ACCESSORY ELECTRIC EQUIPMENT | | | 14,137 | (70,251) | | 2,066 | 317,493 | 75,029 | 336,407 |

**APPENDIX C. EXPLANATION OF VARIANCE
FROM THE PREVIOUS COST STUDY**

| Cost Category | 2021 Cost Estimate | 2016 Cost Estimate | Delta | % of total cost | Discussion |
|--|---------------------|---------------------|---------------|-----------------|------------|
| Labor | | | | | |
| Labor - Direct | \$5,180,119 | | | | |
| Labor Supervision | \$310,807 | | | | |
| Show-up time | \$103,602 | | | | |
| Construction Management | \$559,453 | | | | |
| Field Office Expenses | \$123,080 | | | | |
| Safety | \$110,520 | | | | |
| Temporary Facilities | \$84,086 | | | | |
| Mob/Demob | \$88,617 | | | | |
| Small tools & consumables | \$55,945 | | | | |
| General Liability Insurance | \$55,945 | | | | |
| Constr Equip Mob/Demob | \$144,008 | | | | |
| Legal Expenses/Claims | \$13,091 | | | | |
| General Conditions (Indirect) - Labor | \$1,649,154 | | | | |
| Subcontract | \$372,500 | | | | |
| Construction Equipment | \$1,440,078 | | | | |
| Labor Subtotal | \$8,641,851 | \$7,308,897 | 18.2% | 11.1% | |
| Material | | | | | |
| Material w/o freight | \$762,007 | | | | |
| General Conditions -Freight on Material | \$38,100 | | | | |
| Material Subtotal | \$800,107 | \$985,693 | -18.8% | -1.5% | |
| Scrap | | | | | |
| Mixed Steel | -\$1,859,734 | -\$847,989 | | | |
| Copper | -\$20,785 | -\$1,508,560 | | | |
| Subtotal Scrap Value | -\$1,880,519 | -\$1,941,577 | -3.1% | 0.5% | |
| Subtotal - Direct & Indirect Demolition | \$7,561,439 | \$6,353,013 | 19.0% | 10.1% | |
| Contractor G&A and Profit | | | | | |
| Contractor G&A | \$620,864 | \$365,445 | 69.9% | | |
| Contractor Profit | \$886,951 | \$663,567 | 33.7% | | |
| Subcontractor Contractor G&A and Profit | \$1,507,815 | \$1,029,012 | 46.5% | 4.0% | |
| Indirect | | | | | |
| Engineering | \$231,000 | \$220,000 | | | |
| Construction Management | \$0 | \$147,641 | | | |
| Other SDGE Internal Costs | \$902,000 | \$0 | | | |
| Subtotal Indirect Costs | \$1,133,000 | \$367,641 | 208% | 6.4% | |
| Contingency | \$1,812,416 | \$2,326,564 | -22.1% | -4.3% | |
| Total | \$12,014,670 | \$10,076,230 | 19.2% | | |
| SCRAP | \$/ton | tons | \$/ton | tons | |
| Carbon Steel | \$175 | 9,747 | \$87 | 9,747 | |
| Steel/Copper mix (large transformers) | \$350 | 390 | | | |
| # 1 Copper | | | \$3,460 | 436 | |
| #2 Copper | \$6,145 | 1 | | | |
| #2 Insulated Copper Wire | \$2,440 | 6 | | | |
| Labor hours | 63,004 hours | 65,280 hours | -3.5% | | |

The labor hours for the 2021 cost estimate are -3.5% less than the 2016 cost estimate. The main reason is that the 2021 cost estimate includes subcontracts (w/o labor hours), based on updated S&L standards, and no planting or seeding.

SL-016628.B_SDGE Decom(Miramar

Decommissioning Study

**Prepared for
San Diego Gas & Electric Company
Miramar Energy Facility**

Prepared by Sargent & Lundy

LEGAL NOTICE

This deliverable was prepared by Sargent & Lundy, L.L.C. (S&L) expressly for the sole use of San Diego Gas & Electric Company (Client) in accordance with the contract agreement between S&L and Client. This deliverable was prepared using the degree of skill and care ordinarily exercised by engineers practicing under similar circumstances. Client acknowledges: (1) S&L prepared this deliverable subject to the particular scope limitations, budgetary and time constraints, and business objectives of Client; (2) information and data provided by others, including Client, may not have been independently verified by S&L; and (3) the information and data contained in this deliverable are time-sensitive and changes in the data, applicable codes, standards, and acceptable engineering practices may invalidate the findings of this deliverable. Any use or reliance upon this deliverable by third parties shall be at their sole risk.

Sargent & Lundy is one of the oldest and most experienced full-service architect engineering firms in the world. Founded in 1891, the firm is a global leader in power and energy with expertise in grid modernization, renewable energy, energy storage, nuclear power, and fossil fuels. Sargent & Lundy delivers comprehensive project services—from consulting, design, and implementation to construction management, commissioning, and operations/maintenance—with an emphasis on quality and safety. The firm serves public and private sector clients in the power and energy, gas distribution, industrial, and government sectors.

55 East Monroe Street • Chicago, IL 60603-5780 USA • 312-269-2000

VERSION LOG

| Version | Issue Date | Sections Modified |
|----------|------------------|-------------------|
| Draft v0 | December 3, 2021 | Initial Issue |
| Final | April 4, 2022 | ES, 2, |

ISSUE SUMMARY AND APPROVAL PAGE

This is to certify that this document has been prepared, reviewed, and approved in accordance with Sargent & Lundy's Standard Operating Procedure SOP-0405, which is based on ANSI/ISO/ASSQC Q9001 Quality Management Systems.

Contributors

Prepared by:

| Name | Title | Section(s) Prepared | Signature | Date |
|----------------|---------------------------|---------------------------|-----------|----------|
| Kyle E. Folken | Energy Consultant | ES, Section 1, Section 2, | | 4/4/2022 |
| Gregory Amen | Cost Information Division | Section 3, Appendix A | | 4/4/2022 |

Reviewed by:

| Name | Title | Section(s) Reviewed | Signature | Date |
|--------------------|---|-----------------------|-----------|----------|
| Borko Andric | Manager | Section 3, Appendix A | | 4/4/2022 |
| Craig Gitchell | Senior Energy Consultant | All | | 4/4/2022 |
| Robert. P. Charles | Senior Principal Consultant & Project Manager | All | | 4/4/2022 |

Approved by:

Kevin C. Hopkins
Principal Consultant & Project
Manager

April 4, 2022

Date

TABLE OF CONTENTS

| | |
|---------------------------------------|----------|
| EXECUTIVE SUMMARY | I |
| METHODOLOGY | I |
| CONCEPTUAL COST ESTIMATE | I |
| 1. INTRODUCTION | 1 |
| 1.1. SCOPE OF WORK | 1 |
| 1.2. SARGENT & LUNDY BACKGROUND | 1 |
| FACILITY DESCRIPTION..... | 1 |
| 1.3. | 1 |
| 2. COST ESTIMATE | 2 |
| 2.1. METHODOLOGY | 2 |
| 2.2. COST ESTIMATE SUMMARY..... | 3 |
| 3. BASIS OF ESTIMATE | 5 |
| 4. REFERENCES | 9 |

TABLES

| | |
|--|----|
| TABLE ES-1 — MIRAMAR COST ESTIMATE SUMMARY | II |
| TABLE ES-2 — MIRAMAR COST ESTIMATE SUMMARY BY FERC ACCOUNT | II |
| TABLE 2-1 — MIRAMAR COST ESTIMATE SUMMARY | 3 |
| TABLE 2-2 — MIRAMAR COST ESTIMATE SUMMARY BY FERC ACCOUNT | 4 |
| TABLE 3-1 — SCRAP VALUE..... | 6 |
| TABLE 3-2 – SDG&E INTERNAL COSTS IN SUPPORT OF DECOMMISSIONING | 6 |

APPENDIXES

| |
|--|
| APPENDIX A. CONCEPTUAL ESTIMATE OF COST TO DISMANTLE MIRAMAR ENERGY FACILITY |
| APPENDIX B. CONCEPTUAL ESTIMATE OF COST — FERC ACCOUNT |
| APPENDIX C. EXPLANATION OF VARIANCE FROM THE PREVIOUS COST STUDY |

ACRONYMS AND ABBREVIATIONS

| Acronym/Abbreviation | Definition/Clarification |
|----------------------|--------------------------------------|
| CT | Combustion Turbine |
| FERC | Federal Energy Regulatory Commission |
| G&A | General & Administrative |
| GSU | Generator Step-up Transformer |
| Owner | San Diego Gas & Electric Company |
| PCB | Polychlorinated biphenyl |
| S&L | Sargent & Lundy, L.L.C. |
| SCR | Selective Catalytic Reduction |
| SDG&E | San Diego Gas & Electric Company |

EXECUTIVE SUMMARY

Sargent & Lundy was contracted by San Diego Gas & Electric Company (“SDG&E” or the “Owner”) to perform an independent conceptual cost estimate for dismantlement and an estimate of the average service life of the facility’s peer group for the Miramar Energy Facility (Miramar) in San Diego, California. The facility consists of two natural gas-fired combustion turbines in peaking service with a combined output rating of 92 MW. The work scope included updating the 2016 conceptual demolition cost estimate and the benchmarking analysis for the facility.

METHODOLOGY

The S&L methodology for developing the cost estimate consist of three elements: (1) S&L experience in developing plant demolition costs and the existing S&L database for numerous other projects; (2) use of the unit cost factor methodology; and (3) quotes from previous projects for similar activities. The cost estimate was developed based on the drawings, documents, and data provided by SDG&E. These drawings and documents were used to estimate the building foundation sizes, building volumes, steel quantities, and the quantity of piping, valves, and other equipment. A site walkdown was performed to conduct a review of the site for dismantlement and determine any specific site-unique requirements. This site walkdown was performed in 2016; however, recent discussions with the Owner and facility management confirmed that no significant modifications have occurred since that time. This information was used with unit cost factors developed by S&L based on industry data and our experience. Unit cost factors for concrete removal, steel removal, cutting costs etc. were developed from labor and material cost information. S&L estimated the quantities of recoverable metals that could be recovered and sold for scrap. The estimate includes the value of scrap metals; however, equipment is assumed to have no resale or other salvage value besides the value of scrap metal at the end of its life.

The benchmarking analysis considers publicly available data to determine the average service life of similar facilities.

CONCEPTUAL COST ESTIMATE

The summary of the cost estimate for decommissioning Miramar is shown in Table ES-1. The cost estimate broken into FERC accounts is shown in Table ES-2. All costs are in 2021 US dollars, and the total is the same in both tables, \$1,773,720. The decommissioning costs are expected to increase by the end of service life of the asset due to escalation and other factors.

Table ES-1 — Miramar Cost Estimate Summary

| Description | Total Cost | Subtotal |
|---|--------------------|-----------|
| Demolition Direct Costs | \$933,065 | – |
| Labor | – | \$658,508 |
| Subcontracts | – | \$48,240 |
| Equipment | – | \$192,047 |
| Material | – | \$34,270 |
| General Conditions (Decommissioning Contractor Indirect) Costs | \$394,285 | – |
| Scrap Value | (\$185,132) | – |
| Subtotal Demolition Contractor Costs | \$1,142,218 | – |
| –Project Indirect Costs | \$376,000 | – |
| Engineering | – | \$66,000 |
| SDG&E Internal Costs | – | \$310,000 |
| Contingency Costs | \$255,502 | – |
| Total Demolition Costs | \$1,773,720 | – |

Table ES-2 — Miramar Cost Estimate Summary by FERC Account

| FERC No. | Description | Total Cost |
|----------|--|--------------------|
| 341 | Other Production – Structures & Improvements | \$327,239 |
| 342 | Other Production – Fuel Holders, Producers and Accessories | \$213,446 |
| 344 | Other Production – Generators | \$799,785 |
| 345 | Other Production – Accessory Electric Equipment | \$433,251 |
| | General Conditions | Included Above |
| | Engineering | Included Above |
| | Contingency | Included Above |
| | Total Project Cost | \$1,773,720 |

1. INTRODUCTION

1.1. SCOPE OF WORK

Sargent & Lundy (S&L) was contracted by San Diego Gas & Electric Company (“SDG&E” or the “Owner”) to perform an independent conceptual cost estimate for the dismantlement of the Miramar Energy Facility (Miramar) and estimate the average service life of the facility’s peer group. The work scope included updating the 2016 conceptual demolition cost estimate, report, and benchmarking analysis.

1.2. SARGENT & LUNDY BACKGROUND

S&L has been dedicated to providing complete engineering and environmental services exclusively to the power industry since 1891. Through work with various utilities, lending institutions, and developers over the years, the Sargent & Lundy Consulting Group has become one of the premier power project consultants in the power industry. This commitment to quality is proven by the successful completion of the ISO 9001 certification audit. S&L’s experience encompasses independent engineer services—including decommissioning cost estimation and average service life evaluation—for both global and domestic electric power assets.

S&L has extensive decommissioning and related services experience, including power plant dismantling, demolition, and layup for fossil fuel, renewable energy, and nuclear plants. This includes decommissioning cost estimates, decommissioning studies, and related services for 18 clients at more than 70 stations. S&L also has extensive experience providing clients with testimony services.

Having engineered over 958 power plant units, S&L has both the benefit of extensive design experience—supported with feedback from operating plants—and individuals with extensive plant operations experience to support consulting services such as those performed for Miramar.

1.3. FACILITY DESCRIPTION

The Miramar Energy Facility in central San Diego consists of two simple-cycle GE LM6000 combustion turbines (CTs) firing only natural gas. The Miramar facility is used for peaking duty and is capable of generating 92 MW. The facility uses the latest generation of peaking turbines with water injection and selective catalytic reduction for nitrogen oxide (NOX) reduction. The Miramar CTs can be started remotely from the Palomar control room and are operated and maintained by personnel based out of the Palomar Energy Center. The first unit at Miramar went into service in 2005. The second turbine is a virtual replica of the first, with a capacity of approximately 46 MW of peaking energy and capacity for SDG&E’s service territory. The second unit went into commercial operation in 2009.

2. COST ESTIMATE

2.1. METHODOLOGY

The methodology used for developing the cost estimate includes a combination of deterministic and stochastic methods. Deterministic methods were used based on the quantity and size of equipment (e.g., the number of foundations, linear feet of piping, equipment, etc.). Stochastic methods were also used if quantitative information (e.g., fire lines and hydrants, miscellaneous electrical equipment, etc.) was unavailable.

The cost estimate was developed based on drawings, documents, and data provided by the Owner. These drawings and documents were used to estimate the building foundation sizes, building volumes, steel quantities, and the quantity of piping, valves, and other equipment.

The S&L methodology for developing the cost estimate consist of three elements: (1) S&L experience in developing plant demolition cost and the existing S&L database for numerous other projects; (2) use of the unit cost factor methodology; and (3) quotes from previous projects for similar activities.

Cost estimates were created using the S&L cost model format and the S&L cost database. The estimates developed include both summaries and details for each type of work performed, indirect costs, and contingencies. The cost estimate database report lists costs by buildings, plant systems, and several other categories.

An inventory of plant piping, valves, equipment, HVAC ducts, concrete, galleries, cable tray, and other equipment was developed based on review of drawings and a site walkdown to conduct a review of the site for dismantlement and determine any specific site-unique requirements. This information was used with unit cost factors developed by S&L based on industry data and experience. Unit cost factors for concrete removal, steel removal, cutting costs, and other tasks were developed from labor and material cost information. S&L also estimated the quantities of recoverable metals that could be recovered and sold for scrap. The estimate includes the value of scrap metals; however, equipment is assumed to have no resale or other salvage value besides the value of scrap metal.

S&L worked from site general arrangement drawings and company documentation for the facilities, including information about any existing metal cleaning storage ponds, asbestos inventories, polychlorinated biphenyl (PCB) inventories, or sludge ponds. S&L relied on SDG&E to identify the location of environmental issues that need to be considered in the estimates, since S&L's scope of work excludes a detailed survey and testing program to identify such problems.

2.2. COST ESTIMATE SUMMARY

The summary of the cost estimate for decommissioning Miramar is shown in Table 2-1. The commercial and technical basis for the estimate is described in Section 4, and the detailed estimate is included in Appendix A. The summary breakdown into FERC accounts is shown in

Table 2-2, and the detailed allocation of FERC accounts is shown in Appendix B. All costs are in 2021 U.S. dollars. The decommissioning costs are expected to increase by the end of the service life of the asset due to escalation and other factors.

The 2021 cost estimate format was changed to be consistent with S&L's current standards. The variance between the 2021 and 2016 cost estimate is shown in Appendix C.

Table 2-1 — Miramar Cost Estimate Summary

| Description | Total Cost | Subtotal |
|---|--------------------|-----------|
| Demolition Direct Costs | \$933,065 | – |
| Labor | – | \$658,508 |
| Subcontracts | – | \$48,240 |
| Equipment | – | \$192,047 |
| Material | – | \$34,270 |
| General Conditions (Decommissioning Contractor Indirect) Costs | \$394,285 | – |
| Scrap Value | (\$185,132) | – |
| Subtotal Demolition Contractor Costs | \$1,142,218 | – |
| –Project Indirect Costs | \$376,000 | – |
| Engineering | – | \$66,000 |
| SDG&E Internal Costs | – | \$310,000 |
| Contingency Costs | \$255,502 | – |
| Total Demolition Costs | \$1,773,720 | – |

Table 2-2 — Miramar Cost Estimate Summary by FERC Account

| FERC No. | Description | Total Cost |
|-----------------|--|--------------------|
| 341 | Other Production – Structures & Improvements | \$327,239 |
| 342 | Other Production – Fuel Holders, Producers and Accessories | \$213,446 |
| 344 | Other Production – Generators | \$799,785 |
| 345 | Other Production – Accessory Electric Equipment | \$433,251 |
| | General Conditions | Included Above |
| | Engineering | Included Above |
| | Contingency | Included Above |
| | Total Project Cost | \$1,773,720 |

3. BASIS OF ESTIMATE

The basis for the cost estimate is as follows:

1. Construction Labor Wages

Craft labor rates (craft hourly rate) for the cost estimate are based on the prevailing wages for San Diego, California as published in "R.S. Means Labor Rates for the Construction Industry", (2021). These prevailing rates are representative of union or non-union rates, whichever is prevailing in the area. Costs have been added to cover social security, workmen's compensation, and federal and state unemployment insurance. The resulting burdened craft rates were then used to develop typical crew rates applicable to the task being performed.

2. Labor Work Schedule and Incentives

- The labor estimate is based on a 40-hour workweek with no per diem or other labor incentives.
- An allowance for arrival time is included if workers arrive and are then sent home.

3. Quantity Sources

Quantities of pieces of equipment and/or bulk material commodities used in this cost estimate were developed from supplied engineering information from the sites and the S&L database.

4. General Conditions Cost

Allowances were included for the decommissioning contractor indirect costs in the cost estimate as direct costs as noted for the following:

- Labor supervision (additional compensation for labor foreman/supervisors)
- Construction management
- Field office expenses
- Safety
- Temporary facilities
- Mobilization/demobilization
- Legal expenses/claims
- Small tools and consumables
- General liability insurance
- Construction equipment mobilization/demobilization
- Freight on material
- Contractor general and administrative costs (7% of labor [direct labor, additional labor cost, site overheads, and other construction indirect cost], material [direct material cost and freight cost], and equipment)

- Contractor's profit (10% of labor [direct labor, additional labor cost, site overheads, and other construction indirect cost], material [direct material cost and freight cost], and equipment)

5. Scrap

Scrap metals are a globally traded commodity and are part of the larger metals industry. The value of scrap metal is subject to constantly changing economic conditions; as such, the price of mixed steel, stainless steel, copper, and aluminum can vary greatly over time as a result of global supply and demand. The value of scrap for this study was determined by a 12-month average from *Scrap Metals MarketWatch*¹ (November 2020–October 2021) for the West Coast (Zone 1) of the United States. The values obtained are delivered prices to the recycler. Transportation cost to the recycler is estimated at \$30/ton, resulting in the values shown in Table 3-1.

Table 3-1 — Scrap Value

| Commodity | Scrap Value (\$/ton) |
|--------------------------|----------------------|
| Carbon Steel | 175 |
| #2 Copper | 6,145 |
| #2 Insulated Copper Wire | 2,440 |

Note: 1 ton = 2000 lbs.

6. Project Schedule

Miramar has a 12-month construction schedule.

7. Indirect Expenses

- Engineering is included to cover preparation of the decommissioning work specification, the engineering required to place the plant in a safe shutdown, and any unique engineering required during demolition.
- SDG&E internal costs are included to cover costs in support of decommissioning the facility.

Table 3-2 – SDG&E Internal Costs in Support of Decommissioning

| Activity | Estimated Cost |
|--|------------------|
| Labor to prepare the site for demolition, including drain oils, drain reagents, de-energization of the power buses, etc. | \$120,000 |
| Site security | \$60,000 |
| Subcontracts to remove chemicals, oils, and reagents from the site | \$50,000 |
| SDG&E project management, permitting, and procurement | \$80,000 |
| Total | \$310,000 |

¹ www.americanrecycler.com

8. Escalation Rates

Not included.

9. Sales and Use Taxes

Sales and use taxes not included.

10. Contingency

- A 15% contingency is applied for labor, material, equipment, subcontracting, and indirect costs. General conditions (indirect demolition contractor costs) are allocated across labor, material, and equipment.
- There is no contingency on scrap value

11. Contract Basis for Estimate

The contracting strategy is a multiple lump sum for the estimate.

12. Assumptions

- The facility will be in safe-shutdown mode and ready for a decommissioning contractor to start work.
- All chemicals and lubricating oils will be removed from the facilities to be demolished by the utility before demolition.
- No extraordinary environmental costs for demolition will be needed.
- There will be no PCBs on site at the time of demolition.
- Switchyards within the plant boundaries are not part of the scope, nor are access roads to these facilities.
- All items above grade and to a depth of one foot including foundations will be demolished. Any other items buried more than one foot deep will remain in place.
- Underground piping will be abandoned in place.
- Underground piping larger than four feet in diameter will be filled with sand or slurry and capped at the ends to prevent collapse (none noted at this site). Non-metal pipe will be collapsed.
- All demolished materials are considered debris, except for organic combustibles and non-embedded metals which have scrap value.
- The basis for salvage estimating is for scrap value only. No resale of equipment or material is included.
- Handling on-site and off-site disposal of hazardous materials will be performed in compliance with methods approved by SDG&E's Environmental Services Department.
- All borrow (fill) material is assumed to be from offsite sources.

- Catalyst is assumed to be removed and returned to the original equipment manufacturer before demolition.

4. REFERENCES

1. Sargent & Lundy Cost Data Base
2. RSMeans Cost Data, 2021.
3. Engineering Drawings, Equipment Lists, and other information provided by San Diego Gas & Electric.
4. 2020 Form EIA-860 Data - Schedule 3, 'Generator Data' (Retired & Canceled Units Only)
5. Metal Scrap Values in the United States – West Coast (Zone 1) (www.americanrecycler.com).

**APPENDIX A. CONCEPTUAL ESTIMATE OF COST
TO DISMANTLE MIRAMAR ENERGY FACILITY**

**SAN DIEGO GAS & ELECTRIC
MIRAMAR ENERGY FACILITY
DECOMMISSIONING STUDY**

| | |
|-------------------------|------------|
| Estimator | GA |
| Labor rate table | 21CASAN |
| Project No. | A14520.001 |
| Estimate Date | 11/30/21 |
| Reviewed By | BA |
| Approved By | BA |
| Estimate No. | 30598C |

**SAN DIEGO GAS & ELECTRIC
 MIRAMAR ENERGY FACILITY
 DECOMMISSIONING STUDY**



| Group | Description | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|----------|------------------------|------------------|------------------|---------------|--------------|----------------|----------------|----------------|
| 10.00.00 | WHOLE PLANT DEMOLITION | | | | 7,862 | 653,764 | 187,043 | 840,806 |
| 18.00.00 | SCRAP VALUE | | (185,132) | | 0 | (7) | (1) | (185,140) |
| 21.00.00 | CIVIL WORK | 48,240 | | 34,270 | 52 | 4,752 | 5,005 | 92,267 |
| | TOTAL DIRECT | 48,240 | (185,132) | 34,270 | 7,914 | 658,508 | 192,047 | 747,933 |

**SAN DIEGO GAS & ELECTRIC
 MIRAMAR ENERGY FACILITY
 DECOMMISSIONING STUDY**



Estimate Totals

| Description | Amount | Totals | Hours |
|-------------------------------------|------------------|------------------|-------|
| Labor | 658,508 | | 7,914 |
| Material | 34,270 | | |
| Subcontract | 48,240 | | |
| Construction Equipment | 192,047 | | |
| Scrap Value | <u>(185,132)</u> | | |
| | 747,933 | 747,933 | |
| General Conditions | | | |
| Additional Labor Costs | | | |
| 90-1 Labor Supervision | 39,510 | | |
| 90-2 Show-up Time | 13,170 | | |
| 90-3 Cost Due To OT 5-10's | | | |
| 90-4 Cost Due To OT 6-10's | | | |
| 90-5 Per Diem | | | |
| Site Overheads | | | |
| 91-1 Construction Management | 71,119 | | |
| 91-2 Field Office Expenses | 15,646 | | |
| 91-3 Material&Quality Control | | | |
| 91-4 Site Services | | | |
| 91-5 Safety | 14,050 | | |
| 91-6 Temporary Facilities | 10,689 | | |
| 91-7 Temporary Utilities | | | |
| 91-8 Mobilization/Demob. | 11,265 | | |
| 91-9 Legal Expenses/Claims | 1,664 | | |
| Other Construction Indirects | | | |
| 92-1 Small Tools & Consumables | 7,112 | | |
| 92-2 Scaffolding | | | |
| 92-3 General Liability Insur. | 7,112 | | |
| 92-4 Constr. Equip. Mob/Demob | 19,205 | | |
| 92-5 Freight on Material | 1,714 | | |
| 92-6 Freight on Scrap | | | |
| 92-7 Sales Tax | | | |
| 92-8 Contractors G&A | 74,953 | | |
| 92-9 Contractors Profit | <u>107,076</u> | | |
| | 394,285 | 1,142,218 | |
| Project Indirect Costs | | | |
| 93-1 Engineering Services | 66,000 | | |
| 93-2 CM Support | | | |
| 93-3 Start-Up/Commissioning | | | |
| 93-4 Start-Up/Spare Parts | | | |
| 93-5 Excess Liability Insur. | | | |
| 93-6 Sales Tax On Indirects | | | |
| 93-7 SDG&E Internal Costs | 310,000 | | |
| 93-8 EPC Fee | <u></u> | | |
| | 376,000 | 1,518,218 | |
| Contingency | | | |
| 94-1 Contingency on Const Eq | 36,585 | | |
| 94-3 Contingency on Material | 6,315 | | |
| 94-4 Contingency on Labor | 148,966 | | |
| 94-5 Contingency on Subcontr. | 7,236 | | |
| 94-6 Contingency on Scrap | | | |
| 94-7 Contingency on Indirect | <u>56,400</u> | | |
| | 255,502 | 1,773,720 | |
| Escalation | | | |
| 96-1 Escalation on Const Equip | | | |
| 96-3 Escalation on Material | | | |
| 96-4 Escalation on Labor | | | |
| 96-5 Escalation on Subcontract | | | |
| 96-6 Escalation on Scrap | | | |
| 96-7 Escalation on Indirects | | | |
| | | 1,773,720 | |
| 98 Interest During Constr | | 1,773,720 | |
| Total | | 1,773,720 | |

**SAN DIEGO GAS & ELECTRIC
 MIRAMAR ENERGY FACILITY
 DECOMMISSIONING STUDY**



| Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|-----------------|-----------------|-----------------------------------|--|--------------|------------------|-------------|---------------|--------------|----------------|---------------|----------------|
| 10.00.00 | | WHOLE PLANT DEMOLITION | | | | | | | | | |
| | 10.21.00 | CIVIL WORK | | | | | | | | | |
| | | PAVED SURFACES, 6 IN THICK | | 3,010.00 SY | - | - | | 361 | 32,093 | 16,680 | 48,773 |
| | | CIVIL WORK | | | | | | 361 | 32,093 | 16,680 | 48,773 |
| | 10.22.00 | CONCRETE | | | | | | | | | |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | AUX SKID, U-1 | 58.00 CY | - | - | | 65 | 5,823 | 1,435 | 7,258 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | AUX SKID, U-2 | 58.00 CY | - | - | | 65 | 5,823 | 1,435 | 7,258 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | WATER WASH PAD, U-1 | 6.00 CY | - | - | | 7 | 602 | 148 | 751 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | WATER WASH PAD, U-2 | 6.00 CY | - | - | | 7 | 602 | 148 | 751 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | 15KV SWITCHGEAR, U-1 | 12.00 CY | - | - | | 14 | 1,205 | 297 | 1,502 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | 15KV SWITCHGEAR, U-2 | 12.00 CY | - | - | | 14 | 1,205 | 297 | 1,502 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | ENGINE REMOVAL, U-1 | 2.00 CY | - | - | | 2 | 201 | 49 | 250 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | ENGINE REMOVAL, U-2 | 2.00 CY | - | - | | 2 | 201 | 49 | 250 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | FUEL GAS FILTER SEPARATOR, U-1 | 4.00 CY | - | - | | 5 | 402 | 99 | 501 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | FUEL GAS FILTER SEPARATOR, U-2 | 4.00 CY | - | - | | 5 | 402 | 99 | 501 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | OUTLET DUCT A, U-1 | 4.00 CY | - | - | | 5 | 402 | 99 | 501 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | OUTLET DUCT A, U-2 | 4.00 CY | - | - | | 5 | 402 | 99 | 501 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | OUTLET DUCT B, U-1 | 3.00 CY | - | - | | 3 | 301 | 74 | 375 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | OUTLET DUCT B, U-2 | 3.00 CY | - | - | | 3 | 301 | 74 | 375 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | OUTLET DUCT C, U-1 | 3.00 CY | - | - | | 3 | 301 | 74 | 375 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | OUTLET DUCT C, U-2 | 3.00 CY | - | - | | 3 | 301 | 74 | 375 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | OUTLET DUCT D, U-1 | 10.00 CY | - | - | | 11 | 1,004 | 247 | 1,251 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | OUTLET DUCT D, U-2 | 10.00 CY | - | - | | 11 | 1,004 | 247 | 1,251 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | AUX TRANSFORMER 480V | 29.00 CY | - | - | | 33 | 2,911 | 717 | 3,629 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | SWITCHGEAR, U-1 | | | | | | | | |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | AUX TRANSFORMER 480V | 29.00 CY | - | - | | 33 | 2,911 | 717 | 3,629 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | SWITCHGEAR, U-2 | | | | | | | | |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | AUX ELECTRIC ENCLOSURE, U-1 | 8.00 CY | - | - | | 9 | 803 | 198 | 1,001 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | AUX ELECTRIC ENCLOSURE, U-2 | 8.00 CY | - | - | | 9 | 803 | 198 | 1,001 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | STACK, U-1 | 36.00 CY | - | - | | 41 | 3,614 | 891 | 4,505 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | STACK, U-2 | 36.00 CY | - | - | | 41 | 3,614 | 891 | 4,505 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | CEMS, U-1 | 3.00 CY | - | - | | 3 | 301 | 74 | 375 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | CEMS, U-2 | 3.00 CY | - | - | | 3 | 301 | 74 | 375 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | AMMONIA EVAPORATION SKID, U-1 | 8.00 CY | - | - | | 9 | 803 | 198 | 1,001 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | AMMONIA EVAPORATION SKID, U-2 | 8.00 CY | - | - | | 9 | 803 | 198 | 1,001 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | EMERGENCY EYEWASH, U-1 | 1.00 CY | - | - | | 1 | 100 | 25 | 125 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | EMERGENCY EYEWASH, U-2 | 1.00 CY | - | - | | 1 | 100 | 25 | 125 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | BOP MCC, U-1 | 4.00 CY | - | - | | 5 | 402 | 99 | 501 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | BOP MCC, U-2 | 4.00 CY | - | - | | 5 | 402 | 99 | 501 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | TEMPERING AIR DUCT, U-1 | 13.00 CY | - | - | | 15 | 1,305 | 322 | 1,627 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | TEMPERING AIR DUCT, U-2 | 13.00 CY | - | - | | 15 | 1,305 | 322 | 1,627 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | FIN FAN COOLER, U-1 | 16.00 CY | - | - | | 18 | 1,606 | 396 | 2,002 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | FIN FAN COOLER, U-2 | 16.00 CY | - | - | | 18 | 1,606 | 396 | 2,002 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | WATER TREATMENT, U-1 | 60.00 CY | - | - | | 68 | 6,024 | 1,484 | 7,508 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | WATER TREATMENT, U-2 | 60.00 CY | - | - | | 68 | 6,024 | 1,484 | 7,508 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | DEMINERALIZED WATER PUMP, U-1 | 29.00 CY | - | - | | 33 | 2,911 | 717 | 3,629 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | DEMINERALIZED WATER PUMP, U-2 | 29.00 CY | - | - | | 33 | 2,911 | 717 | 3,629 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | DEMINERALIZED WATER TANK, U-1 | 60.00 CY | - | - | | 68 | 6,024 | 1,484 | 7,508 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | DEMINERALIZED WATER TANK, U-2 | 60.00 CY | - | - | | 68 | 6,024 | 1,484 | 7,508 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | SERVICE BUILDING AND CONTROL ROOM | 33.00 CY | - | - | | 37 | 3,313 | 816 | 4,129 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | AIR COMPRESSOR | 13.00 CY | - | - | | 15 | 1,305 | 322 | 1,627 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | BLACK START DIESEL GENERATOR ENGINE | 156.00 CY | - | - | | 176 | 15,662 | 3,859 | 19,521 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | GAS COMPRESSOR | 226.00 CY | - | - | | 254 | 22,689 | 5,591 | 28,280 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | GAS COMPRESSOR COOLER | 50.00 CY | - | - | | 56 | 5,020 | 1,237 | 6,257 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | WAREHOUSE | 110.00 CY | - | - | | 124 | 11,043 | 2,721 | 13,765 |
| | | TURBINE PEDESTAL | U-1 | 217.00 CY | - | - | | 391 | 34,857 | 8,589 | 43,446 |
| | | TURBINE PEDESTAL | U-2 | 217.00 CY | - | - | | 391 | 34,857 | 8,589 | 43,446 |
| | | CONCRETE | | | | | | 2,273 | 202,838 | 49,982 | 252,820 |
| | 10.24.00 | ARCHITECTURAL | | | | | | | | | |
| | | BUILDING | SERVICE BUILDING AND CONTROL ROOM, 50' X 30' X 14' | 21,000.00 CF | - | - | | 63 | 5,243 | 1,747 | 6,990 |
| | | BUILDING | AIR COMPRESSOR BUILDING, 245 SF | 4,655.00 CF | - | - | | 14 | 1,162 | 387 | 1,550 |

**SAN DIEGO GAS & ELECTRIC
 MIRAMAR ENERGY FACILITY
 DECOMMISSIONING STUDY**



| Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|-------|-----------------|--|--|--------------|------------------|-------------|---------------|--------------|----------------|---------------|----------------|
| | 10.24.00 | ARCHITECTURAL | | | | | | | | | |
| | | BUILDING | X 9' HIGH | 4,655.00 CF | - | - | | 14 | 1,162 | 387 | 1,550 |
| | | BUILDING | GAS COMPRESSOR BUILDING, 1485.33 SF X 9' HIGH | 28,222.00 CF | - | - | | 85 | 7,047 | 2,348 | 9,395 |
| | | BUILDING | WAREHOUSE, 22' X 90' X 18' HIGH | 35,640.00 CF | - | - | | 107 | 8,899 | 2,965 | 11,864 |
| | | ARCHITECTURAL | | | | | | 269 | 22,352 | 7,447 | 29,798 |
| | 10.26.00 | MISCELLANEOUS STRUCTURAL ITEM | | | | | | | | | |
| | | MISCELLANEOUS SMALL OBSTACLE REMOVAL FROM SITE | | 1.00 LT | - | - | | 300 | 23,982 | 6,831 | 30,813 |
| | | MISCELLANEOUS STRUCTURAL ITEM | | | | | | 300 | 23,982 | 6,831 | 30,813 |
| | 10.31.00 | MECHANICAL EQUIPMENT | | | | | | | | | |
| | | COMBUSTION TURBINE | LM6000 PC-SPRINT W/GENERATOR AND ACCESSORIES, U-1 | 266.00 TN | - | - | | 931 | 74,424 | 21,199 | 95,623 |
| | | COMBUSTION TURBINE | LM6000 PC-SPRINT W/GENERATOR AND ACCESSORIES, U-2 | 266.00 TN | - | - | | 931 | 74,424 | 21,199 | 95,623 |
| | | TANKS AND SILOS | 200,000 GAL, DEMINERALIZED WATER TANK, U-1 | 28.00 TN | - | - | | 76 | 6,043 | 1,721 | 7,765 |
| | | TANKS AND SILOS | 200,000 GAL, DEMINERALIZED WATER TANK, U-2 | 28.00 TN | - | - | | 76 | 6,043 | 1,721 | 7,765 |
| | | TANKS AND SILOS | 6,000 GAL, AQUEOUS AMMONIA TANK | 3.00 TN | - | - | | 8 | 648 | 184 | 832 |
| | | MISCELLANEOUS EQUIPMENT | BLACK START DIESEL GENERATOR ENGINE, 625KV, NATURAL GAS | 5.00 TN | - | - | | 14 | 1,079 | 307 | 1,387 |
| | | MISCELLANEOUS EQUIPMENT | SCR CASING, U-1 | 21.00 TN | - | - | | 57 | 4,533 | 1,291 | 5,824 |
| | | MISCELLANEOUS EQUIPMENT | SCR CAVITY DUCTWORK, U-1 | 33.00 TN | - | - | | 89 | 7,123 | 2,029 | 9,151 |
| | | MISCELLANEOUS EQUIPMENT | SCR CASING, U-2 | 21.00 TN | - | - | | 57 | 4,533 | 1,291 | 5,824 |
| | | MISCELLANEOUS EQUIPMENT | SCR CAVITY DUCTWORK, U-2 | 33.00 TN | - | - | | 89 | 7,123 | 2,029 | 9,151 |
| | | MISCELLANEOUS EQUIPMENT | CT AIR INTAKE SYSTEM, DUCTS & SILENCER, U-1 | 20.00 TN | - | - | | 54 | 4,317 | 1,230 | 5,546 |
| | | MISCELLANEOUS EQUIPMENT | CT AIR INTAKE SYSTEM, DUCTS & SILENCER, U-2 | 20.00 TN | - | - | | 54 | 4,317 | 1,230 | 5,546 |
| | | MISCELLANEOUS EQUIPMENT | CT LUBE OIL SYSTEM, INCL FIN FAN COOLER, U-1 | 3.00 TN | - | - | | 8 | 648 | 184 | 832 |
| | | MISCELLANEOUS EQUIPMENT | CT LUBE OIL SYSTEM, INCL FIN FAN COOLER, U-2 | 3.00 TN | - | - | | 8 | 648 | 184 | 832 |
| | | MISCELLANEOUS EQUIPMENT | CT LUBE GAS FUEL, COALESCING FILTER SKID, GAS COMPRESSOR | 1.00 TN | - | - | | 3 | 216 | 61 | 277 |
| | | MISCELLANEOUS EQUIPMENT | DEMINERALIZED WATER TRANSFER PUMPS, U-1 | 0.30 TN | - | - | | 1 | 65 | 18 | 83 |
| | | MISCELLANEOUS EQUIPMENT | DEMINERALIZED WATER TRANSFER PUMPS, U-2 | 0.30 TN | - | - | | 1 | 65 | 18 | 83 |
| | | STEEL EXHAUST STACK | 45 FT X 10 FT DIA, U-1 | 11.00 TN | - | - | | 22 | 1,781 | 507 | 2,288 |
| | | STEEL EXHAUST STACK | 45 FT X 10 FT DIA, U-2 | 11.00 TN | - | - | | 22 | 1,781 | 507 | 2,288 |
| | | MECHANICAL EQUIPMENT | | | | | | 2,499 | 199,808 | 56,913 | 256,721 |
| | 10.35.00 | PIPING | | | | | | | | | |
| | | PIPING, VALVES AND HANGERS | UNIT 1 | 24.00 TN | - | - | | 49 | 3,885 | 1,107 | 4,992 |
| | | PIPING, VALVES AND HANGERS | UNIT 2 | 24.00 TN | - | - | | 49 | 3,885 | 1,107 | 4,992 |
| | | FIRE LINES AND HYDRANTS | | 1.00 LT | - | - | | 80 | 6,395 | 1,822 | 8,217 |
| | | PIPING | | | | | | 177 | 14,165 | 4,035 | 18,200 |
| | 10.41.00 | ELECTRICAL EQUIPMENT | | | | | | | | | |
| | | TRANSFORMERS | STATION AUXILIARY TRANSFORMER, U-1 | 12.00 TN | - | - | | 32 | 2,563 | 730 | 3,293 |
| | | TRANSFORMERS | STATION AUXILIARY TRANSFORMER, U-2 | 12.00 TN | - | - | | 32 | 2,563 | 730 | 3,293 |
| | | OUTDOOR LIGHT POLE / FIXTURE | | 1.00 LT | - | - | | 150 | 11,991 | 3,416 | 15,407 |
| | | MISCELLANEOUS ELECTRICAL EQUIPMENT | CONTROL ROOM EQUIPMENT | 1.00 LT | - | - | | 100 | 7,994 | 2,277 | 10,271 |
| | | MISCELLANEOUS ELECTRICAL EQUIPMENT | GENERATOR BUS, TRANSFORMERS, MISC., U-1 | 63.00 TN | - | - | | 224 | 17,944 | 5,111 | 23,055 |
| | | MISCELLANEOUS ELECTRICAL EQUIPMENT | GENERATOR BUS, TRANSFORMERS, MISC., U-2 | 63.00 TN | - | - | | 224 | 17,944 | 5,111 | 23,055 |
| | | ELECTRICAL EQUIPMENT | | | | | | 763 | 60,999 | 17,375 | 78,375 |

**SAN DIEGO GAS & ELECTRIC
 MIRAMAR ENERGY FACILITY
 DECOMMISSIONING STUDY**



| Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|-----------------|-------|--|---|--------------|------------------|------------------|---------------|--------------|----------------|----------------|------------------|
| 10.42.00 | | RACEWAY, CABLE TRAY, & CONDUIT | | | | | | | | | |
| | | CONDUIT | U-1 | 12,000.00 LF | - | - | | 120 | 9,593 | 2,732 | 12,325 |
| | | CONDUIT | U-2 | 12,000.00 LF | - | - | | 120 | 9,593 | 2,732 | 12,325 |
| | | CABLE TRAY | U-1 | 2,500.00 LF | - | - | | 100 | 7,994 | 2,277 | 10,271 |
| | | CABLE TRAY | U-2 | 2,500.00 LF | - | - | | 100 | 7,994 | 2,277 | 10,271 |
| | | RACEWAY, CABLE TRAY, & CONDUIT | | | | | | 440 | 35,174 | 10,019 | 45,192 |
| 10.43.00 | | CABLE | | | | | | | | | |
| | | COPPER WIRE / CABLE - MEDIUM VOLTAGE | U-1 | 4,500.00 LF | - | - | | 90 | 7,195 | 2,049 | 9,244 |
| | | COPPER WIRE / CABLE - MEDIUM VOLTAGE | U-2 | 4,500.00 LF | - | - | | 90 | 7,195 | 2,049 | 9,244 |
| | | COPPER WIRE / CABLE - LOW VOLTAGE | U-1 | 25,000.00 LF | - | - | | 250 | 19,985 | 5,693 | 25,678 |
| | | COPPER WIRE / CABLE - LOW VOLTAGE | U-2 | 25,000.00 LF | - | - | | 250 | 19,985 | 5,693 | 25,678 |
| | | CABLE | | | | | | 680 | 54,359 | 15,484 | 69,843 |
| 10.44.00 | | CONTROL & INSTRUMENTATION | | | | | | | | | |
| | | CONTROL & INSTRUMENTATION | | 1.00 LT | - | - | | 100 | 7,994 | 2,277 | 10,271 |
| | | CONTROL & INSTRUMENTATION | | | | | | 100 | 7,994 | 2,277 | 10,271 |
| | | WHOLE PLANT DEMOLITION | | | | | | 7,862 | 653,764 | 187,043 | 840,806 |
| 18.00.00 | | SCRAP VALUE | | | | | | | | | |
| 18.10.00 | | MIXED STEEL | | | | | | | | | |
| | | CARBON STEEL | | -104.60 TN | - | (18,305) | - | 0 | (1) | 0 | (18,306) |
| | | CARBON STEEL | | -717.00 TN | - | (125,475) | - | 0 | (6) | (1) | (125,482) |
| | | CARBON STEEL | BUILDINGS | -31.00 TN | - | (5,425) | - | 0 | 0 | 0 | (5,425) |
| | | CARBON STEEL | CONDUIT, 1.5" DIA. AVG SIZE, 2.63 LBS/LF | -31.00 TN | - | (5,425) | - | 0 | | | (5,425) |
| | | CARBON STEEL | CABLE TRAY, 6 LBS/LF | -15.00 TN | - | (2,625) | - | 0 | | | (2,625) |
| | | STEEL / COPPER MIX - LARGE TRANSFORMER > 100 KVA | TRANSFORMERS, GENERATORS, U1 | -12.00 TN | - | (4,200) | - | 0 | | | (4,200) |
| | | STEEL / COPPER MIX - LARGE TRANSFORMER > 100 KVA | TRANSFORMERS, GENERATORS, U2 | -12.00 TN | - | (4,200) | - | 0 | | | (4,200) |
| | | MIXED STEEL | | | | (165,655) | | 0 | (7) | (1) | (165,664) |
| 18.30.00 | | COPPER | | | | | | | | | |
| | | #2 SOLID COPPER / TUBING | BUS BAR | -0.39 TN | - | (2,397) | - | | | | (2,397) |
| | | #2 INSULATED COPPER WIRE | U-1 | -3.50 TN | - | (8,540) | - | 0 | | | (8,540) |
| | | #2 INSULATED COPPER WIRE | U-2 | -3.50 TN | - | (8,540) | - | 0 | | | (8,540) |
| | | COPPER | | | | (19,477) | | 0 | | | (19,477) |
| | | SCRAP VALUE | | | | (185,132) | | 0 | (7) | (1) | (185,140) |
| 21.00.00 | | CIVIL WORK | | | | | | | | | |
| 21.18.00 | | HAULING | | | | | | | | | |
| | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 158.00 CY | 3,160 | - | | | | | 3,160 |
| | | HAULING TO RECYCLE FACILITY | CONCRETE PAVED SURFACES DEBRIS IS RECYCLED. NO DISPOSAL FEE | 502.00 CY | 10,040 | - | | | | | 10,040 |
| | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 590.00 CY | 11,800 | - | | | | | 11,800 |
| | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 906.00 CY | 18,120 | - | | | | | 18,120 |
| | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 106.00 CY | 2,120 | - | | | | | 2,120 |
| | | HAULING | | | 45,240 | | | | | | 45,240 |
| 21.21.00 | | MASS FILL | | | | | | | | | |
| | | MASS FILL, COMMON EARTH 6 INCHES THICK | 8940 SY | 1,490.00 CY | - | - | 34,270 | 52 | 4,752 | 5,005 | 44,027 |
| | | MASS FILL | | | | | 34,270 | 52 | 4,752 | 5,005 | 44,027 |
| 21.52.00 | | WASTE DISPOSAL | | | | | | | | | |
| | | DISPOSAL AND TRANSPORTATION FEE | RUBBISH & TENANT DEBRIS | 100.00 CY | 3,000 | - | | | | | 3,000 |
| | | WASTE DISPOSAL | | | 3,000 | | | | | | 3,000 |

**SAN DIEGO GAS & ELECTRIC
 MIRAMAR ENERGY FACILITY
 DECOMMISSIONING STUDY**



| Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|-------|-------|-------------------|-------|----------|------------------|-------------|---------------|-----------|--------------|--------------|---------------|
| | | CIVIL WORK | | | 48,240 | | 34,270 | 52 | 4,752 | 5,005 | 92,267 |

**APPENDIX B. CONCEPTUAL ESTIMATE OF COST
— FERC ACCOUNT**

**SAN DIEGO GAS & ELECTRIC
MIRAMAR ENERGY FACILITY
DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS**

| | |
|-------------------------|------------|
| Estimator | GA |
| Labor rate table | 21CASAN |
| Project No. | A14520.001 |
| Estimate Date | 11/30/21 |
| Reviewed By | BA |
| Approved By | BA |
| Estimate No. | 30598C |

SAN DIEGO GAS & ELECTRIC
 MIRAMAR ENERGY FACILITY
 DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS



| Area | Description | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|------|--|------------------|-------------|---------------|-----------|------------|--------------|------------|
| 341 | OTHER PRODUCTION - STRUCTURES & IMPROVEMENTS | 23,907 | (5,425) | 62,131 | 940 | 181,285 | 65,340 | 327,239 |
| 342 | OTHER PRODUCTION - FUEL HOLDERS, PRODUCERS AND ACCESSORIES | 17,414 | (18,305) | | 914 | 176,311 | 38,025 | 213,446 |
| 344 | OTHER PRODUCTION - GENERATORS | 26,741 | (125,475) | | 3,959 | 731,492 | 167,027 | 799,785 |
| 345 | OTHER PRODUCTION - ACCESSORY ELECTRIC EQUIPMENT | 3,129 | (35,927) | | 2,102 | 376,505 | 89,544 | 433,251 |

**SAN DIEGO GAS & ELECTRIC
 MIRAMAR ENERGY FACILITY
 DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS**



Estimate Totals

| Description | Amount | Totals | Hours |
|-------------------------------------|------------------|------------------|-------|
| Labor | 1,465,593 | | 7,914 |
| Material | 62,131 | | |
| Subcontract | 71,191 | | |
| Construction Equipment | 359,937 | | |
| Process Equipment | (185,132) | | |
| | 1,773,720 | 1,773,720 | |
| General Conditions | | | |
| Additional Labor Costs | | | |
| Site Overheads | | | |
| Other Construction Indirects | | 1,773,720 | |
| Project Indirect Costs | | 1,773,720 | |
| Contingency | | 1,773,720 | |
| Escalation | | 1,773,720 | |
| Total | | 1,773,720 | |

General Conditions, Indirect Costs and Contingency are allocated in the line items above.

SAN DIEGO GAS & ELECTRIC
 MIRAMAR ENERGY FACILITY
 DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS



| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|------|----------|----------|---|---|--------------|------------------|-------------|---------------|-----------|------------|--------------|------------|
| 341 | | | OTHER PRODUCTION - STRUCTURES & IMPROVEMENTS | | | | | | | | | |
| | 10.00.00 | | WHOLE PLANT DEMOLITION | | | | | | | | | |
| | | 10.21.00 | CIVIL WORK | | | | | | | | | |
| | | | PAVED SURFACES, 6 IN THICK | | 3,010.00 SY | - | - | | 361 | 71,426 | 31,262 | 102,688 |
| | | | CIVIL WORK | | | | | | 361 | 71,426 | 31,262 | 102,688 |
| | | 10.22.00 | CONCRETE | | | | | | | | | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | EMERGENCY EYEWASH, U-1 | 1.00 CY | - | - | | 1 | 223 | 46 | 270 |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | EMERGENCY EYEWASH, U-2 | 1.00 CY | - | - | | 1 | 223 | 46 | 270 |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | SERVICE BUILDING AND CONTROL ROOM | 33.00 CY | - | - | | 37 | 7,374 | 1,530 | 8,904 |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | AIR COMPRESSOR | 13.00 CY | - | - | | 15 | 2,905 | 603 | 3,508 |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | WAREHOUSE | 110.00 CY | - | - | | 124 | 24,579 | 5,100 | 29,679 |
| | | | CONCRETE | | | | | | 178 | 35,304 | 7,326 | 42,630 |
| | | 10.24.00 | ARCHITECTURAL | | | | | | | | | |
| | | | BUILDING | SERVICE BUILDING AND CONTROL ROOM, 50' X 30' X 14' | 21,000.00 CF | - | - | | 63 | 11,670 | 3,274 | 14,944 |
| | | | BUILDING | AIR COMPRESSOR BUILDING, 245 SF X 9' HIGH | 4,655.00 CF | - | - | | 14 | 2,587 | 726 | 3,313 |
| | | | BUILDING | GAS COMPRESSOR BUILDING, 1485.33 SF X 9' HIGH | 28,222.00 CF | - | - | | 85 | 15,683 | 4,400 | 20,084 |
| | | | BUILDING | WAREHOUSE, 22' X 90' X 18' HIGH | 35,640.00 CF | - | - | | 107 | 19,806 | 5,557 | 25,363 |
| | | | ARCHITECTURAL | | | | | | 269 | 49,746 | 13,957 | 63,703 |
| | | 10.35.00 | PIPING | | | | | | | | | |
| | | | FIRE LINES AND HYDRANTS | | 1.00 LT | - | - | | 80 | 14,233 | 3,414 | 17,647 |
| | | | PIPING | | | | | | 80 | 14,233 | 3,414 | 17,647 |
| | | | WHOLE PLANT DEMOLITION | | | | | | 888 | 170,709 | 55,959 | 226,669 |
| | 18.00.00 | | SCRAP VALUE | | | | | | | | | |
| | | 18.10.00 | MIXED STEEL | | | | | | | | | |
| | | | CARBON STEEL | BUILDINGS | -31.00 TN | - | (5,425) | - | 0 | (1) | 0 | (5,426) |
| | | | MIXED STEEL | | | | | | 0 | (1) | 0 | (5,426) |
| | | | SCRAP VALUE | | | | | | 0 | (1) | 0 | (5,426) |
| | 21.00.00 | | CIVIL WORK | | | | | | | | | |
| | | 21.18.00 | HAULING | | | | | | | | | |
| | | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED, NO DISPOSAL FEE | 158.00 CY | 4,663 | - | | | | | 4,663 |
| | | | HAULING TO RECYCLE FACILITY | CONCRETE PAVED SURFACES DEBRIS IS RECYCLED, NO DISPOSAL FEE | 502.00 CY | 14,817 | - | | | | | 14,817 |
| | | | HAULING | | | 19,480 | | | | | | 19,480 |
| | | 21.21.00 | MASS FILL | | | | | | | | | |
| | | | MASS FILL, COMMON EARTH 6 INCHES THICK | 8940 SY | 1,490.00 CY | - | - | 62,131 | 52 | 10,576 | 9,381 | 82,088 |
| | | | MASS FILL | | | | | 62,131 | 52 | 10,576 | 9,381 | 82,088 |
| | | 21.52.00 | WASTE DISPOSAL | | | | | | | | | |
| | | | DISPOSAL AND TRANSPORTATION FEE | RUBBISH & TENANT DEBRIS | 100.00 CY | 4,427 | - | | | | | 4,427 |
| | | | WASTE DISPOSAL | | | 4,427 | | | | | | 4,427 |
| | | | CIVIL WORK | | | 23,907 | | 62,131 | 52 | 10,576 | 9,381 | 105,996 |
| | | | 341 OTHER PRODUCTION - STRUCTURES & IMPROVEMENTS | | | 23,907 | (5,425) | 62,131 | 940 | 181,285 | 65,340 | 327,239 |
| 342 | | | OTHER PRODUCTION - FUEL HOLDERS, PRODUCERS AND ACCESSORIES | | | | | | | | | |
| | 10.00.00 | | WHOLE PLANT DEMOLITION | | | | | | | | | |
| | | 10.22.00 | CONCRETE | | | | | | | | | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | AMMONIA EVAPORATION SKID, U-1 | 8.00 CY | - | - | | 9 | 1,788 | 371 | 2,158 |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | AMMONIA EVAPORATION SKID, U-2 | 8.00 CY | - | - | | 9 | 1,788 | 371 | 2,158 |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | WATER TREATMENT, U-1 | 60.00 CY | - | - | | 68 | 13,407 | 2,782 | 16,188 |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | WATER TREATMENT, U-2 | 60.00 CY | - | - | | 68 | 13,407 | 2,782 | 16,188 |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | DEMINEALIZED WATER PUMP, U-1 | 29.00 CY | - | - | | 33 | 6,480 | 1,345 | 7,824 |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | DEMINEALIZED WATER PUMP, U-2 | 29.00 CY | - | - | | 33 | 6,480 | 1,345 | 7,824 |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | DEMINEALIZED WATER TANK, U-1 | 60.00 CY | - | - | | 68 | 13,407 | 2,782 | 16,188 |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | DEMINEALIZED WATER TANK, U-2 | 60.00 CY | - | - | | 68 | 13,407 | 2,782 | 16,188 |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | GAS COMPRESSOR | 226.00 CY | - | - | | 254 | 50,498 | 10,479 | 60,977 |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | GAS COMPRESSOR COOLER | 50.00 CY | - | - | | 56 | 11,172 | 2,318 | 13,490 |

**SAN DIEGO GAS & ELECTRIC
 MIRAMAR ENERGY FACILITY
 DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS**



| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost | | | | |
|----------|----------|----------|---|--|------------|------------------|-------------|---------------|-----------|------------|--------------|------------|----------|---------|--------|---------|
| | | | CONCRETE | | | | | | | 664 | 131,831 | 27,356 | 159,186 | | | |
| | 10.31.00 | | MECHANICAL EQUIPMENT | | | | | | | | | | | | | |
| | | | TANKS AND SILOS | 200,000 GAL, DEMINERALIZED WATER TANK, U-1 | 28.00 TN | - | - | | 76 | 13,451 | 3,226 | 16,677 | | | | |
| | | | TANKS AND SILOS | 200,000 GAL, DEMINERALIZED WATER TANK, U-2 | 28.00 TN | - | - | | 76 | 13,450 | 3,226 | 16,677 | | | | |
| | | | MISCELLANEOUS EQUIPMENT | DEMINERALIZED WATER TRANSFER PUMPS, U-1 | 0.30 TN | - | - | | 1 | 144 | 35 | 179 | | | | |
| | | | MISCELLANEOUS EQUIPMENT | DEMINERALIZED WATER TRANSFER PUMPS, U-2 | 0.30 TN | - | - | | 1 | 144 | 35 | 179 | | | | |
| | | | MECHANICAL EQUIPMENT | | | | | | | 153 | 27,189 | 6,522 | 33,711 | | | |
| | 10.35.00 | | PIPING | | | | | | | | | | | | | |
| | | | PIPING, VALVES AND HANGERS | UNIT 1 | 24.00 TN | - | - | | 49 | 8,647 | 2,074 | 10,721 | | | | |
| | | | PIPING, VALVES AND HANGERS | UNIT 2 | 24.00 TN | - | - | | 49 | 8,647 | 2,074 | 10,721 | | | | |
| | | | PIPING | | | | | | 97 | 17,293 | 4,148 | 21,442 | | | | |
| | | | WHOLE PLANT DEMOLITION | | | | | | | 914 | 176,313 | 38,026 | 214,339 | | | |
| 18.00.00 | | | SCRAP VALUE | | | | | | | | | | | | | |
| | 18.10.00 | | MIXED STEEL | | | | | | | | | | | | | |
| | | | CARBON STEEL | | -104.60 TN | - | (18,305) | - | 0 | (2) | 0 | (18,307) | | | | |
| | | | MIXED STEEL | | | | | | 0 | (2) | 0 | (18,307) | | | | |
| | | | SCRAP VALUE | | | | | | | 0 | (2) | 0 | (18,307) | | | |
| 21.00.00 | | | CIVIL WORK | | | | | | | | | | | | | |
| | 21.18.00 | | HAULING | | | | | | | | | | | | | |
| | | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 590.00 CY | 17,414 | - | | | | | 17,414 | | | | |
| | | | HAULING | | | 17,414 | | | | | | 17,414 | | | | |
| | | | CIVIL WORK | | | | | | | | | | 17,414 | | | |
| | | | 342 OTHER PRODUCTION - FUEL HOLDERS, PRODUCERS AND ACCESSORIES | | | | | | | 17,414 | (18,305) | | 914 | 176,311 | 38,025 | 213,446 |
| 344 | | | OTHER PRODUCTION - GENERATORS | | | | | | | | | | | | | |
| | 10.00.00 | | WHOLE PLANT DEMOLITION | | | | | | | | | | | | | |
| | | 10.22.00 | CONCRETE | | | | | | | | | | | | | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | AUX SKID, U-1 | 58.00 CY | - | - | | 65 | 12,960 | 2,689 | 15,649 | | | | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | AUX SKID, U-2 | 58.00 CY | - | - | | 65 | 12,960 | 2,689 | 15,649 | | | | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | WATER WASH PAD, U-1 | 6.00 CY | - | - | | 7 | 1,341 | 278 | 1,619 | | | | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | WATER WASH PAD, U-2 | 6.00 CY | - | - | | 7 | 1,341 | 278 | 1,619 | | | | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | ENGINE REMOVAL, U-1 | 2.00 CY | - | - | | 2 | 447 | 93 | 540 | | | | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | ENGINE REMOVAL, U-2 | 2.00 CY | - | - | | 2 | 447 | 93 | 540 | | | | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | FUEL GAS FILTER SEPARATOR, U-1 | 4.00 CY | - | - | | 5 | 894 | 185 | 1,079 | | | | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | FUEL GAS FILTER SEPARATOR, U-2 | 4.00 CY | - | - | | 5 | 894 | 185 | 1,079 | | | | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | OUTLET DUCT A, U-1 | 4.00 CY | - | - | | 5 | 894 | 185 | 1,079 | | | | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | OUTLET DUCT A, U-2 | 4.00 CY | - | - | | 5 | 894 | 185 | 1,079 | | | | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | OUTLET DUCT B, U-1 | 3.00 CY | - | - | | 3 | 670 | 139 | 809 | | | | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | OUTLET DUCT B, U-2 | 3.00 CY | - | - | | 3 | 670 | 139 | 809 | | | | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | OUTLET DUCT C, U-1 | 3.00 CY | - | - | | 3 | 670 | 139 | 809 | | | | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | OUTLET DUCT C, U-2 | 3.00 CY | - | - | | 3 | 670 | 139 | 809 | | | | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | OUTLET DUCT D, U-1 | 10.00 CY | - | - | | 11 | 2,234 | 464 | 2,698 | | | | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | OUTLET DUCT D, U-2 | 10.00 CY | - | - | | 11 | 2,234 | 464 | 2,698 | | | | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | STACK, U-1 | 36.00 CY | - | - | | 41 | 8,044 | 1,669 | 9,713 | | | | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | STACK, U-2 | 36.00 CY | - | - | | 41 | 8,044 | 1,669 | 9,713 | | | | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | CEMS, U-1 | 3.00 CY | - | - | | 3 | 670 | 139 | 809 | | | | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | CEMS, U-2 | 3.00 CY | - | - | | 3 | 670 | 139 | 809 | | | | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | TEMPERING AIR DUCT, U-1 | 13.00 CY | - | - | | 15 | 2,905 | 603 | 3,508 | | | | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | TEMPERING AIR DUCT, U-2 | 13.00 CY | - | - | | 15 | 2,905 | 603 | 3,507 | | | | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | FIN FAN COOLER, U-1 | 16.00 CY | - | - | | 18 | 3,575 | 742 | 4,317 | | | | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | FIN FAN COOLER, U-2 | 16.00 CY | - | - | | 18 | 3,575 | 742 | 4,317 | | | | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | BLACK START DIESEL GENERATOR ENGINE | 156.00 CY | - | - | | 176 | 34,857 | 7,233 | 42,090 | | | | |
| | | | TURBINE PEDESTAL | U-1 | 217.00 CY | - | - | | 391 | 77,579 | 16,098 | 93,677 | | | | |
| | | | TURBINE PEDESTAL | U-2 | 217.00 CY | - | - | | 391 | 77,579 | 16,098 | 93,677 | | | | |
| | | | CONCRETE | | | | | | | 1,312 | 260,623 | 54,081 | 314,704 | | | |
| | 10.26.00 | | MISCELLANEOUS STRUCTURAL ITEM | | | | | | | | | | | | | |
| | | | MISCELLANEOUS SMALL OBSTACLE REMOVAL FROM SITE | | 1.00 LT | - | - | | 300 | 53,375 | 12,803 | 66,178 | | | | |

**SAN DIEGO GAS & ELECTRIC
 MIRAMAR ENERGY FACILITY
 DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS**



| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost | |
|----------|----------|----------|---|--|------------|------------------|-------------|---------------|-----------|------------|--------------|------------|---------|
| | | | MISCELLANEOUS STRUCTURAL ITEM | | | | | | | 300 | 53,375 | 12,803 | 66,178 |
| | 10.31.00 | | MECHANICAL EQUIPMENT | | | | | | | | | | |
| | | | COMBUSTION TURBINE | LM6000 PC-SPRINT W/GENERATOR AND ACCESSORIES, U-1 | 266.00 TN | - | - | | 931 | 165,640 | 39,731 | 205,372 | |
| | | | COMBUSTION TURBINE | LM6000 PC-SPRINT W/GENERATOR AND ACCESSORIES, U-2 | 266.00 TN | - | - | | 931 | 165,640 | 39,731 | 205,372 | |
| | | | TANKS AND SILOS | 6,000 GAL. AQUEOUS AMMONIA TANK | 3.00 TN | - | - | | 8 | 1,441 | 346 | 1,787 | |
| | | | MISCELLANEOUS EQUIPMENT | BLACK START DIESEL GENERATOR ENGINE, 625KV, NATURAL GAS | 5.00 TN | - | - | | 14 | 2,402 | 576 | 2,978 | |
| | | | MISCELLANEOUS EQUIPMENT | SCR CASING, U-1 | 21.00 TN | - | - | | 57 | 10,088 | 2,420 | 12,508 | |
| | | | MISCELLANEOUS EQUIPMENT | SCR CAVITY DUCTWORK, U-1 | 33.00 TN | - | - | | 89 | 15,852 | 3,802 | 19,655 | |
| | | | MISCELLANEOUS EQUIPMENT | SCR CASING, U-2 | 21.00 TN | - | - | | 57 | 10,088 | 2,420 | 12,508 | |
| | | | MISCELLANEOUS EQUIPMENT | SCR CAVITY DUCTWORK, U-2 | 33.00 TN | - | - | | 89 | 15,852 | 3,802 | 19,655 | |
| | | | MISCELLANEOUS EQUIPMENT | CT AIR INTAKE SYSTEM, DUCTS & SILENCER, U-1 | 20.00 TN | - | - | | 54 | 9,608 | 2,304 | 11,912 | |
| | | | MISCELLANEOUS EQUIPMENT | CT AIR INTAKE SYSTEM, DUCTS & SILENCER, U-2 | 20.00 TN | - | - | | 54 | 9,607 | 2,305 | 11,912 | |
| | | | MISCELLANEOUS EQUIPMENT | CT LUBE OIL SYSTEM, INCL FIN FAN COOLER, U-1 | 3.00 TN | - | - | | 8 | 1,441 | 346 | 1,787 | |
| | | | MISCELLANEOUS EQUIPMENT | CT LUBE OIL SYSTEM, INCL FIN FAN COOLER, U-2 | 3.00 TN | - | - | | 8 | 1,441 | 346 | 1,787 | |
| | | | MISCELLANEOUS EQUIPMENT | CT LUBE GAS FUEL, COALESCING FILTER SKID, GAS COMPRESSOR | 1.00 TN | - | - | | 3 | 480 | 115 | 596 | |
| | | | STEEL EXHAUST STACK | 45 FT X 10 FT DIA, U-1 | 11.00 TN | - | - | | 22 | 3,963 | 951 | 4,914 | |
| | | | STEEL EXHAUST STACK | 45 FT X 10 FT DIA, U-2 | 11.00 TN | - | - | | 22 | 3,963 | 951 | 4,914 | |
| | | | MECHANICAL EQUIPMENT | | | | | | 2,347 | 417,508 | 100,145 | 517,653 | |
| | | | WHOLE PLANT DEMOLITION | | | | | | 3,959 | 731,505 | 167,029 | 898,535 | |
| 18.00.00 | | | SCRAP VALUE | | | | | | | | | | |
| | 18.10.00 | | MIXED STEEL | | | | | | | | | | |
| | | | CARBON STEEL | | -717.00 TN | - | (125,475) | - | 0 | (14) | (2) | (125,491) | |
| | | | MIXED STEEL | | | | (125,475) | | 0 | (14) | (2) | (125,491) | |
| | | | SCRAP VALUE | | | | | | 0 | (14) | (2) | (125,491) | |
| 21.00.00 | | | CIVIL WORK | | | | | | | | | | |
| | 21.18.00 | | HAULING | | | | | | | | | | |
| | | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED, NO DISPOSAL FEE | 906.00 CY | 26,741 | - | | | | | 26,741 | |
| | | | HAULING | | | | | | 26,741 | | | 26,741 | |
| | | | CIVIL WORK | | | | | | 26,741 | | | 26,741 | |
| | | | 344 OTHER PRODUCTION - GENERATORS | | | | | | 26,741 | (125,475) | | | 799,785 |
| 345 | | | OTHER PRODUCTION - ACCESSORY | | | | | | | | | | |
| | | | ELECTRIC EQUIPMENT | | | | | | | | | | |
| | 10.00.00 | | WHOLE PLANT DEMOLITION | | | | | | | | | | |
| | | 10.22.00 | CONCRETE | | | | | | | | | | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | 15KV SWITCHGEAR, U-1 | 12.00 CY | - | - | | 14 | 2,681 | 556 | 3,238 | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | 15KV SWITCHGEAR, U-2 | 12.00 CY | - | - | | 14 | 2,681 | 556 | 3,238 | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | AUX TRANSFORMER 480V SWITCHGEAR, U-1 | 29.00 CY | - | - | | 33 | 6,480 | 1,345 | 7,824 | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | AUX TRANSFORMER 480V SWITCHGEAR, U-2 | 29.00 CY | - | - | | 33 | 6,480 | 1,345 | 7,824 | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | AUX ELECTRIC ENCLOSURE, U-1 | 8.00 CY | - | - | | 9 | 1,788 | 371 | 2,158 | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | AUX ELECTRIC ENCLOSURE, U-2 | 8.00 CY | - | - | | 9 | 1,788 | 371 | 2,158 | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | BOP MCC, U-1 | 4.00 CY | - | - | | 5 | 894 | 185 | 1,079 | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | BOP MCC, U-2 | 4.00 CY | - | - | | 5 | 894 | 185 | 1,079 | |
| | | | CONCRETE | | | | | | 119 | 23,685 | 4,915 | 28,600 | |
| | 10.41.00 | | ELECTRICAL EQUIPMENT | | | | | | | | | | |
| | | | TRANSFORMERS | STATION AUXILIARY TRANSFORMER, U-1 | 12.00 TN | - | - | | 32 | 5,705 | 1,368 | 7,073 | |
| | | | TRANSFORMERS | STATION AUXILIARY TRANSFORMER, U-2 | 12.00 TN | - | - | | 32 | 5,705 | 1,368 | 7,073 | |
| | | | OUTDOOR LIGHT POLE / FIXTURE | | 1.00 LT | - | - | | 150 | 26,688 | 6,401 | 33,089 | |
| | | | MISCELLANEOUS ELECTRICAL EQUIPMENT | CONTROL ROOM EQUIPMENT | 1.00 LT | - | - | | 100 | 17,792 | 4,268 | 22,059 | |
| | | | MISCELLANEOUS ELECTRICAL EQUIPMENT | GENERATOR BUS, TRANSFORMERS, MISC., U-1 | 63.00 TN | - | - | | 224 | 39,937 | 9,579 | 49,516 | |
| | | | MISCELLANEOUS ELECTRICAL EQUIPMENT | GENERATOR BUS, TRANSFORMERS, MISC., U-2 | 63.00 TN | - | - | | 224 | 39,937 | 9,579 | 49,516 | |
| | | | ELECTRICAL EQUIPMENT | | | | | | 763 | 135,762 | 32,565 | 168,327 | |
| | 10.42.00 | | RACEWAY, CABLE TRAY, & CONDUIT | | | | | | | | | | |

SAN DIEGO GAS & ELECTRIC
 MIRAMAR ENERGY FACILITY
 DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS



| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|----------|----------|----------|--|--|--------------|------------------|-----------------|---------------|--------------|----------------|---------------|-----------------|
| | | 10.42.00 | RACEWAY, CABLE TRAY, & CONDUIT | | | | | | | | | |
| | | | CONDUIT | U-1 | 12,000.00 LF | - | - | - | 120 | 21,350 | 5,121 | 26,471 |
| | | | CONDUIT | U-2 | 12,000.00 LF | - | - | - | 120 | 21,350 | 5,121 | 26,471 |
| | | | CABLE TRAY | U-1 | 2,500.00 LF | - | - | - | 100 | 17,792 | 4,268 | 22,059 |
| | | | CABLE TRAY | U-2 | 2,500.00 LF | - | - | - | 100 | 17,792 | 4,268 | 22,059 |
| | | | RACEWAY, CABLE TRAY, & CONDUIT | | | | | | 440 | 78,283 | 18,777 | 97,061 |
| | | 10.43.00 | CABLE | | | | | | | | | |
| | | | COPPER WIRE / CABLE - MEDIUM VOLTAGE | U-1 | 4,500.00 LF | - | - | - | 90 | 16,013 | 3,841 | 19,853 |
| | | | COPPER WIRE / CABLE - MEDIUM VOLTAGE | U-2 | 4,500.00 LF | - | - | - | 90 | 16,013 | 3,841 | 19,853 |
| | | | COPPER WIRE / CABLE - LOW VOLTAGE | U-1 | 25,000.00 LF | - | - | - | 250 | 44,479 | 10,669 | 55,148 |
| | | | COPPER WIRE / CABLE - LOW VOLTAGE | U-2 | 25,000.00 LF | - | - | - | 250 | 44,479 | 10,669 | 55,148 |
| | | | CABLE | | | | | | 680 | 120,983 | 29,020 | 150,003 |
| | | 10.44.00 | CONTROL & INSTRUMENTATION | | | | | | | | | |
| | | | CONTROL & INSTRUMENTATION | | 1.00 LT | - | - | - | 100 | 17,792 | 4,268 | 22,059 |
| | | | CONTROL & INSTRUMENTATION | | | | | | 100 | 17,792 | 4,268 | 22,059 |
| | | | WHOLE PLANT DEMOLITION | | | | | | 2,102 | 376,505 | 89,544 | 466,049 |
| 18.00.00 | | | SCRAP VALUE | | | | | | | | | |
| | 18.10.00 | | MIXED STEEL | | | | | | | | | |
| | | | CARBON STEEL | CONDUIT, 1.5" DIA. AVG SIZE, 2.63 LBS/LF | -31.00 TN | - | (5,425) | - | 0 | | | (5,425) |
| | | | CARBON STEEL | CABLE TRAY, 6 LBS/LF | -15.00 TN | - | (2,625) | - | 0 | | | (2,625) |
| | | | STEEL / COPPER MIX - LARGE TRANSFORMER > 100 KVA | TRANSFORMERS, GENERATORS, U1 | -12.00 TN | - | (4,200) | - | 0 | | | (4,200) |
| | | | STEEL / COPPER MIX - LARGE TRANSFORMER > 100 KVA | TRANSFORMERS, GENERATORS, U2 | -12.00 TN | - | (4,200) | - | 0 | | | (4,200) |
| | | | MIXED STEEL | | | | (16,450) | | 0 | | | (16,450) |
| | 18.30.00 | | COPPER | | | | | | | | | |
| | | | #2 SOLID COPPER / TUBING | BUS BAR | -0.39 TN | - | (2,397) | - | 0 | | | (2,397) |
| | | | #2 INSULATED COPPER WIRE | U-1 | -3.50 TN | - | (8,540) | - | 0 | | | (8,540) |
| | | | #2 INSULATED COPPER WIRE | U-2 | -3.50 TN | - | (8,540) | - | 0 | | | (8,540) |
| | | | COPPER | | | | (19,477) | | 0 | | | (19,477) |
| | | | SCRAP VALUE | | | | (35,927) | | 0 | | | (35,927) |
| 21.00.00 | | | CIVIL WORK | | | | | | | | | |
| | 21.18.00 | | HAULING | | | | | | | | | |
| | | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 106.00 CY | 3,129 | - | - | | | | 3,129 |
| | | | HAULING | | | 3,129 | | | | | | 3,129 |
| | | | CIVIL WORK | | | 3,129 | | | | | | 3,129 |
| | | | 345 OTHER PRODUCTION - ACCESSORY ELECTRIC EQUIPMENT | | | 3,129 | (35,927) | | 2,102 | 376,505 | 89,544 | 433,251 |

APPENDIX C. EXPLANATION OF VARIANCE FROM THE PREVIOUS COST STUDY

| Cost Category | 2021 Cost Estimate | | 2016 Cost Estimate | | Delta | % of total cost | Discussion |
|--|--------------------|--------------------|--------------------|--------------------|---------------|-----------------|---|
| Labor | | | | | | | |
| Labor - Direct | | \$658,508 | | | | | |
| Labor Supervision | \$39,510 | | | | | | The 2016 estimate included all demolition contractor costs in labor. The 2021 cost estimate broke out demolition contractor costs (subcontracts, construction equipment, general conditions - labor). Average labor hourly labor cost increased by 15.2%. |
| Show-up time | \$13,170 | | | | | | |
| Construction Management | \$71,119 | | | | | | |
| Field Office Expenses | \$15,646 | | | | | | |
| Safety | \$14,050 | | | | | | |
| Temporary Facilities | \$10,689 | | | | | | |
| Mob/Demob | \$11,265 | | | | | | |
| Small tools & consumables | \$7,112 | | | | | | |
| General Liability Insurance | \$7,112 | | | | | | |
| Constr Equip Mob/Demob | \$19,205 | | | | | | |
| Legal Expenses/Claims | \$1,664 | | | | | | |
| General Conditions (Indirect) - Labor | | \$210,542 | | | | | |
| Subcontract | | \$48,240 | | | | | |
| Construction Equipment | | \$192,047 | | | | | |
| Labor Subtotal | | \$1,109,337 | | \$963,225 | 15.2% | 8.2% | |
| Material | | | | | | | |
| Material w/o freight | \$34,270 | | | | | | The 2021 cost estimate for material is 66.4% less than 2016. |
| General Conditions -Freight on Material | \$1,714 | | | | | | |
| Material Subtotal | | \$35,984 | | \$107,046 | -66.4% | -4.0% | |
| Scrap | | | | | | | The 2021 cost estimate for scrap is 28.3% less than 2016. The main reasons are: (a) cost for scrap mixed steel increased by 114%. Cost for mixed steel in 2021 based on a 12-month average is \$175 per ton as compared to 2016 based on a 3-month average of \$87 per ton (b) cost for copper decreased by -98.6%. Cost for copper in 2021 was broken out into #2 copper (solid) and #2 (insulated wire) as compared to 2016 which was based on #1 copper (solid bright) |
| Mixed Steel | -\$165,655 | | -\$84,493 | | | | |
| Copper | -\$19,477 | | -\$173,692 | | | | |
| Subtotal Scrap Value | | -\$185,132 | | -\$258,185 | -28.3% | 4.1% | |
| Subtotal - Direct & Indirect Demolition | | \$960,189 | | \$812,086 | 18.2% | 8.3% | |
| Contractor G&A and Profit | | | | | | | |
| Contractor G&A | \$74,953 | | \$48,161 | | 55.6% | | Contractor G&A is 55.6% higher. 2021 estimate is 7% of labor, equipment, and materials. 2016 estimate was 5% of labor and materials. Contractor Profit is 25.1% higher. 2021 estimate is 10% of labor, equipment, and materials. 2016 estimate was 8% of labor and materials. |
| Contractor Profit | \$107,076 | | \$85,622 | | 25.1% | | |
| Subcontractor Contractor G&A and Profit | | \$182,029 | | \$133,783 | 36.1% | 2.7% | Increase in Contractor G&A and profit based on S&L database of actual demolition cost since 2016 |
| Indirect | | | | | | | |
| Engineering | \$66,000 | | \$60,000 | | | | Higher cost due to SDGE internal costs in support of demolition as compared to 2016 where no SDGE internal costs were included |
| Construction Management | \$0 | | \$18,917 | | | | |
| Other SDGE Internal Costs | \$310,000 | | \$0 | | | | |
| Subtotal Indirect Costs | | \$376,000 | | \$78,917 | 376% | 16.7% | |
| Contingency | \$255,502 | | \$308,231 | | -17.1% | -3.0% | Contingency is less (-17.1%). Contingency in 2021 is 15% and not applied to scrap. Contingency in 2016 was 20% and applied to scrap. |
| Total | | \$1,773,720 | | \$1,333,017 | 33.1% | | |
| SCRAP | \$/ton | tons | \$/ton | tons | | | |
| Carbon Steel | \$175 | 899 | \$87 | 971 | | | Carbon steel scrap quantity is essentially the same Carbon/copper is for transformer. Copper in 2016 was based on solid bright (#1 grade) copper Copper broken out into solid bar and insulated copper wire Lower copper quantity in 2021 due to copper included in steel/copper mix for larger transformers |
| Steel/Copper mix (large transformers) | \$350 | 24 | | | | | |
| #1 Copper | | | \$3,460 | 50 | | | |
| #2 Copper | \$6,145 | 0.39 | | | | | |
| #2 Insulated Copper Wire | \$2,440 | 7 | | | | | |
| Labor hours | | 7,914 hours | | 8,515 hours | -7.1% | | The labor hours for the 2021 cost estimate are 7.1% less than the 2016 cost estimate. The main reason is that the 2021 cost estimate includes subcontracts (w/o labor hours), based on updated S&L standards |

SL-016628.C_SDGE Decom(Cuyamaca)

Decommissioning Study

**Prepared for
San Diego Gas & Electric Company
Cuyamaca Peak Energy Plant**

Prepared by Sargent & Lundy

LEGAL NOTICE

This deliverable was prepared by Sargent & Lundy, L.L.C. (S&L) expressly for the sole use of San Diego Gas & Electric Company (Client) in accordance with the contract agreement between S&L and Client. This deliverable was prepared using the degree of skill and care ordinarily exercised by engineers practicing under similar circumstances. Client acknowledges: (1) S&L prepared this deliverable subject to the particular scope limitations, budgetary and time constraints, and business objectives of Client; (2) information and data provided by others, including Client, may not have been independently verified by S&L; and (3) the information and data contained in this deliverable are time-sensitive and changes in the data, applicable codes, standards, and acceptable engineering practices may invalidate the findings of this deliverable. Any use or reliance upon this deliverable by third parties shall be at their sole risk.

Sargent & Lundy is one of the oldest and most experienced full-service architect engineering firms in the world. Founded in 1891, the firm is a global leader in power and energy with expertise in grid modernization, renewable energy, energy storage, nuclear power, and fossil fuels. Sargent & Lundy delivers comprehensive project services—from consulting, design, and implementation to construction management, commissioning, and operations/maintenance—with an emphasis on quality and safety. The firm serves public and private sector clients in the power and energy, gas distribution, industrial, and government sectors.

55 East Monroe Street • Chicago, IL 60603-5780 USA • 312-269-2000

VERSION LOG

| Version | Issue Date | Sections Modified |
|----------|------------------|------------------------------|
| Draft v0 | December 3, 2021 | Initial Issue |
| Final | April 4, 2022 | Executive Summary, Section 2 |

ISSUE SUMMARY AND APPROVAL PAGE

This is to certify that this document has been prepared, reviewed, and approved in accordance with Sargent & Lundy's Standard Operating Procedure SOP-0405, which is based on ANSI/ISO/ASSQC Q9001 Quality Management Systems.

Contributors

Prepared by:

| Name | Title | Section(s) Prepared | Signature | Date |
|----------------|---------------------------|--------------------------|-----------|----------|
| Kyle E. Folken | Energy Consultant | ES, Section 1, Section 2 | | 4/4/2022 |
| Gregory Amen | Cost Information Division | Section 3, Appendix A | | 4/4/2022 |

Reviewed by:

| Name | Title | Section(s) Reviewed | Signature | Date |
|--------------------|---|-----------------------|-----------|----------|
| Borko Andric | Manager | Section 3, Appendix A | | 4/4/2022 |
| Craig Gitchell | Senior Energy Consultant | All | | 4/4/2022 |
| Robert. P. Charles | Senior Principal Consultant & Project Manager | All | | 4/4/2022 |

Approved by:

| | |
|--|---------------|
| | April 4, 2022 |
| Kevin C. Hopkins | Date |
| Principal Consultant & Project Manager | |

TABLE OF CONTENTS

| | |
|---------------------------------------|----------|
| EXECUTIVE SUMMARY | I |
| METHODOLOGY | I |
| CONCEPTUAL COST ESTIMATE | I |
| 1. INTRODUCTION..... | 1 |
| 1.1. SCOPE OF WORK | 1 |
| 1.2. SARGENT & LUNDY BACKGROUND | 1 |
| 1.3. FACILITY DESCRIPTION..... | 2 |
| 2. COST ESTIMATE | 3 |
| 2.1. METHODOLOGY | 3 |
| 2.2. COST ESTIMATE SUMMARY..... | 4 |
| 3. BASIS OF ESTIMATE | 6 |
| 4. REFERENCES..... | 9 |

FIGURES AND TABLES

| | |
|--|----|
| TABLE ES-1 — CUYAMACA COST ESTIMATE SUMMARY | II |
| TABLE ES-2 — CUYAMACA COST ESTIMATE SUMMARY BY FERC ACCOUNT | II |
| TABLE 2-1 — CUYAMACA COST ESTIMATE SUMMARY | 4 |
| TABLE 2-2 — CUYAMACA COST ESTIMATE SUMMARY BY FERC ACCOUNT | 5 |
| TABLE 3-1 — SCRAP VALUE..... | 7 |
| TABLE 3-2 – SDG&E INTERNAL COSTS IN SUPPORT OF DECOMMISSIONING | 7 |

APPENDIXES

| | |
|---|--|
| APPENDIX A. CONCEPTUAL ESTIMATE OF COST TO DISMANTLE CUYAMACA PEAK ENERGY PLANT | |
| APPENDIX B. CONCEPTUAL ESTIMATE OF COST — FERC ACCOUNTS | |
| APPENDIX C. EXPLANATION OF VARIANCE FROM THE PREVIOUS COST STUDY | |

ACRONYMS AND ABBREVIATIONS

| Acronym/Abbreviation | Definition/Clarification |
|----------------------|--------------------------------------|
| CT | combustion turbine |
| Cuyamaca | Cuyamaca Peak Energy Plant |
| FERC | Federal Energy Regulatory Commission |
| G&A | general and administrative |
| Owner | San Diego Gas & Electric Company |
| PCB | polychlorinated biphenyl |
| PWPS | Pratt & Whitney Power Systems |
| S&L | Sargent & Lundy, L.L.C. |
| SCR | selective catalytic reduction |
| SDG&E | San Diego Gas & Electric Company |

EXECUTIVE SUMMARY

Sargent & Lundy (S&L) was contracted by San Diego Gas & Electric Company (“SDG&E” or the “Owner”) to perform an independent conceptual cost estimate for the dismantlement of the Cuyamaca Peak Energy Plant (Cuyamaca) and estimate the average service life of the facility’s peer group. The work scope included updating the 2016 conceptual demolition cost estimate and a benchmarking analysis for the facility.

METHODOLOGY

The S&L methodology for developing the cost estimate consist of three elements: (1) S&L experience in developing plant demolition costs and the existing S&L database for numerous other projects; (2) use of the unit cost factor methodology; and (3) quotes from previous projects for similar activities. The cost estimate was developed based on the drawings, documents, and data provided by SDG&E. These drawings and documents were used to estimate the building foundation sizes, building volumes, and quantities of steel, piping, valves, and other equipment. A site walkdown was performed to conduct a review of the site for dismantlement and determine any specific site-unique requirements. This site walkdown was performed in 2016; however, recent discussions with the Owner and facility management confirmed that no significant modifications have occurred since that time. This information was used with unit cost factors developed by S&L based on industry data and experience. Unit cost factors for concrete removal, steel removal, cutting costs, etc. were developed from labor and material cost information. S&L estimated the quantities of metals that could be recovered and sold for scrap. The estimate includes the value of scrap metals; however, equipment is assumed to have no resale or other salvage value besides the value of scrap metal at the end of its life.

The benchmarking analysis considers publicly available data to determine the average service life of similar facilities.

CONCEPTUAL COST ESTIMATE

The summary of the cost estimate for decommissioning Cuyamaca is shown in Table ES-1. The cost estimate broken into FERC accounts is shown in Table ES-2. All costs are in 2021 U.S. dollars, and the total is the same in both tables: \$1,128,058. The decommissioning costs are expected to increase by the end of the service life of the asset due to escalation and other factors.

Table ES-1 — Cuyamaca Cost Estimate Summary

| Description | Total Cost | Subtotal |
|--|--------------------|-----------|
| Demolition Direct Costs | \$541,510 | – |
| Labor | – | \$336,471 |
| Subcontracts | – | \$15,000 |
| Equipment | – | \$98,799 |
| Material | – | \$91,240 |
| General Condition (Decommissioning Contractor Indirect) Costs | \$218,492 | – |
| Scrap Value | (\$110,494) | – |
| Subtotal Demolition Contractor Costs | \$649,508 | – |
| Project Indirect Costs | \$317,000 | – |
| Engineering | – | \$47,000 |
| SDG&E Internal Costs | – | \$270,000 |
| Contingency Costs | \$161,550 | – |
| Total Demolition Costs | \$1,128,058 | – |

Table ES-2 — Cuyamaca Cost Estimate Summary by FERC Account

| FERC No. | Description | Total Cost |
|----------|---|--------------------|
| 341 | Other Production – Structures and Improvements | \$459,273 |
| 342 | Other Production – Fuel Holders, Producers, and Accessories | \$69,713 |
| 344 | Other Production – Generators | \$333,484 |
| 345 | Other Production – Accessory Electric Equipment | \$265,588 |
| – | General Conditions | Included Above |
| – | Engineering | Included Above |
| – | Contingency | Included Above |
| – | Total Project Cost | \$1,128,058 |

1. INTRODUCTION

1.1. SCOPE OF WORK

Sargent & Lundy (S&L) was contracted by San Diego Gas & Electric Company (“SDG&E” or the “Owner”) to perform an independent conceptual cost estimate for the dismantlement of the Cuyamaca Peak Energy Plant (Cuyamaca) and estimate the average service life of the facility’s peer group. The work scope included updating the 2016 conceptual demolition cost estimate report and a benchmarking analysis.

1.2. SARGENT & LUNDY BACKGROUND

S&L has been dedicated to providing complete engineering and environmental services exclusively to the power industry since 1891. Through work with various utilities, lending institutions, and developers over the years, the Sargent & Lundy Consulting Group has become one of the premier power project consultants in the power industry. This commitment to quality is proven by the successful completion of the ISO 9001 certification audit. S&L’s experience encompasses independent engineer services, including decommissioning cost estimation and average service life evaluation, for both global and domestic electric power assets.

S&L has extensive decommissioning and related services experience, including power plant dismantling, demolition, and layup for fossil fuel, renewable energy, and nuclear plants. This includes decommissioning cost estimates, decommissioning studies, and related services for 18 clients at more than 70 stations. S&L also has extensive experience providing clients with testimony services.

Having engineered over 958 power plant units, S&L has both the benefit of extensive design experience—supported with feedback from operating plants—and individuals with extensive plant operations experience to support consulting services such as those performed for Cuyamaca.

1.3. FACILITY DESCRIPTION

Cuyamaca consists of two simple-cycle combustion turbine (CT) generators located in the El Cajon area of San Diego, California. The units began service in May 2002. In January 2012, the ownership of the plant was transferred from Calpeak Power to SDG&E.

The CTs are Pratt & Whitney Power Systems (PWPS) Model FT8® SWIFTPAC® aeroderivative turbines. Each CT is rated for 25 MW and is equipped with dry low-NOx (DLN) burners.

The Cuyamaca plant includes one 71 MVA electric generator mounted on a common shaft with the two CTs, and a selective catalytic reduction (SCR) unit in an exhaust duct common to both CTs to further reduce NOx emissions to the permitted level. Additionally, the CTs are equipped with a fogging system that cools the inlet air and boosts the power output of the CTs.

2. COST ESTIMATE

2.1. METHODOLOGY

The methodology used for developing the cost estimate includes a combination of deterministic and stochastic methods. Deterministic methods were used based on the quantity and size of equipment (e.g., the number of foundations, linear feet of piping, equipment, etc.). Stochastic methods were also used if quantities information (e.g., fire lines and hydrants, miscellaneous electrical equipment, etc.) was unavailable.

The cost estimate was developed based on drawings, documents, and data provided by the Owner. These drawings and documents were used to estimate the building foundation sizes, building volumes, steel quantities, and the quantity of piping, valves, and other equipment.

The S&L methodology for developing the cost estimate consist of three elements: (1) S&L experience in developing plant demolition cost and the existing S&L database for numerous other projects; (2) use of the unit cost factor methodology; and (3) quotes from previous projects for similar activities.

Cost estimates were created using the S&L cost model format and the S&L cost database. The estimates include both summaries and details for each type of work performed, indirect costs, and contingencies. The cost estimate database report lists costs by buildings, plant systems, and several other categories.

An inventory of plant piping, valves, equipment, HVAC ducts, concrete, galleries, cable tray, and other equipment was developed based on a review of drawings and a site walkdown to conduct a review of the site for dismantlement and determine any specific site-unique requirements. This information was used with unit cost factors developed by S&L based on industry data and S&L experience. Unit cost factors for concrete removal, steel removal, cutting costs, and other tasks were developed from labor and material cost information. S&L also estimated the quantities of recoverable metals that could be recovered and sold for scrap. The estimate includes the value of scrap metals; however, equipment is assumed to have no resale or other salvage value besides the value of scrap metal at the end of its life.

S&L worked from site general arrangement drawings and company documentation for the facilities, including information about any existing metal cleaning storage ponds, asbestos inventories, polychlorinated biphenyl (PCB) inventories, or sludge ponds. S&L relied on SDG&E to identify the location of environmental issues that need to be considered in the estimates, since S&L's scope of work excludes a detailed survey and testing program to identify such problems.

2.2. COST ESTIMATE SUMMARY

The summary of the cost estimate for decommissioning Cuyamaca is shown in Table 2-1. The commercial and technical basis for the estimate is described in Section 3, and the detailed estimate is included in Appendix A. The summary breakdown into FERC accounts is shown in

Table 2-2, and the detailed allocation of FERC accounts is shown in Appendix B. All costs are in 2021 U.S. dollars. The decommissioning costs are expected to increase by the end of the service life of the asset due to escalation and other factors.

The 2021 cost estimate format was changed to be consistent with S&L's current standards. The variance between the 2021 and 2016 cost estimate is shown in Appendix C.

Table 2-1 — Cuyamaca Cost Estimate Summary

| Description | Total Cost | Subtotal |
|--|--------------------|-----------|
| Demolition Direct Costs | \$541,510 | – |
| Labor | – | \$336,471 |
| Subcontracts | – | \$15,000 |
| Equipment | – | \$98,799 |
| Material | – | \$91,240 |
| General Condition (Decommissioning Contractor Indirect) Costs | \$218,492 | – |
| Scrap Value | (\$110,494) | – |
| Subtotal Demolition Contractor Costs | \$649,508 | – |
| Project Indirect Costs | \$317,000 | – |
| Engineering | – | \$47,000 |
| SDG&E Internal Costs | – | \$270,000 |
| Contingency Costs | \$161,550 | – |
| Total Demolition Costs | \$1,128,058 | – |

Table 2-2 — Cuyamaca Cost Estimate Summary by FERC Account

| FERC No. | Description | Total Cost |
|-----------------|---|--------------------|
| 341 | Other Production – Structures and Improvements | \$459,273 |
| 342 | Other Production – Fuel Holders, Producers, and Accessories | \$69,713 |
| 344 | Other Production – Generators | \$333,484 |
| 345 | Other Production – Accessory Electric Equipment | \$265,588 |
| – | General Conditions | Included Above |
| – | Engineering | Included Above |
| – | Contingency | Included Above |
| – | Total Project Cost | \$1,128,060 |

3. BASIS OF ESTIMATE

The basis for the cost estimate is as follows:

1. Construction Labor Wages

Craft labor rates (or craft hourly rates) for the cost estimate are based on the prevailing wages for San Diego, California as published in *R.S. Means Labor Rates for the Construction Industry* (2021). These prevailing rates are representative of union or non-union rates, whichever is prevailing in the area. Costs have been added to cover social security, workmen's compensation, and federal and state unemployment insurance. The resulting burdened craft rates were then used to develop typical crew rates applicable to the task being performed.

2. Labor Work Schedule and Incentives

- The labor estimate is based on a 40-hour workweek with no per diem or other labor incentives.
- An allowance for arrival time is included if workers arrive and are then sent home.

3. Quantity Sources

Quantities of pieces of equipment and/or bulk material commodities used in this cost estimate were developed from supplied engineering information from the sites and the S&L database.

4. General Conditions Cost

Allowances were included for the decommissioning contractor indirect costs in the cost estimate as direct costs, as noted for the following:

- Labor supervision (additional compensation for labor foreman/supervisors)
- Construction management
- Field office expenses
- Safety
- Temporary facilities
- Mobilization/demobilization
- Legal expenses/claims
- Small tools and consumables
- General liability insurance
- Construction equipment mobilization/demobilization
- Freight on material
- Contractor general and administrative costs (7% of labor [direct labor, additional labor cost, site overheads, and other construction indirect cost], material [direct material cost and freight cost], and equipment)

- Contractor's profit (10% of labor [direct labor, additional labor cost, site overheads, and other construction indirect cost], material [direct material cost and freight cost], and equipment)

5. Scrap

Scrap metals are a globally traded commodity and are part of the larger metals industry. The value of scrap metal is subject to constantly changing economic conditions; as such, the price of mixed steel, stainless steel, copper, and aluminum can vary greatly over time as a result of global supply and demand. The value of scrap for this study was determined by a 12-month average from *Scrap Metals MarketWatch*¹ (November 2020–October 2021) for the West Coast (Zone 1) of the United States. The values obtained are delivered prices to the recycler. Transportation cost to the recycler is estimated at \$30/ton, resulting in the values shown in Table 3-1:

Table 3-1 — Scrap Value

| Commodity | Scrap Value (\$/ton) |
|--------------------------|----------------------|
| Carbon Steel | 175 |
| #2 Copper | 6,145 |
| #2 Insulated Copper Wire | 2,440 |

Note: 1 ton = 2000 lbs.

6. Project Schedule

Cuyamaca has a 12-month construction schedule.

7. Indirect Expenses

- Engineering is included to cover preparation of the decommissioning work specification, the engineering required to place the plant in a safe shutdown, and any unique engineering required during demolition.
- SDG&E internal costs are included to cover costs in support of decommissioning the facility.

Table 3-2 – SDG&E Internal Costs in Support of Decommissioning

| Activity | Estimated Cost |
|--|------------------|
| Labor to prepare the site for demolition, including drain oils, drain reagents, de-energization of the power buses, etc. | \$90,000 |
| Site security | \$60,000 |
| Subcontracts to remove chemicals, oils, and reagents from the site | \$40,000 |
| SDG&E project management, permitting, and procurement | \$80,000 |
| Total | \$270,000 |

8. Escalation Rates

Escalation rates were excluded from the estimates.

¹ www.americanrecycler.com

9. Sales and Use Taxes

Sales and use taxes were excluded from the estimates.

10. Contingency

- A 15% contingency is applied for labor, material, equipment, subcontracting, and indirect costs. General conditions (indirect demolition contractor costs) are allocated across labor, material, and equipment.
- There is no contingency on scrap value

11. Contract Basis for Estimate

The contracting strategy is a multiple lump sum for the estimate.

12. Assumptions

- The facility will be in safe-shutdown mode and ready for a decommissioning contractor to start work.
- All chemicals and lubricating oils will be removed from the facilities to be demolished by the utility before demolition.
- No extraordinary environmental costs for demolition will be needed.
- There will be no PCBs on site at the time of demolition.
- Switchyards within the plant boundaries are not part of the scope, nor are access roads to these facilities.
- All items above grade and to a depth of one foot, including foundations, will be demolished. Any other items buried more than one foot deep will remain in place.
- Underground piping will be abandoned in place.
- Underground piping larger than four feet in diameter will be filled with sand or slurry and capped at the ends to prevent collapse (none noted at this site). Non-metal pipe will be collapsed.
- All demolished materials are considered debris, except for organic combustibles and non-embedded metals, which have scrap value.
- The basis for salvage estimating is for scrap value only. No resale of equipment or material is included.
- Handling onsite and offsite disposal of hazardous materials will be performed in compliance with methods approved by SDG&E's Environmental Services Department.
- All borrow (fill) material is assumed to be from offsite sources.
- Catalyst is assumed to be removed and returned to the original equipment manufacturer before demolition.

4. REFERENCES

1. Sargent & Lundy Cost Database.
2. R.S. Means Cost Data, 2021.
3. Engineering drawings, equipment lists, and other information provided by the San Diego Gas & Electric.
4. 2020 Form EIA-860 Data – Schedule 3, “Generator Data” (Retired & Canceled Units Only).
5. *Scrap Metals MarketWatch*, West Coast (Zone 1), www.americanrecycler.com.

**APPENDIX A. CONCEPTUAL ESTIMATE OF COST
TO DISMANTLE CUYAMACA PEAK ENERGY
PLANT**

**SAN DIEGO GAS & ELECTRIC
CAYAMACA PEAK ENERGY PLANT
DECOMMISSIONING STUDY**

| | |
|-------------------------|------------|
| Estimator | GA |
| Labor rate table | 21CASAN |
| Project No. | A14520.001 |
| Estimate Date | 11/30/21 |
| Reviewed By | BA |
| Approved By | BA |
| Estimate No. | 33965B |

SAN DIEGO GAS & ELECTRIC
 CAYAMACA PEAK ENERGY PLANT
 DECOMMISSIONING STUDY



| Group | Description | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|----------|------------------------|------------------|------------------|---------------|--------------|----------------|---------------|----------------|
| 10.00.00 | WHOLE PLANT DEMOLITION | | | | 3,604 | 296,981 | 86,240 | 383,221 |
| 18.00.00 | SCRAP VALUE | | (110,494) | | 0 | | | (110,494) |
| 21.00.00 | CIVIL WORK | 15,000 | | 91,240 | 472 | 39,490 | 12,559 | 158,289 |
| | TOTAL DIRECT | 15,000 | (110,494) | 91,240 | 4,076 | 336,471 | 98,799 | 431,016 |

**SAN DIEGO GAS & ELECTRIC
 CAYAMACA PEAK ENERGY PLANT
 DECOMMISSIONING STUDY**



Estimate Totals

| Description | Amount | Totals | Hours |
|-------------------------------------|------------------|------------------|-------|
| Labor | 336,471 | | 4,076 |
| Material | 91,240 | | |
| Subcontract | 15,000 | | |
| Construction Equipment | 98,799 | | |
| Scrap Value | <u>(110,494)</u> | | |
| | 431,016 | 431,016 | |
| General Conditions | | | |
| Additional Labor Costs | | | |
| 90-1 Labor Supervision | 20,188 | | |
| 90-2 Show-up Time | 6,729 | | |
| 90-3 Cost Due To OT 5-10's | | | |
| 90-4 Cost Due To OT 6-10's | | | |
| 90-5 Per Diem | | | |
| Site Overheads | | | |
| 91-1 Construction Management | 36,339 | | |
| 91-2 Field Office Expenses | 7,995 | | |
| 91-3 Material&Quality Control | | | |
| 91-4 Site Services | | | |
| 91-5 Safety | 7,179 | | |
| 91-6 Temporary Facilities | 5,462 | | |
| 91-7 Temporary Utilities | | | |
| 91-8 Mobilization/Demob. | 5,756 | | |
| 91-9 Legal Expenses/Claims | 850 | | |
| Other Construction Indirects | | | |
| 92-1 Small Tools & Consumables | 3,634 | | |
| 92-2 Scaffolding | | | |
| 92-3 General Liability Insur. | 3,634 | | |
| 92-4 Constr. Equip. Mob/Demob | 9,880 | | |
| 92-5 Freight on Material | 4,562 | | |
| 92-6 Freight on Scrap | | | |
| 92-7 Sales Tax | | | |
| 92-8 Contractors G&A | 43,764 | | |
| 92-9 Contractors Profit | <u>62,520</u> | | |
| | 218,492 | 649,508 | |
| Project Indirect Costs | | | |
| 93-1 Engineering Services | 47,000 | | |
| 93-2 CM Support | | | |
| 93-3 Start-Up/Commissioning | | | |
| 93-4 Start-Up/Spare Parts | | | |
| 93-5 Excess Liability Insur. | | | |
| 93-6 Sales Tax On Indirects | | | |
| 93-7 SDG&E Internal Costs | 270,000 | | |
| 93-8 EPC Fee | <u></u> | | |
| | 317,000 | 966,508 | |
| Contingency | | | |
| 94-1 Contingency on Const Eq | 18,821 | | |
| 94-3 Contingency on Material | 16,813 | | |
| 94-4 Contingency on Labor | 76,116 | | |
| 94-5 Contingency on Subcontr. | 2,250 | | |
| 94-6 Contingency on Scrap | | | |
| 94-7 Contingency on Indirect | <u>47,550</u> | | |
| | 161,550 | 1,128,058 | |
| Escalation | | | |
| 96-1 Escalation on Const Equip | | | |
| 96-3 Escalation on Material | | | |
| 96-4 Escalation on Labor | | | |
| 96-5 Escalation on Subcontract | | | |
| 96-6 Escalation on Scrap | | | |
| 96-7 Escalation on Indirects | | 1,128,058 | |
| 98 Interest During Constr | | 1,128,058 | |
| Total | | 1,128,058 | |

**SAN DIEGO GAS & ELECTRIC
 CAYAMACA PEAK ENERGY PLANT
 DECOMMISSIONING STUDY**



| Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|-----------------|-----------------|--|---|-------------|------------------|-------------|---------------|------------|---------------|---------------|---------------|
| 10.00.00 | | WHOLE PLANT DEMOLITION | | | | | | | | | |
| | 10.21.00 | CIVIL WORK | | | | | | | | | |
| | | REMOVE FENCE | | 370.00 LF | - | - | | 44 | 3,945 | 2,050 | 5,995 |
| | | INCORPORATE EXISTING PAVED SURFACES INTO NEW PARKING LOT | EXISTING PAVED SURFACES (IF NOT DISTURBED, WILL NOT BE DEMOLISHED) | 1,500.00 SY | - | - | | 180 | 15,993 | 8,312 | 24,305 |
| | | CIVIL WORK | | | | | | 224 | 19,938 | 10,363 | 30,301 |
| | 10.22.00 | CONCRETE | | | | | | | | | |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | SCR | 89.00 CY | - | - | | 100 | 8,935 | 2,202 | 11,137 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | STACK FDN | 36.00 CY | - | - | | 41 | 3,614 | 891 | 4,505 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | RAW AND DEMIN WATER TANKS | 84.00 CY | - | - | | 95 | 8,433 | 2,078 | 10,511 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | AMMONIA AND WASH DOWN TANK | 27.00 CY | - | - | | 30 | 2,711 | 668 | 3,379 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | CURBS AND WALL | | | | | | | | |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | 850 LF OF PERIMETER CURB | 45.00 CY | - | - | | 51 | 4,518 | 1,113 | 5,631 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | SWITCHYARD AND MAIN | 20.00 CY | - | - | | 23 | 2,008 | 495 | 2,503 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | TRANSFORMER FDN | | | | | | | | |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | AUX TRANSFORMERS FDN | 8.00 CY | - | - | | 9 | 803 | 198 | 1,001 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | CONTROL / SWITCHGEAR BUILDING | 22.00 CY | - | - | | 25 | 2,209 | 544 | 2,753 |
| | | TURBINE GENERATOR FDN | BOTH CT'S AND GENERATOR | 148.00 CY | - | - | | 266 | 23,774 | 5,858 | 29,632 |
| | | CONCRETE | | | | | | 639 | 57,004 | 14,047 | 71,051 |
| | 10.23.00 | STEEL | | | | | | | | | |
| | | STRUCTURAL, GIRT AND GALLERY STEEL | | 57.00 TN | - | - | | 58 | 4,955 | 976 | 5,931 |
| | | PERIMETER SHEET METAL WALL | INCLUDES STEEL COLUMNS | 31.00 TN | - | - | | 84 | 7,161 | 1,411 | 8,573 |
| | | STEEL | | | | | | 142 | 12,116 | 2,388 | 14,504 |
| | 10.24.00 | ARCHITECTURAL | | | | | | | | | |
| | | CONTROL / SWITCHGEAR BUILDING | 13' X 40' X 12'H | 6,240.00 CF | - | - | | 19 | 1,558 | 519 | 2,077 |
| | | ELECTRICAL BUILDING | 12' X 50' X 12'H | 7,200.00 CF | - | - | | 22 | 1,798 | 599 | 2,397 |
| | | MASONRY WALLS | 80'L X 22'H X 2' THICK | 1,760.00 SF | - | - | | 14 | 1,172 | 390 | 1,562 |
| | | ARCHITECTURAL | | | | | | 54 | 4,528 | 1,509 | 6,036 |
| | 10.26.00 | MISCELLANEOUS STRUCTURAL ITEM | | | | | | | | | |
| | | MISCELLANEOUS SMALL OBSTACLE REMOVAL FROM SITE | | 1.00 LT | - | - | | 300 | 23,982 | 6,831 | 30,813 |
| | | MISCELLANEOUS STRUCTURAL ITEM | | | | | | 300 | 23,982 | 6,831 | 30,813 |
| | 10.31.00 | MECHANICAL EQUIPMENT | | | | | | | | | |
| | | COMBUSTION TURBINE | FT8 SWIFTPAC (2 CTs W/GENERATOR AND ACCESSORIES) | 119.00 TN | - | - | | 417 | 33,295 | 9,484 | 42,779 |
| | | SCR CASING | | 19.00 TN | - | - | | 51 | 4,101 | 1,168 | 5,269 |
| | | SCR CAVITY DUCTWORK | | 39.00 TN | - | - | | 105 | 8,418 | 2,398 | 10,815 |
| | | TANKS AND SILOS | 47,000 GAL, RAW WATER STORAGE TANK | 12.00 TN | - | - | | 32 | 2,590 | 738 | 3,328 |
| | | TANKS AND SILOS | 47,000 GAL, DEMINERALIZED WATER TANK | 12.00 TN | - | - | | 32 | 2,590 | 738 | 3,328 |
| | | TANKS AND SILOS | 12,000 GAL, AQUEOUS AMMONIA TANK | 5.00 TN | - | - | | 14 | 1,079 | 307 | 1,387 |
| | | FUEL GAS COMPRESSOR AND GAS CONDITIONING SKID | | 25.00 TN | - | - | | 68 | 5,396 | 1,537 | 6,933 |
| | | MISCELLANEOUS EQUIPMENT | | 15.00 TN | - | - | | 41 | 3,238 | 922 | 4,160 |
| | | CT AIR INTAKE SYSTEM W DUCTS & SILENCER | 2 CT'S | 28.00 TN | - | - | | 76 | 6,043 | 1,721 | 7,765 |
| | | WASHDOWN DRAIN TANK | | 2.00 TN | - | - | | 8 | 640 | 182 | 822 |
| | | CT LUBE OIL SYSTEM | | 3.00 TN | - | - | | 15 | 1,199 | 342 | 1,541 |
| | | STEEL EXHAUST STACK | 55 FT X 10 FT DIA | 20.00 TN | - | - | | 41 | 3,238 | 922 | 4,160 |
| | | MECHANICAL EQUIPMENT | | | | | | 899 | 71,826 | 20,459 | 92,285 |
| | 10.35.00 | PIPING | | | | | | | | | |
| | | LARGE BORE PIPING, VALVES AND HANGERS | 3550 LF | 24.00 TN | - | - | | 49 | 3,885 | 1,107 | 4,992 |
| | | SMALL BORE PIPING, VALVES AND HANGERS | | 8.00 TN | - | - | | 16 | 1,295 | 369 | 1,664 |
| | | FIRE LINES AND HYDRANTS | | 1.00 LT | - | - | | 80 | 6,395 | 1,822 | 8,217 |
| | | PIPING | | | | | | 145 | 11,575 | 3,297 | 14,872 |
| | 10.41.00 | ELECTRICAL EQUIPMENT | | | | | | | | | |
| | | TRANSFORMERS | ONE (1) SDG&E Decommission/Exh No SDG&E-36-WP-S/Witness: D. A. Watson | | | | | 24 | 1,922 | 548 | 2,470 |

**SAN DIEGO GAS & ELECTRIC
 CAYAMACA PEAK ENERGY PLANT
 DECOMMISSIONING STUDY**



| Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|-----------------|-----------------|--|--|--------------|------------------|------------------|---------------|--------------|----------------|---------------|------------------|
| | 10.41.00 | ELECTRICAL EQUIPMENT | | | | | | | | | |
| | | TRANSFORMERS | 13.8 KV / 480 V | 9.00 TN | - | - | | 24 | 1,922 | 548 | 2,470 |
| | | OUTDOOR LIGHT POLE / FIXTURE | | 1.00 LT | - | - | | 150 | 11,991 | 3,416 | 15,407 |
| | | MISCELLANEOUS ELECTRICAL EQUIPMENT | | 103.00 TN | - | - | | 367 | 29,337 | 8,356 | 37,693 |
| | | ELECTRICAL EQUIPMENT | | | | | | 541 | 43,251 | 12,319 | 55,570 |
| | 10.42.00 | RACEWAY, CABLE TRAY, & CONDUIT | | | | | | | | | |
| | | CONDUIT | | 12,000.00 LF | - | - | | 120 | 9,593 | 2,732 | 12,325 |
| | | CABLE TRAY | | 2,500.00 LF | - | - | | 100 | 7,994 | 2,277 | 10,271 |
| | | RACEWAY, CABLE TRAY, & CONDUIT | | | | | | 220 | 17,587 | 5,009 | 22,596 |
| | 10.43.00 | CABLE | | | | | | | | | |
| | | COPPER WIRE / CABLE - MEDIUM VOLTAGE | | 4,500.00 LF | - | - | | 90 | 7,195 | 2,049 | 9,244 |
| | | COPPER WIRE / CABLE - LOW VOLTAGE | | 25,000.00 LF | - | - | | 250 | 19,985 | 5,693 | 25,678 |
| | | CABLE | | | | | | 340 | 27,180 | 7,742 | 34,921 |
| | 10.44.00 | CONTROL & INSTRUMENTATION | | | | | | | | | |
| | | CONTROL & INSTRUMENTATION | | 1.00 LT | - | - | | 100 | 7,994 | 2,277 | 10,271 |
| | | CONTROL & INSTRUMENTATION | | | | | | 100 | 7,994 | 2,277 | 10,271 |
| | | WHOLE PLANT DEMOLITION | | | | | | 3,604 | 296,981 | 86,240 | 383,221 |
| 18.00.00 | | SCRAP VALUE | | | | | | | | | |
| | 18.10.00 | MIXED STEEL | | | | | | | | | |
| | | CARBON STEEL | | -78.00 TN | - | (13,650) | - | 0 | | | (13,650) |
| | | CARBON STEEL | | -253.00 TN | - | (44,275) | - | 0 | | | (44,275) |
| | | CARBON STEEL | BUILDINGS | -5.32 TN | - | (931) | - | 0 | | | (931) |
| | | CARBON STEEL | CONDUIT, 1.5" DIA. AVG SIZE, 2.63 LBS/LF | -15.78 TN | - | (2,761) | - | 0 | | | (2,761) |
| | | CARBON STEEL | CABLE TRAY, 6 LBS/LF | -7.50 TN | - | (1,312) | - | 0 | | | (1,312) |
| | | CARBON STEEL | | -88.00 TN | - | (15,400) | - | 0 | | | (15,400) |
| | | CARBON STEEL | MISCELLANEOUS ELECTRICAL EQUIPMENT | -103.00 TN | - | (18,025) | - | 0 | | | (18,025) |
| | | STEEL / COPPER MIX - LARGE TRANSFORMER > 100 KVA | | -9.00 TN | - | (3,150) | - | 0 | | | (3,150) |
| | | MIXED STEEL | | | | (99,505) | | 0 | | | (99,505) |
| | 18.30.00 | COPPER | | | | | | | | | |
| | | #2 SOLID COPPER / TUBING | BUS BAR | -0.20 TN | - | (1,229) | - | 0 | | | (1,229) |
| | | #2 INSULATED COPPER WIRE | | -4.00 TN | - | (9,760) | - | 0 | | | (9,760) |
| | | COPPER | | | | (10,989) | | 0 | | | (10,989) |
| | | SCRAP VALUE | | | | (110,494) | | 0 | | | (110,494) |
| 21.00.00 | | CIVIL WORK | | | | | | | | | |
| | 21.18.00 | HAULING | | | | | | | | | |
| | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 308.00 CY | 6,160 | - | | | | | 6,160 |
| | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 111.00 CY | 2,220 | - | | | | | 2,220 |
| | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 273.00 CY | 5,460 | - | | | | | 5,460 |
| | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 28.00 CY | 560 | - | | | | | 560 |
| | | HAULING | | | 14,400 | | | | | | 14,400 |
| | 21.21.00 | MASS FILL | | | | | | | | | |
| | | MASS FILL, COMMON EARTH 6 INCHES THICK | COVER DISTURBED AREAS OF SITE WITH 1' OF BACKFILL MATERIAL | 652.00 CY | - | - | 13,040 | 23 | 2,079 | 2,190 | 17,310 |
| | | MASS FILL | | | | | 13,040 | 23 | 2,079 | 2,190 | 17,310 |
| | 21.52.00 | WASTE DISPOSAL | | | | | | | | | |
| | | DISPOSAL AND TRANSPORTATION FEE | RUBBISH & TENANT DEBRIS | 20.00 CY | 600 | - | | | | | 600 |
| | | WASTE DISPOSAL | | | 600 | | | | | | 600 |

SAN DIEGO GAS & ELECTRIC
 CAYAMACA PEAK ENERGY PLANT
 DECOMMISSIONING STUDY



| Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|----------|-------|---|-----------------|-------------|------------------|-------------|---------------|------------|---------------|---------------|----------------|
| 21.57.00 | | ROAD, PARKING AREA, & SURFACED AREA | | | | | | | | | |
| | | COVER DISTURBED AREAS OF SITE WITH 2.5" OF ASPHALT OVER 4" OF CRUSHED ROCK BASE | NEW PARKING LOT | 1,955.00 SY | - | - | 78,200 | 450 | 37,411 | 10,369 | 125,980 |
| | | ROAD, PARKING AREA, & SURFACED AREA | | | | | <u>78,200</u> | <u>450</u> | <u>37,411</u> | <u>10,369</u> | <u>125,980</u> |
| | | CIVIL WORK | | | 15,000 | | 91,240 | 472 | 39,490 | 12,559 | 158,289 |

**APPENDIX B. CONCEPTUAL ESTIMATE OF COST
— FERC ACCOUNTS**

**SAN DIEGO GAS & ELECTRIC
CAYAMACA PEAK ENERGY PLANT
DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS**

| | |
|-------------------------|------------|
| Estimator | GA |
| Labor rate table | 21CASAN |
| Project No. | A14520.001 |
| Estimate Date | 11/30/21 |
| Reviewed By | BA |
| Approved By | BA |
| Estimate No. | 33965B |

SAN DIEGO GAS & ELECTRIC
 CAYAMACA PEAK ENERGY PLANT
 DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS



| Area | Description | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|------|--|------------------|-------------|---------------|-----------|------------|--------------|------------|
| 341 | OTHER PRODUCTION - STRUCTURES & IMPROVEMENTS | 11,017 | (16,331) | 182,667 | 1,048 | 219,215 | 62,705 | 459,273 |
| 342 | OTHER PRODUCTION - FUEL HOLDERS, PRODUCERS AND ACCESSORIES | 3,618 | (13,650) | | 316 | 65,033 | 14,713 | 69,713 |
| 344 | OTHER PRODUCTION - GENERATORS | 8,898 | (44,275) | | 1,479 | 299,831 | 69,030 | 333,484 |
| 345 | OTHER PRODUCTION - ACCESSORY ELECTRIC EQUIPMENT | 913 | (36,238) | | 1,233 | 242,879 | 58,034 | 265,588 |

**SAN DIEGO GAS & ELECTRIC
 CAYAMACA PEAK ENERGY PLANT
 DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS**



Estimate Totals

| Description | Amount | Totals | Hours |
|-------------------------------------|------------------|------------------|-------|
| Labor | 826,958 | | 4,076 |
| Material | 162,667 | | |
| Subcontract | 24,445 | | |
| Construction Equipment | 204,483 | | |
| Scrap Value | <u>(110,494)</u> | | |
| | 1,128,059 | 1,128,059 | |
| General Conditions | | | |
| Additional Labor Costs | | | |
| Site Overheads | | | |
| Other Construction Indirects | | | |
| | | 1,128,059 | |
| Project Indirect Costs | | | |
| | | 1,128,059 | |
| Contingency | | | |
| | | 1,128,059 | |
| Escalation | | | |
| | | 1,128,059 | |
| Total | | 1,128,059 | |

General Conditions, Indirect Costs and Contingency are allocated in the line items above.

**SAN DIEGO GAS & ELECTRIC
 CAYAMACA PEAK ENERGY PLANT
 DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS**



| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|------------|----------|----------|---|--|-------------|------------------|-----------------|----------------|--------------|----------------|---------------|-----------------|
| 341 | | | OTHER PRODUCTION - STRUCTURES & IMPROVEMENTS | | | | | | | | | |
| | 10.00.00 | | WHOLE PLANT DEMOLITION | | | | | | | | | |
| | | 10.21.00 | CIVIL WORK | | | | | | | | | |
| | | | REMOVE FENCE | | 370.00 LF | - | - | | 44 | 9,696 | 4,244 | 13,939 |
| | | | INCORPORATE EXISTING PAVED SURFACES INTO NEW PARKING LOT | EXISTING PAVED SURFACES (IF NOT DISTURBED, WILL NOT BE DEMOLISHED) | 1,500.00 SY | - | - | | 180 | 39,307 | 17,204 | 56,511 |
| | | | CIVIL WORK | | | | | | <u>224</u> | <u>49,002</u> | <u>21,448</u> | <u>70,450</u> |
| | | 10.22.00 | CONCRETE | | | | | | | | | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | 850 LF OF PERIMETER CURB | 45.00 CY | - | - | | 51 | 11,104 | 2,304 | 13,408 |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | CONTROL / SWITCHGEAR BUILDING | 22.00 CY | - | - | | 25 | 5,428 | 1,126 | 6,555 |
| | | | CONCRETE | | | | | | <u>75</u> | <u>16,532</u> | <u>3,430</u> | <u>19,962</u> |
| | | 10.23.00 | STEEL | | | | | | | | | |
| | | | STRUCTURAL, GIRT AND GALLERY STEEL | | 57.00 TN | - | - | | 58 | 12,178 | 2,021 | 14,199 |
| | | | PERIMETER SHEET METAL WALL | INCLUDES STEEL COLUMNS | 31.00 TN | - | - | | 84 | 17,601 | 2,921 | 20,521 |
| | | | STEEL | | | | | | <u>142</u> | <u>29,779</u> | <u>4,942</u> | <u>34,720</u> |
| | | 10.24.00 | ARCHITECTURAL | | | | | | | | | |
| | | | CONTROL / SWITCHGEAR BUILDING | 13' X 40' X 12H | 6,240.00 CF | - | - | | 19 | 3,829 | 1,074 | 4,904 |
| | | | ELECTRICAL BUILDING | 12' X 50' X 12H | 7,200.00 CF | - | - | | 22 | 4,418 | 1,240 | 5,658 |
| | | | MASONRY WALLS | 80'L X 22'H X 2' THICK | 1,760.00 SF | - | - | | 14 | 2,880 | 808 | 3,688 |
| | | | ARCHITECTURAL | | | | | | <u>54</u> | <u>11,128</u> | <u>3,122</u> | <u>14,250</u> |
| | | 10.35.00 | PIPING | | | | | | | | | |
| | | | FIRE LINES AND HYDRANTS | | 1.00 LT | - | - | | 80 | 15,718 | 3,770 | 19,488 |
| | | | PIPING | | | | | | <u>80</u> | <u>15,718</u> | <u>3,770</u> | <u>19,488</u> |
| | | | WHOLE PLANT DEMOLITION | | | | | | <u>576</u> | <u>122,159</u> | <u>36,712</u> | <u>158,871</u> |
| | 18.00.00 | | SCRAP VALUE | | | | | | | | | |
| | | 18.10.00 | MIXED STEEL | | | | | | | | | |
| | | | CARBON STEEL | BUILDINGS | -5.32 TN | - | (931) | | 0 | | | (931) |
| | | | CARBON STEEL | | -88.00 TN | - | (15,400) | | 0 | | | (15,400) |
| | | | MIXED STEEL | | | | <u>(16,331)</u> | | <u>0</u> | | | <u>(16,331)</u> |
| | | | SCRAP VALUE | | | | <u>(16,331)</u> | | <u>0</u> | | | <u>(16,331)</u> |
| | 21.00.00 | | CIVIL WORK | | | | | | | | | |
| | | 21.18.00 | HAULING | | | | | | | | | |
| | | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 308.00 CY | 10,039 | - | | | | | 10,039 |
| | | | HAULING | | | <u>10,039</u> | | | | | | <u>10,039</u> |
| | | 21.21.00 | MASS FILL | | | | | | | | | |
| | | | MASS FILL, COMMON EARTH 6 INCHES THICK | COVER DISTURBED AREAS OF SITE WITH 1' OF BACKFILL MATERIAL | 652.00 CY | - | - | 26,107 | 23 | 5,111 | 4,533 | 35,750 |
| | | | MASS FILL | | | | | <u>26,107</u> | <u>23</u> | <u>5,111</u> | <u>4,533</u> | <u>35,750</u> |
| | | 21.52.00 | WASTE DISPOSAL | | | | | | | | | |
| | | | DISPOSAL AND TRANSPORTATION FEE | RUBBISH & TENANT DEBRIS | 20.00 CY | 978 | - | | | | | 978 |
| | | | WASTE DISPOSAL | | | <u>978</u> | | | | | | <u>978</u> |
| | | 21.57.00 | ROAD, PARKING AREA, & SURFACED AREA | | | | | | | | | |
| | | | COVER DISTURBED AREAS OF SITE WITH 2.5" OF ASPHALT OVER 4" OF CRUSHED ROCK BASE | NEW PARKING LOT | 1,955.00 SY | - | - | 156,560 | 450 | 91,946 | 21,460 | 269,967 |
| | | | ROAD, PARKING AREA, & SURFACED AREA | | | | | <u>156,560</u> | <u>450</u> | <u>91,946</u> | <u>21,460</u> | <u>269,967</u> |
| | | | CIVIL WORK | | | <u>11,017</u> | | <u>182,667</u> | <u>472</u> | <u>97,957</u> | <u>25,994</u> | <u>316,734</u> |
| | | | 341 OTHER PRODUCTION - STRUCTURES & IMPROVEMENTS | | | 11,017 | (16,331) | 182,667 | 1,048 | 219,215 | 62,705 | 459,273 |
| 342 | | | OTHER PRODUCTION - FUEL HOLDERS, PRODUCERS AND ACCESSORIES | | | | | | | | | |
| | 10.00.00 | | WHOLE PLANT DEMOLITION | | | | | | | | | |
| | | 10.22.00 | CONCRETE | | | | | | | | | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | RAW AND DEMIN WATER TANKS | 84.00 CY | - | - | | 95 | 20,727 | 4,301 | 25,027 |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | AMMONIA AND WASH DOWN TANK CURBS AND WALL | 27.00 CY | - | - | | 30 | 6,662 | 1,382 | 8,045 |

**SAN DIEGO GAS & ELECTRIC
 CAYAMACA PEAK ENERGY PLANT
 DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS**



| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost | | |
|----------|----------|----------|---|--|------------|------------------|-------------|---------------|-----------|------------|--------------|------------|---------|--------|
| | | | CONCRETE | | | | | | | 125 | 27,389 | 5,683 | 33,072 | |
| | 10.31.00 | | MECHANICAL EQUIPMENT | | | | | | | | | | | |
| | | | TANKS AND SILOS | 47,000 GAL, RAW WATER STORAGE TANK | 12.00 TN | - | - | - | 32 | 6,366 | 1,527 | 7,893 | | |
| | | | TANKS AND SILOS | 47,000 GAL, DEMINERALIZED WATER TANK | 12.00 TN | - | - | - | 32 | 6,366 | 1,527 | 7,893 | | |
| | | | TANKS AND SILOS | 12,000 GAL, AQUEOUS AMMONIA TANK | 5.00 TN | - | - | - | 14 | 2,652 | 636 | 3,289 | | |
| | | | MISCELLANEOUS EQUIPMENT | | 15.00 TN | - | - | - | 41 | 7,957 | 1,909 | 9,866 | | |
| | | | WASHDOWN DRAIN TANK | | 2.00 TN | - | - | - | 8 | 1,572 | 377 | 1,949 | | |
| | | | MECHANICAL EQUIPMENT | | | | | | | | | | | |
| | | | | | | | | | 127 | 24,913 | 5,976 | 30,888 | | |
| | 10.35.00 | | PIPING | | | | | | | | | | | |
| | | | LARGE BORE PIPING, VALVES AND HANGERS | 3550 LF | 24.00 TN | - | - | - | 49 | 9,549 | 2,290 | 11,839 | | |
| | | | SMALL BORE PIPING, VALVES AND HANGERS | | 8.00 TN | - | - | - | 16 | 3,183 | 763 | 3,946 | | |
| | | | PIPING | | | | | | | | | | | |
| | | | | | | | | | 65 | 12,731 | 3,054 | 15,785 | | |
| | | | WHOLE PLANT DEMOLITION | | | | | | | 316 | 65,033 | 14,713 | 79,745 | |
| 18.00.00 | | | SCRAP VALUE | | | | | | | | | | | |
| | 18.10.00 | | MIXED STEEL | | | | | | | | | | | |
| | | | CARBON STEEL | | -78.00 TN | - | (13,650) | - | 0 | | | (13,650) | | |
| | | | MIXED STEEL | | | | | | | | | | | |
| | | | | | | | (13,650) | | 0 | | | (13,650) | | |
| | | | SCRAP VALUE | | | | | | | | | | | |
| | | | | | | | (13,650) | | 0 | | | (13,650) | | |
| 21.00.00 | | | CIVIL WORK | | | | | | | | | | | |
| | 21.18.00 | | HAULING | | | | | | | | | | | |
| | | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED, NO DISPOSAL FEE | 111.00 CY | 3,618 | - | - | | | | 3,618 | | |
| | | | HAULING | | | | | | | | | | | |
| | | | | | | 3,618 | | | | | | 3,618 | | |
| | | | CIVIL WORK | | | | | | | | | | | |
| | | | | | | 3,618 | | | | | | 3,618 | | |
| | | | 342 OTHER PRODUCTION - FUEL HOLDERS, PRODUCERS AND ACCESSORIES | | | | | | 3,618 | (13,650) | 316 | 65,033 | 14,713 | 69,713 |
| 344 | | | OTHER PRODUCTION - GENERATORS | | | | | | | | | | | |
| | 10.00.00 | | WHOLE PLANT DEMOLITION | | | | | | | | | | | |
| | | 10.22.00 | CONCRETE | | | | | | | | | | | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | SCR | 89.00 CY | - | - | - | 100 | 21,960 | 4,557 | 26,517 | | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | STACK FDN | 36.00 CY | - | - | - | 41 | 8,883 | 1,843 | 10,726 | | |
| | | | TURBINE GENERATOR FDN | BOTH CTS AND GENERATOR | 148.00 CY | - | - | - | 266 | 58,429 | 12,124 | 70,554 | | |
| | | | CONCRETE | | | | | | | | | | | |
| | | | | | | | | | 407 | 89,272 | 18,525 | 107,797 | | |
| | | 10.26.00 | MISCELLANEOUS STRUCTURAL ITEM | | | | | | | | | | | |
| | | | MISCELLANEOUS SMALL OBSTACLE REMOVAL FROM SITE | | 1.00 LT | - | - | - | 300 | 58,942 | 14,138 | 73,080 | | |
| | | | MISCELLANEOUS STRUCTURAL ITEM | | | | | | | | | | | |
| | | | | | | | | | 300 | 58,942 | 14,138 | 73,080 | | |
| | | 10.31.00 | MECHANICAL EQUIPMENT | | | | | | | | | | | |
| | | | COMBUSTION TURBINE | FT8 SWIFTPAC (2 CTS W/GENERATOR AND ACCESSORIES) | 119.00 TN | - | - | - | 417 | 81,830 | 19,628 | 101,459 | | |
| | | | SCR CASING | | 19.00 TN | - | - | - | 51 | 10,079 | 2,418 | 12,497 | | |
| | | | SCR CAVITY DUCTWORK | | 39.00 TN | - | - | - | 105 | 20,688 | 4,962 | 25,651 | | |
| | | | FUEL GAS COMPRESSOR AND GAS CONDITIONING SKID | | 25.00 TN | - | - | - | 68 | 13,262 | 3,181 | 16,443 | | |
| | | | CT AIR INTAKE SYSTEM W DUCTS & SILENCER | 2 CTS | 28.00 TN | - | - | - | 76 | 14,853 | 3,563 | 18,416 | | |
| | | | CT LUBE OIL SYSTEM | | 3.00 TN | - | - | - | 15 | 2,947 | 707 | 3,654 | | |
| | | | STEEL EXHAUST STACK | 55 FT X 10 FT DIA | 20.00 TN | - | - | - | 41 | 7,957 | 1,909 | 9,866 | | |
| | | | MECHANICAL EQUIPMENT | | | | | | | | | | | |
| | | | | | | | | | 772 | 151,617 | 36,368 | 187,985 | | |
| | | | WHOLE PLANT DEMOLITION | | | | | | | 1,479 | 299,831 | 69,030 | 368,861 | |
| 18.00.00 | | | SCRAP VALUE | | | | | | | | | | | |
| | 18.10.00 | | MIXED STEEL | | | | | | | | | | | |
| | | | CARBON STEEL | | -253.00 TN | - | (44,275) | - | 0 | | | (44,275) | | |
| | | | MIXED STEEL | | | | | | | | | | | |
| | | | | | | | (44,275) | | 0 | | | (44,275) | | |
| | | | SCRAP VALUE | | | | | | | | | | | |
| | | | | | | | (44,275) | | 0 | | | (44,275) | | |
| 21.00.00 | | | CIVIL WORK | | | | | | | | | | | |
| | 21.18.00 | | HAULING | | | | | | | | | | | |
| | | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED, NO DISPOSAL FEE | 273.00 CY | 8,898 | - | - | | | | 8,898 | | |
| | | | HAULING | | | | | | | | | | | |
| | | | | | | 8,898 | | | | | | 8,898 | | |

SAN DIEGO GAS & ELECTRIC
 CAYAMACA PEAK ENERGY PLANT
 DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS



| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|------------|-----------------|-----------------|--|--|--------------|------------------|-----------------|---------------|--------------|----------------|---------------|-----------------|
| | | | CIVIL WORK | | | 8,898 | | | | | | 8,898 |
| | | | 344 OTHER PRODUCTION - GENERATORS | | | 8,898 | (44,275) | | 1,479 | 299,831 | 69,030 | 333,484 |
| 345 | | | OTHER PRODUCTION - ACCESSORY | | | | | | | | | |
| | | | ELECTRIC EQUIPMENT | | | | | | | | | |
| | 10.00.00 | | WHOLE PLANT DEMOLITION | | | | | | | | | |
| | | 10.22.00 | CONCRETE | | | | | | | | | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | SWITCHYARD AND MAIN TRANSFORMER FDN | 20.00 CY | - | - | | 23 | 4,935 | 1,024 | 5,959 |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | AUX TRANSFORMERS FDN | 8.00 CY | - | - | | 9 | 1,974 | 410 | 2,384 |
| | | | CONCRETE | | | | | | 32 | 6,909 | 1,434 | 8,343 |
| | | 10.41.00 | ELECTRICAL EQUIPMENT | | | | | | | | | |
| | | | TRANSFORMERS | ONE (1) 13.8 KV / 4.16 KV, ONE (1) 13.8 KV / 480 V | 9.00 TN | - | - | | 24 | 4,725 | 1,133 | 5,858 |
| | | | OUTDOOR LIGHT POLE / FIXTURE | | 1.00 LT | - | - | | 150 | 29,471 | 7,069 | 36,540 |
| | | | MISCELLANEOUS ELECTRICAL EQUIPMENT | | 103.00 TN | - | - | | 367 | 72,103 | 17,295 | 89,398 |
| | | | ELECTRICAL EQUIPMENT | | | | | | 541 | 106,299 | 25,497 | 131,796 |
| | | 10.42.00 | RACEWAY, CABLE TRAY, & CONDUIT | | | | | | | | | |
| | | | CONDUIT | | 12,000.00 LF | - | - | | 120 | 23,577 | 5,655 | 29,232 |
| | | | CABLE TRAY | | 2,500.00 LF | - | - | | 100 | 19,647 | 4,713 | 24,360 |
| | | | RACEWAY, CABLE TRAY, & CONDUIT | | | | | | 220 | 43,224 | 10,368 | 53,592 |
| | | 10.43.00 | CABLE | | | | | | | | | |
| | | | COPPER WIRE / CABLE - MEDIUM VOLTAGE | | 4,500.00 LF | - | - | | 90 | 17,682 | 4,241 | 21,924 |
| | | | COPPER WIRE / CABLE - LOW VOLTAGE | | 25,000.00 LF | - | - | | 250 | 49,118 | 11,782 | 60,900 |
| | | | CABLE | | | | | | 340 | 66,800 | 16,023 | 82,823 |
| | | 10.44.00 | CONTROL & INSTRUMENTATION | | | | | | | | | |
| | | | CONTROL & INSTRUMENTATION | | 1.00 LT | - | - | | 100 | 19,647 | 4,713 | 24,360 |
| | | | CONTROL & INSTRUMENTATION | | | | | | 100 | 19,647 | 4,713 | 24,360 |
| | | | WHOLE PLANT DEMOLITION | | | | | | 1,233 | 242,879 | 58,034 | 300,913 |
| | 18.00.00 | | SCRAP VALUE | | | | | | | | | |
| | | 18.10.00 | MIXED STEEL | | | | | | | | | |
| | | | CARBON STEEL | CONDUIT, 1.5" DIA. AVG SIZE. 2.63 LBS/LF | -15.78 TN | - | (2,761) | - | 0 | | | (2,761) |
| | | | CARBON STEEL | CABLE TRAY, 6 LBS/LF | -7.50 TN | - | (1,312) | - | 0 | | | (1,312) |
| | | | CARBON STEEL | MISCELLANEOUS ELECTRICAL EQUIPMENT | -103.00 TN | - | (18,025) | - | 0 | | | (18,025) |
| | | | STEEL / COPPER MIX - LARGE TRANSFORMER > 100 KVA | | -9.00 TN | - | (3,150) | - | 0 | | | (3,150) |
| | | | MIXED STEEL | | | | (25,249) | | 0 | | | (25,249) |
| | | 18.30.00 | COPPER | | | | | | | | | |
| | | | SOLID COPPER | BUS BAR | -0.20 TN | - | (1,229) | - | 0 | | | (1,229) |
| | | | #2 INSULATED COPPER WIRE | | -4.00 TN | - | (9,760) | - | 0 | | | (9,760) |
| | | | COPPER | | | | (10,989) | | 0 | | | (10,989) |
| | | | SCRAP VALUE | | | | (36,238) | | 0 | | | (36,238) |
| | 21.00.00 | | CIVIL WORK | | | | | | | | | |
| | | 21.18.00 | HAULING | | | | | | | | | |
| | | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 28.00 CY | 913 | - | | | | | 913 |
| | | | HAULING | | | 913 | | | | | | 913 |
| | | | CIVIL WORK | | | 913 | | | | | | 913 |
| | | | 345 OTHER PRODUCTION - ACCESSORY | | | 913 | (36,238) | | 1,233 | 242,879 | 58,034 | 265,588 |
| | | | ELECTRIC EQUIPMENT | | | | | | | | | |

**APPENDIX C. EXPLANATION OF VARIANCE
FROM THE PREVIOUS COST STUDY**

| Cost Category | 2021 Cost Estimate | | 2016 Cost Estimate | | Delta | % of total cost | Discussion |
|--|--------------------|--------------------|--------------------|-------------------|---------------|-----------------|---|
| Labor | | | | | | | |
| Labor - Direct | | \$336,471 | | | | | |
| Labor Supervision | \$20,188 | | | | | | The 2016 estimate included all demolition contractor costs in labor. The 2021 cost estimate broke out demolition contractor costs (subcontracts, construction equipment, general conditions - labor). Average labor hourly labor cost increased by 9.4%. |
| Show-up time | \$6,729 | | | | | | |
| Construction Management | \$36,339 | | | | | | |
| Field Office Expenses | \$7,995 | | | | | | |
| Safety | \$7,179 | | | | | | |
| Temporary Facilities | \$5,462 | | | | | | |
| Mob/Demob | \$5,756 | | | | | | |
| Small tools & consumables | \$3,634 | | | | | | |
| General Liability Insurance | \$3,634 | | | | | | |
| Constr Equip Mob/Demob | \$9,880 | | | | | | |
| Legal Expenses/Claims | \$850 | | | | | | |
| General Conditions (Indirect) - Labor | | \$107,646 | | | | | |
| Subcontract | | \$15,000 | | | | | |
| Construction Equipment | | \$98,799 | | | | | |
| Labor Subtotal | | \$557,916 | | \$510,052 | 9.4% | 4.2% | |
| Material | | | | | | | |
| Material w/o freight | \$91,240 | | | | | | The 2021 cost estimate for material is 13.5% more than 2016. |
| General Conditions -Freight on Material | \$4,562 | | | | | | |
| Material Subtotal | | \$95,802 | | \$84,371 | 13.5% | 1.0% | |
| Scrap | | | | | | | The 2021 cost estimate for scrap is 22.7% less than 2016. The main reasons are: (a) cost for scrap mixed steel increased by 114%. Cost for mixed steel in 2021 based on a 12-month average is \$175 per ton as compared to 2016 based on a 3-month average of \$87 per ton (b) cost for copper decreased by -98.6%. Cost for copper in 2021 was broken out into #2 copper (solid) and #2 (insulated wire) as compared to 2016 which was based on #1 copper (solid bright) |
| Mixed Steel | -\$99,505 | | -\$46,101 | | | | |
| Copper | -\$10,989 | | -\$96,880 | | | | |
| Subtotal Scrap Value | | -\$110,494 | | -\$142,981 | -22.7% | 2.9% | |
| Subtotal - Direct & Indirect Demolition | | \$543,224 | | \$451,442 | 20.3% | 8.1% | |
| Contractor G&A and Profit | | | | | | | |
| Contractor G&A | \$43,764 | | \$25,503 | | 71.6% | | Contractor G&A is 71.6% higher. 2021 estimate is 7% of labor, equipment, and materials. 2016 estimate was 5% of labor and materials. Contractor Profit is 31.5%t higher. 2021 estimate is 10% of labor, equipment, and materials. 2016 estimate was 8% of labor and materials. |
| Contractor Profit | \$62,520 | | \$47,554 | | 31.5% | | |
| Subcontractor Contractor G&A and Profit | | \$106,284 | | \$73,057 | 45.5% | 2.9% | Increase in Contractor G&A and profit based on S&L database of actual demolition cost since 2016 |
| Indirect | | | | | | | |
| Engineering | \$47,000 | | \$45,000 | | | | Higher cost due to SDGE internal costs in support of demolition as compared to 2016 where no SDGE internal costs were included |
| Construction Management | \$0 | | \$10,490 | | | | |
| Other SDGE Internal Costs | \$270,000 | | \$0 | | | | |
| Subtotal Indirect Costs | | \$317,000 | | \$55,490 | 471% | 23.2% | |
| Contingency | \$161,550 | | \$173,190 | | -6.7% | -1.0% | Contingency is less (-6.7%). Contingency in 2021 is 15% and not applied to scrap. Contingency in 2016 was 20% and applied to scrap. |
| Total | | \$1,128,058 | | \$753,179 | 49.8% | | |
| SCRAP | \$/ton | tons | \$/ton | tons | | | Carbon steel scrap quantity is essentially the same Carbon/copper is for transformer. Copper in 2016 was based on solid bright (#1 grade) copper Copper broken out into solid bar and insulated copper wire Lower copper quantity in 2021 due to copper included in steel/copper mix for larger transformers |
| Carbon Steel | \$175 | 551 | \$87 | 529 | | | |
| Steel/Copper mix (large transformers) | \$350 | 9 | | | | | |
| # 1 Copper | | | \$3,460 | 28 | | | |
| #2 Copper | \$6,145 | 0.2 | | | | | |
| #2 Insulated Copper Wire | \$2,440 | 4 | | | | | |
| Labor hours | | 4,076 hours | | 4,465 hours | -8.7% | | The labor hours for the 2021 cost estimate are -8.7% less than the 2016 cost estimate. The main reason is that the 2021 cost estimate includes subcontracts (w/o labor hours), based on updated S&L standards |

SL-016628.D_SDGE Decom(Desert Star)

Decommissioning Study

Prepared for
San Diego Gas & Electric Company
Desert Star Energy Center

Prepared by Sargent & Lundy

LEGAL NOTICE

This deliverable was prepared by Sargent & Lundy, L.L.C. (S&L) expressly for the sole use of San Diego Gas & Electric Company (Client) in accordance with the contract agreement between S&L and Client. This deliverable was prepared using the degree of skill and care ordinarily exercised by engineers practicing under similar circumstances. Client acknowledges: (1) S&L prepared this deliverable subject to the particular scope limitations, budgetary and time constraints, and business objectives of Client; (2) information and data provided by others, including Client, may not have been independently verified by S&L; and (3) the information and data contained in this deliverable are time-sensitive and changes in the data, applicable codes, standards, and acceptable engineering practices may invalidate the findings of this deliverable. Any use or reliance upon this deliverable by third parties shall be at their sole risk.

Sargent & Lundy is one of the oldest and most experienced full-service architect engineering firms in the world. Founded in 1891, the firm is a global leader in power and energy with expertise in grid modernization, renewable energy, energy storage, nuclear power, and fossil fuels. Sargent & Lundy delivers comprehensive project services—from consulting, design, and implementation to construction management, commissioning, and operations/maintenance—with an emphasis on quality and safety. The firm serves public and private sector clients in the power and energy, gas distribution, industrial, and government sectors.

55 East Monroe Street • Chicago, IL 60603-5780 USA • 312-269-2000

VERSION LOG

| Version | Issue Date | Sections Modified |
|----------|-------------------|-------------------------|
| Draft v0 | November 30, 2021 | Initial Issue |
| Final | April 4, 2022 | ES, 2.2, 3, App A, B, D |

ISSUE SUMMARY AND APPROVAL PAGE

This is to certify that this document has been prepared, reviewed, and approved in accordance with Sargent & Lundy's Standard Operating Procedure SOP-0405, which is based on ANSI/ISO/ASSQC Q9001 Quality Management Systems.

Contributors

Prepared by:

| Name | Title | Section(s) Prepared | Signature | Date |
|----------------|---------------------------|---|-----------|----------|
| Kyle E. Folken | Energy Consultant | Section ES, Section 1, Section 2; Section 4 | | 4/4/2022 |
| Gregory Amen | Cost Information Division | Section 3, Appendix A | | 4/4/2022 |

Reviewed by:

| Name | Title | Section(s) Reviewed | Signature | Date |
|--------------------|---|-----------------------|-----------|----------|
| Borko Andric | Manager | Section 3, Appendix A | | 4/4/2022 |
| Craig Gitchell | Senior Energy Consultant | All | | 4/4/2022 |
| Robert. P. Charles | Senior Principal Consultant & Project Manager | All | | 4/4/2022 |

Approved by:

| | |
|---|---------------|
| | April 4, 2022 |
| Kevin C. Hopkins Principal Consultant & Project Manager | Date |

TABLE OF CONTENTS

| | |
|---------------------------------------|-----------|
| EXECUTIVE SUMMARY | 1 |
| METHODOLOGY | 1 |
| CONCEPTUAL COST ESTIMATE | 1 |
| 1. INTRODUCTION..... | 1 |
| 1.1. SCOPE OF WORK | 1 |
| 1.2. SARGENT & LUNDY BACKGROUND | 1 |
| 1.3. FACILITY DESCRIPTION..... | 1 |
| 2. COST ESTIMATE | 4 |
| 2.1. METHODOLOGY | 4 |
| 2.2. COST ESTIMATE SUMMARY..... | 5 |
| 3. BASIS OF ESTIMATE | 7 |
| 4. REFERENCES..... | 11 |

FIGURES AND TABLES

| | |
|---|----|
| FIGURE 1-1 — DESERT STAR OVERVIEW | 2 |
| FIGURE 1-2 — DESERT STAR UNIT 2 HRSG..... | 3 |
| FIGURE 1-3 — DESERT STAR ACC..... | 3 |
| | |
| TABLE ES-1 — COST ESTIMATE SUMMARY..... | II |
| TABLE ES-2 — FERC ACCOUNT COST ESTIMATE SUMMARY..... | II |
| TABLE 2-1 — DESERT STAR COST ESTIMATE SUMMARY | 5 |
| TABLE 2-2 — DESERT STAR COST ESTIMATE SUMMARY BY FERC ACCOUNT | 6 |
| TABLE 3-1 — SCRAP VALUE..... | 8 |
| TABLE 3-2 — SDG&E INTERNAL COSTS IN SUPPORT OF DECOMMISSIONING..... | 8 |

APPENDIXES

| |
|--|
| APPENDIX A. CONCEPTUAL ESTIMATE OF COST TO DISMANTLE DESERT STAR |
| APPENDIX B. CONCEPTUAL COST ESTIMATE — FERC ACCOUNTS |
| APPENDIX C. EXPLANATION OF VARIANCE FROM THE PREVIOUS COST STUDY |

ACRONYMS AND ABBREVIATIONS

| Acronym/Abbreviation | Definition/Clarification |
|----------------------|--------------------------------------|
| ACC | air-cooled condenser |
| CCW | closed cooling water |
| CT | combustion turbine |
| Desert Star | Desert Star Energy Center |
| FERC | Federal Energy Regulatory Commission |
| GSU | generator step-up transformer |
| HRSG | heat recovery steam generator |
| Owner | San Diego Gas & Electric Company |
| PCB | polychlorinated biphenyl |
| S&L | Sargent & Lundy, L.L.C. |
| SCR | selective catalytic reduction |
| SDG&E | San Diego Gas & Electric Company |
| ST | steam turbine |

EXECUTIVE SUMMARY

Sargent & Lundy (S&L) was contracted by San Diego Gas & Electric Company (“SDG&E” or the “Owner”) to perform an independent conceptual cost estimate for the dismantlement of the Desert Star Energy Center (Desert Star) and estimate the average service life of the facility’s peer group. The work scope included updating the 2016 conceptual demolition cost estimate and the benchmarking analysis for the facility.

METHODOLOGY

The S&L methodology for developing the cost estimate consists of three elements: (1) S&L experience in developing plant demolition costs and the existing S&L database for numerous other projects; (2) use of the unit cost factor methodology; and (3) quotes from previous projects for similar activities. The cost estimate was developed based on the drawings, documents, and data provided by SDG&E. These drawings and documents were used to estimate the building foundation sizes, building volumes, steel quantities, and the quantity of piping, valves, and other equipment. Additionally, S&L performed a site walkdown to evaluate the site for dismantlement and determine any project-specific requirements. This site walkdown was performed in 2016, but recent discussions with the Owner and facility management confirmed that no significant modifications have occurred since that time. This information was used with unit cost factors developed by S&L based on industry data and experience. The unit cost factors for concrete removal, steel removal, and cost cutting were developed from labor and material cost information, and S&L estimated the quantities of recoverable metals that could be recovered and sold for scrap. As such, the estimate includes the value of scrap metals; however, equipment is assumed to have no resale or other salvage value besides the value of scrap metal at the end of its life.

The benchmarking analysis considers publicly available data to determine the average service life of similar facilities.

CONCEPTUAL COST ESTIMATE

The summary of the cost estimate for decommissioning Desert Star is shown in Table ES-1. The cost estimate, divided into FERC accounts, is shown in Table ES-2. All costs are in 2021 U.S. dollars, and the total is the same in both tables: \$11,226,187. The decommissioning costs are expected to increase by the end of the service life of the asset due to escalation and other factors.

Table ES-1 — Cost Estimate Summary

| Description | Total Cost | Subtotal |
|---|----------------------|-------------|
| Demolition Direct Costs | \$7,496,912 | – |
| Labor | – | \$4,069,698 |
| Subcontracts | – | \$253,380 |
| Equipment | – | \$1,928,009 |
| Material | – | \$1,245,825 |
| General Conditions (Decommissioning Contractor Indirect) Costs | \$2,873,137 | – |
| Scrap Value | (\$1,978,169) | – |
| Subtotal Demolition Contractor Costs | \$8,391,880 | – |
| Project Indirect Costs | \$1,112,000 | – |
| Engineering | – | \$210,000 |
| SDG&E Internal Costs | – | \$902,000 |
| Contingency Costs | \$1,722,307 | – |
| Total Demolition Costs | \$11,226,187 | – |

Table ES-2 — FERC Account Cost Estimate Summary

| FERC No. | Description | Total Cost |
|----------|---|---------------------|
| 311 | Structures & Improvements | \$3,671,588 |
| 312 | Boiler Plant Equipment | \$2,243,392 |
| 314 | Turbo Generator Units | \$1,316,775 |
| 315 | Accessory Electrical Equipment | \$412,082 |
| 316 | Miscellaneous Power Plant Equipment | \$39,201 |
| 341 | Other Production – Structures & Improvements | \$2,455,075 |
| 342 | Other Production – Fuel Holders, Producers, and Accessories | \$12,092 |
| 344 | Other Production – Generators | \$844,735 |
| 345 | Other Production – Accessory Electric Equipment | \$231,248 |
| – | General Conditions | Included Above |
| – | Engineering | Included Above |
| – | SDG&E Internal Costs | Included Above |
| – | Contingency | Included Above |
| – | Total Project Cost | \$11,226,188 |

1. INTRODUCTION

1.1. SCOPE OF WORK

Sargent & Lundy (S&L) was contracted by San Diego Gas & Electric Company (“SDG&E” or the “Owner”) to perform an independent conceptual cost estimate for the dismantlement of the Desert Star Energy Center (Desert Star) and estimate the average service life of the facility’s peer group. The work scope included updating the 2016 conceptual demolition cost estimate, report, and benchmarking analysis.

1.2. SARGENT & LUNDY BACKGROUND

S&L has been dedicated to providing complete engineering and environmental services exclusively to the power industry since 1891. Through work with various utilities, lending institutions, and developers over the years, the Sargent & Lundy Consulting Group has become one of the premier power project consultants in the power industry, and this commitment to quality is proven by the successful completion of the ISO 9001 certification audit. S&L’s experience encompasses independent engineering services—including decommissioning cost estimations and average service life evaluations—for both global and domestic electric power assets.

S&L has extensive decommissioning and related services experience, including power plant dismantling, demolition, and layup for fossil fuel, renewable energy, and nuclear plants. This includes decommissioning cost estimates, decommissioning studies, and related services for 18 clients at more than 70 stations. S&L also has extensive experience providing clients with testimonial services.

Having engineered over 958 power plant units, S&L has both the benefit of extensive design experience—supported with feedback from operating plants—and individuals with extensive plant operations expertise to support consulting services such as those performed for Desert Star.

1.3. FACILITY DESCRIPTION

Desert Star is a 2x2x1 gas-fired, combined-cycle power plant located about 40 miles southeast of Las Vegas, Nevada. The plant is rated at 490 MW and became operational in May 2000. The plant consists of two Siemens-Westinghouse 501FC+ combustion turbine (CT) generators and a Westinghouse BB 33-65 steam turbine (ST). Each gas turbine generator is rated for 160 MW, and the ST is rated for 170 MW. Each CT exhausts into a separate Nooter Ericksen triple-pressure heat recovery steam generator (HRSG) equipped with selective catalytic reduction (SCR). The steam produced by the two HRSGs drives the single ST generator, and the exhaust steam is condensed in a 30 Bay GEA air-cooled condenser (ACC).

Views of the overall sites, the Unit 2 HRSG, and the ACC are shown in Figure 1-1, Figure 1-2, and Figure 1-3, respectively.

Figure 1-1 — Desert Star Overview



Figure 1-2 — Desert Star Unit 2 HRSG



Figure 1-3 — Desert Star ACC



2. COST ESTIMATE

2.1. METHODOLOGY

The methodology used for developing the cost estimate includes a combination of deterministic and stochastic methods. Deterministic methods were used based on the quantity and size of equipment (e.g., the number of foundations, linear feet of piping, equipment, etc.). Stochastic methods were also used if quantitative information (e.g., fire lines and hydrants, miscellaneous electrical equipment, etc.) was unavailable.

The cost estimate was developed based on drawings, documents, and data provided by the Owner. These drawings and documents were used to estimate the building foundation sizes, building volumes, steel quantities, and the quantity of piping, valves, and other equipment.

The S&L methodology for developing the cost estimate consists of three elements: (1) S&L experience in developing plant demolition cost and the existing S&L database for other projects; (2) use of the unit cost factor methodology; and (3) quotes from previous projects for similar activities.

Cost estimates were created using the S&L cost model format and the S&L cost database. The estimates include both summaries and details for each type of work performed, indirect costs, and contingencies. The database report lists costs by buildings, plant systems, and other categories.

S&L developed an inventory of plant piping, valves, equipment, HVAC ducts, concrete, galleries, cable trays, and other equipment based on a review of drawings and a site walkdown that evaluated dismantlement and determined any project-specific requirements. This information was used with unit cost factors developed by S&L based on industry data and experience. Unit cost factors for concrete removal, steel removal, cost cutting, and other tasks were developed from labor and material cost information. S&L also estimated the quantities of recoverable metals that could be recovered and sold for scrap. As such, the estimate includes the value of scrap metals; however, equipment is assumed to have no resale or other salvage value besides the value of scrap metal at the end of its life.

S&L worked from site general arrangement drawings and company documentation for the facilities, including information about any existing metal cleaning storage ponds, asbestos inventories, polychlorinated biphenyl (PCB) inventories, or sludge ponds. S&L relied on SDG&E to identify the location of environmental issues that need to be considered in the estimates (S&L's scope of work excludes a detailed survey and testing program to identify such problems).

2.2. COST ESTIMATE SUMMARY

The summary of the Desert Star decommissioning cost estimate is shown in Table 2-1. The commercial and technical basis for the estimate is described in Section 3, and the detailed estimate is included in Appendix A. The cost estimate breakdown into FERC accounts is shown in Table 2-2, and the allocation of FERC accounts is shown in Appendix B. All costs are in 2021 U.S. dollars. The decommissioning costs are expected to increase by the end of the service life of the asset due to escalation and other factors.

The 2021 cost estimate format was changed to be consistent with S&L's current standards. The variance between the 2021 and 2016 cost estimate is shown in Appendix C.

Table 2-1 — Desert Star Cost Estimate Summary

| Description | Total Cost | Subtotal |
|---|----------------------|-------------|
| Demolition Direct Costs | \$7,496,912 | – |
| Labor | – | \$4,069,698 |
| Subcontracts | – | \$253,380 |
| Equipment | – | \$1,928,009 |
| Material | – | \$1,245,825 |
| General Conditions (Decommissioning Contractor Indirect) Costs | \$2,873,137 | – |
| Scrap Value | (\$1,978,169) | – |
| Subtotal Demolition Contractor Costs | \$8,391,880 | – |
| Project Indirect Costs | \$1,112,000 | – |
| Engineering | – | \$210,000 |
| SDG&E Internal Costs | – | \$902,000 |
| Contingency Costs | \$1,722,307 | – |
| Total Demolition Costs | \$11,226,187 | – |

Table 2-2 — Desert Star Cost Estimate Summary by FERC Account

| FERC No. | Description | Total Cost |
|-----------------|---|---------------------|
| 311 | Structures & Improvements | \$3,671,588 |
| 312 | Boiler Plant Equipment | \$2,243,392 |
| 314 | Turbo Generator Units | \$1,316,775 |
| 315 | Accessory Electrical Equipment | \$412,082 |
| 316 | Miscellaneous Power Plant Equipment | \$39,201 |
| 341 | Other Production – Structures & Improvements | \$2,455,075 |
| 342 | Other Production – Fuel Holders, Producers, and Accessories | \$12,092 |
| 344 | Other Production – Generators | \$844,735 |
| 345 | Other Production – Accessory Electric Equipment | \$231,248 |
| – | General Conditions | Included Above |
| – | Engineering | Included Above |
| – | SDG&E Internal Costs | Included Above |
| – | Contingency | Included Above |
| – | Total Project Cost | \$11,226,188 |

3. BASIS OF ESTIMATE

The basis for the cost estimate is as follows:

1. Construction Labor Wages

Craft labor rates (or craft hourly rates) for the cost estimate are based on the prevailing wages for Las Vegas, Nevada as published in *R.S. Means Labor Rates for the Construction Industry* (2021). These prevailing rates are representative of union or non-union rates, whichever prevails in the area. Costs have been added to cover social security, workmen's compensation, and federal and state unemployment insurance. The resulting burdened craft rates were then used to develop typical crew rates applicable to the task being performed.

2. Labor Work Schedule and Incentives

- The labor estimate is based on a 40-hour workweek with no per diem or other labor incentives.
- An allowance for arrival time is included if workers arrive and are then sent home.

3. Quantity Sources

Quantities of pieces of equipment and/or bulk material commodities used in this cost estimate were developed from supplied engineering information from the sites and the S&L database.

4. General Conditions Cost

Allowances were included in the decommissioning contractor indirect costs for the following:

- Labor supervision (additional compensation for the labor foreman/supervisors)
- Construction management
- Field office expenses
- Safety
- Temporary facilities
- Mobilization/demobilization
- Legal expenses/claims
- Small tools and consumables
- General liability insurance
- Construction equipment mobilization/demobilization
- Freight on material
- Contractor general and administrative costs (7% of labor [direct labor, additional labor cost, site overheads, and other construction indirect cost], materials [direct material cost and freight cost], and equipment)
- Contractor's profit (10% of labor [direct labor, additional labor cost, site overheads, and other construction indirect cost], materials [direct material cost and freight cost], and equipment)

5. Scrap

Scrap metals are a globally traded commodity and part of the larger metals industry. The value of scrap metal is subject to constantly changing economic conditions; as such, the price of mixed steel, stainless steel, copper, and aluminum can vary greatly over time as a result of global supply and demand. The value of scrap for this study was determined by a 12-month average from *Scrap Metals MarketWatch*¹ (November 2020–October 2021) for the West Coast (Zone 1) in the United States. The values obtained are delivered prices to the recycler. Transportation cost to the recycler is estimated at \$30/ton, resulting in the values shown in Table 3-2:

Table 3-1 — Scrap Value

| Commodity | Scrap Value (\$/ton) |
|--------------------------|----------------------|
| Carbon Steel | 175 |
| #2 Copper | 6145 |
| #2 Insulated Copper Wire | 2440 |

Note: 1 ton = 2000 lbs.

6. Project Schedule

Desert Star has an 18-month construction schedule.

7. Indirect Expenses

- Engineering is included to cover preparation of the decommissioning work specification, the engineering required to place the plant in a safe shutdown, and any unique engineering required during demolition.
- SDG&E internal costs are included to cover costs in support of decommissioning the facility.

Table 3-2 — SDG&E Internal Costs in Support of Decommissioning

| Activity | Estimated Cost |
|--|------------------|
| Labor to prepare the site for demolition, including drain oils, drain reagents, de-energization of the power buses, etc. | \$602,000 |
| Site security | \$80,000 |
| Subcontracts to remove chemicals, oils, and reagents from the site | \$100,000 |
| SDG&E project management, permitting, and procurement | \$120,000 |
| Total | \$902,000 |

8. Escalation Rates

Escalation rates were excluded from the estimates.

¹ www.americanrecycler.com

9. Sales and Use Taxes

Sales and use taxes were excluded from the estimates.

10. Contingency

- A 15% contingency is applied for labor, material, equipment, subcontracting, and indirect costs. General conditions (indirect demolition contractor costs) are allocated across labor, material, and equipment.
- There is no contingency on scrap value.

11. Contract Basis

The contracting strategy is a multiple lump sum for the estimate.

12. Assumptions

- The facility will be in safe-shutdown mode and ready for a decommissioning contractor to begin work.
- All chemicals and lubricating oils will be removed from the facilities to be properly disposed of by the utility before demolition. Chemical removal will include ammonia hydroxide and 25,000 gallons of CCW glycol. Oil removal will include all oil-filled systems and equipment such as lubrication systems, transformers, ACC fans, CCW fans, etc.
- No extraordinary environmental costs for demolition will be needed.
- There will be no PCBs on site at the time of demolition.
- Switchyards within the plant boundaries are not part of the scope, nor are access roads to these facilities.
- All items above grade and to a depth of one foot—including foundations—will be demolished. Any other items buried more than one foot deep will remain in place.
- Underground piping will be abandoned in place.
- Underground piping larger than four feet in diameter will be filled with sand or slurry and capped at the ends to prevent collapse (though there was no such piping noted at the site). Non-metal pipes will be collapsed.
- All demolished materials are considered debris, except for organic combustibles and non-embedded metals, which have scrap value.
- The basis for salvage estimating is for scrap value only. No resale of equipment or material is included.
- Handling onsite and offsite disposal of hazardous materials will be performed in compliance with methods approved by SDG&E's Environmental Services Department.
- All borrow (fill) material will be from offsite sources.
- Catalyst will be removed and returned to the original equipment manufacturer before demolition.

- Most of the water in the evaporation ponds will evaporate after retirement. Removing the solids and/or any pond liner after evaporation is not included in the estimate as an SDG&E internal cost or as a demolition cost.
- The entire site (ponds included) will be covered with 6 inches of material. Pond berms are to be leveled without consideration to the final topography or elevation of the ponds.
- The water from the demineralized water/reverse-osmosis tanks will be removed from the tanks by SDG&E prior to demolition (up to 500,000 gallons).

4. REFERENCES

1. Sargent & Lundy Cost Database
2. RS Means Cost Data, 2021
3. Engineering drawings, equipment lists, and other information provided by San Diego Gas & Electric Company
4. 2020 Form EIA-860 Data – Schedule 3, “Generator Data” (retired and canceled units only)
5. *Scrap Metals MarketWatch* – West Coast (Zone 1), www.americanrecycler.com
6. Lease Agreement – The City of Boulder City and El Dorado Energy, LLC
7. Lease Agreement – First Renewal Option, 2016

**APPENDIX A. CONCEPTUAL ESTIMATE OF COST
TO DISMANTLE DESERT STAR**

**SAN DIEGO GAS & ELECTRIC
DESERT STAR
DECOMMISSIONING STUDY**

| | |
|-------------------------|------------|
| Estimator | GA |
| Labor rate table | 21NVLAS |
| Project No. | A14520.001 |
| Estimate Date | 03/12/2022 |
| Reviewed By | BA |
| Approved By | BA |
| Estimate No. | 31088D |

**SAN DIEGO GAS & ELECTRIC
 DESERT STAR
 DECOMMISSIONING STUDY**



| Group | Description | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|----------|------------------------|------------------|--------------------|------------------|---------------|------------------|------------------|------------------|
| 10.00.00 | WHOLE PLANT DEMOLITION | | | | 45,045 | 3,323,442 | 1,082,369 | 4,405,811 |
| 18.00.00 | SCRAP VALUE | | (1,978,169) | | | | | (1,978,169) |
| 21.00.00 | CIVIL WORK | 253,380 | | 1,245,825 | 8,811 | 746,256 | 845,639 | 3,091,101 |
| | TOTAL DIRECT | 253,380 | (1,978,169) | 1,245,825 | 53,856 | 4,069,698 | 1,928,009 | 5,518,743 |

**SAN DIEGO GAS & ELECTRIC
 DESERT STAR
 DECOMMISSIONG STUDY**



Estimate Totals

| Description | Amount | Totals | Hours |
|-------------------------------------|--------------------|-------------------|--------|
| Labor | 4,069,698 | | 53,856 |
| Material | 1,245,825 | | |
| Subcontract | 253,380 | | |
| Construction Equipment | 1,928,009 | | |
| Scrap Value | <u>(1,978,169)</u> | | |
| | 5,518,743 | 5,518,743 | |
| General Conditions | | | |
| Additional Labor Costs | | | |
| 90-1 Labor Supervision | 244,182 | | |
| 90-2 Show-up Time | 81,394 | | |
| 90-3 Cost Due To OT 5-10's | | | |
| 90-4 Cost Due To OT 6-10's | | | |
| 90-5 Per Diem | | | |
| Site Overheads | | | |
| 91-1 Construction Management | 439,527 | | |
| 91-2 Field Office Expenses | 96,696 | | |
| 91-3 Material&Quality Control | | | |
| 91-4 Site Services | | | |
| 91-5 Safety | 86,829 | | |
| 91-6 Temporary Facilities | 66,061 | | |
| 91-7 Temporary Utilities | | | |
| 91-8 Mobilization/Demob. | 69,621 | | |
| 91-9 Legal Expenses/Claims | 10,285 | | |
| Other Construction Indirects | | | |
| 92-1 Small Tools & Consumables | 43,953 | | |
| 92-2 Scaffolding | | | |
| 92-3 General Liability Insur. | 43,953 | | |
| 92-4 Constr. Equip. Mob/Demob | 192,801 | | |
| 92-5 Freight on Material | 62,291 | | |
| 92-6 Freight on Scrap | | | |
| 92-7 Sales Tax | | | |
| 92-8 Contractors G&A | 591,106 | | |
| 92-9 Contractors Profit | <u>844,438</u> | | |
| | 2,873,137 | 8,391,880 | |
| Project Indirect Costs | | | |
| 93-1 Engineering Services | 210,000 | | |
| 93-2 CM Support | | | |
| 93-3 Start-Up/Commissioning | | | |
| 93-4 Start-Up/Spare Parts | | | |
| 93-5 Excess Liability Insur. | | | |
| 93-6 Sales Tax On Indirects | | | |
| 93-7 SDG&E Internal Cost | 902,000 | | |
| 93-8 EPC Fee | <u></u> | | |
| | 1,112,000 | 9,503,880 | |
| Contingency | | | |
| 94-1 Contingency on Const Eq | 367,286 | | |
| 94-3 Contingency on Material | 229,574 | | |
| 94-4 Contingency on Labor | 920,640 | | |
| 94-5 Contingency on Subcontr. | 38,007 | | |
| 94-6 Contingency on Scrap | | | |
| 94-7 Contingency on Indirect | <u>166,800</u> | | |
| | 1,722,307 | 11,226,187 | |
| Escalation | | | |
| 96-1 Escalation on Const Equip | | | |
| 96-3 Escalation on Material | | | |
| 96-4 Escalation on Labor | | | |
| 96-5 Escalation on Subcontract | | | |
| 96-6 Escalation on Scrap | | | |
| 96-7 Escalation on Indirects | | | |
| | | 11,226,187 | |
| 98 Interest During Constr | | | |
| | | 11,226,187 | |
| Total | | 11,226,187 | |

**SAN DIEGO GAS & ELECTRIC
 DESERT STAR
 DECOMMISSIONING STUDY**



| Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|-----------------|-----------------|--|--|-------------|------------------|-------------|---------------|--------------|----------------|----------------|----------------|
| 10.00.00 | | WHOLE PLANT DEMOLITION | | | | | | | | | |
| | 10.21.00 | CIVIL WORK | | | | | | | | | |
| | | REMOVE FENCE | | 8,260.00 LF | - | - | | 330 | 27,093 | 15,258 | 42,351 |
| | | PAVED SURFACES, 6 IN THICK | STEAM PLANT | 9,029.00 SY | - | - | | 1,083 | 88,845 | 50,035 | 138,880 |
| | | PAVED SURFACES, 6 IN THICK | OTHER PRODUCTION | 9,029.00 SY | - | - | | 1,083 | 88,845 | 50,035 | 138,880 |
| | | CIVIL WORK | | | | | | 2,497 | 204,784 | 115,328 | 320,112 |
| | 10.22.00 | CONCRETE | | | | | | | | | |
| | | HRSG / STACK FDN | U-1, S-030 REV D | 480.00 CY | - | - | | 540 | 44,545 | 11,875 | 56,419 |
| | | HRSG / STACK FDN | U-2, S-033 REV D | 480.00 CY | - | - | | 540 | 44,545 | 11,875 | 56,419 |
| | | CEMS ENCLOSURE | U-1, S-031 REV D, 8'X21'X1' | 6.00 CY | - | - | | 7 | 557 | 148 | 705 |
| | | CEMS ENCLOSURE | U-12 S-031 REV D, 8'X21'X1' | 6.00 CY | - | - | | 7 | 557 | 148 | 705 |
| | | AIR COMPRESSOR | S-034 HRSG FOUNDATION AREA | 3.00 CY | - | - | | 3 | 278 | 74 | 353 |
| | | AIR DRYER | S-034 HRSG FOUNDATION AREA | 1.00 CY | - | - | | 1 | 93 | 25 | 118 |
| | | AIR RECEIVER | S-034 HRSG FOUNDATION AREA | 35.00 CY | - | - | | 39 | 3,248 | 866 | 4,114 |
| | | BOILER FEED PUMPS (4) | S-034 HRSG FOUNDATION AREA | 33.00 CY | - | - | | 37 | 3,062 | 816 | 3,879 |
| | | SCR SKID | S-034 HRSG FOUNDATION AREA | 8.00 CY | - | - | | 9 | 742 | 198 | 940 |
| | | BURNER SKID | S-034 HRSG FOUNDATION AREA | 1.00 CY | - | - | | 1 | 93 | 25 | 118 |
| | | BURNER BLOWER SKID | S-034 HRSG FOUNDATION AREA | 1.00 CY | - | - | | 1 | 93 | 25 | 118 |
| | | BLOWDOWN TANK | S-034 HRSG FOUNDATION AREA | 2.00 CY | - | - | | 2 | 186 | 49 | 235 |
| | | EXCITATION SKID | S-039 STEAM TURBINE/GENERATOR EQUIPMENT FDNS | 6.00 CY | - | - | | 7 | 557 | 148 | 705 |
| | | EXCITATION TRANSFORMER | S-039 STEAM TURBINE/GENERATOR EQUIPMENT FDNS | 4.00 CY | - | - | | 5 | 371 | 99 | 470 |
| | | STEAM TURBINE LUBE OIL MODULE | S-039 STEAM TURBINE/GENERATOR EQUIPMENT FDNS | 24.00 CY | - | - | | 27 | 2,227 | 594 | 2,821 |
| | | SEAL OIL SUPPLY SKID | S-039 STEAM TURBINE/GENERATOR EQUIPMENT FDNS | 8.00 CY | - | - | | 9 | 742 | 198 | 940 |
| | | GLAND STEAM CONDENSER SKID | S-039 STEAM TURBINE/GENERATOR EQUIPMENT FDNS | 3.00 CY | - | - | | 3 | 278 | 74 | 353 |
| | | GLAND STEAM SUPPLY SKID | S-039 STEAM TURBINE/GENERATOR EQUIPMENT FDNS | 9.00 CY | - | - | | 10 | 835 | 223 | 1,058 |
| | | MAIN & AUX TRANSFORMER FDNS | S-045 MAIN & AUX TRANSFORMERS (1) | 148.00 CY | - | - | | 167 | 13,735 | 3,661 | 17,396 |
| | | MAIN & AUX TRANSFORMER FDNS | S-047 MAIN & AUX TRANSFORMERS (2) | 160.00 CY | - | - | | 180 | 14,848 | 3,958 | 18,806 |
| | | SPARE TRANSFORMER (ALSTOM) PAD AND CONTAINMENT) | | 22.00 CY | - | - | | 25 | 2,042 | 544 | 2,586 |
| | | SPARE TRANSFORMER (ALSTOM) PAD AND CONTAINMENT) | | 57.00 CY | - | - | | 64 | 5,290 | 1,410 | 6,700 |
| | | AQUEOUS AMMONIA STORAGE TANK AND UNLOADING AREA FDNS | S-076 | 196.00 CY | - | - | | 221 | 18,189 | 4,849 | 23,038 |
| | | PIPE RACK FOUNDATION | S-048 | 218.00 CY | - | - | | 245 | 20,231 | 5,393 | 25,624 |
| | | AIR COOLED CONDENSER FDN | S-60 REV J | 440.00 CY | - | - | | 495 | 40,833 | 10,885 | 51,718 |
| | | AIR COOLED CONDENSER AREA MISC FDN | S-61 REV G | 60.00 CY | - | - | | 68 | 5,568 | 1,484 | 7,052 |
| | | FLASH TANK AND TRANSFER PUMP FDN | S-062 | 23.00 CY | - | - | | 26 | 2,134 | 569 | 2,703 |
| | | CCW HEAT EXCHANGER, PUMP AND HEAD TANK FDNS | S-068 | 62.00 CY | - | - | | 70 | 5,754 | 1,534 | 7,287 |
| | | FIRE WATER STORAGE TANK FDN | S-070, Steam Plant | 25.00 CY | - | - | | 28 | 2,320 | 618 | 2,939 |
| | | FIRE WATER STORAGE TANK FDN | S-070, Other Plant | 25.00 CY | - | - | | 28 | 2,320 | 618 | 2,939 |
| | | DEMIN WATER STORAGE TANK FDN | S-070 | 50.00 CY | - | - | | 56 | 4,640 | 1,237 | 5,877 |
| | | WATER TREATMENT FDNS | | 130.00 CY | - | - | | 146 | 12,064 | 3,216 | 15,280 |
| | | MISC FDNS | | 80.00 CY | - | - | | 90 | 7,424 | 1,979 | 9,403 |
| | | CONTROL/ADMINISTRATION BLDG | S-043 Steam Plant @ 50% | 352.00 CY | - | - | | 396 | 32,666 | 8,708 | 41,374 |
| | | CONTROL/ADMINISTRATION BLDG | S-043, Other Plant @ 50% | 352.00 CY | - | - | | 396 | 32,666 | 8,708 | 41,374 |
| | | SAMPLE BUILDING | DWG S-073 | 27.00 CY | - | - | | 30 | 2,506 | 668 | 3,174 |
| | | BULK STORAGE BUILDING | S-074 , 50% Steam Plant | 28.00 CY | - | - | | 32 | 2,598 | 693 | 3,291 |
| | | BULK STORAGE BUILDING | S-074 , 50% Other Plant | 28.00 CY | - | - | | 32 | 2,598 | 693 | 3,291 |
| | | SAMPLE PANEL BUILDING | 28'X22'X12 HIGH STEEL BLDG | 29.00 CY | - | - | | 33 | 2,691 | 717 | 3,409 |
| | | WAREHOUSE #2 | 30'X40'X24' HIGH STEEL BLDG 50% Steam Plant | 28.00 CY | - | - | | 32 | 2,598 | 693 | 3,291 |
| | | WAREHOUSE #2 | 30'X40'X24' HIGH STEEL BLDG, 50% Other Plant | 28.00 CY | - | - | | 32 | 2,598 | 693 | 3,291 |
| | | VISITOR CENTER | 24'X64'X10' STEEL BLDG | 72.00 CY | - | - | | 81 | 6,682 | 1,781 | 8,463 |
| | | PHOTOVOLTAIC ARRAY SUPPORTS | 72 CAISSONS | 25.00 CY | - | - | | 28 | 2,320 | 618 | 2,939 |
| | | NEW EQUIPMENT BUILDING | Steam Plant @ 50% | 94.00 CY | - | - | | 106 | 8,723 | 2,325 | 11,049 |
| | | NEW EQUIPMENT BUILDING | Other Plant @ 50% | 94.00 CY | - | - | | 106 | 8,723 | 2,325 | 11,049 |
| | | NEW WAREHOUSE #3 | Steam Plant @ 50% | 104.00 CY | - | - | | 117 | 9,651 | 2,573 | 12,224 |
| | | NEW WAREHOUSE #3 | Other Plant @ 50% | 104.00 CY | - | - | | 117 | 9,651 | 2,573 | 12,224 |

**SAN DIEGO GAS & ELECTRIC
 DESERT STAR
 DECOMMISSIONING STUDY**



| Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|-------|-----------------|--|--|--------------|------------------|-------------|---------------|--------------|----------------|----------------|----------------|
| | 10.22.00 | CONCRETE | | | | | | | | | |
| | | TURBINE PEDESTAL | U-1, S-021 REV F | 720.00 CY | - | - | | 1,296 | 106,907 | 28,499 | 135,406 |
| | | TURBINE PEDESTAL | U-2, S-025 REV F | 720.00 CY | - | - | | 1,296 | 106,907 | 28,499 | 135,406 |
| | | STEAM TURBINE GEN COLUMNS | S-036, S-037 | 673.00 CY | - | - | | 1,211 | 99,928 | 26,639 | 126,567 |
| | | CONCRETE | | | | | | 8,496 | 700,817 | 186,822 | 887,639 |
| | 10.23.00 | STEEL | | | | | | | | | |
| | | PIPE RACK | 50% Steam Plant S-052,-53,-54 & -55 | 85.00 TN | - | - | | 86 | 6,723 | 1,456 | 8,179 |
| | | PIPE RACK | 50% other plant S-052,-53,-54 & -55 | 85.00 TN | - | - | | 86 | 6,723 | 1,456 | 8,179 |
| | | MISCELLANEOUS STEEL | CCW PIPE RACK, PIPE SUPPORTS, MISC BRACING ETC. | 100.00 TN | - | - | | 102 | 7,910 | 1,713 | 9,623 |
| | | GALLERIES | S-056 + NEW PLATFORMS FOR GENERATOR AND HRSG DOORS | 40.00 TN | - | - | | 41 | 3,164 | 685 | 3,849 |
| | | S-056 + NEW PLATFORMS FOR GENERATOR AND HRSG DOORS | PV-1 & 2 | 10.00 TN | - | - | | 10 | 791 | 171 | 962 |
| | | STEEL | | | | | | 325 | 25,311 | 5,482 | 30,792 |
| | 10.24.00 | ARCHITECTURAL | | | | | | | | | |
| | | CONTROL/ADMINISTRATION BLDG | 188'X79'X12' HIGH STEEL BLDG, 50% Steam Plant | 89,112.00 CF | - | - | | 267 | 20,029 | 7,413 | 27,442 |
| | | CONTROL/ADMINISTRATION BLDG | 188'X79'X12' HIGH STEEL BLDG, 50% Other Plant | 89,112.00 CF | - | - | | 267 | 20,029 | 7,413 | 27,442 |
| | | SAMPLE BUILDING | 30'X24'X10' HIGH STEEL BLDG | 7,200.00 CF | - | - | | 22 | 1,618 | 599 | 2,217 |
| | | BULK STORAGE BUILDING | 56'X13'X12 HIGH STEEL BLDG, 50% Steam Plant | 4,368.00 CF | - | - | | 13 | 982 | 363 | 1,345 |
| | | BULK STORAGE BUILDING | 56'X13'X12 HIGH STEEL BLDG, 50% Other Plant | 4,368.00 CF | - | - | | 13 | 982 | 363 | 1,345 |
| | | SAMPLE PANEL BUILDING | 28'X22'X12 HIGH STEEL BLDG | 7,392.00 CF | - | - | | 22 | 1,661 | 615 | 2,276 |
| | | WAREHOUSE #2 | 30'X40'X24' HIGH STEEL BLDG, 50% Steam Plant | 19,200.00 CF | - | - | | 58 | 4,315 | 1,597 | 5,913 |
| | | WAREHOUSE #2 | 30'X40'X24' HIGH STEEL BLDG, 50% Other Plant | 19,200.00 CF | - | - | | 58 | 4,315 | 1,597 | 5,913 |
| | | VISITOR CENTER (AT PHOTOVOLTAIC FIELD) | 24'X64'X10' STEEL BLDG | 15,360.00 CF | - | - | | 46 | 3,452 | 1,278 | 4,730 |
| | | NEW EQUIPMENT BUILDING | 45'X90'X26' HIGH STEEL BLDG, 50% Steam Plant | 52,650.00 CF | - | - | | 158 | 11,834 | 4,380 | 16,214 |
| | | NEW EQUIPMENT BUILDING | 45'X90'X26' HIGH STEEL BLDG, 50% Other Plant | 52,650.00 CF | - | - | | 158 | 11,834 | 4,380 | 16,214 |
| | | NEW WAREHOUSE #3 | 45'X100'X21' HIGH STEEL BLDG, 50% Steam Plant | 47,250.00 CF | - | - | | 142 | 10,620 | 3,931 | 14,551 |
| | | NEW WAREHOUSE #3 | 45'X100'X21' HIGH STEEL BLDG, 50% Other Plant | 47,250.00 CF | - | - | | 142 | 10,620 | 3,931 | 14,551 |
| | | ARCHITECTURAL | | | | | | 1,365 | 102,291 | 37,861 | 140,152 |
| | 10.26.00 | MISCELLANEOUS STRUCTURAL ITEM | | | | | | | | | |
| | | MISCELLANEOUS SMALL OBSTACLE REMOVAL FROM SITE | | 1.00 LT | - | - | | 500 | 35,385 | 11,385 | 46,770 |
| | | MISCELLANEOUS STRUCTURAL ITEM | | | | | | 500 | 35,385 | 11,385 | 46,770 |
| | 10.31.00 | MECHANICAL EQUIPMENT | | | | | | | | | |
| | | COMBUSTION TURBINE | U-1, SIEMENS STG6-5000F (501FC+)C/T - NOMINAL 170 MW, FIRING NATURAL GAS ONLY, W DRY LOW NOX BURNERS | 213.00 TN | - | - | | 746 | 52,759 | 16,975 | 69,734 |
| | | COMBUSTION TURBINE | U-2, SIEMENS STG6-5000F (501FC+)C/T - NOMINAL 170 MW, FIRING NATURAL GAS ONLY, W DRY LOW NOX BURNERS | 213.00 TN | - | - | | 746 | 52,759 | 16,975 | 69,734 |
| | | HEAT RECOVERY STEAM GENERATOR | U-1, 3-PRESS HRSG W/REHEAT SUPPLEMENTAL DUCT BURNERS INCL INTERGRAL DEAEERATOR, SCR INC 110' STACK | 2,156.00 TN | - | - | | 7,546 | 534,030 | 171,822 | 705,853 |
| | | HEAT RECOVERY STEAM GENERATOR | U-2, 3-PRESS HRSG W/REHEAT SUPPLEMENTAL DUCT BURNERS INCL INTERGRAL DEAEERATOR, SCR INC 110' STACK | 2,156.00 TN | - | - | | 7,546 | 534,030 | 171,822 | 705,853 |
| | | STEAM TURBINE GENERATOR | SIEMENS/WESTINGHOUSE | 465.00 TN | - | - | | 1,628 | 115,178 | 37,058 | 152,236 |

**SAN DIEGO GAS & ELECTRIC
 DESERT STAR
 DECOMMISSIONING STUDY**



| Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|-----------------|---|---|---|--------------|------------------|-------------|---------------|---------------|------------------|----------------|------------------|
| 10.31.00 | MECHANICAL EQUIPMENT | STEAM TURBINE GENERATOR | B33/65CC, 175 MW CONDENSING REHEAT TURBINE W STANDARD ACCESSORIES | 465.00 TN | - | - | - | 1,628 | 115,178 | 37,058 | 152,236 |
| | | AIR COMPRESSOR, CENTRIFUGAL | 2 @ 1335 SCFM STATION | 9.00 TN | - | - | - | 18 | 1,290 | 415 | 1,705 |
| | | CCW HEAT EXCHANGER | 10 CELLS @ 30,000 LB EA | 150.00 TN | - | - | - | 304 | 21,496 | 6,916 | 28,413 |
| | | DEMIN WATER STORAGE TANK | 250,000 GALLON, 38' DIA X 30' HIGH | 30.00 TN | - | - | - | 81 | 5,732 | 1,844 | 7,577 |
| | | RAW/FIRE WATER STORAGE TANK | 250,000 GALLON, 38' DIA X 30' HIGH , 50% Steam Plant | 15.00 TN | - | - | - | 41 | 2,866 | 922 | 3,788 |
| | | RAW/FIRE WATER STORAGE TANK | 250,000 GALLON, 38' DIA X 30' HIGH , 50% Other Plant | 15.00 TN | - | - | - | 41 | 2,866 | 922 | 3,788 |
| | | AQUEOUS AMMONIA STORAGE TANK | 20,000 GALLON, | 6.00 TN | - | - | - | 16 | 1,146 | 369 | 1,515 |
| | | WATER TREATMENT DEMINERALIZATION & CHEMICAL TREATMENT EQUIPMENT | | 30.00 TN | - | - | - | 61 | 4,299 | 1,383 | 5,683 |
| | | AIR COOLED CONDENSER & ACCESSORIES | 250K BUNDLES @ 12 TN EA, 50D BUNDLES @ 10 TN EA & 30-200 HP FANS | 3,500.00 TN | - | - | - | 7,088 | 501,582 | 161,382 | 662,965 |
| | | BOILER FEED PUMPS | U-1, 2 @ 1350 GPM FOR HRSGS, 2150 HP | 22.00 TN | - | - | - | 59 | 4,204 | 1,353 | 5,556 |
| | | BOILER FEED PUMPS | U-2, 2 @ 1350 GPM FOR HRSGS, 2150 HP | 22.00 TN | - | - | - | 59 | 4,204 | 1,353 | 5,556 |
| | | CT LUBE OIL SYSTEM INCL FIN FAN COOLER | U-1 | 3.00 TN | - | - | - | 12 | 849 | 273 | 1,122 |
| | | CT LUBE OIL SYSTEM INCL FIN FAN COOLER | U-2 | 3.00 TN | - | - | - | 12 | 849 | 273 | 1,122 |
| | | CLOSED COOLING WATER PUMPS | 2 @ 7000 GPM @ 213 TDH, 550 HP | 4.00 TN | - | - | - | 16 | 1,132 | 364 | 1,497 |
| | | CONDENSATE COLLECTION TANK | 10,000 GALLON, | 4.00 TN | - | - | - | 16 | 1,132 | 364 | 1,497 |
| | | FUEL GAS PREHEAT | 2 SHELL & TUBE HT EX | 1.00 TN | - | - | - | 5 | 354 | 114 | 468 |
| | | FIRE PUMPS | U-0, 2 @ 1500 GPM @ 125 PSI, 300 HP, Steam Plant | 0.80 TN | - | - | - | 4 | 283 | 91 | 374 |
| | | FIRE PUMPS | U-0, 2 @ 1500 GPM @ 125 PSI, 300 HP, Other Plant | 0.80 TN | - | - | - | 4 | 283 | 91 | 374 |
| | | MISCELLANEOUS PUMPS | 14 SMALL PUMPS E.G. TRANSFER, DEMIN WTR RAW WATER, VACUUM , BLOWDOWN SUMPS AND SUMP PUMPS | 2.50 TN | - | - | - | 13 | 885 | 285 | 1,169 |
| | | CONDENSATE PUMPS | U-0, 3 @ 1400 GPM & 625 TDH, 300 HP | 4.00 TN | - | - | - | 20 | 1,415 | 455 | 1,871 |
| | | MECHANICAL EQUIPMENT | | | | | | 26,079 | 1,845,627 | 593,824 | 2,439,451 |
| 10.35.00 | PIPING | PIPING, VALVES AND HANGERS | U1, 14,000 LF/UNIT, 67 % Steam Plant | 182.00 TN | - | - | - | 369 | 26,082 | 8,392 | 34,474 |
| | | PIPING, VALVES AND HANGERS | U1, 14,000 LF/UNIT, 33 % Other Plant | 90.00 TN | - | - | - | 182 | 12,898 | 4,150 | 17,048 |
| | | PIPING, VALVES AND HANGERS | U2, 14,300 LF/UNIT, 67% Steam Plant | 196.00 TN | - | - | - | 397 | 28,089 | 9,037 | 37,126 |
| | | PIPING, VALVES AND HANGERS | U2, 14,300 LF/UNIT, 33% Other Plant | 97.00 TN | - | - | - | 196 | 13,901 | 4,473 | 18,374 |
| | | FIRE LINES & HYDRANTS | U-0, ABANDON UNDERGND LINES REMOVE HYDRANTS, 50% Steam Plant | 1.00 LT | - | - | - | 40 | 2,831 | 911 | 3,742 |
| | | FIRE LINES & HYDRANTS | U-0, ABANDON UNDERGND LINES REMOVE HYDRANTS, 50% Other Plant | 1.00 LT | - | - | - | 40 | 2,831 | 911 | 3,742 |
| | | PIPING | | | | | | 1,224 | 86,631 | 27,873 | 114,505 |
| 10.41.00 | ELECTRICAL EQUIPMENT | TRANSFORMERS | U-1, U-2, 67% Steam Plant | 261.00 TN | - | - | - | 697 | 49,354 | 15,880 | 65,234 |
| | | TRANSFORMERS | U-1, U-2, 33% Other Plant | 129.00 TN | - | - | - | 345 | 24,394 | 7,849 | 32,242 |
| | | MISC ELECT EQUIPMENT | U-1, U-2, 33% Other Plant | 60.00 TN | - | - | - | 160 | 11,346 | 3,650 | 14,996 |
| | | MISC ELECT EQUIPMENT | U-1, U-2, 67% Steam Plant | 122.00 TN | - | - | - | 326 | 23,070 | 7,423 | 30,493 |
| | | OUTDOOR LIGHT POLE / FIXTURE | U-0 | 1.00 LT | - | - | - | 150 | 10,616 | 3,416 | 14,031 |
| | | ELECTRICAL EQUIPMENT | U-0, CONTROL RM, 50% Steam Plant | 1.00 LT | - | - | - | 50 | 3,539 | 1,139 | 4,677 |
| | | ELECTRICAL EQUIPMENT | U-0, CONTROL RM, 50% Other Plant | 1.00 LT | - | - | - | 50 | 3,539 | 1,139 | 4,677 |
| | | ELECTRICAL EQUIPMENT | | | | | | 1,778 | 125,856 | 40,494 | 166,350 |
| 10.42.00 | RACEWAY, CABLE TRAY, & CONDUIT | CONDUIT | Steam Plant 67% U-1 | 30,150.00 LF | - | - | - | 302 | 21,337 | 6,865 | 28,202 |
| | | CONDUIT | Other Plant 33% U-1 | 14,850.00 LF | - | - | - | 149 | 10,509 | 3,381 | 13,891 |
| | | CONDUIT | Steam Plant 67% U-2 | 30,150.00 LF | - | - | - | 302 | 21,337 | 6,865 | 28,202 |
| | | CONDUIT | Other Plant 33% U-2 | 14,850.00 LF | - | - | - | 149 | 10,509 | 3,381 | 13,891 |
| | | CABLE TRAY | Steam Plant 67% U-1 | 1,675.00 LF | - | - | - | 67 | 4,742 | 1,526 | 6,267 |
| | | CABLE TRAY | Other Plant 33% U-1 | 825.00 LF | - | - | - | 33 | 2,335 | 751 | 3,087 |

**SAN DIEGO GAS & ELECTRIC
 DESERT STAR
 DECOMMISSIONING STUDY**



| Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|-----------------|-------|--|--|---------------|------------------|--------------------|---------------|---------------|------------------|------------------|--------------------|
| 10.42.00 | | RACEWAY, CABLE TRAY, & CONDUIT | | | | | | | | | |
| | | CABLE TRAY | Steam Plant 67% U-2 | 1,675.00 LF | - | - | | 67 | 4,742 | 1,526 | 6,267 |
| | | CABLE TRAY | Other Plant 33% U-2 | 825.00 LF | - | - | | 33 | 2,335 | 751 | 3,087 |
| | | RACEWAY, CABLE TRAY, & CONDUIT | | | | | | 1,100 | 77,847 | 25,047 | 102,894 |
| 10.43.00 | | CABLE | | | | | | | | | |
| | | COPPER WIRE / CABLE - MEDIUM VOLTAGE | Steam Plant 67% U-1 | 19,430.00 LF | - | - | | 194 | 13,751 | 4,424 | 18,175 |
| | | COPPER WIRE / CABLE - MEDIUM VOLTAGE | Other Plant 33% U-1 | 9,570.00 LF | - | - | | 96 | 6,773 | 2,179 | 8,952 |
| | | COPPER WIRE / CABLE - MEDIUM VOLTAGE | Steam Plant 67% U-2 | 19,430.00 LF | - | - | | 194 | 13,751 | 4,424 | 18,175 |
| | | COPPER WIRE / CABLE - MEDIUM VOLTAGE | Other Plant 33% U-2 | 9,570.00 LF | - | - | | 96 | 6,773 | 2,179 | 8,952 |
| | | COPPER WIRE / CABLE - LOW VOLTAGE | Steam Plant 67% U-1 | 67,000.00 LF | - | - | | 335 | 23,708 | 7,628 | 31,336 |
| | | COPPER WIRE / CABLE - LOW VOLTAGE | Other Plant 33% U-1 | 33,000.00 LF | - | - | | 165 | 11,677 | 3,757 | 15,434 |
| | | COPPER WIRE / CABLE - LOW VOLTAGE | Steam Plant 67% U-2 | 67,000.00 LF | - | - | | 335 | 23,708 | 7,628 | 31,336 |
| | | COPPER WIRE / CABLE - LOW VOLTAGE | Other Plant 33% U-2 | 33,000.00 LF | - | - | | 165 | 11,677 | 3,757 | 15,434 |
| | | CABLE | | | | | | 1,580 | 111,817 | 35,977 | 147,793 |
| 10.44.00 | | CONTROL & INSTRUMENTATION | | | | | | | | | |
| | | CONTROL & INSTRUMENTATION | | 1.00 LT | - | - | | 100 | 7,077 | 2,277 | 9,354 |
| | | CONTROL & INSTRUMENTATION | | | | | | 100 | 7,077 | 2,277 | 9,354 |
| | | WHOLE PLANT DEMOLITION | | | | | | 45,045 | 3,323,442 | 1,082,369 | 4,405,811 |
| 18.00.00 | | SCRAP VALUE | | | | | | | | | |
| 18.10.00 | | MIXED STEEL | | | | | | | | | |
| | | CARBON STEEL | | -4,526.00 TN | - | (792,050) | - | | | | (792,050) |
| | | CARBON STEEL | CONDUIT, 1.5" DIA. AVG SIZE, 2.63 LBS/LF | -79.00 TN | - | (13,825) | - | | | | (13,825) |
| | | CARBON STEEL | CONDUIT, 1.5" DIA. AVG SIZE, 2.63 LBS/LF | -39.00 TN | - | (6,825) | - | | | | (6,825) |
| | | CARBON STEEL | CABLE TRAY, 6 LBS/LF | -10.00 TN | - | (1,750) | - | | | | (1,750) |
| | | CARBON STEEL | CABLE TRAY, 6 LBS/LF | -4.95 TN | - | (866) | - | | | | (866) |
| | | CARBON STEEL | | -4,601.00 TN | - | (805,175) | - | | | | (805,175) |
| | | CARBON STEEL | | -11.50 TN | - | (2,012) | - | | | | (2,012) |
| | | CARBON STEEL | | -10.80 TN | - | (1,890) | - | | | | (1,890) |
| | | CARBON STEEL | | -101.80 TN | - | (17,815) | - | | | | (17,815) |
| | | CARBON STEEL | | -659.00 TN | - | (115,325) | - | | | | (115,325) |
| | | CARBON STEEL | MISC ELECT EQUIPMENT | -60.00 TN | - | (10,500) | - | | | | (10,500) |
| | | CARBON STEEL | BUILDINGS | -80.00 TN | - | (14,000) | - | | | | (14,000) |
| | | CARBON STEEL | BUILDINGS | -80.00 TN | - | (14,000) | - | | | | (14,000) |
| | | CARBON STEEL | FENCE | -20.00 TN | - | (3,500) | - | | | | (3,500) |
| | | CARBON STEEL | MISC ELECT EQUIPMENT | -122.00 TN | - | (21,350) | - | | | | (21,350) |
| | | STEEL / COPPER MIX - LARGE TRANSFORMER > 100 KVA | | -261.00 TN | - | (91,350) | - | | | | (91,350) |
| | | STEEL / COPPER MIX - LARGE TRANSFORMER > 100 KVA | | -129.00 TN | - | (45,150) | - | | | | (45,150) |
| | | MIXED STEEL | | | | (1,957,384) | | | | | (1,957,384) |
| 18.30.00 | | COPPER | | | | | | | | | |
| | | #2 SOLID COPPER / TUBING | BUS BAR | -0.67 TN | - | (4,117) | - | | | | (4,117) |
| | | #2 SOLID COPPER / TUBING | BUS BAR | -0.33 TN | - | (2,028) | - | | | | (2,028) |
| | | #2 INSULATED COPPER WIRE | | -4.00 TN | - | (9,760) | - | | | | (9,760) |
| | | #2 INSULATED COPPER WIRE | | -2.00 TN | - | (4,880) | - | | | | (4,880) |
| | | COPPER | | | | (20,785) | | | | | (20,785) |
| | | SCRAP VALUE | | | | (1,978,169) | | | | | (1,978,169) |
| 21.00.00 | | CIVIL WORK | | | | | | | | | |
| 21.17.00 | | EXCAVATION | | | | | | | | | |
| | | EXCAVATION, BULLDOZER | LEVEL POND BERMS | 190,163.00 CY | - | - | | 5,705 | 483,204 | 547,555 | 1,030,760 |
| | | EXCAVATION | | | | | | 5,705 | 483,204 | 547,555 | 1,030,760 |
| 21.18.00 | | HAULING | | | | | | | | | |
| | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. | 662.00 CY | 13,240 | - | | | | | 13,240 |
| | | | NO DISPOSAL FEE | | | | | | | | |
| | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. | 1,636.00 CY | 32,720 | - | | | | | 32,720 |
| | | | NO DISPOSAL FEE | | | | | | | | |
| | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. | 1,312.00 CY | 26,240 | - | | | | | 26,240 |

**SAN DIEGO GAS & ELECTRIC
 DESERT STAR
 DECOMMISSIONING STUDY**



| Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|-------|-----------------|--|---|--------------|------------------|-------------|------------------|--------------|----------------|----------------|------------------|
| | 21.18.00 | HAULING | | | | | | | | | |
| | | HAULING TO RECYCLE FACILITY | NO DISPOSAL FEE | 1,312.00 CY | 26,240 | - | | | | | 26,240 |
| | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 170.00 CY | 3,400 | - | | | | | 3,400 |
| | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 119.00 CY | 2,380 | - | | | | | 2,380 |
| | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 703.00 CY | 14,060 | - | | | | | 14,060 |
| | | HAULING TO RECYCLE FACILITY | CONCRETE PAVING DEBRIS IS RECYCLED. NO DISPOSAL FEE | 1,505.00 CY | 30,100 | - | | | | | 30,100 |
| | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 25.00 CY | 500 | - | | | | | 500 |
| | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 1,440.00 CY | 28,800 | - | | | | | 28,800 |
| | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 217.00 CY | 4,340 | - | | | | | 4,340 |
| | | HAULING TO RECYCLE FACILITY | CONCRETE PAVING DEBRIS IS RECYCLED. NO DISPOSAL FEE | 1,505.00 CY | 30,100 | - | | | | | 30,100 |
| | | HAULING | | | 185,880 | | | | | | 185,880 |
| | 21.21.00 | MASS FILL | | | | | | | | | |
| | | MASS FILL, COMMON EARTH 6 INCHES THICK | | 86,981.00 CY | - | - | 1,221,213 | 3,044 | 257,855 | 292,195 | 1,771,264 |
| | | MASS FILL, COMMON EARTH 6 INCHES THICK, C/T SPECIFIC OTHER PLANT | | 607.00 CY | - | - | 8,522 | 21 | 1,799 | 2,039 | 12,361 |
| | | MASS FILL, COMMON EARTH 6 INCHES THICK, PHOTOVOLTAIC PLANT | | 1,146.00 CY | - | - | 16,090 | 40 | 3,397 | 3,850 | 23,337 |
| | | MASS FILL | | | | | 1,245,825 | 3,106 | 263,052 | 298,084 | 1,806,961 |
| | 21.52.00 | WASTE DISPOSAL | | | | | | | | | |
| | | DISPOSAL AND TRANSPORTATION FEE | CONCRETE DEBRIS, DISPOSED ON SITE | CY | | | | | | | |
| | | DISPOSAL AND TRANSPORTATION FEE | RUBBISH & TENANT DEBRIS | 2,250.00 CY | 67,500 | | | | | | 67,500 |
| | | WASTE DISPOSAL | | | 67,500 | | | | | | 67,500 |
| | | CIVIL WORK | | | 253,380 | | 1,245,825 | 8,811 | 746,256 | 845,639 | 3,091,101 |

**APPENDIX B. CONCEPTUAL COST ESTIMATE —
FERC ACCOUNTS**

**SAN DIEGO GAS & ELECTRIC
DESERT STAR
DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS**

| | |
|-------------------------|------------|
| Estimator | GA |
| Labor rate table | 21NVLAS |
| Project No. | A14520.001 |
| Estimate Date | 3/12/2022 |
| Reviewed By | BA |
| Approved By | BA |
| Estimate No. | 31088D |

SAN DIEGO GAS & ELECTRIC
 DESERT STAR
 DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS



| Area | Description | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|------|--|------------------|-------------|---------------|-----------|------------|--------------|------------|
| 311 | STRUCTURES AND IMPROVEMENTS | 141,134 | (17,500) | 1,910,307 | 6,255 | 989,139 | 648,508 | 3,671,588 |
| 312 | BOILER PLANT EQUIPMENT | 41,663 | (792,050) | | 17,132 | 2,365,834 | 627,946 | 2,243,392 |
| 314 | TURBO GENERATOR UNITS | 33,412 | (805,175) | | 11,852 | 1,655,531 | 433,007 | 1,316,775 |
| 315 | ACCESSORY ELECTRIC EQUIPMENT | 4,329 | (142,152) | | 3,160 | 433,782 | 116,124 | 412,082 |
| 316 | MISCELLANEOUS POWER PLANT EQUIPMENT | 3,030 | (2,012) | | 205 | 30,818 | 7,365 | 39,201 |
| 341 | OTHER PRODUCTION - STRUCTURES & IMPROVEMENTS | 56,230 | (15,890) | 38,500 | 8,379 | 1,339,656 | 1,036,579 | 2,455,075 |
| 342 | OTHER PRODUCTION - FUEL HOLDERS, PRODUCERS AND ACCESSORIES | 637 | (17,815) | | 164 | 24,093 | 5,177 | 12,092 |
| 344 | OTHER PRODUCTION - GENERATORS | 36,672 | (115,325) | | 5,026 | 741,969 | 181,419 | 844,735 |
| 345 | OTHER PRODUCTION - ACCESSORY ELECTRIC EQUIPMENT | 5,526 | (70,249) | | 1,684 | 234,288 | 61,683 | 231,248 |

**SAN DIEGO GAS & ELECTRIC
 DESERT STAR
 DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS**



Estimate Totals

| Description | Amount | Totals | Hours |
|-------------------------------------|--------------------|-------------------|--------|
| Labor | 7,815,109 | | 53,856 |
| Material | 1,948,807 | | |
| Subcontract | 322,633 | | |
| Construction Equipment | 3,117,808 | | |
| Process Equipment | <u>(1,978,169)</u> | | |
| | 11,226,188 | 11,226,188 | |
| General Conditions | | | |
| Additional Labor Costs | | | |
| Site Overheads | | | |
| Other Construction Indirects | | 11,226,188 | |
| Project Indirect Costs | | 11,226,188 | |
| Contingency | | 11,226,188 | |
| Escalation | | 11,226,188 | |
| Total | | 11,226,188 | |

General Conditions, Indirect Costs and Contingency are allocated in the line items above.

**SAN DIEGO GAS & ELECTRIC
 DESERT STAR
 DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS**



| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|------------|-----------------|-----------------|--|---|--------------|------------------|-----------------|------------------|--------------|----------------|----------------|------------------|
| 311 | | | STRUCTURES AND IMPROVEMENTS | | | | | | | | | |
| | 10.00.00 | | WHOLE PLANT DEMOLITION | | | | | | | | | |
| | | 10.21.00 | CIVIL WORK | | | | | | | | | |
| | | | REMOVE FENCE | | 8,260.00 LF | - | - | | 330 | 52,027 | 24,674 | 76,700 |
| | | | PAVED SURFACES, 6 IN THICK | STEAM PLANT | 9,029.00 SY | - | - | | 1,083 | 170,611 | 80,912 | 251,524 |
| | | | CIVIL WORK | | | | | | 1,414 | 222,638 | 105,586 | 328,224 |
| | | 10.22.00 | CONCRETE | | | | | | | | | |
| | | | AQUEOUS AMMONIA STORAGE TANK AND UNLOADING AREA FDNS | S-076 | 196.00 CY | - | - | | 221 | 34,929 | 7,841 | 42,770 |
| | | | CONTROL/ADMINISTRATION BLDG | S-043 Steam Plant @ 50% | 352.00 CY | - | - | | 396 | 62,729 | 14,082 | 76,811 |
| | | | SAMPLE BUILDING | DWG S-073 | 27.00 CY | - | - | | 30 | 4,812 | 1,080 | 5,892 |
| | | | BULK STORAGE BUILDING | S-074 - 50% Steam Plant | 28.00 CY | - | - | | 32 | 4,990 | 1,120 | 6,110 |
| | | | SAMPLE PANEL BUILDING | 28'X22'X12 HIGH STEEL BLDG | 29.00 CY | - | - | | 33 | 5,168 | 1,160 | 6,328 |
| | | | WAREHOUSE #2 | 30'X40'X24' HIGH STEEL BLDG 50% Steam Plant | 28.00 CY | - | - | | 32 | 4,990 | 1,120 | 6,110 |
| | | | NEW EQUIPMENT BUILDING | Steam Plant @ 50% | 94.00 CY | - | - | | 106 | 16,752 | 3,761 | 20,512 |
| | | | NEW WAREHOUSE #3 | Steam Plant @ 50% | 104.00 CY | - | - | | 117 | 18,534 | 4,161 | 22,694 |
| | | | CONCRETE | | | | | | 965 | 152,902 | 34,325 | 187,227 |
| | | 10.24.00 | ARCHITECTURAL | | | | | | | | | |
| | | | CONTROL/ADMINISTRATION BLDG | 188'X79'X12' HIGH STEEL BLDG, 50% Steam Plant | 89,112.00 CF | - | - | | 267 | 38,462 | 11,988 | 50,450 |
| | | | SAMPLE BUILDING | 30'X24'X10' HIGH STEEL BLDG | 7,200.00 CF | - | - | | 22 | 3,108 | 969 | 4,076 |
| | | | BULK STORAGE BUILDING | 56'X13'X12 HIGH STEEL BLDG, 50% Steam Plant | 4,368.00 CF | - | - | | 13 | 1,885 | 588 | 2,473 |
| | | | SAMPLE PANEL BUILDING | 28'X22'X12 HIGH STEEL BLDG | 7,392.00 CF | - | - | | 22 | 3,190 | 994 | 4,185 |
| | | | WAREHOUSE #2 | 30'X40'X24' HIGH STEEL BLDG, 50% Steam Plant | 19,200.00 CF | - | - | | 58 | 8,287 | 2,583 | 10,870 |
| | | | NEW EQUIPMENT BUILDING | 45'X90'X26' HIGH STEEL BLDG, 50% Steam Plant | 52,650.00 CF | - | - | | 158 | 22,724 | 7,083 | 29,807 |
| | | | NEW WAREHOUSE #3 | 45'X100'X21' HIGH STEEL BLDG, 50% Steam Plant | 47,250.00 CF | - | - | | 142 | 20,394 | 6,356 | 26,750 |
| | | | ARCHITECTURAL | | | | | | 682 | 98,050 | 30,561 | 128,611 |
| | | 10.41.00 | ELECTRICAL EQUIPMENT | | | | | | | | | |
| | | | OUTDOOR LIGHT POLE / FIXTURE | U-0 | 1.00 LT | - | - | | 150 | 20,385 | 5,523 | 25,908 |
| | | | ELECTRICAL EQUIPMENT | | | | | | 150 | 20,385 | 5,523 | 25,908 |
| | | | WHOLE PLANT DEMOLITION | | | | | | 3,211 | 493,975 | 175,995 | 669,970 |
| | 18.00.00 | | SCRAP VALUE | | | | | | | | | |
| | | 18.10.00 | MIXED STEEL | | | | | | | | | |
| | | | CARBON STEEL | BUILDINGS | -80.00 TN | - | (14,000) | - | | | | (14,000) |
| | | | CARBON STEEL | FENCE | -20.00 TN | - | (3,500) | - | | | | (3,500) |
| | | | MIXED STEEL | | | | (17,500) | | | | | (17,500) |
| | | | SCRAP VALUE | | | | (17,500) | | | | | (17,500) |
| | 21.00.00 | | CIVIL WORK | | | | | | | | | |
| | | 21.18.00 | HAULING | | | | | | | | | |
| | | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 662.00 CY | 16,859 | - | | | | | 16,859 |
| | | | HAULING TO RECYCLE FACILITY | CONCRETE PAVING DEBRIS IS RECYCLED. NO DISPOSAL FEE | 1,505.00 CY | 38,327 | - | | | | | 38,327 |
| | | | HAULING | | | 55,186 | | | | | | 55,186 |
| | | 21.21.00 | MASS FILL | | | | | | | | | |
| | | | MASS FILL, COMMON EARTH 6 INCHES THICK | OFFSITE SUPPLY - 10 MILE ROUND TRIP AND SPREADING | 86,981.00 CY | - | - | 1,910,307 | 3,044 | 495,164 | 472,513 | 2,877,984 |
| | | | MASS FILL | | | | | 1,910,307 | 3,044 | 495,164 | 472,513 | 2,877,984 |
| | | 21.52.00 | WASTE DISPOSAL | | | | | | | | | |
| | | | DISPOSAL AND TRANSPORTATION FEE | CONCRETE DEBRIS, DISPOSED ON SITE | CY | - | - | | | | | |
| | | | DISPOSAL AND TRANSPORTATION FEE | RUBBISH & TENANT DEBRIS | 2,250.00 CY | 85,949 | - | | | | | 85,949 |
| | | | WASTE DISPOSAL | | | 85,949 | | | | | | 85,949 |
| | | | CIVIL WORK | | | 141,134 | | 1,910,307 | 3,044 | 495,164 | 472,513 | 3,019,118 |
| | | | 311 STRUCTURES AND IMPROVEMENTS | | | 141,134 | (17,500) | 1,910,307 | 6,255 | 989,139 | 648,508 | 3,671,588 |

312
10.00.00
10.22.00 **CONCRETE**

SAN DIEGO GAS & ELECTRIC
 DESERT STAR
 DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS



| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|------|-------|----------|---|--|--------------|------------------|------------------|---------------|---------------|------------------|----------------|------------------|
| | | 10.22.00 | CONCRETE | | | | | | | | | |
| | | | HRSG / STACK FDN | U-1, S-030 REV D | 480.00 CY | - | - | - | 540 | 85,540 | 19,203 | 104,742 |
| | | | HRSG / STACK FDN | U-2, S-033 REV D | 480.00 CY | - | - | - | 540 | 85,540 | 19,203 | 104,742 |
| | | | CEMS ENCLOSURE | U-1, S-031 REV D, 8'X21'X1' | 6.00 CY | - | - | - | 7 | 1,069 | 240 | 1,309 |
| | | | CEMS ENCLOSURE | U-12 S-031 REV D, 8'X21'X1' | 6.00 CY | - | - | - | 7 | 1,069 | 240 | 1,309 |
| | | | BOILER FEED PUMPS (4) | S-034 HRSG FOUNDATION AREA | 33.00 CY | - | - | - | 37 | 5,881 | 1,320 | 7,201 |
| | | | SCR SKID | S-034 HRSG FOUNDATION AREA | 8.00 CY | - | - | - | 9 | 1,426 | 320 | 1,746 |
| | | | BURNER SKID | S-034 HRSG FOUNDATION AREA | 1.00 CY | - | - | - | 1 | 178 | 40 | 218 |
| | | | BURNER BLOWER SKID | S-034 HRSG FOUNDATION AREA | 1.00 CY | - | - | - | 1 | 178 | 40 | 218 |
| | | | BLOWDOWN TANK | S-034 HRSG FOUNDATION AREA | 2.00 CY | - | - | - | 2 | 356 | 80 | 436 |
| | | | PIPE RACK FOUNDATION | S-048 | 218.00 CY | - | - | - | 245 | 38,849 | 8,721 | 47,570 |
| | | | FIRE WATER STORAGE TANK FDN | S-070, Steam Plant | 25.00 CY | - | - | - | 28 | 4,455 | 1,000 | 5,455 |
| | | | DEMIN WATER STORAGE TANK FDN | S-070 | 50.00 CY | - | - | - | 56 | 8,910 | 2,000 | 10,911 |
| | | | WATER TREATMENT FDNS | | 130.00 CY | - | - | - | 146 | 23,167 | 5,201 | 28,368 |
| | | | CONCRETE | | | | | | 1,620 | 256,619 | 57,608 | 314,227 |
| | | 10.23.00 | STEEL | | | | | | | | | |
| | | | PIPE RACK | 50% Steam Plant S-052,-53,-54 & -55 | 85.00 TN | - | - | - | 86 | 12,911 | 2,355 | 15,265 |
| | | | STEEL | | | | | | 86 | 12,911 | 2,355 | 15,265 |
| | | 10.31.00 | MECHANICAL EQUIPMENT | | | | | | | | | |
| | | | HEAT RECOVERY STEAM GENERATOR | U-1, 3-PRESS HRSG W/REHEAT SUPPLEMENTAL DUCT BURNERS INCL INTERGRAL DEAEERATOR, SCR INC 110' STACK | 2,156.00 TN | - | - | - | 7,546 | 1,025,508 | 277,856 | 1,303,364 |
| | | | HEAT RECOVERY STEAM GENERATOR | U-2, 3-PRESS HRSG W/REHEAT SUPPLEMENTAL DUCT BURNERS INCL INTERGRAL DEAEERATOR, SCR INC 110' STACK | 2,156.00 TN | - | - | - | 7,546 | 1,025,508 | 277,856 | 1,303,364 |
| | | | DEMIN WATER STORAGE TANK | 250,000 GALLON, 38" DIA X 30' HIGH | 30.00 TN | - | - | - | 81 | 11,008 | 2,983 | 13,991 |
| | | | RAW/FIRE WATER STORAGE TANK | 250,000 GALLON, 38" DIA X 30' HIGH , 50% Steam Plant | 15.00 TN | - | - | - | 41 | 5,504 | 1,491 | 6,995 |
| | | | AQUEOUS AMMONIA STORAGE TANK | 20,000 GALLON, | 6.00 TN | - | - | - | 16 | 2,202 | 597 | 2,798 |
| | | | WATER TREATMENT DEMINERALIZATION & CHEMICAL TREATMENT EQUIPMENT | | 30.00 TN | - | - | - | 61 | 8,256 | 2,237 | 10,493 |
| | | | BOILER FEED PUMPS | U-1, 2 @ 1350 GPM FOR HRSGS, 2150 HP | 22.00 TN | - | - | - | 59 | 8,073 | 2,187 | 10,260 |
| | | | BOILER FEED PUMPS | U-2, 2 @ 1350 GPM FOR HRSGS, 2150 HP | 22.00 TN | - | - | - | 59 | 8,073 | 2,187 | 10,260 |
| | | | CONDENSATE COLLECTION TANK | 10,000 GALLON, | 4.00 TN | - | - | - | 16 | 2,174 | 589 | 2,764 |
| | | | MECHANICAL EQUIPMENT | | | | | | 15,425 | 2,096,304 | 567,983 | 2,664,287 |
| | | | WHOLE PLANT DEMOLITION | | | | | | 17,132 | 2,365,834 | 627,946 | 2,993,779 |
| | | 18.00.00 | SCRAP VALUE | | | | | | | | | |
| | | 18.10.00 | MIXED STEEL | | | | | | | | | |
| | | | CARBON STEEL | | -4,526.00 TN | - | (792,050) | - | | | | (792,050) |
| | | | MIXED STEEL | | | | (792,050) | | | | | (792,050) |
| | | | SCRAP VALUE | | | | (792,050) | | | | | (792,050) |
| | | 21.00.00 | CIVIL WORK | | | | | | | | | |
| | | 21.18.00 | HAULING | | | | | | | | | |
| | | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 1,636.00 CY | 41,663 | - | - | | | | 41,663 |
| | | | HAULING | | | 41,663 | | | | | | 41,663 |
| | | | CIVIL WORK | | | 41,663 | | | | | | 41,663 |
| | | | 312 BOILER PLANT EQUIPMENT | | | 41,663 | (792,050) | | 17,132 | 2,365,834 | 627,946 | 2,243,392 |
| 314 | | 10.00.00 | TURBO GENERATOR UNITS | | | | | | | | | |
| | | 10.22.00 | WHOLE PLANT DEMOLITION | | | | | | | | | |
| | | | CONCRETE | | | | | | | | | |
| | | | EXCITATION SKID | S-039 STEAM TURBINE/GENERATOR EQUIPMENT FDNS | 6.00 CY | - | - | - | 7 | 1,069 | 240 | 1,309 |
| | | | EXCITATION TRANSFORMER | S-039 STEAM TURBINE/GENERATOR EQUIPMENT FDNS | 4.00 CY | - | - | - | 5 | 713 | 160 | 873 |
| | | | STEAM TURBINE LUBE OIL MODULE | S-039 STEAM TURBINE/GENERATOR EQUIPMENT FDNS | 24.00 CY | - | - | - | 27 | 4,277 | 960 | 5,237 |
| | | | SEAL OIL SUPPLY SKID | S-039 STEAM TURBINE/GENERATOR EQUIPMENT FDNS | 8.00 CY | - | - | - | 9 | 1,426 | 320 | 1,746 |
| | | | GLAND STEAM CONDENSER SKID | S-039 STEAM TURBINE/GENERATOR EQUIPMENT FDNS | 3.00 CY | - | - | - | 3 | 535 | 120 | 655 |
| | | | GLAND STEAM SUPPLY SKID | S-039 STEAM TURBINE/GENERATOR EQUIPMENT FDNS | 9.00 CY | - | - | - | 10 | 1,604 | 360 | 1,964 |
| | | | AIR COOLED CONDENSER FDN | S-60 REV J | 440.00 CY | - | - | - | 495 | 78,411 | 17,602 | 96,014 |
| | | | AIR COOLED CONDENSER AREA MISC FDN | S-61 REV J | 68.00 CY | - | - | - | 68 | 10,692 | 2,400 | 13,093 |

SAN DIEGO GAS & ELECTRIC
 DESERT STAR
 DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS



| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|----------|----------|----------|---|--|--------------|------------------|-------------|---------------|-----------|------------|--------------|------------|
| | | 10.22.00 | CONCRETE | | | | | | | | | |
| | | | FLASH TANK AND TRANSFER PUMP FDN | S-062 | 23.00 CY | - | - | - | 26 | 4,099 | 920 | 5,019 |
| | | | CCW HEAT EXCHANGER, PUMP AND HEAD TANK FDNS | S-068 | 62.00 CY | - | - | - | 70 | 11,049 | 2,480 | 13,529 |
| | | | STEAM TURBINE GEN COLUMNS | S-036, S-037 | 673.00 CY | - | - | - | 1,211 | 191,894 | 43,078 | 234,972 |
| | | | CONCRETE | | | | | | 1,930 | 305,769 | 68,641 | 374,410 |
| | | 10.23.00 | STEEL | | | | | | | | | |
| | | | MISCELLANEOUS STEEL | CCW PIPE RACK, PIPE SUPPORTS , MISC BRACING ETC. | 100.00 TN | - | - | - | 102 | 15,189 | 2,770 | 17,959 |
| | | | STEEL | | | | | | 102 | 15,189 | 2,770 | 17,959 |
| | | 10.31.00 | MECHANICAL EQUIPMENT | | | | | | | | | |
| | | | STEAM TURBINE GENERATOR | SIEMENS/WESTINGHOUSE B33/65CC, 175 MW CONDENSING REHEAT TURBINE W STANDARD ACCESSORIES | 465.00 TN | - | - | - | 1,628 | 221,179 | 59,927 | 281,106 |
| | | | CCW HEAT EXCHANGER | 10 CELLS @ 30,000 LB EA | 150.00 TN | - | - | - | 304 | 41,280 | 11,185 | 52,465 |
| | | | AIR COOLED CONDENSER & ACCESSORIES | 250K BUNDLES @ 12 TN EA, 50D BUNDLES @ 10 TN EA & 30-200 HP FANS | 3,500.00 TN | - | - | - | 7,088 | 963,197 | 260,974 | 1,224,171 |
| | | | CLOSED COOLING WATER PUMPS | 2 @ 7000 GPM @ 213 TDH, 550 HP | 4.00 TN | - | - | - | 16 | 2,174 | 589 | 2,764 |
| | | | CONDENSATE PUMPS | U-0, 3 @ 1400 GPM & 625 TDH, 300 HP | 4.00 TN | - | - | - | 20 | 2,718 | 736 | 3,454 |
| | | | MECHANICAL EQUIPMENT | | | | | | 9,055 | 1,230,548 | 333,411 | 1,563,959 |
| | | 10.35.00 | PIPING | | | | | | | | | |
| | | | PIPING, VALVES AND HANGERS | U1, 14,000 LF/UNIT, 67 % Steam Plant | 182.00 TN | - | - | - | 369 | 50,086 | 13,571 | 63,657 |
| | | | PIPING, VALVES AND HANGERS | U2, 14,300 LF/UNIT, 67% Steam Plant | 196.00 TN | - | - | - | 397 | 53,939 | 14,615 | 68,554 |
| | | | PIPING | | | | | | 765 | 104,025 | 28,185 | 132,210 |
| | | | WHOLE PLANT DEMOLITION | | | | | | 11,852 | 1,655,531 | 433,007 | 2,088,538 |
| 18.00.00 | | | SCRAP VALUE | | | | | | | | | |
| | | 18.10.00 | MIXED STEEL | | | | | | | | | |
| | | | CARBON STEEL | | -4,601.00 TN | - | (805,175) | - | | | | (805,175) |
| | | | MIXED STEEL | | | | (805,175) | | | | | (805,175) |
| | | | SCRAP VALUE | | | | (805,175) | | | | | (805,175) |
| 21.00.00 | | | CIVIL WORK | | | | | | | | | |
| | | 21.18.00 | HAULING | | | | | | | | | |
| | | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 1,312.00 CY | 33,412 | - | - | | | | 33,412 |
| | | | HAULING | | | 33,412 | | | | | | 33,412 |
| | | | CIVIL WORK | | | 33,412 | | | | | | 33,412 |
| | | | 314 TURBO GENERATOR UNITS | | | 33,412 | (805,175) | | 11,852 | 1,655,531 | 433,007 | 1,316,775 |
| 315 | | | ACCESSORY ELECTRIC EQUIPMENT | | | | | | | | | |
| | 10.00.00 | | WHOLE PLANT DEMOLITION | | | | | | | | | |
| | | 10.22.00 | CONCRETE | | | | | | | | | |
| | | | MAIN & AUX TRANSFORMER FDNS | S-045 MAIN & AUX TRANSFORMERS (1) | 148.00 CY | - | - | - | 167 | 26,375 | 5,921 | 32,296 |
| | | | SPARE TRANSFORMER (ALSTOM) PAD AND CONTAINMENT) | | 22.00 CY | - | - | - | 25 | 3,921 | 880 | 4,801 |
| | | | CONCRETE | | | | | | 191 | 30,295 | 6,801 | 37,096 |
| | | 10.41.00 | ELECTRICAL EQUIPMENT | | | | | | | | | |
| | | | TRANSFORMERS | U-1, U-2, 67% Steam Plant | 261.00 TN | - | - | - | 697 | 94,776 | 25,679 | 120,455 |
| | | | MISC ELECT EQUIPMENT | U-1, U-2, 67% Steam Plant | 122.00 TN | - | - | - | 326 | 44,302 | 12,003 | 56,305 |
| | | | ELECTRICAL EQUIPMENT | U-0, CONTROL RM, 50% Steam Plant | 1.00 LT | - | - | - | 50 | 6,795 | 1,841 | 8,636 |
| | | | ELECTRICAL EQUIPMENT | | | | | | 1,073 | 145,873 | 39,524 | 185,396 |
| | | 10.42.00 | RACEWAY, CABLE TRAY, & CONDUIT | | | | | | | | | |
| | | | CONDUIT | Steam Plant 67% U-1 | 30,150.00 LF | - | - | - | 302 | 40,974 | 11,102 | 52,076 |
| | | | CONDUIT | Steam Plant 67% U-2 | 30,150.00 LF | - | - | - | 302 | 40,974 | 11,102 | 52,076 |
| | | | CABLE TRAY | Steam Plant 67% U-1 | 1,675.00 LF | - | - | - | 67 | 9,105 | 2,467 | 11,572 |
| | | | CABLE TRAY | Steam Plant 67% U-2 | 1,675.00 LF | - | - | - | 67 | 9,105 | 2,467 | 11,572 |
| | | | RACEWAY, CABLE TRAY, & CONDUIT | | | | | | 737 | 100,159 | 27,138 | 127,297 |
| | | 10.43.00 | CABLE | | | | | | | | | |
| | | | COPPER WIRE / CABLE - MEDIUM VOLTAGE | Steam Plant 67% U-1 | 19,430.00 LF | - | - | - | 194 | 26,406 | 7,154 | 33,560 |
| | | | COPPER WIRE / CABLE - MEDIUM VOLTAGE | Steam Plant 67% U-2 | 19,430.00 LF | - | - | - | 194 | 26,406 | 7,154 | 33,560 |
| | | | COPPER WIRE / CABLE - LOW VOLTAGE | Steam Plant 67% U-1 | 67,000.00 LF | - | - | - | 335 | 45,527 | 12,335 | 57,862 |
| | | | COPPER WIRE / CABLE - LOW VOLTAGE | Steam Plant 67% U-2 | 67,000.00 LF | - | - | - | 335 | 45,527 | 12,335 | 57,862 |
| | | | CABLE | | | | | | 1,059 | 143,865 | 38,979 | 182,844 |

SAN DIEGO GAS & ELECTRIC
 DESERT STAR
 DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS



| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|------|----------|----------|---|---|------------|------------------|------------------|---------------|--------------|----------------|----------------|------------------|
| | | 10.44.00 | CONTROL & INSTRUMENTATION | | | | | | | | | |
| | | | CONTROL & INSTRUMENTATION | | 1.00 LT | - | - | - | 100 | 13,590 | 3,682 | 17,272 |
| | | | CONTROL & INSTRUMENTATION | | | | | | 100 | 13,590 | 3,682 | 17,272 |
| | | | WHOLE PLANT DEMOLITION | | | | | | 3,160 | 433,782 | 116,124 | 549,905 |
| | 18.00.00 | | SCRAP VALUE | | | | | | | | | |
| | 18.10.00 | | MIXED STEEL | | | | | | | | | |
| | | | CARBON STEEL | CONDUIT, 1.5" DIA. AVG SIZE, 2.63 LBS/LF | -79.00 TN | - | (13,825) | - | | | | (13,825) |
| | | | CARBON STEEL | CABLE TRAY, 6 LBS/LF | -10.00 TN | - | (1,750) | - | | | | (1,750) |
| | | | CARBON STEEL | MISC ELECT EQUIPMENT | -122.00 TN | - | (21,350) | - | | | | (21,350) |
| | | | STEEL / COPPER MIX - LARGE TRANSFORMER > 100 KVA | | -261.00 TN | - | (91,350) | - | | | | (91,350) |
| | | | MIXED STEEL | | | | (128,275) | | | | | (128,275) |
| | 18.30.00 | | COPPER | | | | | | | | | |
| | | | #2 SOLID COPPER / TUBING | BUS BAR | -0.67 TN | - | (4,117) | - | | | | (4,117) |
| | | | #2 INSULATED COPPER WIRE | | -4.00 TN | - | (9,780) | - | | | | (9,780) |
| | | | COPPER | | | | (13,877) | | | | | (13,877) |
| | | | SCRAP VALUE | | | | (142,152) | | | | | (142,152) |
| | 21.00.00 | | CIVIL WORK | | | | | | | | | |
| | 21.18.00 | | HAULING | | | | | | | | | |
| | | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 170.00 CY | 4,329 | - | - | | | | 4,329 |
| | | | HAULING | | | 4,329 | | | | | | 4,329 |
| | | | CIVIL WORK | | | 4,329 | | | | | | 4,329 |
| | | | 315 ACCESSORY ELECTRIC EQUIPMENT | | | 4,329 | (142,152) | | 3,160 | 433,782 | 116,124 | 412,082 |
| 316 | | | MISCELLANEOUS POWER PLANT EQUIPMENT | | | | | | | | | |
| | 10.00.00 | | WHOLE PLANT DEMOLITION | | | | | | | | | |
| | 10.22.00 | | CONCRETE | | | | | | | | | |
| | | | AIR COMPRESSOR | S-034 HRSG FOUNDATION AREA | 3.00 CY | - | - | - | 3 | 535 | 120 | 655 |
| | | | AIR DRYER | S-034 HRSG FOUNDATION AREA | 1.00 CY | - | - | - | 1 | 178 | 40 | 218 |
| | | | AIR RECEIVER | S-034 HRSG FOUNDATION AREA | 35.00 CY | - | - | - | 39 | 6,237 | 1,400 | 7,637 |
| | | | MISC FDNS | | 80.00 CY | - | - | - | 90 | 14,257 | 3,200 | 17,457 |
| | | | CONCRETE | | | | | | 134 | 21,207 | 4,761 | 25,967 |
| | 10.31.00 | | MECHANICAL EQUIPMENT | | | | | | | | | |
| | | | AIR COMPRESSOR, CENTRIFUGAL | 2 @ 1335 SCFM STATION | 9.00 TN | - | - | - | 18 | 2,477 | 671 | 3,148 |
| | | | MISCELLANEOUS PUMPS | 14 SMALL PUMPS E.G. TRANSFER, DEMIN WTR RAW WATER, VACUUM , BLOWDOWN SUMPS AND SUMP PUMPS | 2.50 TN | - | - | - | 13 | 1,699 | 460 | 2,159 |
| | | | MECHANICAL EQUIPMENT | | | | | | 31 | 4,176 | 1,131 | 5,307 |
| | 10.35.00 | | PIPING | | | | | | | | | |
| | | | FIRE LINES & HYDRANTS | U-0. ABANDON UNDERGND LINES REMOVE HYDRANTS, 50% Steam Plant | 1.00 LT | - | - | - | 40 | 5,436 | 1,473 | 6,909 |
| | | | PIPING | | | | | | 40 | 5,436 | 1,473 | 6,909 |
| | | | WHOLE PLANT DEMOLITION | | | | | | 205 | 30,818 | 7,365 | 38,183 |
| | 18.00.00 | | SCRAP VALUE | | | | | | | | | |
| | 18.10.00 | | MIXED STEEL | | | | | | | | | |
| | | | CARBON STEEL | | -11.50 TN | - | (2,012) | - | | | | (2,012) |
| | | | MIXED STEEL | | | | (2,012) | | | | | (2,012) |
| | | | SCRAP VALUE | | | | (2,012) | | | | | (2,012) |
| | 21.00.00 | | CIVIL WORK | | | | | | | | | |
| | 21.18.00 | | HAULING | | | | | | | | | |
| | | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 119.00 CY | 3,030 | - | - | | | | 3,030 |
| | | | HAULING | | | 3,030 | | | | | | 3,030 |
| | | | CIVIL WORK | | | 3,030 | | | | | | 3,030 |
| | | | 316 MISCELLANEOUS POWER PLANT EQUIPMENT | | | 3,030 | (2,012) | | 205 | 30,818 | 7,365 | 39,201 |
| 341 | | | OTHER PRODUCTION - STRUCTURES & IMPROVEMENTS | | | | | | | | | |

SAN DIEGO GAS & ELECTRIC
 DESERT STAR
 DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS



| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|------|----------|----------|--|--|---------------|------------------|-------------|---------------|-----------|------------|--------------|------------|
| | 10.00.00 | | WHOLE PLANT DEMOLITION | | | | | | | | | |
| | | 10.21.00 | CIVIL WORK | | | | | | | | | |
| | | | PAVED SURFACES, 6 IN THICK | OTHER PRODUCTION | 9,029.00 SY | - | - | | 1,083 | 170,611 | 80,912 | 251,524 |
| | | | CIVIL WORK | | | | | | 1,083 | 170,611 | 80,912 | 251,524 |
| | | 10.22.00 | CONCRETE | | | | | | | | | |
| | | | CONTROL/ADMINISTRATION BLDG | S-043, Other Plant @ 50% | 352.00 CY | - | - | | 396 | 62,729 | 14,082 | 76,811 |
| | | | BULK STORAGE BUILDING | S-074 , 50% Other Plant | 28.00 CY | - | - | | 32 | 4,990 | 1,120 | 6,110 |
| | | | WAREHOUSE #2 | 30'X40'X24' HIGH STEEL BLDG, 50% Other Plant | 28.00 CY | - | - | | 32 | 4,990 | 1,120 | 6,110 |
| | | | VISITOR CENTER | 24'X64'X10' STEEL BLDG | 72.00 CY | - | - | | 81 | 12,831 | 2,880 | 15,711 |
| | | | PHOTOVOLTAIC ARRAY SUPPORTS | 72 CAISSONS | 25.00 CY | - | - | | 28 | 4,455 | 1,000 | 5,455 |
| | | | NEW EQUIPMENT BUILDING | Other Plant @ 50% | 94.00 CY | - | - | | 106 | 16,752 | 3,761 | 20,512 |
| | | | NEW WAREHOUSE #3 | Other Plant @ 50% | 104.00 CY | - | - | | 117 | 18,534 | 4,161 | 22,694 |
| | | | CONCRETE | | | | | | 791 | 125,280 | 28,124 | 153,404 |
| | | 10.23.00 | STEEL | | | | | | | | | |
| | | | S-056 + NEW PLATFORMS FOR GENERATOR AND HRSG DOORS | PV-1 & 2 | 10.00 TN | - | - | | 10 | 1,519 | 277 | 1,796 |
| | | | STEEL | | | | | | 10 | 1,519 | 277 | 1,796 |
| | | 10.24.00 | ARCHITECTURAL | | | | | | | | | |
| | | | CONTROL/ADMINISTRATION BLDG | 188'X79'X12' HIGH STEEL BLDG, 50% Other Plant | 89,112.00 CF | - | - | | 267 | 38,462 | 11,988 | 50,450 |
| | | | BULK STORAGE BUILDING | 56'X13'X12 HIGH STEEL BLDG, 50% Other Plant | 4,368.00 CF | - | - | | 13 | 1,885 | 588 | 2,473 |
| | | | WAREHOUSE #2 | 30'X40'X24' HIGH STEEL BLDG, 50% Other Plant | 19,200.00 CF | - | - | | 58 | 8,287 | 2,583 | 10,870 |
| | | | VISITOR CENTER (AT PHOTOVOLTAIC FIELD) | 24'X64'X10' STEEL BLDG | 15,360.00 CF | - | - | | 46 | 6,630 | 2,066 | 8,696 |
| | | | NEW EQUIPMENT BUILDING | 45'X90'X26' HIGH STEEL BLDG, 50% Other Plant | 52,650.00 CF | - | - | | 158 | 22,724 | 7,083 | 29,807 |
| | | | NEW WAREHOUSE #3 | 45'X100'X21' HIGH STEEL BLDG, 50% Other Plant | 47,250.00 CF | - | - | | 142 | 20,394 | 6,356 | 26,750 |
| | | | ARCHITECTURAL | | | | | | 684 | 98,381 | 30,664 | 129,045 |
| | | 10.31.00 | MECHANICAL EQUIPMENT | | | | | | | | | |
| | | | FIRE PUMPS | U-0, 2 @ 1500 GPM @ 125 PSI, 300 HP, Other Plant | 0.80 TN | - | - | | 4 | 544 | 147 | 691 |
| | | | MECHANICAL EQUIPMENT | | | | | | 4 | 544 | 147 | 691 |
| | | 10.35.00 | PIPING | | | | | | | | | |
| | | | FIRE LINES & HYDRANTS | U-0, ABANDON UNDERGND LINES REMOVE HYDRANTS, 50% Other Plant | 1.00 LT | - | - | | 40 | 5,436 | 1,473 | 6,909 |
| | | | PIPING | | | | | | 40 | 5,436 | 1,473 | 6,909 |
| | | | WHOLE PLANT DEMOLITION | | | | | | 2,612 | 401,771 | 141,598 | 543,369 |
| | 18.00.00 | | SCRAP VALUE | | | | | | | | | |
| | | 18.10.00 | MIXED STEEL | | | | | | | | | |
| | | | CARBON STEEL | | -10.80 TN | - | (1,890) | - | | | | (1,890) |
| | | | CARBON STEEL | BUILDINGS | -80.00 TN | - | (14,000) | - | | | | (14,000) |
| | | | MIXED STEEL | | | | (15,890) | | | | | (15,890) |
| | | | SCRAP VALUE | | | | (15,890) | | | | | (15,890) |
| | 21.00.00 | | CIVIL WORK | | | | | | | | | |
| | | 21.17.00 | EXCAVATION | | | | | | | | | |
| | | | EXCAVATION, BULLDOZER | LEVEL POND BERMS | 190,163.00 CY | - | - | | 5,705 | 927,905 | 885,459 | 1,813,364 |
| | | | EXCAVATION | | | | | | 5,705 | 927,905 | 885,459 | 1,813,364 |
| | | 21.18.00 | HAULING | | | | | | | | | |
| | | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 703.00 CY | 17,903 | - | | | | | 17,903 |
| | | | HAULING TO RECYCLE FACILITY | CONCRETE PAVING DEBRIS IS RECYCLED. NO DISPOSAL FEE | 1,505.00 CY | 38,327 | - | | | | | 38,327 |
| | | | HAULING | | | 56,230 | | | | | | 56,230 |
| | | 21.21.00 | MASS FILL | | | | | | | | | |
| | | | MASS FILL, COMMON EARTH 6 INCHES THICK, C/T | OFFSITE SUPPLY - 10 MILE ROUND TRIP AND SPREADING | 607.00 CY | - | - | 13,331 | 21 | 3,456 | 3,297 | 20,084 |
| | | | MASS FILL, COMMON EARTH 6 INCHES THICK, PHOTOVOLTAIC PLANT | OFFSITE SUPPLY - 10 MILE ROUND TRIP AND SPREADING | 1,146.00 CY | - | - | 25,169 | 40 | 6,524 | 6,226 | 37,918 |

SAN DIEGO GAS & ELECTRIC
 DESERT STAR
 DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS



| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|------|----------|----------|---|--|------------|------------------|-----------------|---------------|--------------|------------------|------------------|------------------|
| | | | MASS FILL | | | | | 38,500 | 61 | 9,979 | 9,523 | 58,002 |
| | | | CIVIL WORK | | | 56,230 | | 38,500 | 5,766 | 937,885 | 894,982 | 1,927,596 |
| 342 | | | 341 OTHER PRODUCTION - STRUCTURES & IMPROVEMENTS | | | 56,230 | (15,890) | 38,500 | 8,379 | 1,339,656 | 1,036,579 | 2,455,075 |
| | | | OTHER PRODUCTION - FUEL HOLDERS, PRODUCERS AND ACCESSORIES | | | | | | | | | |
| | 10.00.00 | | WHOLE PLANT DEMOLITION | | | | | | | | | |
| | | 10.22.00 | CONCRETE | | | | | | | | | |
| | | | FIRE WATER STORAGE TANK FDN | S-070, Other Plant | 25.00 CY | - | - | | 28 | 4,455 | 1,000 | 5,455 |
| | | | CONCRETE | | | | | | 28 | 4,455 | 1,000 | 5,455 |
| | | 10.23.00 | STEEL | | | | | | | | | |
| | | | PIPE RACK | 50% other plant S-052,-53,-54 & -55 | 85.00 TN | - | - | | 86 | 12,911 | 2,355 | 15,265 |
| | | | STEEL | | | | | | 86 | 12,911 | 2,355 | 15,265 |
| | | 10.31.00 | MECHANICAL EQUIPMENT | | | | | | | | | |
| | | | RAW/FIRE WATER STORAGE TANK | 250,000 GALLON, 38" DIA X 30' HIGH , 50% Other Plant | 15.00 TN | - | - | | 41 | 5,504 | 1,491 | 6,995 |
| | | | FUEL GAS PREHEAT | 2 SHELL & TUBE HT EX | 1.00 TN | - | - | | 5 | 680 | 184 | 864 |
| | | | FIRE PUMPS | U-0, 2 @ 1500 GPM @ 125 PSI, 300 HP, Steam Plant | 0.80 TN | - | - | | 4 | 544 | 147 | 691 |
| | | | MECHANICAL EQUIPMENT | | | | | | 50 | 6,727 | 1,823 | 8,550 |
| | | | WHOLE PLANT DEMOLITION | | | | | | 164 | 24,093 | 5,177 | 29,270 |
| | 18.00.00 | | SCRAP VALUE | | | | | | | | | |
| | | 18.10.00 | MIXED STEEL | | | | | | | | | |
| | | | CARBON STEEL | | -101.80 TN | - | (17,815) | - | | | | (17,815) |
| | | | MIXED STEEL | | | | (17,815) | | | | | (17,815) |
| | | | SCRAP VALUE | | | | (17,815) | | | | | (17,815) |
| | 21.00.00 | | CIVIL WORK | | | | | | | | | |
| | | 21.18.00 | HAULING | | | | | | | | | |
| | | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 25.00 CY | 637 | - | | | | | 637 |
| | | | HAULING | | | 637 | | | | | | 637 |
| | | | CIVIL WORK | | | 637 | | | | | | 637 |
| 342 | | | 342 OTHER PRODUCTION - FUEL HOLDERS, PRODUCERS AND ACCESSORIES | | | 637 | (17,815) | | 164 | 24,093 | 5,177 | 12,092 |
| 344 | | | OTHER PRODUCTION - GENERATORS | | | | | | | | | |
| | 10.00.00 | | WHOLE PLANT DEMOLITION | | | | | | | | | |
| | | 10.22.00 | CONCRETE | | | | | | | | | |
| | | | TURBINE PEDESTAL | U-1, S-021 REV F | 720.00 CY | - | - | | 1,296 | 205,295 | 46,086 | 251,382 |
| | | | TURBINE PEDESTAL | U-2, S-025 REV F | 720.00 CY | - | - | | 1,296 | 205,295 | 46,086 | 251,382 |
| | | | CONCRETE | | | | | | 2,592 | 410,591 | 92,172 | 502,763 |
| | | 10.23.00 | STEEL | | | | | | | | | |
| | | | GALLERIES | S-056 + NEW PLATFORMS FOR GENERATOR AND HRSG DOORS | 40.00 TN | - | - | | 41 | 6,076 | 1,108 | 7,184 |
| | | | STEEL | | | | | | 41 | 6,076 | 1,108 | 7,184 |
| | | 10.26.00 | MISCELLANEOUS STRUCTURAL ITEM | | | | | | | | | |
| | | | MISCELLANEOUS SMALL OBSTACLE REMOVAL FROM SITE | | 1.00 LT | - | - | | 500 | 67,950 | 18,411 | 86,361 |
| | | | MISCELLANEOUS STRUCTURAL ITEM | | | | | | 500 | 67,950 | 18,411 | 86,361 |
| | | 10.31.00 | MECHANICAL EQUIPMENT | | | | | | | | | |
| | | | COMBUSTION TURBINE | U-1, SIEMENS STG6-5000F (501FC+)C/T - NOMINAL 170 MW, FIRING NATURAL GAS ONLY, W DRY LOW NOX BURNERS | 213.00 TN | - | - | | 746 | 101,314 | 27,451 | 128,765 |
| | | | COMBUSTION TURBINE | U-2, SIEMENS STG6-5000F (501FC+)C/T - NOMINAL 170 MW, FIRING NATURAL GAS ONLY, W DRY LOW NOX BURNERS | 213.00 TN | - | - | | 746 | 101,314 | 27,451 | 128,765 |
| | | | CT LUBE OIL SYSTEM INCL FIN FAN COOLER | U-1 | 3.00 TN | - | - | | 12 | 1,631 | 442 | 2,073 |
| | | | CT LUBE OIL SYSTEM INCL FIN FAN COOLER | U-2 | 3.00 TN | - | - | | 12 | 1,631 | 442 | 2,073 |
| | | | MECHANICAL EQUIPMENT | | | | | | 1,515 | 205,890 | 55,785 | 261,675 |

SAN DIEGO GAS & ELECTRIC
 DESERT STAR
 DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS



| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|----------|-------|----------|--|--|--------------|------------------|------------------|---------------|--------------|----------------|----------------|------------------|
| | | 10.35.00 | PIPING | | | | | | | | | |
| | | | PIPING, VALVES AND HANGERS | U1, 14,000 LF/UNIT, 33 % Other Plant | 90.00 TN | - | - | | 182 | 24,768 | 6,711 | 31,479 |
| | | | PIPING, VALVES AND HANGERS | U2, 14,300 LF/UNIT, 33% Other Plant | 97.00 TN | - | - | | 196 | 26,694 | 7,233 | 33,927 |
| | | | PIPING | | | | | | 379 | 51,462 | 13,943 | 65,406 |
| | | | WHOLE PLANT DEMOLITION | | | | | | 5,026 | 741,969 | 181,419 | 923,388 |
| 18.00.00 | | | SCRAP VALUE | | | | | | | | | |
| | | 18.10.00 | MIXED STEEL | | | | | | | | | |
| | | | CARBON STEEL | | -659.00 TN | - | (115,325) | - | | | | (115,325) |
| | | | MIXED STEEL | | | | (115,325) | | | | | (115,325) |
| | | | SCRAP VALUE | | | | (115,325) | | | | | (115,325) |
| 21.00.00 | | | CIVIL WORK | | | | | | | | | |
| | | 21.18.00 | HAULING | | | | | | | | | |
| | | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 1,440.00 CY | 36,672 | - | | | | | 36,672 |
| | | | HAULING | | | 36,672 | | | | | | 36,672 |
| | | | CIVIL WORK | | | 36,672 | | | | | | 36,672 |
| | | | 344 OTHER PRODUCTION - GENERATORS | | | 36,672 | (115,325) | | 5,026 | 741,969 | 181,419 | 844,735 |
| 345 | | | OTHER PRODUCTION - ACCESSORY | | | | | | | | | |
| | | | ELECTRIC EQUIPMENT | | | | | | | | | |
| | | | WHOLE PLANT DEMOLITION | | | | | | | | | |
| | | 10.22.00 | CONCRETE | | | | | | | | | |
| | | | MAIN & AUX TRANSFORMER FDNS | S-047 MAIN & AUX TRANSFORMERS (2) | 160.00 CY | - | - | | 180 | 28,513 | 6,401 | 34,914 |
| | | | SPARE TRANSFORMER (ALSTOM) PAD AND CONTAINMENT) | | 57.00 CY | - | - | | 64 | 10,158 | 2,280 | 12,438 |
| | | | CONCRETE | | | | | | 244 | 38,671 | 8,681 | 47,352 |
| | | 10.41.00 | ELECTRICAL EQUIPMENT | | | | | | | | | |
| | | | TRANSFORMERS | U-1, U-2, 33% Other Plant | 129.00 TN | - | - | | 345 | 46,843 | 12,692 | 59,535 |
| | | | MISC ELECT EQUIPMENT | U-1, U-2, 33% Other Plant | 60.00 TN | - | - | | 160 | 21,788 | 5,903 | 27,691 |
| | | | ELECTRICAL EQUIPMENT | U-0, CONTROL RM, 50% Other Plant | 1.00 LT | - | - | | 50 | 6,795 | 1,841 | 8,636 |
| | | | ELECTRICAL EQUIPMENT | | | | | | 555 | 75,426 | 20,436 | 95,862 |
| | | 10.42.00 | RACEWAY, CABLE TRAY, & CONDUIT | | | | | | | | | |
| | | | CONDUIT | Other Plant 33% U-1 | 14,850.00 LF | - | - | | 149 | 20,181 | 5,468 | 25,649 |
| | | | CONDUIT | Other Plant 33% U-2 | 14,850.00 LF | - | - | | 149 | 20,181 | 5,468 | 25,649 |
| | | | CABLE TRAY | Other Plant 33% U-1 | 825.00 LF | - | - | | 33 | 4,485 | 1,215 | 5,700 |
| | | | CABLE TRAY | Other Plant 33% U-2 | 825.00 LF | - | - | | 33 | 4,485 | 1,215 | 5,700 |
| | | | RACEWAY, CABLE TRAY, & CONDUIT | | | | | | 363 | 49,332 | 13,366 | 62,698 |
| | | 10.43.00 | CABLE | | | | | | | | | |
| | | | COPPER WIRE / CABLE - MEDIUM VOLTAGE | Other Plant 33% U-1 | 9,570.00 LF | - | - | | 96 | 13,006 | 3,524 | 16,530 |
| | | | COPPER WIRE / CABLE - MEDIUM VOLTAGE | Other Plant 33% U-2 | 9,570.00 LF | - | - | | 96 | 13,006 | 3,524 | 16,530 |
| | | | COPPER WIRE / CABLE - LOW VOLTAGE | Other Plant 33% U-1 | 33,000.00 LF | - | - | | 165 | 22,424 | 6,076 | 28,499 |
| | | | COPPER WIRE / CABLE - LOW VOLTAGE | Other Plant 33% U-2 | 33,000.00 LF | - | - | | 165 | 22,424 | 6,076 | 28,499 |
| | | | CABLE | | | | | | 521 | 70,859 | 19,199 | 90,058 |
| | | | WHOLE PLANT DEMOLITION | | | | | | 1,684 | 234,288 | 61,683 | 295,970 |
| 18.00.00 | | | SCRAP VALUE | | | | | | | | | |
| | | 18.10.00 | MIXED STEEL | | | | | | | | | |
| | | | CARBON STEEL | CONDUIT, 1.5" DIA. AVG SIZE, 2.63 LBS/LF | -39.00 TN | - | (6,825) | - | | | | (6,825) |
| | | | CARBON STEEL | CABLE TRAY, 6 LBS/LF | -4.95 TN | - | (866) | - | | | | (866) |
| | | | CARBON STEEL | MISC ELECT EQUIPMENT | -60.00 TN | - | (10,500) | - | | | | (10,500) |
| | | | STEEL / COPPER MIX - LARGE TRANSFORMER > 100 KVA | | -129.00 TN | - | (45,150) | - | | | | (45,150) |
| | | | MIXED STEEL | | | | (63,341) | | | | | (63,341) |
| | | 18.30.00 | COPPER | | | | | | | | | |
| | | | #2 SOLID COPPER / TUBING | BUS BAR | -0.33 TN | - | (2,028) | - | | | | (2,028) |
| | | | #2 INSULATED COPPER WIRE | | -2.00 TN | - | (4,880) | - | | | | (4,880) |
| | | | COPPER | | | | (6,908) | | | | | (6,908) |
| | | | SCRAP VALUE | | | | (70,249) | | | | | (70,249) |
| 21.00.00 | | | CIVIL WORK | | | | | | | | | |
| | | 21.18.00 | HAULING | | | | | | | | | |
| | | | HAULING TO RECYCLE FACILITY | CONCRETE DEBRIS IS RECYCLED. NO DISPOSAL FEE | 217.00 CY | 5,526 | - | | | | | 5,526 |

SAN DIEGO GAS & ELECTRIC
 DESERT STAR
 DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS



| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|------|-------|-------|--|-------|----------|------------------|-------------|---------------|-----------|------------|--------------|------------|
| | | | HAULING | | | 5,526 | | | | | | 5,526 |
| | | | CIVIL WORK | | | 5,526 | | | | | | 5,526 |
| | | | 345 OTHER PRODUCTION - ACCESSORY ELECTRIC EQUIPMENT | | | 5,526 | (70,249) | | 1,684 | 234,288 | 61,683 | 231,248 |

**APPENDIX C. EXPLANATION OF VARIANCE
FROM THE PREVIOUS COST STUDY**

| Cost Category, Desert Star | 2021 Cost Estimate | | 2016 Cost Estimate | | Delta | % of total cost | Discussion |
|--|--------------------|---------------------|--------------------|---------------------|---------------|-----------------|---|
| Labor | | | | | | | |
| Labor - Direct | | \$4,069,698 | | | | | <p>The 2016 estimate included all demolition contractor costs in labor. The 2021 cost estimate broke out demolition contractor costs (subcontracts, construction equipment, general conditions - labor).</p> <p>Average hourly labor cost increased by 19%. The average labor cost for the 2021 cost estimate is \$69.99/hr. as compared to the 2016 cost estimate of \$58.66.</p> <p>The 2021 estimate includes the cost of leveling the pond berms. Per SDGE direction, this was not included in the 2016 estimate.</p> |
| Labor Supervision | | \$244,182 | | | | | |
| Show-up time | | \$81,394 | | | | | |
| Construction Management | | \$439,527 | | | | | |
| Field Office Expenses | | \$96,696 | | | | | |
| Safety | | \$86,829 | | | | | |
| Temporary Facilities | | \$66,061 | | | | | |
| Mob/Demob | | \$69,621 | | | | | |
| Small tools & consumables | | \$43,953 | | | | | |
| General Liability Insurance | | \$43,953 | | | | | |
| Constr Equip Mob/Demob | | \$192,801 | | | | | |
| Legal Expenses/Claims | | \$10,285 | | | | | |
| General Conditions (Indirect) - Labor | | \$1,375,302 | | | | | |
| Subcontract | | \$253,380 | | | | | |
| Construction Equipment | | \$1,928,009 | | | | | |
| Labor Subtotal | | \$7,626,389 | | \$6,486,187 | 17.6% | 10.2% | |
| Material | | | | | | | <p>The 2021 cost estimate for material is -6.1% less than 2016.</p> |
| Material w/o freight | | \$1,245,825 | | | | | |
| General Conditions -Freight on Material | | \$62,291 | | | | | |
| Material Subtotal | | \$1,308,116 | | \$1,393,132 | -6.1% | -0.8% | |
| Scrap | | | | | | | <p>The 2021 cost estimate for scrap is -19.5% less than 2016. The main reasons are: (a) cost for scrap mixed steel increased by 114%. Cost for mixed steel in 2021 based on a 12-month average is \$175 per ton as compared to 2016 based on a 3-month average of \$87 per ton (b) cost for copper decreased by -98.6%. Cost for copper in 2021 was broken out into #2 copper (solid) and #2 (insulated wire) as compared to 2016 which was based on #1 copper (solid bright)</p> |
| Mixed Steel | | -\$1,957,384 | | -\$950,092 | | | |
| Copper | | -\$20,785 | | -\$1,507,072 | | | |
| Subtotal Scrap Value | | -\$1,978,169 | | -\$2,457,164 | -19.5% | 4.3% | |
| Subtotal - Direct & Indirect Demolition | | \$6,956,336 | | \$5,422,155 | 28.3% | 13.7% | |
| Contractor G&A and Profit | | | | | | | <p>Contractor G&A is 82.3 percent higher. 2021 estimate is 7% of labor, equipment, and materials. 2016 estimate was 5% of labor and materials. Contractor G&A is 34 percent higher. 2021 estimate is 10% of labor, equipment, and materials. 2016 estimate was 8% of labor and materials. Increase in Contractor G&A and profit based on S&L database of actual demolition cost since 2016</p> |
| Contractor G&A | | \$591,106 | | \$324,309 | | 82.3% | |
| Contractor Profit | | \$844,438 | | \$630,346 | | 34.0% | |
| Subcontractor Contractor G&A and Profit | | \$1,435,544 | | \$954,655 | 50.4% | 4.3% | |
| Indirect | | | | | | | <p>Higher cost due to SDGE internal costs in support of demolition as compared to 2016 where no SDGE internal costs were included</p> |
| Engineering | | \$210,000 | | \$200,000 | | | |
| Construction Management | | \$0 | | \$127,536 | | | |
| Other SDGE Internal Costs | | \$902,000 | | \$0 | | | |
| Subtotal Indirect Costs | | \$1,112,000 | | \$327,536 | 240% | 7.0% | |
| Contingency | | \$1,722,307 | | \$2,323,735 | | -25.9% | -5.4% |
| Total | | \$11,226,187 | | \$9,028,081 | 24.3% | | |
| SCRAP | | | | | | | <p>Carbon steel scrap quantity is essentially the same Carbon/copper is for transformer. Copper in 2016 was based on solid bright (#1 grade) copper Copper broken out into solid bar and insulated copper wire Lower copper quantity in 2021 due to copper included in steel/copper mix for larger transformers</p> |
| Carbon Steel | \$/ton | tons | \$/ton | tons | | | |
| Carbon Steel | \$175 | 10,845 | \$87 | 10,738 | | | |
| Steel/Copper mix (large transformers) | \$350 | 390 | | | | | |
| # 1 Copper | | | \$3,460 | 436 | | | |
| #2 Copper | \$6,145 | 1 | | | | | |
| #2 Insulated Copper Wire | \$2,440 | 6 | | | | | |
| Labor hours | | 53,856 hours | | 56,934 hours | | -5.4% | The labor hours for the 2021 cost estimate are -5.4% less than the 2016 cost estimate. The main reason is that the 2021 cost estimate includes subcontracts (w/o labor hours), based on updated S&L standards, and no planting or seeding. |

SL-016628.E_SDGE Decom(PV)

Decommissioning Study

Prepared for
San Diego Gas & Electric Company
Photovoltaic (PV Sites)

Prepared by Sargent & Lundy

LEGAL NOTICE

This deliverable was prepared by Sargent & Lundy, L.L.C. (S&L) expressly for the sole use of San Diego Gas & Electric Company (Client) in accordance with the contract agreement between S&L and Client. This deliverable was prepared using the degree of skill and care ordinarily exercised by engineers practicing under similar circumstances. Client acknowledges: (1) S&L prepared this deliverable subject to the particular scope limitations, budgetary and time constraints, and business objectives of Client; (2) information and data provided by others, including Client, may not have been independently verified by S&L; and (3) the information and data contained in this deliverable are time-sensitive and changes in the data, applicable codes, standards, and acceptable engineering practices may invalidate the findings of this deliverable. Any use or reliance upon this deliverable by third parties shall be at their sole risk.

Sargent & Lundy is one of the oldest and most experienced full-service architect engineering firms in the world. Founded in 1891, the firm is a global leader in power and energy with expertise in grid modernization, renewable energy, energy storage, nuclear power, and fossil fuels. Sargent & Lundy delivers comprehensive project services—from consulting, design, and implementation to construction management, commissioning, and operations/maintenance—with an emphasis on quality and safety. The firm serves public and private sector clients in the power and energy, gas distribution, industrial, and government sectors.

55 East Monroe Street • Chicago, IL 60603-5780 USA • 312-269-2000

VERSION LOG

| Version | Issue Date | Sections Modified |
|----------|------------------|-------------------|
| Draft v0 | December 9, 2021 | Initial Issue |
| Final | March 30, 2022 | N/A |

ISSUE SUMMARY AND APPROVAL PAGE

This is to certify that this document has been prepared, reviewed, and approved in accordance with Sargent & Lundy's Standard Operating Procedure SOP-0405, which is based on ANSI/ISO/ASSQC Q9001 Quality Management Systems.

Contributors

Prepared by:

| Name | Title | Section(s) Prepared | Signature | Date |
|----------------|--------------------------|---------------------|-----------|-----------|
| Craig Gitchell | Senior Energy Consultant | Appendix A | | 3/30/2022 |
| Kyle Folken | Management Consultant | All | | 3/30/2022 |

Reviewed by:

| Name | Title | Section(s) Reviewed | Signature | Date |
|--------------------|---|---------------------|-----------|-----------|
| Kevin Hopkins | Senior Principal Consultant & Project Manager | All | | 3/30/2022 |
| Robert. P. Charles | Senior Principal Consultant & Project Manager | All | | 3/30/2022 |

Approved by:

Kevin Hopkins
Principal Consultant & Project
Manager

March 30, 2022

Date

TABLE OF CONTENTS

| | |
|--|-----------|
| EXECUTIVE SUMMARY | I |
| METHODOLOGY | I |
| CONCEPTUAL COST ESTIMATE | I |
| 1. INTRODUCTION | 1 |
| 1.1. SCOPE OF WORK | 1 |
| 1.2. SARGENT & LUNDY BACKGROUND | 1 |
| 1.3. PV ROOFTOP AND CARPORT DESCRIPTIONS | 2 |
| 2. COST ESTIMATE | 3 |
| 2.1. METHODOLOGY | 3 |
| 2.2. COST ESTIMATE SUMMARY | 4 |
| 2.2.1. PV ENERGY SITES..... | 4 |
| 2.2.2. VARIANCE FROM 2016 STUDY..... | 7 |
| 3. BASIS OF ESTIMATE | 8 |
| 3.1. PROCEDURE | 8 |
| 3.2. PRICING AND QUANTITIES | 9 |
| 4. REFERENCES | 12 |

FIGURES AND TABLES

| | |
|--|-----|
| TABLE ES-1 — COST ESTIMATE SUMMARY FOR PV SITES..... | II |
| TABLE ES-2 — COST ESTIMATE SUMMARY BY FERC ACCOUNT FOR PV SITES..... | III |
| TABLE 2-1 — COST ESTIMATE SUMMARY FOR PV SITES | 4 |
| TABLE 2-2 — COST ESTIMATE SUMMARY BY FERC ACCOUNT FOR PV SITES..... | 6 |
| TABLE 3-1 — SCRAP VALUE..... | 10 |

APPENDIXES

| |
|--|
| APPENDIX A. CONCEPTUAL ESTIMATE OF COST TO DECOMMISSION PV SITES |
|--|

ACRONYMS AND ABBREVIATIONS

| Acronym/Abbreviation | Definition/Clarification |
|----------------------|--------------------------------------|
| AC | alternating current |
| BESS(s) | battery energy storage system(s) |
| DC | direct current |
| FERC | Federal Energy Regulatory Commission |
| LID | light-induced degradation |
| O&M | operations and maintenance |
| Owner | San Diego Gas & Electric Company |
| PV | photovoltaic |
| S&L | Sargent & Lundy LLC |
| SDG&E | San Diego Gas & Electric Company |

EXECUTIVE SUMMARY

Sargent & Lundy (S&L) was contracted by San Diego Gas & Electric Company (“SDG&E” or the “Owner”) to perform an independent conceptual decommissioning cost estimate SDG&E’s portfolio of photovoltaic (PV) generation sites. The work scope included updating the 2016 conceptual demolition cost estimate and report as well as the benchmarking analysis.

METHODOLOGY

The S&L methodology for developing the cost estimate consisted of three elements: (i) S&L experience in developing plant demolition costs and the S&L database for numerous other projects; (ii) the use of the unit cost factor methodology; and (iii) quotes from previous projects for similar activities. The cost estimate was developed based on the drawings, documents, and data provided by SDG&E, including the number of PV panels at each site. These drawings and documents were used to steel quantities, electrical equipment quantities, and other related items. S&L performed a site walkdown of a typical roof-installed PV site and a canopy-type PV installation to review the site components and determine any unique site-specific requirements. This site walkdown was performed in 2016; however, recent discussions with SDG&E confirmed that no significant modifications have occurred since that time other than the removal of six sites from the portfolio.

The gathered information was used with unit cost factors developed by S&L based on industry data and experience. Unit cost factors for panel removal, concrete removal, steel removal, cutting costs, etc. were developed from labor and material cost information. S&L estimated the quantities of metals that could be recovered and sold for scrap. The estimate includes the value of scrap metals; however, equipment is assumed to have no resale or other salvage value besides the value of scrap metal at the end of its life. Solar panels were assumed to be recycled by a company such as We Recycle Solar at a cost to SDG&E of \$20/panel based on a publication by the National Renewable Energy Laboratory and verbal information from We Recycle Solar.

CONCEPTUAL COST ESTIMATE

The summary of the cost estimate for decommissioning the SDG&E PV sites is shown in Table ES-1. The cost estimate broken into FERC accounts is shown in Table ES-2. All costs are in 2021 U.S. dollars, and the total in both tables is \$8,499,701. Decommissioning costs are expected to increase by the end of service life due to escalation.

Table ES-1 — Cost Estimate Summary for PV Sites

| | Customer | Location | Includes Contingency | | | | Scrap Value | G&A and Profit | Total Cost |
|--------------------------|------------------------------------|----------|----------------------|------------|-----------------------------|----------------------|-------------|---------------------|--------------|
| | | | Subcontract Cost | Labor Cost | Subcontractor Indirect Cost | SDG&E Internal Costs | | | |
| Roof Top PV Sites | | | | | | | | | |
| 1 | X-nth (formerly TKG) | Roof | \$ 82,271 | \$ 57,890 | \$ 12,518 | \$ 15,195 | \$ (7,452) | \$ 19,453 | \$ 179,875 |
| 2 | Reuben H Fleet (Science Center) | Roof | \$ 168,176 | \$ 149,951 | \$ 28,149 | \$ 34,170 | \$ (19,320) | \$ 43,743 | \$ 404,868 |
| 3 | Hunter Industries | Roof | \$ 151,685 | \$ 133,005 | \$ 25,204 | \$ 30,595 | \$ (17,163) | \$ 39,167 | \$ 362,494 |
| 4 | The Towers at Bressi Ranch | Roof | \$ 127,397 | \$ 104,876 | \$ 20,611 | \$ 25,019 | \$ (13,571) | \$ 32,029 | \$ 296,360 |
| 5 | Del Sur Elementary | Roof | \$ 77,717 | \$ 52,732 | \$ 11,667 | \$ 14,163 | \$ (6,780) | \$ 18,131 | \$ 167,631 |
| 6 | Ladera Ranch 555 | Roof | \$ 94,018 | \$ 68,942 | \$ 14,529 | \$ 17,637 | \$ (8,894) | \$ 22,578 | \$ 208,809 |
| 7 | High Tech High Chula Vista | Roof | \$ 159,827 | \$ 140,368 | \$ 26,580 | \$ 32,265 | \$ (18,071) | \$ 41,305 | \$ 382,274 |
| 8 | Hanna Gabriel Wells | Roof | \$ 48,116 | \$ 18,562 | \$ 6,081 | \$ 7,382 | \$ (2,389) | \$ 9,451 | \$ 87,203 |
| 9 | San Diego CC Skills Center | Roof | \$ 102,557 | \$ 79,098 | \$ 16,168 | \$ 19,627 | \$ (10,162) | \$ 25,126 | \$ 232,414 |
| 10 | Alterra Apartments | Roof | \$ 104,075 | \$ 80,420 | \$ 16,416 | \$ 19,927 | \$ (10,373) | \$ 25,510 | \$ 235,975 |
| 11 | Thomas Jefferson School of Law | Roof | \$ 79,045 | \$ 54,055 | \$ 11,895 | \$ 14,440 | \$ (7,004) | \$ 18,485 | \$ 170,916 |
| 12 | Broadway Pier Cruise Ship Terminal | Roof | \$ 61,778 | \$ 34,023 | \$ 8,633 | \$ 10,480 | \$ (4,389) | \$ 13,416 | \$ 123,941 |
| 13 | Wilco | Roof | \$ 459,770 | \$ 466,635 | \$ 81,549 | \$ 98,992 | \$ (60,119) | \$ 126,727 | \$ 1,173,553 |
| 14 | High Tech High North County | Roof | \$ 98,003 | \$ 73,792 | \$ 15,303 | \$ 18,576 | \$ (9,499) | \$ 23,781 | \$ 219,957 |
| 15 | Urban Corps | Roof | \$ 54,378 | \$ 25,778 | \$ 7,262 | \$ 8,816 | \$ (3,314) | \$ 11,286 | \$ 104,206 |
| 16 | Pacific Ridge School | Roof | \$ 51,532 | \$ 22,530 | \$ 6,731 | \$ 8,171 | \$ (2,869) | \$ 10,460 | \$ 96,555 |
| 17 | Sanford Burnham Medical Research | Roof | \$ 173,489 | \$ 155,991 | \$ 29,141 | \$ 35,375 | \$ (20,117) | \$ 45,286 | \$ 419,164 |
| 18 | High Tech High Chula Vista K-8 | Roof | \$ 160,586 | \$ 141,412 | \$ 26,740 | \$ 32,460 | \$ (18,168) | \$ 41,555 | \$ 384,585 |
| 19 | CSUSM - Public Safety Building | Roof | \$ 66,332 | \$ 39,328 | \$ 9,494 | \$ 11,525 | \$ (5,089) | \$ 14,754 | \$ 136,345 |
| 20 | SDG&E EIC (roof) | Roof | \$ 76,579 | \$ 51,262 | \$ 11,437 | \$ 13,883 | \$ (6,620) | \$ 17,773 | \$ 164,314 |
| 21 | UCSD - Revelle College | Roof | \$ 69,368 | \$ 43,017 | \$ 10,086 | \$ 12,243 | \$ (5,529) | \$ 15,674 | \$ 144,859 |
| 22 | Soledad | Roof | \$ 123,982 | \$ 101,348 | \$ 20,009 | \$ 24,289 | \$ (13,031) | \$ 31,094 | \$ 287,692 |
| 23 | Pacific Station | Roof | \$ 130,813 | \$ 109,152 | \$ 21,287 | \$ 25,841 | \$ (14,074) | \$ 33,080 | \$ 306,099 |
| 24 | UCSD - Structural & Materials Engr | Roof | \$ 143,716 | \$ 124,173 | \$ 23,734 | \$ 28,811 | \$ (15,987) | \$ 36,883 | \$ 341,329 |
| 25 | UCSD MESOM | Roof | \$ 89,654 | \$ 64,078 | \$ 13,721 | \$ 16,656 | \$ (8,250) | \$ 21,323 | \$ 197,182 |
| 26 | Village Lindo Paseo | Roof | \$ 60,640 | \$ 32,553 | \$ 8,402 | \$ 10,200 | \$ (4,229) | \$ 13,057 | \$ 120,623 |
| 27 | Del Lago Academy | Roof | \$ 180,700 | \$ 164,383 | \$ 30,510 | \$ 37,036 | \$ (21,172) | \$ 47,413 | \$ 438,870 |
| Subtotal - Roof | | | | | | | | | |
| | | | | | | | | \$ 7,388,093 | |

| | Customer | Location | Includes Contingency | | | | Scrap Value | G&A and Profit | Total Cost |
|--------------------------------|--|------------------------------------|----------------------|------------|-----------------------------|----------------------|--------------|---------------------|------------|
| | | | Subcontract Cost | Labor Cost | Subcontractor Indirect Cost | SDG&E Internal Costs | | | |
| Carport PV Sites | | | | | | | | | |
| 28 | Sony Corporation | Carport - Canopy | \$ 21,574 | \$ 213,014 | \$ 13,041 | \$ 15,831 | \$ (64,508) | \$ 23,712 | \$ 222,664 |
| 29 | County Operations Center Parking Structure A | Carport - Canopy | \$ 45,448 | \$ 470,350 | \$ 28,494 | \$ 34,589 | \$ (143,774) | \$ 51,807 | \$ 486,913 |
| 30 | SDG&E EIC (parking) | Carport, Free-standing, Multi-axis | \$ 6,486 | \$ 72,326 | \$ 4,416 | \$ 5,361 | \$ (21,303) | \$ 8,029 | \$ 75,314 |
| 31 | Sharp Rees Stealy Wellness Center | Carport - Canopy | \$ 8,602 | \$ 83,979 | \$ 5,209 | \$ 6,324 | \$ (24,790) | \$ 9,472 | \$ 88,796 |
| 32 | San Diego Zoo | Carport - Canopy | \$ 10,764 | \$ 104,625 | \$ 6,459 | \$ 7,841 | \$ (31,257) | \$ 11,744 | \$ 110,175 |
| 33 | Fast EV Suncharge/Del Lago Park N Ride | Carport - Canopy | \$ 2,162 | \$ 18,058 | \$ 1,228 | \$ 1,490 | \$ (4,452) | \$ 2,232 | \$ 20,717 |
| 34 | Agua Hedionda | Carport - Canopy | \$ 2,116 | \$ 10,048 | \$ 822 | \$ 998 | \$ (1,787) | \$ 1,495 | \$ 13,692 |
| 35 | Civita Westpark Apartments | Carport | \$ 8,648 | \$ 88,813 | \$ 5,474 | \$ 6,645 | \$ (26,199) | \$ 9,954 | \$ 93,336 |
| Subtotal - Carport | | | | | | | | | |
| | | | | | | | | \$ 1,111,608 | |
| TOTAL Rooftop + Carport | | | | | | | | | |
| | | | | | | | | \$ 8,499,701 | |

Table ES-2 — Cost Estimate Summary by FERC Account for PV Sites

| | <i>Customer</i> | <i>Location</i> | E344.1: Generators - Solar | E345.1: Accessory Electrical Equipment | TOTAL COST |
|--------------------------------|--|----------------------|-------------------------------|---|-------------------|
| Roof Top PV Sites | | | | | |
| 1 | X-nth (formerly TKG) | Roof | \$ 172,680 | \$ 7,195 | \$ 179,875 |
| 2 | Reuben H Fleet (Science Center) | Roof | \$ 388,673 | \$ 16,195 | \$ 404,868 |
| 3 | Hunter Industries | Roof | \$ 347,994 | \$ 14,500 | \$ 362,494 |
| 4 | The Towers at Bressi Ranch | Roof | \$ 284,506 | \$ 11,854 | \$ 296,360 |
| 5 | Del Sur Elementary | Roof | \$ 160,925 | \$ 6,705 | \$ 167,631 |
| 6 | Ladera Ranch 555 | Roof | \$ 200,457 | \$ 8,352 | \$ 208,809 |
| 7 | High Tech High Chula Vista | Roof | \$ 366,983 | \$ 15,291 | \$ 382,274 |
| 8 | Hanna Gabriel Wells | Roof | \$ 83,715 | \$ 3,488 | \$ 87,203 |
| 9 | San Diego CC Skills Center | Roof | \$ 223,118 | \$ 9,297 | \$ 232,414 |
| 10 | Alterra Apartments | Roof | \$ 226,536 | \$ 9,439 | \$ 235,975 |
| 11 | Thomas Jefferson School of Law | Roof | \$ 164,079 | \$ 6,837 | \$ 170,916 |
| 12 | Broadway Pier Cruise Ship Terminal | Roof | \$ 118,983 | \$ 4,958 | \$ 123,941 |
| 13 | Wilco | Roof | \$ 1,126,611 | \$ 46,942 | \$ 1,173,553 |
| 14 | High Tech High North County | Roof | \$ 211,158 | \$ 8,798 | \$ 219,957 |
| 15 | Urban Corps | Roof | \$ 100,037 | \$ 4,168 | \$ 104,206 |
| 16 | Pacific Ridge School | Roof | \$ 92,693 | \$ 3,862 | \$ 96,555 |
| 17 | Sanford Burnham Medical Research | Roof | \$ 402,398 | \$ 16,767 | \$ 419,164 |
| 18 | High Tech High Chula Vista K-8 | Roof | \$ 369,202 | \$ 15,383 | \$ 384,585 |
| 19 | CSUSM - Public Safety Building | Roof | \$ 130,891 | \$ 5,454 | \$ 136,345 |
| 20 | SDG&E EIC (roof) | Roof | \$ 157,741 | \$ 6,573 | \$ 164,314 |
| 21 | UCSD - Revelle College | Roof | \$ 139,065 | \$ 5,794 | \$ 144,859 |
| 22 | Soledad | Roof | \$ 276,184 | \$ 11,508 | \$ 287,692 |
| 23 | Pacific Station | Roof | \$ 293,855 | \$ 12,244 | \$ 306,099 |
| 24 | UCSD - Structural & Materials Engr | Roof | \$ 327,676 | \$ 13,653 | \$ 341,329 |
| 25 | UCSD MESOM | Roof | \$ 189,295 | \$ 7,887 | \$ 197,182 |
| 26 | Village Lindo Paseo | Roof | \$ 115,799 | \$ 4,825 | \$ 120,623 |
| 27 | Del Lago Academy | Roof | \$ 421,315 | \$ 17,555 | \$ 438,870 |
| <i>Subtotal - Roof</i> | | | \$ 7,092,569 | \$ 295,524 | \$ 7,388,093 |
| Carport PV Sites | | | | | |
| 28 | Sony Corporation | Carport - Canopy | \$ 213,757 | \$ 8,907 | \$ 222,664 |
| 29 | County Operations Center Parking Structure | Carport - Canopy | \$ 467,437 | \$ 19,477 | \$ 486,913 |
| 30 | SDG&E EIC (parking) | standing, Multi-axis | \$ 72,302 | \$ 3,013 | \$ 75,314 |
| 31 | Sharp Rees Stealy Wellness Center | Carport - Canopy | \$ 85,244 | \$ 3,552 | \$ 88,796 |
| 32 | San Diego Zoo | Carport - Canopy | \$ 105,768 | \$ 4,407 | \$ 110,175 |
| 33 | Fast EV Suncharge/Del Lago Park N Ride | Carport - Canopy | \$ 19,889 | \$ 829 | \$ 20,717 |
| 34 | Agua Hedionda | Carport - Canopy | \$ 13,144 | \$ 548 | \$ 13,692 |
| 35 | Civita Westpark Apartments | Carport | \$ 89,602 | \$ 3,733 | \$ 93,336 |
| <i>Subtotal - Carport</i> | | | \$ 1,067,144 | \$ 44,464 | \$ 1,111,608 |
| TOTAL Rooftop + Carport | | | \$ 8,159,713 | \$ 339,988 | \$ 8,499,701 |

1. INTRODUCTION

1.1. SCOPE OF WORK

Sargent & Lundy (S&L) was contracted by San Diego Gas & Electric Company (“SDG&E” or the “Owner”) to perform a conceptual cost estimate for the dismantlement of the SDG&E portfolio of rooftop and carport photovoltaic (PV) generation sites. The work scope included updating the 2016 conceptual demolition cost estimate and report. The estimate for the 4950-kW utility-scale Ramona PV site is summarized under a separate report.

1.2. SARGENT & LUNDY BACKGROUND

S&L has been dedicated to providing complete engineering and environmental services exclusively to the power industry since 1891. Through work with various utilities, lending institutions, and developers, over the years Sargent & Lundy Consulting has become one of the premier power project consultants in the power industry. This commitment to quality is proven by the successful completion of the ISO 9001 certification audit. S&L’s experience encompasses independent engineer services, including decommissioning cost estimation.

S&L has extensive decommissioning and related services experience, including power plant dismantling, demolition, and layup for fossil fuel, renewable energy, and nuclear plants. This includes decommissioning cost estimates, decommissioning studies, and related services for 18 clients at more than 70 stations. S&L also has extensive experience providing clients with testimony services.

Having engineered over 958 power plant units, S&L has both the benefit of extensive design experience—supported with feedback from operating plants—and individuals with extensive plant operations experience to support consulting services such as those performed for the PV sites.

1.3. PV ROOFTOP AND CARPORT DESCRIPTIONS

SDG&E's portfolio of PV sites consists of three types of installations: rooftop, canopy, and utility-scale sites. The rooftop and canopy sites are addressed in this report, and a separate S&L report summarizes the Ramona utility-scale site decommissioning estimate. Many of the rooftop and canopy sites are part of the San Diego Sustainable Communities program that engages local partners to be involved with renewable energy projects in the area. Descriptions of the sites are as follows:

- Most rooftop installations are fixed-tilt PV panels located on commercial buildings, school and university buildings, and other structures. The oldest rooftop PV installation was energized in 2004, and they range in size from 16 to 384 kW.
- Canopy-mounted PV sites are primarily freestanding carport canopies located in parking lots. "Solar tree" canopy installations are multi-axial while the rest are fixed-tilt. The oldest canopy site installed was energized in 2009, and the sites range in size from 5 to 359 kW.

2. COST ESTIMATE

2.1. METHODOLOGY

The methodology used for developing the cost estimate includes a combination of stochastic and deterministic methods. Deterministic methods were used based on the quantity and size of equipment (e.g., the number of PV panels, steel framing, etc.). Stochastic methods were also used if quantitative information (e.g., quantity of conduits, miscellaneous electrical equipment) was unavailable.

The cost estimate was developed based on the list of PV projects, typical drawings, and data provided by the Owner and found in the S&L database. (Satellite images from Google Maps were used to determine the installation type for some canopy sites.) These drawings and documents were used to estimate the quantity of aluminum framing, the quantity of steel in canopy and in-ground frames, and other components. The number of panels at each site was provided by SDG&E.

The methodology for developing the cost estimate consisted of three elements: (i) S&L experience in developing plant demolition costs and the existing S&L database for numerous other projects; (ii) the use of the unit cost factor methodology; and (iii) quotes from previous projects for similar activities.

Cost estimates were created using the S&L cost model format and the S&L cost database. The estimates include details for each type of work performed, indirect costs, and contingencies.

The SDG&E portfolio of PV sites provided the number of panels, power rating, and type of installation. S&L visited a representative rooftop installation and solar tree site at the SDG&E Energy Innovation Center in 2016. This information was used with unit cost factors developed by S&L based on industry data alongside S&L experience. Unit cost factors for PV panel removal, roof repair, steel removal for canopy sites, and other tasks were developed from labor and material cost information. S&L estimated the quantities of recoverable metals that could be recovered and sold for scrap. The estimate includes the value of scrap metals; however, equipment is assumed to have no resale or other salvage value besides the value of scrap metal at the end of its life. Solar panels were assumed to be recycled by a company such as We Recycle Solar at a cost to SDG&E of \$20/panel based on a publication by the National Renewable Energy Laboratory and verbal information from We Recycle Solar.

S&L relied on SDG&E to identify the location of environmental problems that need to be considered in the estimates (none were identified). The S&L scope of work excludes a detailed survey and testing program to identify such problems.

2.2. COST ESTIMATE SUMMARY

2.2.1. PV Energy Sites

The summary of the cost estimate for decommissioning the portfolio of PV energy sites is shown in Table 2-1. The commercial and technical basis for the estimate is included in Section 3, and the detailed estimate is included in Appendix A. The cost estimate breakdown into FERC accounts is shown in Table 2-2. All costs are in 2021 U.S. dollars. The decommissioning costs are expected to increase by the end of service life of the asset due to escalation and other factors.

Table 2-1 — Cost Estimate Summary for PV Sites

| | | Includes Contingency | | | | | | | |
|--------------------------|------------------------------------|----------------------|-------------------------|-------------------|------------------------------------|---------------------------------|--------------------|---------------------------|---------------------|
| | <i>Customer</i> | <i>Location</i> | <i>Subcontract Cost</i> | <i>Labor Cost</i> | <i>Subcontractor Indirect Cost</i> | <i>SDG&E Internal Costs</i> | <i>Scrap Value</i> | <i>G&A and Profit</i> | <i>Total Cost</i> |
| Roof Top PV Sites | | | | | | | | | |
| 1 | X-nth (formerly TKG) | Roof | \$ 82,271 | \$ 57,890 | \$ 12,518 | \$ 15,195 | \$ (7,452) | \$ 19,453 | \$ 179,875 |
| 2 | Reuben H Fleet (Science Center) | Roof | \$ 168,176 | \$ 149,951 | \$ 28,149 | \$ 34,170 | \$ (19,320) | \$ 43,743 | \$ 404,868 |
| 3 | Hunter Industries | Roof | \$ 151,685 | \$ 133,005 | \$ 25,204 | \$ 30,595 | \$ (17,163) | \$ 39,167 | \$ 362,494 |
| 4 | The Towers at Bressi Ranch | Roof | \$ 127,397 | \$ 104,876 | \$ 20,611 | \$ 25,019 | \$ (13,571) | \$ 32,029 | \$ 296,360 |
| 5 | Del Sur Elementary | Roof | \$ 77,717 | \$ 52,732 | \$ 11,667 | \$ 14,163 | \$ (6,780) | \$ 18,131 | \$ 167,631 |
| 6 | Ladera Ranch 555 | Roof | \$ 94,018 | \$ 68,942 | \$ 14,529 | \$ 17,637 | \$ (8,894) | \$ 22,578 | \$ 208,809 |
| 7 | High Tech High Chula Vista | Roof | \$ 159,827 | \$ 140,368 | \$ 26,580 | \$ 32,265 | \$ (18,071) | \$ 41,305 | \$ 382,274 |
| 8 | Hanna Gabriel Wells | Roof | \$ 48,116 | \$ 18,562 | \$ 6,081 | \$ 7,382 | \$ (2,389) | \$ 9,451 | \$ 87,203 |
| 9 | San Diego CC Skills Center | Roof | \$ 102,557 | \$ 79,098 | \$ 16,168 | \$ 19,627 | \$ (10,162) | \$ 25,126 | \$ 232,414 |
| 10 | Alterra Apartments | Roof | \$ 104,075 | \$ 80,420 | \$ 16,416 | \$ 19,927 | \$ (10,373) | \$ 25,510 | \$ 235,975 |
| 11 | Thomas Jefferson School of Law | Roof | \$ 79,045 | \$ 54,055 | \$ 11,895 | \$ 14,440 | \$ (7,004) | \$ 18,485 | \$ 170,916 |
| 12 | Broadway Pier Cruise Ship Terminal | Roof | \$ 61,778 | \$ 34,023 | \$ 8,633 | \$ 10,480 | \$ (4,389) | \$ 13,416 | \$ 123,941 |
| 13 | Wilco | Roof | \$ 459,770 | \$ 466,635 | \$ 81,549 | \$ 98,992 | \$ (60,119) | \$ 126,727 | \$ 1,173,553 |
| 14 | High Tech High North County | Roof | \$ 98,003 | \$ 73,792 | \$ 15,303 | \$ 18,576 | \$ (9,499) | \$ 23,781 | \$ 219,957 |
| 15 | Urban Corps | Roof | \$ 54,378 | \$ 25,778 | \$ 7,262 | \$ 8,816 | \$ (3,314) | \$ 11,286 | \$ 104,206 |
| 16 | Pacific Ridge School | Roof | \$ 51,532 | \$ 22,530 | \$ 6,731 | \$ 8,171 | \$ (2,869) | \$ 10,460 | \$ 96,555 |
| 17 | Sanford Burnham Medical Research | Roof | \$ 173,489 | \$ 155,991 | \$ 29,141 | \$ 35,375 | \$ (20,117) | \$ 45,286 | \$ 419,164 |
| 18 | High Tech High Chula Vista K-8 | Roof | \$ 160,586 | \$ 141,412 | \$ 26,740 | \$ 32,460 | \$ (18,168) | \$ 41,555 | \$ 384,585 |
| 19 | CSUSM - Public Safety Building | Roof | \$ 66,332 | \$ 39,328 | \$ 9,494 | \$ 11,525 | \$ (5,089) | \$ 14,754 | \$ 136,345 |
| 20 | SDG&E EIC (roof) | Roof | \$ 76,579 | \$ 51,262 | \$ 11,437 | \$ 13,883 | \$ (6,620) | \$ 17,773 | \$ 164,314 |
| 21 | UCSD - Revelle College | Roof | \$ 69,368 | \$ 43,017 | \$ 10,086 | \$ 12,243 | \$ (5,529) | \$ 15,674 | \$ 144,859 |
| 22 | Soledad | Roof | \$ 123,982 | \$ 101,348 | \$ 20,009 | \$ 24,289 | \$ (13,031) | \$ 31,094 | \$ 287,692 |
| 23 | Pacific Station | Roof | \$ 130,813 | \$ 109,152 | \$ 21,287 | \$ 25,841 | \$ (14,074) | \$ 33,080 | \$ 306,099 |
| 24 | UCSD - Structural & Materials Engr | Roof | \$ 143,716 | \$ 124,173 | \$ 23,734 | \$ 28,811 | \$ (15,987) | \$ 36,883 | \$ 341,329 |
| 25 | UCSD MESOM | Roof | \$ 89,654 | \$ 64,078 | \$ 13,721 | \$ 16,656 | \$ (8,250) | \$ 21,323 | \$ 197,182 |
| 26 | Village Lindo Paseo | Roof | \$ 60,640 | \$ 32,553 | \$ 8,402 | \$ 10,200 | \$ (4,229) | \$ 13,057 | \$ 120,623 |
| 27 | Del Lago Academy | Roof | \$ 180,700 | \$ 164,383 | \$ 30,510 | \$ 37,036 | \$ (21,172) | \$ 47,413 | \$ 438,870 |
| Subtotal - Roof | | | | | | | | | \$ 7,388,093 |

| | Customer | Location | Includes Contingency | | | | Scrap Value | G&A and Profit | Total Cost |
|--------------------------------|--|------------------------------------|----------------------|------------|-----------------------------|----------------------|--------------|----------------|---------------------|
| | | | Subcontract Cost | Labor Cost | Subcontractor Indirect Cost | SDG&E Internal Costs | | | |
| Carport PV Sites | | | | | | | | | |
| 28 | Sony Corporation | Carport - Canopy | \$ 21,574 | \$ 213,014 | \$ 13,041 | \$ 15,831 | \$ (64,508) | \$ 23,712 | \$ 222,664 |
| 29 | County Operations Center Parking Structure A | Carport - Canopy | \$ 45,448 | \$ 470,350 | \$ 28,494 | \$ 34,589 | \$ (143,774) | \$ 51,807 | \$ 486,913 |
| 30 | SDG&E EIC (parking) | Carport, Free-standing, Multi-axis | \$ 6,486 | \$ 72,326 | \$ 4,416 | \$ 5,361 | \$ (21,303) | \$ 8,029 | \$ 75,314 |
| 31 | Sharp Rees Stealy Wellness Center | Carport - Canopy | \$ 8,602 | \$ 83,979 | \$ 5,209 | \$ 6,324 | \$ (24,790) | \$ 9,472 | \$ 88,796 |
| 32 | San Diego Zoo | Carport - Canopy | \$ 10,764 | \$ 104,625 | \$ 6,459 | \$ 7,841 | \$ (31,257) | \$ 11,744 | \$ 110,175 |
| 33 | Fast EV Suncharge/Del Lago Park N Ride | Carport - Canopy | \$ 2,162 | \$ 18,058 | \$ 1,228 | \$ 1,490 | \$ (4,452) | \$ 2,232 | \$ 20,717 |
| 34 | Agua Hedionda | Carport - Canopy | \$ 2,116 | \$ 10,048 | \$ 822 | \$ 998 | \$ (1,787) | \$ 1,495 | \$ 13,692 |
| 35 | Civita Westpark Apartments | Carport | \$ 8,648 | \$ 88,813 | \$ 5,474 | \$ 6,645 | \$ (26,199) | \$ 9,954 | \$ 93,336 |
| Subtotal - Carport | | | | | | | | | \$ 1,111,608 |
| TOTAL Rooftop + Carport | | | | | | | | | \$ 8,499,701 |

Table 2-2 — Cost Estimate Summary by FERC Account for PV Sites

| | <i>Customer</i> | <i>Location</i> | E344.1: Generators - Solar | E345.1: Accessory Electrical Equipment | <i>TOTAL COST</i> |
|--------------------------------|--|----------------------|-------------------------------|---|-------------------|
| Roof Top PV Sites | | | | | |
| 1 | X-nth (formerly TKG) | Roof | \$ 172,680 | \$ 7,195 | \$ 179,875 |
| 2 | Reuben H Fleet (Science Center) | Roof | \$ 388,673 | \$ 16,195 | \$ 404,868 |
| 3 | Hunter Industries | Roof | \$ 347,994 | \$ 14,500 | \$ 362,494 |
| 4 | The Towers at Bressi Ranch | Roof | \$ 284,506 | \$ 11,854 | \$ 296,360 |
| 5 | Del Sur Elementary | Roof | \$ 160,925 | \$ 6,705 | \$ 167,631 |
| 6 | Ladera Ranch 555 | Roof | \$ 200,457 | \$ 8,352 | \$ 208,809 |
| 7 | High Tech High Chula Vista | Roof | \$ 366,983 | \$ 15,291 | \$ 382,274 |
| 8 | Hanna Gabriel Wells | Roof | \$ 83,715 | \$ 3,488 | \$ 87,203 |
| 9 | San Diego CC Skills Center | Roof | \$ 223,118 | \$ 9,297 | \$ 232,414 |
| 10 | Alterra Apartments | Roof | \$ 226,536 | \$ 9,439 | \$ 235,975 |
| 11 | Thomas Jefferson School of Law | Roof | \$ 164,079 | \$ 6,837 | \$ 170,916 |
| 12 | Broadway Pier Cruise Ship Terminal | Roof | \$ 118,983 | \$ 4,958 | \$ 123,941 |
| 13 | Wilco | Roof | \$ 1,126,611 | \$ 46,942 | \$ 1,173,553 |
| 14 | High Tech High North County | Roof | \$ 211,158 | \$ 8,798 | \$ 219,957 |
| 15 | Urban Corps | Roof | \$ 100,037 | \$ 4,168 | \$ 104,206 |
| 16 | Pacific Ridge School | Roof | \$ 92,693 | \$ 3,862 | \$ 96,555 |
| 17 | Sanford Burnham Medical Research | Roof | \$ 402,398 | \$ 16,767 | \$ 419,164 |
| 18 | High Tech High Chula Vista K-8 | Roof | \$ 369,202 | \$ 15,383 | \$ 384,585 |
| 19 | CSUSM - Public Safety Building | Roof | \$ 130,891 | \$ 5,454 | \$ 136,345 |
| 20 | SDG&E EIC (roof) | Roof | \$ 157,741 | \$ 6,573 | \$ 164,314 |
| 21 | UCSD - Revelle College | Roof | \$ 139,065 | \$ 5,794 | \$ 144,859 |
| 22 | Soledad | Roof | \$ 276,184 | \$ 11,508 | \$ 287,692 |
| 23 | Pacific Station | Roof | \$ 293,855 | \$ 12,244 | \$ 306,099 |
| 24 | UCSD - Structural & Materials Engr | Roof | \$ 327,676 | \$ 13,653 | \$ 341,329 |
| 25 | UCSD MESOM | Roof | \$ 189,295 | \$ 7,887 | \$ 197,182 |
| 26 | Village Lindo Paseo | Roof | \$ 115,799 | \$ 4,825 | \$ 120,623 |
| 27 | Del Lago Academy | Roof | \$ 421,315 | \$ 17,555 | \$ 438,870 |
| <i>Subtotal - Roof</i> | | | \$ 7,092,569 | \$ 295,524 | \$ 7,388,093 |
| Carport PV Sites | | | | | |
| 28 | Sony Corporation | Carport - Canopy | \$ 213,757 | \$ 8,907 | \$ 222,664 |
| 29 | County Operations Center Parking Structure | Carport - Canopy | \$ 467,437 | \$ 19,477 | \$ 486,913 |
| 30 | SDG&E EIC (parking) | standing, Multi-axis | \$ 72,302 | \$ 3,013 | \$ 75,314 |
| 31 | Sharp Rees Stealy Wellness Center | Carport - Canopy | \$ 85,244 | \$ 3,552 | \$ 88,796 |
| 32 | San Diego Zoo | Carport - Canopy | \$ 105,768 | \$ 4,407 | \$ 110,175 |
| 33 | Fast EV Suncharge/Del Lago Park N Ride | Carport - Canopy | \$ 19,889 | \$ 829 | \$ 20,717 |
| 34 | Agua Hedionda | Carport - Canopy | \$ 13,144 | \$ 548 | \$ 13,692 |
| 35 | Civita Westpark Apartments | Carport | \$ 89,602 | \$ 3,733 | \$ 93,336 |
| <i>Subtotal - Carport</i> | | | \$ 1,067,144 | \$ 44,464 | \$ 1,111,608 |
| TOTAL Rooftop + Carport | | | \$ 8,159,713 | \$ 339,988 | \$ 8,499,701 |

The decommissioning cost of PV sites on a per-panel basis varies with site characteristics and the number of panels. In general, decommissioning costs at sites with fewer panels are higher per panel than sites with many panels due to economy of scale. For example, the SDG&E rooftop site “Pacific Ridge School” has 102 panels and a decommissioning cost of approximately \$947 per panel. In contrast, the SDG&E rooftop site “Hunter Industries” has six times the number of panels, 608, and a decommissioning cost of

approximately \$596 per panel. The trend between decommissioning costs per panel and the number of panels is asymptotic and levels out for sites with a significant number of panels.

2.2.2. Variance from 2016 Study

The following list summarizes the changes from S&L's 2016 report. Note that material quantities and labor hours in the estimate were unchanged from 2016.

- Six sites were removed from the list, and several of the remaining 35 sites were renamed. The removed sites were all rooftop installations, and they totaled 1259 kW.
- The 2016 estimates assumed that the panels would be disposed with rubbish removed from the site. This has been replaced with a higher cost, where SDG&E pays a company such as We Recycle Solar to recycle the panels for \$20/panel. This cost is based on a publication by the National Renewable Energy Laboratory and a conversation with We Recycle Solar.
- The contractor general and administrative costs and profit were increased from 5% and 8%, respectively, to 7% and 10% based on the S&L database.
- SDG&E internal costs were added to the estimate. These were excluded from the 2016 estimate. The internal costs include disconnecting the units from the grid and securing and managing the contractor.
- The current estimates utilize updated labor rates, material costs, and scrap value to current 2021 values.

3. BASIS OF ESTIMATE

The basis for the cost estimates is as follows:

The decommissioning cost estimates in Section 2 and Appendix A are for the dismantlement and removal of 35 different PV sites. In general, the sites can be categorized into two groups: rooftop installations and canopy installations. The rooftop installations are mounted on bolts attached to roofs. The canopy installations are freestanding, and the demolition of the canopy's steel and concrete structure is included with the decommissioning costs.

The cost estimates are based primarily on the data provided by SDG&E and S&L's experience with similar projects.

3.1. PROCEDURE

In general, the methodology to decommission the PV sites is as follows:

- Rooftop Installations
 - De-energize the system.
 - Dismantle and remove all electrical equipment.
 - Remove solar panels.
 - Remove panel racking.
 - Remove mounting points on the rooftop.
 - Remove repair/patch roof holes/damage from removing mounting bolts.
 - Remove the inverter, combiner box, and electrical box aboveground conduits and wiring.
 - Remove transformers.
 - Attain scrap value for metals.
 - Recycle the panels.
 - Dispose of materials.
- Canopy Installations
 - De-energize the system.
 - Dismantle and remove all electrical equipment.
 - Remove the solar panels.
 - Remove the panel racking.
 - Remove the steel canopy structure and cut for scrap as necessary.

- Demolish the steel structures' concrete foundations and remove the concrete down to one foot.
- Cap and abandon the conduit.
- Remove the inverter, combiner box, and electrical box aboveground conduits and wiring.
- Remove the transformers.
- Attain scrap value for metals.
- Recycle the panels.
- Dispose of materials.

3.2. PRICING AND QUANTITIES

1. Construction Labor Wages

Craft labor rates (or craft hourly rates) for the cost estimate are based on the prevailing wages for San Diego, California as published in *R. S. Means Labor Rates for the Construction Industry* (2021). These prevailing rates are representative of union or non-union rates, whichever is prevailing in the area. Costs have been added to cover social security, workmen's compensation, and federal and state unemployment insurance. The resulting burdened craft rates were then used to develop typical crew rates applicable to the task being performed.

2. Labor Work Schedule and Incentives

- The labor estimate is based on a 40-hour workweek with no per diem or other labor incentives.
- An allowance for show-up time is included if workers arrive and are then sent home.

3. Quantity Sources

Quantities of pieces of equipment and/or bulk material commodities used in this cost estimate were developed from engineering-supplied information from the sites and the S&L database.

4. General Conditions Cost

Allowances were included in the cost estimate as direct costs as noted for the following:

- Labor supervision
- Construction management
- Field office expenses
- Safety
- Temporary facilities
- Mobilization/demobilization
- Legal expenses/claims
- Small tools and consumables
- General liability insurance

- Construction equipment mobilization/demobilization
- Freight on material
- Contractor general and administrative costs (7% of labor [direct labor, additional labor cost, site overheads, and other construction indirect cost], material [direct material cost and freight cost], and equipment)
- Contractor's profit (10% of labor [direct labor, additional labor cost, site overheads, and other construction indirect cost], material [direct material cost and freight cost], and equipment)

5. Scrap

Scrap metals are a globally traded commodity and are part of the larger metals industry. The value of scrap metal is subject to constantly changing economic conditions; as such, the price of mixed steel, stainless steel, copper, and aluminum can vary greatly over time as a result of global supply and demand. The value of scrap for this study was determined by a 12-month average from *Scrap Metals MarketWatch*¹ (November 2020–October 2021) for the West Coast (Zone 1) of the United States. The values obtained are delivered prices to the recycler. Transportation cost to the recycler is estimated at \$30/ton, resulting in the values shown in Table 3-1:

Table 3-1 — Scrap Value

| Commodity | Scrap Value (\$/ton) |
|--------------------------|----------------------|
| Carbon Steel | 175 |
| Aluminum | 1172 |
| #2 Insulated Copper Wire | 2440 |
| Stainless Steel | 1217 |

Note: 1 ton = 2000 lbs.

6. Indirect Expenses

- Engineering is included to cover preparation of the decommissioning work specification, engineering required to place the relevant equipment in safe shutdown, and any unique engineering required during demolition.
- SDG&E internal costs are included to cover costs in support of decommissioning the stations such as disconnecting the units from the grid and securing and managing the contractor.

7. Escalation Rates

Escalation rates are not included.

8. Sales and Use Taxes

Sales and use taxes are not included.

9. Contingency

- A 15% contingency is applied for material, labor, and indirect expenses.

¹ www.americanrecycler.com

- There is no contingency on scrap value.

10. Contract Basis for Estimates

The contracting strategy is a multiple lump sum for the estimates.

11. Assumptions

- All electrical equipment and wiring is de-energized by SDG&E.
- Transmission/distribution equipment beyond each PV sites' step-up transformer is excluded from the estimate. This includes overhead transmission wires, switchyards, substations, etc.
- Per SDG&E's direction, all rooftop PV panels are assumed to be fixed to the roof by four bolts. A cost of \$165/panel has been allocated for roof repair based on S&L's database of experience with similar repair work.
- No extraordinary environmental costs for demolition will be needed.
- All items above grade and to a depth of one foot will be demolished (canopy foundations). All foundations will be removed. Any other items buried more than one foot deep will remain in place.
- Solar panels are recycled by a company such as We Recycle Solar at a cost to SDG&E of \$20/panel based on a publication by the National Renewable Energy Laboratory and verbal information from We Recycle Solar.
- All demolished materials are considered debris, except for non-embedded metals that have scrap value.
- The basis for salvage estimating is for scrap value only. No resale of equipment or material is included.

4. REFERENCES

12. Sargent & Lundy Cost Database.
13. RSMeans Cost Data, 2021.
14. Engineering Drawings, Equipment Lists and other information provided by San Diego Gas & Electric.
15. *Scrap Metals MarketWatch* – West Coast (Zone 1), www.americanrecycler.com.
16. Satellite images of sites (Google Maps).
17. *A Circular Economy for Solar Photovoltaic System Materials: Drivers, Barriers, Enablers, and U.S. Policy Considerations* by T. Curtis, H. Buchanan, L. Smith, and G. Heath for the DOE National Renewable Energy Laboratory, Technical Report NREL/TP-6A20-74550, April 2021.

**APPENDIX A. CONCEPTUAL ESTIMATE OF COST
TO DECOMMISSION PV SITES**

San Diego Gas & Electric
 Decommissioning Cost Estimates
 PV Sites - Roof Mounted

| Project ID | | Code | Customer | Address | PV Location | Tech. | Date Energized | Facility Nameplate (kW) | Panel Qty | | | |
|------------|----------|----------|---|--|-------------|------------------|----------------|-------------------------|-----------|-----------|------------|------------|
| 1 | | XNT | X-nth (formerly TKG) | 5670 Oberlin Dr, San Diego | Roof | PV | 6/24/2004 | 40,70 | 264 | | | |
| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Crew Rate | Labor Cost | Total Cost |
| Roof top | 11.00.00 | 11.22.00 | Concrete | | | | | | | | | |
| | | | Concrete | Electrical equipment (Transformer, inverter, etc.) pad | 7 /CY | | | | 9 /MH | \$ 140.47 | \$ 1,264 | \$ 1,264 |
| | 11.41.00 | | Electrical Equipment | | | | | | | | | |
| | | | Disconnect wiring and components at service rack | | 1 EA | | | | 9 /MH | \$ 127.80 | \$ 1,150 | \$ 1,150 |
| | | | Disconnect wiring at inverter | | 1 EA | | | | 2 /MH | \$ 127.80 | \$ 256 | \$ 256 |
| | | | Disconnect wiring at combiner boxes, remove boxes | | 2 EA | | | | 21 /MH | \$ 127.80 | \$ 2,684 | \$ 2,684 |
| | | | Pull wire from combiners to inverter | | 2 EA | | | | 15 /MH | \$ 127.80 | \$ 1,917 | \$ 1,917 |
| | | | Disconnect and remove wiring at PV panels | | 264 EA | | | | 40 /MH | \$ 127.80 | \$ 5,112 | \$ 5,112 |
| | | | Disconnect and remove grounding at PV panels and racks, Remove ground rods | | 264 EA | | | | 11 /MH | \$ 127.80 | \$ 1,406 | \$ 1,406 |
| | | | Demo conduit from rack to tie point | | 1 EA | | | | 9 /MH | \$ 127.80 | \$ 1,150 | \$ 1,150 |
| | | | Demo conduit from rack to transformer | | 1 EA | | | | 7 /MH | \$ 127.80 | \$ 895 | \$ 895 |
| | | | Demo conduit from combiners to inverter | | 1 EA | | | | 38 /MH | \$ 127.80 | \$ 4,856 | \$ 4,856 |
| | | | Remove Conduits to inverters | | 1 EA | | | | 2 /MH | \$ 127.80 | \$ 256 | \$ 256 |
| | | | Remove inverters | | 1 EA | | | | 4 /MH | \$ 127.80 | \$ 511 | \$ 511 |
| | | | Remove PV panel and place in dumpster | | 264 EA | | | | 132 /MH | \$ 127.80 | \$ 16,870 | \$ 16,870 |
| | | | Remove points where panel is fixed to roof | | 264 EA | | | | 59 /MH | \$ 127.80 | \$ 7,540 | \$ 7,540 |
| | | | Remove lightning projection and other auxiliary equipment | | 1 EA | | | | 25 /MH | \$ 127.80 | \$ 3,195 | \$ 3,195 |
| | | | Remove transformer | | 1 LT | | | | 10 /MH | \$ 127.80 | \$ 1,278 | \$ 1,278 |
| | | | Demolition | | | \$ - | \$ - | \$ - | | | \$ 50,339 | \$ 50,339 |
| | 18.00.00 | | Scrap Value | | | | | | | | | |
| | | 18.10.00 | Mixed Steel | | | | | | | | | |
| | | | Steel | 1 EA, inverter 402 kW | 0.18 TN | \$ (32) | | | /MH | | \$ (32) | \$ (32) |
| | | | Steel | Service rack components | 0.07 TN | \$ (12) | | | /MH | | \$ (12) | \$ (12) |
| | | | Steel | Conduit and fittings | 0.07 TN | \$ (12) | | | /MH | | \$ (12) | \$ (12) |
| | | | Steel | Transformers | 2.15 TN | \$ (376) | | | /MH | | \$ (376) | \$ (376) |
| | | | Steel | Roof ladder, 1@ 350 lb each | 0.03 TN | \$ (5) | | | /MH | | \$ (5) | \$ (5) |
| | | 18.20.00 | Stainless Steel | | | | | | | | | |
| | | | Stainless Steel | 1788 Racks, 13.61 lbs each | 1.8 TN | \$ (2,110) | | | /MH | | \$ (2,110) | \$ (2,110) |
| | | 18.30.00 | Copper | | | | | | | | | |
| | | | Copper | 1 EA, 402 kW inverter | 0.06 TN | \$ (146) | | | /MH | | \$ (146) | \$ (146) |
| | | | Copper | Wire | 0.4 TN | \$ (976) | | | /MH | | \$ (976) | \$ (976) |
| | | | Copper | Transformers | 1.02 TN | \$ (2,489) | | | /MH | | \$ (2,489) | \$ (2,489) |
| | | 18.50.00 | Aluminum | | | | | | | | | |
| | | | PV Module | 1788 Modules @ 8 lbs each | 2112 LB | \$ (1,285) | | | /MH | | \$ (1,285) | \$ (1,285) |
| | | | Conduit and fittings | 100 @ 1 lb each | 14.77 LB | \$ (9) | | | /MH | | \$ (9) | \$ (9) |
| | | | Scrap Value | | | \$ - | \$ (7,452) | \$ - | | | \$ - | \$ (7,452) |
| | 21.00.00 | | Civil Work | | | | | | | | | |
| | | 21.19.00 | Disposal | | | | | | | | | |
| | | | Dumpster, 40 CY Capacity | Concrete, PV panels, rubbish (panels to recycler) | 1 EA | \$ 1,800 | | | /MH | | \$ 1,800 | \$ 1,800 |
| | | | Dumpster, 40 CY Capacity | Fix point rods | 1 EA | \$ 900 | | | /MH | | \$ 900 | \$ 900 |
| | | 21.20.00 | Backfill | | | | | | | | | |
| | | | Foundation backfill, imported material fill | Backfill concrete pads | 7 /CY | \$ 280 | | | /MH | | \$ 280 | \$ 280 |
| | | | Civil Work | | | \$ 2,980 | \$ - | \$ - | | | \$ - | \$ 2,980 |
| | 24.00.00 | | Architectural | | | | | | | | | |
| | | 24.37.00 | Roofing | | | | | | | | | |
| | | | Roof repair at fix points | Installation | 264 EA | \$ 43,560 | | | /MH | | \$ - | \$ 43,560 |
| | | | Architectural | | | \$ 43,560 | \$ - | \$ - | | | \$ - | \$ 43,560 |
| | | | | | | \$ - | \$ - | \$ - | | | \$ - | \$ 89,427 |
| | | | Direct Costs | | | | | | | | | |
| | 61.00.00 | | Construction Indirect | | | | | | | | | |
| | | 61.99.00 | Miscellaneous | | | | | | | | | |
| | | | Downspout / Chute | | 1 LS | \$ 25,000 | | | /MH | | \$ 25,000 | \$ 25,000 |
| | | | Construction Indirect | | | \$ 25,000 | \$ - | \$ - | | | \$ - | \$ 25,000 |
| | | | Subtotal | | | \$ 71,540 | \$ (7,452) | \$ - | | | \$ 50,339 | \$ 114,427 |
| | 91.00.00 | | Other Direct & Construction Indirect Costs | | | | | | | | | |
| | | 91.09 | Contractor's General and Administration Expense | | | | | | | | | \$ 8,010 |
| | | 91.10 | Contractor's Profit | | | | | | | | | \$ 11,443 |
| | | | | | | | | | | | | \$ 19,453 |
| | | | Direct Costs + Construction Indirect Costs | | | \$ 71,540 | \$ (7,452) | \$ - | | | \$ 50,339 | \$ 133,880 |
| | 93.00.00 | | Indirect Costs | | | | | | | | | |
| | | 93.1 | Engineering, Procurement, & Project Services | | | | | | | | | \$ 8,033 |
| | | 93.2 | Construction Management Support | | | | | | | | | \$ 2,678 |
| | | 93.3 | SDG&E Internal Costs | | | | | | | | | \$ 13,388 |
| | 95.00.00 | | Contingency | | | | | | | | | |
| | | 95.1 | Contingency on Subcontractor | | | \$ 10,731 | | | | | | \$ 10,731 |
| | | 95.2 | Contingency on Scrap Value | | | \$ - | | | | | | \$ - |
| | | 95.3 | Contingency on Material | | | \$ - | | \$ - | | | \$ 7,551 | \$ 7,551 |
| | | 95.4 | Contingency on Labor | | | | | | | | \$ 7,551 | \$ 7,551 |
| | | 95.5 | Contingency on Indirect | | | | | | | | | \$ 3,615 |
| | | | Total | | | \$ 82,271 | \$ (7,452) | \$ - | | | \$ 57,890 | \$ 179,875 |

San Diego Gas & Electric
Decommissioning Cost Estimates
PV Sites - Roof Mounted

| Project ID | Code | Customer | Address | PV Location | Tech. | Date Energized | Facility Nameplate (kW) | Panel Qty | | | | | | |
|--------------|----------|---------------------------------|--|--|----------|------------------|-------------------------|---------------|-----------|-----------|------------|--------------|------------|--|
| 2 | RHF | Reuben H Fleet (Science Center) | 1875 El Prado, San Diego | Roof | PV | 3/30/2007 | 100.10 | 684 | | | | | | |
| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Crew Rate | Labor Cost | Total Cost | | |
| Roof top | 11.00.00 | | Demolition | | | | | | | | | | | |
| | 11.22.00 | | Concrete | Electrical equipment (Transformer, inverter, etc.) pad | 7 /CY | | | | 23 /MH | \$ 140.47 | \$ 3,231 | \$ 3,231 | | |
| | 11.41.00 | | Electrical Equipment | | | | | | | | | | | |
| | | | Disconnect wiring and components at service rack | | 1 EA | | | | 24 /MH | \$ 127.80 | \$ 3,067 | \$ 3,067 | | |
| | | | Disconnect wiring at inverter | | 1 EA | | | | 6 /MH | \$ 127.80 | \$ 767 | \$ 767 | | |
| | | | Disconnect wiring at combiner boxes, remove boxes | | 5 EA | | | | 55 /MH | \$ 127.80 | \$ 7,029 | \$ 7,029 | | |
| | | | Pull wire from combiners to inverter | | 5 EA | | | | 40 /MH | \$ 127.80 | \$ 5,112 | \$ 5,112 | | |
| | | | Disconnect and remove wiring at PV panels | | 684 EA | | | | 103 /MH | \$ 127.80 | \$ 13,163 | \$ 13,163 | | |
| | | | Disconnect and remove grounding at PV panels and racks, Remove ground rods | | 684 EA | | | | 28 /MH | \$ 127.80 | \$ 3,578 | \$ 3,578 | | |
| | | | Demo conduit from rack to tie point | | 1 EA | | | | 24 /MH | \$ 127.80 | \$ 3,067 | \$ 3,067 | | |
| | | | Demo conduit from rack to transformer | | 1 EA | | | | 18 /MH | \$ 127.80 | \$ 2,300 | \$ 2,300 | | |
| | | | Demo conduit from combiners to inverter | | 1 EA | | | | 98 /MH | \$ 127.80 | \$ 12,524 | \$ 12,524 | | |
| | | | Remove Conduits to inverters | | 1 EA | | | | 6 /MH | \$ 127.80 | \$ 767 | \$ 767 | | |
| | | | Remove inverters | | 1 EA | | | | 9 /MH | \$ 127.80 | \$ 1,150 | \$ 1,150 | | |
| | | | Remove PV panel and place in dumpster | | 684 EA | | | | 342 /MH | \$ 127.80 | \$ 43,708 | \$ 43,708 | | |
| | | | Remove points where panel is fixed to roof | | 684 EA | | | | 153 /MH | \$ 127.80 | \$ 19,553 | \$ 19,553 | | |
| | | | Remove lightning projection and other auxiliary equipment | | 1 EA | | | | 64 /MH | \$ 127.80 | \$ 8,179 | \$ 8,179 | | |
| | | | Remove transformer | | 1 LT | | | | 25 /MH | \$ 127.80 | \$ 3,195 | \$ 3,195 | | |
| | | | Demolition | | | \$ - | \$ - | \$ - | | | \$ 130,392 | \$ 130,392 | | |
| | 18.00.00 | | Scrap Value | | | | | | | | | | | |
| | 18.10.00 | | Mixed Steel | | | | | | | | | | | |
| | | | Steel | 1 EA, inverter 402 kW | 0.48 TN | | \$ (84) | | /MH | | | \$ (84) | | |
| | | | Steel | Service rack components | 0.18 TN | | \$ (32) | | /MH | | | \$ (32) | | |
| | | | Steel | Conduit and fittings | 0.19 TN | | \$ (33) | | /MH | | | \$ (33) | | |
| | | | Steel | Transformers | 5.57 TN | | \$ (975) | | /MH | | | \$ (975) | | |
| | | | Steel | Roof ladder, 1@ 350 lb each | 0.07 TN | | \$ (12) | | /MH | | | \$ (12) | | |
| | 18.20.00 | | Stainless Steel | | | | | | | | | | | |
| | | | Stainless Steel | 1788 Racks, 13.61 lbs each | 4.66 TN | | \$ (5,462) | | /MH | | | \$ (5,462) | | |
| | 18.30.00 | | Copper | | | | | | | | | | | |
| | | | Copper | 1 EA, 402 kW inverter | 0.15 TN | | \$ (366) | | /MH | | | \$ (366) | | |
| | | | Copper | Wire | 1.04 TN | | \$ (2,538) | | /MH | | | \$ (2,538) | | |
| | | | Copper | Transformers | 2.65 TN | | \$ (6,466) | | /MH | | | \$ (6,466) | | |
| | 18.50.00 | | Aluminum | | | | | | | | | | | |
| | | | PV Module | 1788 Modules @ 8 lbs each | 5472 LB | | \$ (3,330) | | /MH | | | \$ (3,330) | | |
| | | | Conduit and fittings | 100 @ 1 lb each | 38.26 LB | | \$ (23) | | /MH | | | \$ (23) | | |
| | | | Scrap Value | | | \$ - | \$ (19,320) | \$ - | | | \$ - | \$ (19,320) | | |
| | 21.00.00 | | Civil Work | | | | | | | | | | | |
| | 21.19.00 | | Disposal | | | | | | | | | | | |
| | | | Dumpster, 40 CY Capacity | Concrete, PV panels, rubbish (panels to recycler) | 4 EA | \$ 7,200 | | | /MH | | | \$ 7,200 | | |
| | | | Dumpster, 40 CY Capacity | Fix point rods | 1 EA | \$ 900 | | | /MH | | | \$ 900 | | |
| | 21.20.00 | | Backfill | | | | | | | | | | | |
| | | | Foundation backfill, imported material fill | Backfill concrete pads | 7 /CY | \$ 280 | | | /MH | | | \$ 280 | | |
| | | | Civil Work | | | \$ 8,380 | \$ - | \$ - | | | \$ - | \$ 8,380 | | |
| | 24.00.00 | | Architectural | | | | | | | | | | | |
| | 24.37.00 | | Roofing | | | | | | | | | | | |
| | | | Roof repair at fix points | Installation | 684 EA | \$ 112,860 | | | /MH | | \$ - | \$ 112,860 | | |
| | | | Architectural | | | \$ 112,860 | \$ - | \$ - | | | \$ - | \$ 112,860 | | |
| | | | Direct Costs | | | | | | | | | | \$ 232,312 | |
| | 61.00.00 | | Construction Indirect | | | | | | | | | | | |
| | 61.99.00 | | Miscellaneous | | | | | | | | | | | |
| | | | Downspout / Chute | | 1 LS | \$ 25,000 | | | /MH | | | \$ 25,000 | | |
| | | | Construction Indirect | | | \$ 25,000 | \$ - | \$ - | | | \$ - | \$ 25,000 | | |
| | | | Subtotal | | | \$ 146,240 | \$ (19,320) | \$ - | | | \$ 130,392 | \$ 257,312 | | |
| | 91.00.00 | | Other Direct & Construction Indirect Costs | | | | | | | | | | | |
| | | | 91.09 Contractor's General and Administration Expense | | | | | | | | | \$ 18,012 | | |
| | | | 91.10 Contractor's Profit | | | | | | | | | \$ 25,731 | | |
| | | | Direct Costs + Construction Indirect Costs | | | \$ 146,240 | \$ (19,320) | \$ - | | | \$ 130,392 | \$ 301,055 | | |
| | 93.00.00 | | Indirect Costs | | | | | | | | | | | |
| | | | 93.1 Engineering, Procurement, & Project Services | | | | | | | | | \$ 18,063 | | |
| | | | 93.2 Construction Management Support | | | | | | | | | \$ 6,021 | | |
| | | | 93.3 SDG&E Internal Costs | | | | | | | | | \$ 30,105 | | |
| | 95.00.00 | | Contingency | | | | | | | | | | | |
| | | | 95.1 Contingency on Subcontractor | | | \$ 21,936 | | | | | | \$ 21,936.00 | | |
| | | | 95.2 Contingency on Scrap Value | | | \$ - | | | | | | \$ - | | |
| | | | 95.3 Contingency on Material | | | \$ - | | \$ - | | | \$ 19,559 | \$ 19,559 | | |
| | | | 95.4 Contingency on Labor | | | | | | | | | \$ - | | |
| | | | 95.5 Contingency on Indirect | | | | | | | | | \$ 8,128 | | |
| Total | | | | | | \$ 168,176 | \$ (19,320) | \$ - | | | \$ 149,951 | \$ 404,868 | | |

San Diego Gas & Electric
Decommissioning Cost Estimates
PV Sites - Roof Mounted

| Project ID | Code | Customer | Address | PV Location | Tech. | Date Energized | Facility Nameplate (kW) | Panel Qty | | | | |
|--|----------|-------------------|---|--|----------|------------------|-------------------------|---------------|-----------|-----------|------------|-------------|
| 3 | HUI | Hunter Industries | 1840 La Costa Meadows Rd, San Marcos | Roof | PV | 12/4/2007 | 101.80 | 608 | | | | |
| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Crew Rate | Labor Cost | Total Cost |
| Roof top | 11.00.00 | 11.22.00 | Demolition Concrete | | | | | | | | | |
| | | | Concrete | Electrical equipment (Transformer, inverter, etc.) pad | 7 /CY | | | | 20 /MH | \$ 140.47 | \$ 2,809 | \$ 2,809 |
| | 11.41.00 | | Electrical Equipment | | | | | | | | | |
| | | | Disconnect wiring and components at service rack | | 1 EA | | | | 22 /MH | \$ 127.80 | \$ 2,812 | \$ 2,812 |
| | | | Disconnect wiring at inverter | | 1 EA | | | | 5 /MH | \$ 127.80 | \$ 639 | \$ 639 |
| | | | Disconnect wiring at combiner boxes, remove boxes | | 4 EA | | | | 49 /MH | \$ 127.80 | \$ 6,262 | \$ 6,262 |
| | | | Pull wire from combiners to inverter | | 4 EA | | | | 35 /MH | \$ 127.80 | \$ 4,473 | \$ 4,473 |
| | | | Disconnect and remove wiring at PV panels | | 608 EA | | | | 91 /MH | \$ 127.80 | \$ 11,630 | \$ 11,630 |
| | | | Disconnect and remove grounding at PV panels and racks, | | | | | | | | | |
| | | | Remove ground rods | | 608 EA | | | | 24 /MH | \$ 127.80 | \$ 3,067 | \$ 3,067 |
| | | | Demo conduit from rack to tie point | | 1 EA | | | | 22 /MH | \$ 127.80 | \$ 2,812 | \$ 2,812 |
| | | | Demo conduit from rack to transformer | | 1 EA | | | | 16 /MH | \$ 127.80 | \$ 2,045 | \$ 2,045 |
| | | | Demo conduit from combiners to inverter | | 1 EA | | | | 87 /MH | \$ 127.80 | \$ 11,119 | \$ 11,119 |
| | | | Remove Conduits to inverters | | 1 EA | | | | 5 /MH | \$ 127.80 | \$ 639 | \$ 639 |
| | | | Remove inverters | | 1 EA | | | | 8 /MH | \$ 127.80 | \$ 1,022 | \$ 1,022 |
| | | | Remove PV panel and place in dumpster | | 608 EA | | | | 304 /MH | \$ 127.80 | \$ 38,851 | \$ 38,851 |
| | | | Remove points where panel is fixed to roof | | 608 EA | | | | 136 /MH | \$ 127.80 | \$ 17,381 | \$ 17,381 |
| | | | Remove lightning projection and other auxiliary equipment | | 1 EA | | | | 57 /MH | \$ 127.80 | \$ 7,285 | \$ 7,285 |
| | | | Remove transformer | | 1 LT | | | | 22 /MH | \$ 127.80 | \$ 2,812 | \$ 2,812 |
| | | | Demolition | | | \$ - | \$ - | \$ - | | | \$ 115,657 | \$ 115,657 |
| | 18.00.00 | | Scrap Value | | | | | | | | | |
| | 18.10.00 | | Mixed Steel | | | | | | | | | |
| | | | Steel | 1 EA, inverter 402 kW | 0.43 TN | | \$ (75) | | /MH | | | \$ (75) |
| | | | Steel | Service rack components | 0.16 TN | | \$ (28) | | /MH | | | \$ (28) |
| | | | Steel | Conduit and fittings | 0.17 TN | | \$ (30) | | /MH | | | \$ (30) |
| | | | Steel | Transformers | 4.95 TN | | \$ (866) | | /MH | | | \$ (866) |
| | | | Steel | Roof ladder, 1@ 350 lb each | 0.06 TN | | \$ (11) | | /MH | | | \$ (11) |
| | 18.20.00 | | Stainless Steel | | | | | | | | | |
| | | | Stainless Steel | 1788 Racks, 13.61 lbs each | 4.14 TN | | \$ (4,852) | | /MH | | | \$ (4,852) |
| | 18.30.00 | | Copper | | | | | | | | | |
| | | | Copper | 1 EA, 402 kW inverter | 0.14 TN | | \$ (342) | | /MH | | | \$ (342) |
| | | | Copper | Wire | 0.92 TN | | \$ (2,245) | | /MH | | | \$ (2,245) |
| | | | Copper | Transformers | 2.35 TN | | \$ (5,734) | | /MH | | | \$ (5,734) |
| | 18.50.00 | | Aluminum | | | | | | | | | |
| | | | PV Module | 1788 Modules @ 8 lbs each | 4864 LB | | \$ (2,960) | | /MH | | | \$ (2,960) |
| | | | Conduit and fittings | 100 @ 1 lb each | 34 LB | | \$ (21) | | /MH | | | \$ (21) |
| | | | Scrap Value | | | \$ - | \$ (17,163) | \$ - | | | \$ - | \$ (17,163) |
| | 21.00.00 | | Civil Work | | | | | | | | | |
| | 21.19.00 | | Disposal | | | | | | | | | |
| | | | Dumpster, 40 CY Capacity | Concrete, PV panels, rubbish (panels to recycler) | 3 EA | \$ 5,400 | | | /MH | | \$ 5,400 | \$ 5,400 |
| | | | Dumpster, 40 CY Capacity | Fix point rods | 1 EA | \$ 900 | | | /MH | | \$ 900 | \$ 900 |
| | 21.20.00 | | Backfill | | | | | | | | | |
| | | | Foundation backfill, imported material fill | Backfill concrete pads | 7 /CY | \$ 280 | | | /MH | | \$ 280 | \$ 280 |
| | | | Civil Work | | | \$ 6,580 | \$ - | \$ - | | | \$ - | \$ 6,580 |
| | 24.00.00 | | Architectural | | | | | | | | | |
| | 24.37.00 | | Roofing | | | | | | | | | |
| | | | Roof repair at fix points | Installation | 608 EA | \$ 100,320 | | | /MH | | \$ - | \$ 100,320 |
| | | | Architectural | | | \$ 100,320 | \$ - | \$ - | | | \$ - | \$ 100,320 |
| Direct Costs | | | | | | | | | | | | \$ 205,394 |
| | 61.00.00 | | Construction Indirect | | | | | | | | | |
| | 61.99.00 | | Miscellaneous | | | | | | | | | |
| | | | Downspout / Chute | | 1 LS | \$ 25,000 | | | /MH | | \$ - | \$ 25,000 |
| | | | Construction Indirect | | | \$ 25,000 | \$ - | \$ - | | | \$ - | \$ 25,000 |
| Subtotal | | | | | | \$ 131,900 | \$ (17,163) | \$ - | | | \$ 115,657 | \$ 230,394 |
| | 91.00.00 | | Other Direct & Construction Indirect Costs | | | | | | | | | |
| | | 91.09 | Contractor's General and Administration Expense | | | | | | | | | \$ 16,128 |
| | | 91.10 | Contractor's Profit | | | | | | | | | \$ 23,039 |
| | | | | | | | | | | | | \$ 39,167 |
| Direct Costs + Construction Indirect Costs | | | | | | \$ 131,900 | \$ (17,163) | \$ - | | | \$ 115,657 | \$ 269,561 |
| | 93.00.00 | | Indirect Costs | | | | | | | | | |
| | | 93.1 | Engineering, Procurement, & Project Services | | | | | | | | | \$ 16,174 |
| | | 93.2 | Construction Management Support | | | | | | | | | \$ 5,391 |
| | | 93.3 | SDG&E Internal Costs | | | | | | | | | \$ 26,956 |
| | 95.00.00 | | Contingency | | | | | | | | | |
| | | 95.1 | Contingency on Subcontractor | | | \$ 19,785 | | | | | | \$ 19,785 |
| | | 95.2 | Contingency on Scrap Value | | | \$ - | | | | | | \$ - |
| | | 95.3 | Contingency on Material | | | \$ - | | | | | | \$ - |
| | | 95.4 | Contingency on Labor | | | | | | | \$ 17,349 | | \$ 17,349 |
| | | 95.5 | Contingency on Indirect | | | | | | | | | \$ 7,278 |
| Total | | | | | | \$ 151,685 | \$ (17,163) | \$ - | | | \$ 133,005 | \$ 362,494 |

San Diego Gas & Electric
Decommissioning Cost Estimates
PV Sites - Roof Mounted

| Project ID | Code | Customer | Address | PV Location | Tech. | Date Energized | Facility Nameplate (kW) | Panel Qty | | | | | | |
|------------|----------|----------------------------|---|--|----------|------------------|-------------------------|---------------|-----------|-----------|--------------|--------------|--|--|
| 4 | TBR | The Towers at Bressi Ranch | 6156 Innovation Way, Carlsbad, CA | Roof | PV | 2/28/2008 | 80.40 | 480 | | | | | | |
| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Crew Rate | Labor Cost | Total Cost | | |
| Roof top | 11.00.00 | | Demolition | | | | | | | | | | | |
| | 11.22.00 | | Concrete | Electrical equipment (Transformer, inverter, etc.) pad | 7 /CY | | | | 16 /MH | \$ 140.47 | \$ 2,248 | \$ 2,248 | | |
| | 11.41.00 | | Electrical Equipment | | | | | | | | | | | |
| | | | Disconnect wiring and components at service rack | | 1 EA | | | | 17 /MH | \$ 127.80 | \$ 2,173 | \$ 2,173 | | |
| | | | Disconnect wiring at inverter | | 1 EA | | | | 4 /MH | \$ 127.80 | \$ 511 | \$ 511 | | |
| | | | Disconnect wiring at combiner boxes, remove boxes | | 3 EA | | | | 38 /MH | \$ 127.80 | \$ 4,856 | \$ 4,856 | | |
| | | | Pull wire from combiners to inverter | | 3 EA | | | | 28 /MH | \$ 127.80 | \$ 3,578 | \$ 3,578 | | |
| | | | Disconnect and remove wiring at PV panels | | 480 EA | | | | 72 /MH | \$ 127.80 | \$ 9,202 | \$ 9,202 | | |
| | | | Disconnect and remove grounding at PV panels and racks, | | | | | | | | | | | |
| | | | Remove ground rods | | 480 EA | | | | 19 /MH | \$ 127.80 | \$ 2,428 | \$ 2,428 | | |
| | | | Demo conduit from rack to tie point | | 1 EA | | | | 17 /MH | \$ 127.80 | \$ 2,173 | \$ 2,173 | | |
| | | | Demo conduit from rack to transformer | | 1 EA | | | | 13 /MH | \$ 127.80 | \$ 1,661 | \$ 1,661 | | |
| | | | Demo conduit from combiners to inverter | | 1 EA | | | | 69 /MH | \$ 127.80 | \$ 8,818 | \$ 8,818 | | |
| | | | Remove Conduits to inverters | | 1 EA | | | | 4 /MH | \$ 127.80 | \$ 511 | \$ 511 | | |
| | | | Remove inverters | | 1 EA | | | | 6 /MH | \$ 127.80 | \$ 767 | \$ 767 | | |
| | | | Remove PV panel and place in dumpster | | 480 EA | | | | 240 /MH | \$ 127.80 | \$ 30,672 | \$ 30,672 | | |
| | | | Remove points where panel is fixed to roof | | 480 EA | | | | 107 /MH | \$ 127.80 | \$ 13,675 | \$ 13,675 | | |
| | | | Remove lightning projection and other auxiliary equipment | | 1 EA | | | | 45 /MH | \$ 127.80 | \$ 5,751 | \$ 5,751 | | |
| | | | Remove transformer | | 1 LT | | | | 17 /MH | \$ 127.80 | \$ 2,173 | \$ 2,173 | | |
| | | | Demolition | | | \$ - | \$ - | \$ - | | | \$ 91,196 | \$ 91,196 | | |
| | 18.00.00 | | Scrap Value | | | | | | | | | | | |
| | 18.10.00 | | Mixed Steel | | | | | | | | | | | |
| | | | Steel | 1 EA, inverter 402 kW | 0.34 TN | \$ (60) | | | /MH | | \$ (60) | \$ (60) | | |
| | | | Steel | Service rack components | 0.13 TN | \$ (23) | | | /MH | | \$ (23) | \$ (23) | | |
| | | | Steel | Conduit and fittings | 0.13 TN | \$ (23) | | | /MH | | \$ (23) | \$ (23) | | |
| | | | Steel | Transformers | 3.91 TN | \$ (684) | | | /MH | | \$ (684) | \$ (684) | | |
| | | | Steel | Roof ladder, 1@ 350 lb each | 0.05 TN | \$ (9) | | | /MH | | \$ (9) | \$ (9) | | |
| | 18.20.00 | | Stainless Steel | | | | | | | | | | | |
| | | | Stainless Steel | 1788 Racks, 13.61 lbs each | 3.27 TN | \$ (3,832) | | | /MH | | \$ (3,832) | \$ (3,832) | | |
| | 18.30.00 | | Copper | | | | | | | | | | | |
| | | | Copper | 1 EA, 402 kW inverter | 0.11 TN | \$ (268) | | | /MH | | \$ (268) | \$ (268) | | |
| | | | Copper | Wire | 0.73 TN | \$ (1,781) | | | /MH | | \$ (1,781) | \$ (1,781) | | |
| | | | Copper | Transformers | 1.86 TN | \$ (4,538) | | | /MH | | \$ (4,538) | \$ (4,538) | | |
| | 18.50.00 | | Aluminum | | | | | | | | | | | |
| | | | PV Module | 1788 Modules @ 8 lbs each | 3840 LB | \$ (2,337) | | | /MH | | \$ (2,337) | \$ (2,337) | | |
| | | | Conduit and fittings | 100 @ 1 lb each | 26.85 LB | \$ (16) | | | /MH | | \$ (16) | \$ (16) | | |
| | | | Scrap Value | | | \$ - | \$ (13,571) | \$ - | | | \$ - | \$ (13,571) | | |
| | 21.00.00 | | Civil Work | | | | | | | | | | | |
| | 21.19.00 | | Disposal | | | | | | | | | | | |
| | | | Dumpster, 40 CY Capacity | Concrete, PV panels, rubbish (panels to recycler) | 3 EA | \$ 5,400 | | | /MH | | \$ 5,400 | \$ 5,400 | | |
| | | | Dumpster, 40 CY Capacity | Fix point rods | 1 EA | \$ 900 | | | /MH | | \$ 900 | \$ 900 | | |
| | 21.20.00 | | Backfill | | | | | | | | | | | |
| | | | Foundation backfill, imported material fill | Backfill concrete pads | 7 /CY | \$ 280 | | | /MH | | \$ 280 | \$ 280 | | |
| | | | Civil Work | | | \$ 6,580 | \$ - | \$ - | | | \$ - | \$ 6,580 | | |
| | 24.00.00 | | Architectural | | | | | | | | | | | |
| | 24.37.00 | | Roofing | | | | | | | | | | | |
| | | | Roof repair at fix points | Installation | 480 EA | \$ 79,200 | | | /MH | | \$ - | \$ 79,200 | | |
| | | | Architectural | | | \$ 79,200 | \$ - | \$ - | | | \$ - | \$ 79,200 | | |
| | | | Direct Costs | | | | | | | | | \$ 163,405 | | |
| | 61.00.00 | | Construction Indirect | | | | | | | | | | | |
| | 61.99.00 | | Miscellaneous | | | | | | | | | | | |
| | | | Downspout / Chute | | 1 LS | \$ 25,000 | | | /MH | | \$ 25,000 | \$ 25,000 | | |
| | | | Construction Indirect | | | \$ 25,000 | \$ - | \$ - | | | \$ - | \$ 25,000 | | |
| | | | Subtotal | | | \$ 110,780 | \$ (13,571) | \$ - | | | \$ 91,196 | \$ 188,405 | | |
| | 91.00.00 | | Other Direct & Construction Indirect Costs | | | | | | | | | | | |
| | | | 91.09 Contractor's General and Administration Expense | | | | | | | | | \$ 13,188 | | |
| | | | 91.10 Contractor's Profit | | | | | | | | | \$ 18,840 | | |
| | | | | | | | | | | | | \$ 32,029 | | |
| | | | Direct Costs + Construction Indirect Costs | | | \$ 110,780 | \$ (13,571) | \$ - | | | \$ 91,196 | \$ 220,434 | | |
| | 93.00.00 | | Indirect Costs | | | | | | | | | | | |
| | | | 93.1 Engineering, Procurement, & Project Services | | | | | | | | | \$ 13,226 | | |
| | | | 93.2 Construction Management Support | | | | | | | | | \$ 4,409 | | |
| | | | 93.3 SDG&E Internal Costs | | | | | | | | | \$ 22,043 | | |
| | 95.00.00 | | Contingency | | | | | | | | | | | |
| | | | 95.1 Contingency on Subcontractor | | | \$ 16,617 | | | | | | \$ 16,617.00 | | |
| | | | 95.2 Contingency on Scrap Value | | | \$ - | | | | | | \$ - | | |
| | | | 95.3 Contingency on Material | | | \$ - | | | | | | \$ - | | |
| | | | 95.4 Contingency on Labor | | | | | | | | \$ 13,679.45 | \$ 13,679 | | |
| | | | 95.5 Contingency on Indirect | | | | | | | | | \$ 5,952 | | |
| | | | Total | | | \$ 127,397 | \$ (13,571) | \$ - | | | \$ 104,876 | \$ 296,360 | | |

San Diego Gas & Electric
Decommissioning Cost Estimates
PV Sites - Roof Mounted

| Project ID | Code | Customer | Address | PV Location | Tech. | Date Energized | Facility Nameplate (kW) | Panel Qty | | | | |
|------------|----------|--------------------|--|--|--|------------------|-------------------------|---------------|--|--|---|---|
| S | DSE | Del Sur Elementary | 15665 Paseo Del Sur, San Diego | Roof | PV | 9/5/2008 | 42.40 | 240 | | | | |
| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Crew Rate | Labor Cost | Total Cost |
| Roof top | 11.00.00 | 11.22.00 | Demolition Concrete | Electrical equipment (Transformer, inverter, etc.) pad | 7 /CY | | | | 8 /MH | \$ 140.47 | \$ 1,124 | \$ 1,124 |
| | 11.41.00 | | Electrical Equipment Disconnect wiring and components at service rack Disconnect wiring at inverter Disconnect wiring at combiner boxes, remove boxes Pull wire from combiners to inverter Disconnect and remove wiring at PV panels Disconnect and remove grounding at PV panels and racks, Remove ground rods Demo conduit from rack to tie point Demo conduit from rack to transformer Demo conduit from combiners to inverter Remove Conduits to inverters Remove inverters Remove PV panel and place in dumpster Remove points where panel is fixed to roof Remove lightning projection and other auxiliary equipment Remove transformer | | 1 EA 1 EA 2 EA 2 EA 240 EA 240 EA 1 EA 1 EA 1 EA 1 EA 1 EA 240 EA 240 EA 1 EA 1 LT | | | | 9 /MH 2 /MH 19 /MH 14 /MH 36 /MH 10 /MH 9 /MH 6 /MH 34 /MH 2 /MH 3 /MH 120 /MH 54 /MH 23 /MH 9 /MH | \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 | \$ 1,150 \$ 256 \$ 2,428 \$ 1,789 \$ 4,601 \$ 1,278 \$ 1,150 \$ 767 \$ 4,345 \$ 256 \$ 383 \$ 15,336 \$ 6,901 \$ 2,939 \$ 1,150 | \$ 1,150 \$ 256 \$ 2,428 \$ 1,789 \$ 4,601 \$ 1,278 \$ 1,150 \$ 767 \$ 4,345 \$ 256 \$ 383 \$ 15,336 \$ 6,901 \$ 2,939 \$ 1,150 |
| | 18.00.00 | | Scrap Value Mixed Steel | | | | | | | | | |
| | 18.10.00 | | Steel | 1 EA, inverter 402 kW | 0.17 TN | \$ (30) | | | /MH | | \$ (30) | \$ (30) |
| | | | Steel | Service rack components | 0.06 TN | \$ (11) | | | /MH | | \$ (11) | \$ (11) |
| | | | Steel | Conduit and fittings | 0.07 TN | \$ (12) | | | /MH | | \$ (12) | \$ (12) |
| | | | Steel | Transformers | 1.96 TN | \$ (343) | | | /MH | | \$ (343) | \$ (343) |
| | | | Steel | Roof ladder, 1@ 350 lb each | 0.02 TN | \$ (4) | | | /MH | | \$ (4) | \$ (4) |
| | 18.20.00 | | Stainless Steel | 1788 Racks, 13.61 lbs each | 1.63 TN | \$ (1,910) | | | /MH | | \$ (1,910) | \$ (1,910) |
| | 18.30.00 | | Copper | 1 EA, 402 kW inverter | 0.05 TN | \$ (122) | | | /MH | | \$ (122) | \$ (122) |
| | | | Copper | Wire | 0.37 TN | \$ (903) | | | /MH | | \$ (903) | \$ (903) |
| | | | Copper | Transformers | 0.93 TN | \$ (2,269) | | | /MH | | \$ (2,269) | \$ (2,269) |
| | 18.50.00 | | Aluminum | 1788 Modules @ 8 lbs each | 1920 LB | \$ (1,168) | | | /MH | | \$ (1,168) | \$ (1,168) |
| | | | PV Module | Conduit and fittings | 100 @ 1 lb each | \$ (8) | | | /MH | | \$ (8) | \$ (8) |
| | | | Scrap Value | | | \$ (6,780) | \$ - | | | | \$ - | \$ (6,780) |
| | 21.00.00 | | Civil Work Disposal | | | | | | | | | |
| | 21.19.00 | | Dumpster, 40 CY Capacity | Concrete, PV panels, rubbish (panels to recycler) | 1 EA | \$ 1,800 | | | /MH | | \$ 1,800 | \$ 1,800 |
| | | | Dumpster, 40 CY Capacity | Fix point rods | 1 EA | \$ 900 | | | /MH | | \$ 900 | \$ 900 |
| | 21.20.00 | | Backfill | Foundation backfill, imported material fill | 7 /CY | \$ 280 | | | /MH | | \$ 280 | \$ 280 |
| | | | Civil Work | Backfill concrete pads | | \$ 2,980 | \$ - | \$ - | | | \$ - | \$ 2,980 |
| | 24.00.00 | | Architectural Roofing | | | | | | | | | |
| | 24.37.00 | | Roof repair at fix points | Installation | 240 EA | \$ 39,600 | | | /MH | | \$ - | \$ 39,600 |
| | | | Architectural | | | \$ 39,600 | \$ - | \$ - | | | \$ - | \$ 39,600 |
| | | | Direct Costs | | | | | | | | | \$ 81,654 |
| | 61.00.00 | | Construction Indirect Miscellaneous | | | | | | | | | |
| | 61.99.00 | | Downspout / Chute | | 1 LS | \$ 25,000 | | | /MH | | \$ 25,000 | \$ 25,000 |
| | | | Construction Indirect | | | \$ 25,000 | \$ - | \$ - | | | \$ - | \$ 25,000 |
| | | | Subtotal | | | \$ 67,580 | \$ (6,780) | \$ - | | | \$ 45,854 | \$ 106,654 |
| | 91.00.00 | | Other Direct & Construction Indirect Costs | | | | | | | | | |
| | 91.09 | | Contractor's General and Administration Expense | | | | | | | | | \$ 7,466 |
| | 91.10 | | Contractor's Profit | | | | | | | | | \$ 10,655 |
| | | | | | | | | | | | | \$ 18,131 |
| | | | Direct Costs + Construction Indirect Costs | | | \$ 67,580 | \$ (6,780) | \$ - | | | \$ 45,854 | \$ 124,785 |
| | 93.00.00 | | Indirect Costs | | | | | | | | | |
| | 93.1 | | Engineering, Procurement, & Project Services | | | | | | | | | \$ 7,487 |
| | 93.2 | | Construction Management Support | | | | | | | | | \$ 2,496 |
| | 93.3 | | SDG&E Internal Costs | | | | | | | | | \$ 12,479 |
| | 95.00.00 | | Contingency | | | | | | | | | |
| | 95.1 | | Contingency on Subcontractor | | | \$ 10,137 | | | | | | \$ 10,137.00 |
| | 95.2 | | Contingency on Scrap Value | | | \$ - | | | | | | \$ - |
| | 95.3 | | Contingency on Material | | | | \$ - | | | | | \$ - |
| | 95.4 | | Contingency on Labor | | | | | | | | \$ 6,878 | \$ 6,878 |
| | 95.5 | | Contingency on Indirect | | | | | | | | | \$ 3,369 |
| | | | Total | | | \$ 77,717 | \$ (6,780) | \$ - | | | \$ 52,732 | \$ 167,631 |

San Diego Gas & Electric
Decommissioning Cost Estimates
PV Sites - Roof Mounted

| Project ID | Code | Customer | Address | PV Location | Tech. | Date Energized | Facility Nameplate (kW) | Panel Qty | | | | | |
|------------|----------|------------------|--|---|--|---|-------------------------|---------------|---|--|---|---|--|
| 6 | LRF | Ladera Ranch 555 | 555 Corporate Drive, Ladera Ranch | Roof | PV | 9/17/2008 | 49.20 | 315 | | | | | |
| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Crew Rate | Labor Cost | Total Cost | |
| Roof top | 11.00.00 | 11.22.00 | Demolition Concrete | Electrical equipment (Transformer, inverter, etc.) pad | 7 /CY | | | | 11 /MH | \$ 140.47 | \$ 1,545 | \$ 1,545 | |
| | 11.41.00 | | Electrical Equipment Disconnect wiring and components at service rack Disconnect wiring at inverter Disconnect wiring at combiner boxes, remove boxes Pull wire from combiners to inverter Disconnect and remove wiring at PV panels Disconnect and remove grounding at PV panels and racks, Remove ground rods Demo conduit from rack to tie point Demo conduit from rack to transformer Demo conduit from combiners to inverter Remove Conduits to inverters Remove inverters Remove PV panel and place in dumpster Remove points where panel is fixed to roof Remove lightning projection and other auxiliary equipment Remove transformer | | 1 EA 1 EA 2 EA 2 EA 315 EA 315 EA 1 EA 1 EA 1 EA 1 EA 1 EA 315 EA 315 EA 1 EA 1 LT | | | | 11 /MH 3 /MH 25 /MH 18 /MH 47 /MH 13 /MH 11 /MH 8 /MH 45 /MH 3 /MH 4 /MH 158 /MH 70 /MH 30 /MH 11 /MH | \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 | \$ 1,406 \$ 383 \$ 3,195 \$ 2,300 \$ 6,007 \$ 1,661 \$ 1,406 \$ 1,022 \$ 5,751 \$ 383 \$ 511 \$ 20,192 \$ 8,946 \$ 3,834 \$ 1,406 | \$ 1,406 \$ 383 \$ 3,195 \$ 2,300 \$ 6,007 \$ 1,661 \$ 1,406 \$ 1,022 \$ 5,751 \$ 383 \$ 511 \$ 20,192 \$ 8,946 \$ 3,834 \$ 1,406 | |
| | 18.00.00 | | Demolition | | | \$ - | \$ - | \$ - | | | \$ 59,950 | \$ 59,950 | |
| | 18.00.00 | | Scrap Value | | | | | | | | | | |
| | 18.10.00 | | Mixed Steel Steel Steel Steel Steel | 1 EA, inverter 402 kW Service rack components Conduit and fittings Transformers Roof ladder, 1@ 350 lb each | 0.22 TN 0.08 TN 0.09 TN 2.57 TN 0.03 TN | \$ (39) \$ (14) \$ (16) \$ (450) \$ (5) | | | /MH /MH /MH /MH /MH | | \$ (39) \$ (14) \$ (16) \$ (450) \$ (5) | | |
| | 18.20.00 | | Stainless Steel Stainless Steel | 1788 Racks, 13.61 lbs each | 2.14 TN | \$ (2,508) | | | /MH | | \$ (2,508) | | |
| | 18.30.00 | | Copper Copper Copper Copper | 1 EA, 402 kW inverter Wire Transformers | 0.07 TN 0.48 TN 1.22 TN | \$ (171) \$ (1,171) \$ (2,977) | | | /MH /MH /MH | | \$ (171) \$ (1,171) \$ (2,977) | | |
| | 18.50.00 | | Aluminum PV Module Conduit and fittings Scrap Value | 1788 Modules @ 8 lbs each 100 @ 1 lb each | 2520 LB 17.62 LB | \$ (1,533) \$ (11) | | | /MH /MH | | \$ (1,533) \$ (11) | \$ (8,894) | |
| | 21.00.00 | | Civil Work | | | | | | | | | | |
| | 21.19.00 | | Disposal Dumpster, 40 CY Capacity Dumpster, 40 CY Capacity | Concrete, PV panels, rubbish (panels to recycler) Fix point rods | 2 EA 1 EA | \$ 3,600 \$ 900 | | | /MH /MH | | \$ 3,600 \$ 900 | | |
| | 21.20.00 | | Backfill Foundation backfill, imported material fill Civil Work | Backfill concrete pads | 7 /CY | \$ 280 \$ 4,780 | | | /MH | | \$ 280 \$ 4,780 | | |
| | 24.00.00 | | Architectural | | | | | | | | | | |
| | 24.37.00 | | Roofing Roof repair at fix points Architectural | Installation | 315 EA | \$ 51,975 | | | /MH | | \$ 51,975 | \$ 51,975 | |
| | | | Direct Costs | | | | | | | | | \$ 107,810 | |
| | 61.00.00 | | Construction Indirect | | | | | | | | | | |
| | 61.99.00 | | Miscellaneous Downspout / Chute Construction Indirect | | 1 LS | \$ 25,000 | | | /MH | | \$ 25,000 | \$ 25,000 | |
| | | | Subtotal | | | \$ 81,755 | \$ (8,894) | \$ - | | | \$ 59,950 | \$ 132,810 | |
| | 91.00.00 | | Other Direct & Construction Indirect Costs 91.09 Contractor's General and Administration Expense 91.10 Contractor's Profit | | | | | | | | | \$ 9,297 \$ 13,281 \$ 22,578 | |
| | | | Direct Costs + Construction Indirect Costs | | | \$ 81,755 | \$ (8,894) | \$ - | | | \$ 59,950 | \$ 155,388 | |
| | 93.00.00 | | Indirect Costs 93.1 Engineering, Procurement, & Project Services 93.2 Construction Management Support 93.3 SDG&E Internal Costs | | | | | | | | | \$ 9,323.30 \$ 3,107.77 \$ 15,539 | |
| | 95.00.00 | | Contingency 95.1 Contingency on Subcontractor 95.2 Contingency on Scrap Value 95.3 Contingency on Material 95.4 Contingency on Labor 95.5 Contingency on Indirect | | | \$ 12,263 | \$ - | \$ - | | | \$ 8,992 | \$ 12,263.25 \$ - \$ - \$ 8,992 \$ 4,195 | |
| | | | Total | | | \$ 94,018 | \$ (8,894) | \$ - | | | \$ 68,942 | \$ 208,809 | |

San Diego Gas & Electric
Decommissioning Cost Estimates
PV Sites - Roof Mounted

| Project ID | Code | Customer | Address | PV Location | Tech. | Date Energized | Facility Nameplate (kW) | Panel Qty | | | | |
|--|----------|----------------------------|--|--|----------|------------------|-------------------------|---------------|---|--|--|--|
| 7 | HTC | High Tech High Chula Vista | 1945 Discovery Falls Drive, Chula Vista | Roof | PV | 2/9/2009 | 101 | 640 | | | | |
| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Crew Rate | Labor Cost | Total Cost |
| Roof top | 11.00.00 | 11.22.00 | Demolition Concrete | Electrical equipment (Transformer, inverter, etc.) pad | 7 /CY | | | | 21 /MH | \$ 140.47 | \$ 2,950 | \$ 2,950 |
| | 11.41.00 | | Electrical Equipment Disconnect wiring and components at service rack Disconnect wiring at inverter Disconnect wiring at combiner boxes, remove boxes Pull wire from combiners to inverter Disconnect and remove wiring at PV panels Disconnect and remove grounding at PV panels and racks, Remove ground rods Demo conduit from rack to tie point Demo conduit from rack to transformer Demo conduit from combiners to inverter Remove Conduits to inverters Remove inverters Remove PV panel and place in dumpster Remove points where panel is fixed to roof Remove lightning projection and other auxiliary equipment Remove transformer | 1 EA 1 EA 5 EA 5 EA 640 EA 640 EA 1 EA 1 EA 1 EA 1 EA 1 EA 640 EA 640 EA 1 EA 1 EA | | | | | 23 /MH 6 /MH 51 /MH 37 /MH 96 /MH 26 /MH 23 /MH 17 /MH 92 /MH 6 /MH 9 /MH 320 /MH 143 /MH 60 /MH 23 /MH | \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 | \$ 2,939 \$ 767 \$ 6,518 \$ 4,729 \$ 12,269 \$ 3,323 \$ 2,939 \$ 2,173 \$ 11,758 \$ 767 \$ 1,150 \$ 40,896 \$ 18,275 \$ 7,668 \$ 2,939 | \$ 2,939 \$ 767 \$ 6,518 \$ 4,729 \$ 12,269 \$ 3,323 \$ 2,939 \$ 2,173 \$ 11,758 \$ 767 \$ 1,150 \$ 40,896 \$ 18,275 \$ 7,668 \$ 2,939 |
| | 18.00.00 | 18.10.00 | Scrap Value Mixed Steel | 1 EA, inverter 402 kW | 0.45 TN | | \$ (79) | | /MH | | | \$ (79) |
| | | | Steel | Service rack components | 0.17 TN | | \$ (30) | | /MH | | | \$ (30) |
| | | | Steel | Conduit and fittings | 0.18 TN | | \$ (32) | | /MH | | | \$ (32) |
| | | | Steel | Transformers | 5.22 TN | | \$ (914) | | /MH | | | \$ (914) |
| | | | Steel | Roof ladder, 1@ 350 lb each | 0.06 TN | | \$ (11) | | /MH | | | \$ (11) |
| | 18.20.00 | | Stainless Steel | 1788 Racks, 13.61 lbs each | 4.36 TN | | \$ (5,110) | | /MH | | | \$ (5,110) |
| | 18.30.00 | | Copper | 1 EA, 402 kW inverter | 0.14 TN | | \$ (342) | | /MH | | | \$ (342) |
| | | | Copper | Wire | 0.97 TN | | \$ (2,367) | | /MH | | | \$ (2,367) |
| | | | Copper | Transformers | 2.48 TN | | \$ (6,051) | | /MH | | | \$ (6,051) |
| | 18.50.00 | | Aluminum | 1788 Modules @ 8 lbs each | 5120 LB | | \$ (3,116) | | /MH | | | \$ (3,116) |
| | | | Conduit and fittings | 100 @ 1 lb each | 35.79 LB | | \$ (22) | | /MH | | | \$ (22) |
| | | | Scrap Value | | | \$ - | \$ (18,071) | \$ - | | | \$ - | \$ (18,071) |
| | 21.00.00 | 21.19.00 | Civil Work Disposal | Concrete, PV panels, rubbish (panels to recycler) | 4 EA | \$ 7,200 | | | /MH | | | \$ 7,200 |
| | | | Disposal | Fix point rods | 1 EA | \$ 900 | | | /MH | | | \$ 900 |
| | 21.20.00 | | Backfill | Foundation backfill, imported material fill | 7 /CY | \$ 280 | | | /MH | | | \$ 280 |
| | | | Civil Work | Backfill concrete pads | | \$ 8,380 | \$ - | \$ - | | | \$ - | \$ 8,380 |
| | 24.00.00 | 24.37.00 | Architectural Roofing | Roof repair at fix points | 640 EA | \$ 105,600 | | | /MH | | | \$ 105,600 |
| | | | Architectural | Installation | | \$ 105,600 | \$ - | \$ - | | | \$ - | \$ 105,600 |
| Direct Costs | | | | | | | | | | | | \$ 217,969 |
| | 61.00.00 | 61.99.00 | Construction Indirect Miscellaneous | Downspout / Chute | 1 LS | \$ 25,000 | | | /MH | | | \$ 25,000 |
| | | | Construction Indirect | | | \$ 25,000 | \$ - | \$ - | | | \$ - | \$ 25,000 |
| Subtotal | | | | | | \$ 138,980 | \$ (18,071) | \$ - | | | \$ 122,059 | \$ 242,969 |
| | 91.00.00 | | Other Direct & Construction Indirect Costs | | | | | | | | | |
| | | 91.09 | Contractor's General and Administration Expense | | | | | | | | | \$ 17,008 |
| | | 91.10 | Contractor's Profit | | | | | | | | | \$ 24,297 |
| | | | | | | | | | | | | \$ 41,305 |
| Direct Costs + Construction Indirect Costs | | | | | | \$ 138,980 | \$ (18,071) | \$ - | | | \$ 122,059 | \$ 284,273 |
| | 93.00.00 | | Indirect Costs | | | | | | | | | |
| | | 93.1 | Engineering, Procurement, & Project Services | | | | | | | | | \$ 17,056.40 |
| | | 93.2 | Construction Management Support | | | | | | | | | \$ 5,685.47 |
| | | 93.3 | SDG&E Internal Costs | | | | | | | | | \$ 28,427 |
| | 95.00.00 | | Contingency | | | | | | | | | |
| | | 95.1 | Contingency on Subcontractor | | | \$ 20,847.00 | | | | | | \$ 20,847.00 |
| | | 95.2 | Contingency on Scrap Value | | | \$ - | | | | | | \$ - |
| | | 95.3 | Contingency on Material | | | | \$ - | | | | | \$ - |
| | | 95.4 | Contingency on Labor | | | | | | | \$ 18,308.92 | | \$ 18,309 |
| | | 95.5 | Contingency on Indirect | | | | | | | | | \$ 7,675 |
| Total | | | | | | \$ 159,827 | \$ (18,071) | \$ - | | | \$ 140,368 | \$ 382,274 |

San Diego Gas & Electric
Decommissioning Cost Estimates
PV Sites - Roof Mounted

| Project ID | Code | Customer | Address | PV Location | Tech. | Date Energized | Facility Nameplate (kW) | Panel Qty | | | | | | |
|------------|----------|---------------------|--|---|--|--------------------|---|---------------|---|--|--|--|-----------|-----------|
| 8 | HGW | Hanna Gabriel Wells | 1955 Bacon St. San Diego | Roof | PV | 3/12/2009 | 16.30 | 84 | | | | | | |
| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Crew Rate | Labor Cost | Total Cost | | |
| Roof top | 11.00.00 | 11.22.00 | Demolition Concrete | Electrical equipment (Transformer, inverter, etc.) pad | 7 /CY | | | | 3 /MH | \$ 140.47 | \$ 421 | \$ 421 | | |
| | 11.41.00 | | Electrical Equipment Disconnect wiring and components at service rack Disconnect wiring at inverter Disconnect wiring at combiner boxes, remove boxes Pull wire from combiners to inverter Disconnect and remove wiring at PV panels Disconnect and remove grounding at PV panels and racks, Remove ground rods Demo conduit from rack to tie point Demo conduit from rack to transformer Demo conduit from combiners to inverter Remove Conduits to inverters Remove inverters Remove PV panel and place in dumpster Remove points where panel is fixed to roof Remove lightning projection and other auxiliary equipment Remove transformer | | 1 EA 1 EA 1 EA 1 EA 84 EA 84 EA 1 EA 1 EA 1 EA 1 EA 1 EA 84 EA 84 EA 1 EA 1 LT | | | | 3 /MH 1 /MH 7 /MH 5 /MH 13 /MH 3 /MH 3 /MH 2 /MH 12 /MH 1 /MH 1 /MH 42 /MH 19 /MH 8 /MH 3 /MH | \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 | \$ 383 \$ 128 \$ 895 \$ 639 \$ 1,661 \$ 383 \$ 383 \$ 256 \$ 1,534 \$ 128 \$ 128 \$ 5,368 \$ 2,428 \$ 1,022 \$ 383 | \$ 383 \$ 128 \$ 895 \$ 639 \$ 1,661 \$ 383 \$ 383 \$ 256 \$ 1,534 \$ 128 \$ 128 \$ 5,368 \$ 2,428 \$ 1,022 \$ 383 | \$ 16,141 | \$ 16,141 |
| | 18.00.00 | | Scrap Value Mixed Steel | | | | | | | | | | | |
| | 18.10.00 | | Steel Steel Steel Steel Steel | 1 EA, inverter 402 kW Service rack components Conduit and fittings Transformers Roof ladder, 1@ 350 lb each | 0.06 TN 0.02 TN 0.02 TN 0.68 TN 0.01 TN | | \$ (11) \$ (4) \$ (4) \$ (119) \$ (2) | | /MH /MH /MH /MH /MH | | | \$ (11) \$ (4) \$ (4) \$ (119) \$ (2) | | |
| | 18.20.00 | | Stainless Steel Stainless Steel | 1788 Racks, 13.61 lbs each | 0.57 TN | | \$ (668) | | /MH | | | \$ (668) | | |
| | 18.30.00 | | Copper Copper Copper | 1 EA, 402 kW inverter Wire Transformers | 0.02 TN 0.13 TN 0.33 TN | | \$ (49) \$ (317) \$ (805) | | /MH /MH /MH | | | \$ (49) \$ (317) \$ (805) | | |
| | 18.50.00 | | Aluminum PV Module Conduit and fittings Scrap Value | 1788 Modules @ 8 lbs each 100 @ 1 lb each | 672 LB 4.7 LB | | \$ (409) \$ (3) | | /MH /MH | | | \$ (409) \$ (3) \$ (2,389) | | |
| | 21.00.00 | | Civil Work Disposal | | | | | | | | | | | |
| | 21.19.00 | | Dumpster, 40 CY Capacity Dumpster, 40 CY Capacity | Concrete, PV panels, rubbish (panels to recycler) Fix point rods | 1 EA 1 EA | \$ 1,800 \$ 900 | | | /MH /MH | | | \$ 1,800 \$ 900 | | |
| | 21.20.00 | | Backfill Foundation backfill, imported material fill Civil Work | Backfill concrete pads | 7 /CY | \$ 280 | | | /MH | | | \$ 280 | | |
| | 24.00.00 | | Architectural Roofing Roof repair at fix points Architectural | Installation | 84 EA | \$ 13,860 | | | /MH | | | \$ 13,860 | | |
| | | | | | | \$ 13,860 | \$ - | \$ - | | | | \$ 13,860 | | |
| | | | | | | | | | | | | \$ 30,592 | | |
| | 61.00.00 | | Construction Indirect Miscellaneous Downspout / Chute Construction Indirect | | 1 LS | \$ 25,000 | | | /MH | | | \$ 25,000 | | |
| | | | | | | \$ 25,000 | \$ - | \$ - | | | | \$ 25,000 | | |
| | | | | | | \$ 41,840 | \$ (2,389) | \$ - | | | \$ 16,141 | \$ 55,592 | | |
| | 91.00.00 | | Other Direct & Construction Indirect Costs 91.09 Contractor's General and Administration Expense 91.10 Contractor's Profit | | | | | | | | | \$ 3,891 \$ 5,559 | | |
| | | | | | | | | | | | | \$ 9,451 | | |
| | | | | | | \$ 41,840 | \$ (2,389) | \$ - | | | \$ 16,141 | \$ 65,042 | | |
| | 93.00.00 | | Indirect Costs 93.1 Engineering, Procurement, & Project Services 93.2 Construction Management Support 93.3 SDG&E Internal Costs | | | | | | | | | \$ 3,903 \$ 1,301 \$ 6,504 | | |
| | 95.00.00 | | Contingency 95.1 Contingency on Subcontractor 95.2 Contingency on Scrap Value 95.3 Contingency on Material 95.4 Contingency on Labor 95.5 Contingency on Indirect | | | \$ 6,276.00 | \$ - | \$ - | | | \$ 2,421.12 | \$ 6,276 \$ - \$ - \$ 2,421 \$ 1,756 | | |
| | | | | | | \$ 48,116 | \$ (2,389) | \$ - | | | \$ 18,562 | \$ 87,203 | | |

San Diego Gas & Electric
Decommissioning Cost Estimates
PV Sites - Roof Mounted

| Project ID | Code | Customer | Address | PV Location | Tech. | Date Energized | Facility Nameplate (kW) | Panel Qty | | | | |
|--|----------|----------------------------|---|--|----------|------------------|-------------------------|---------------|-----------|-----------|------------|--------------|
| 9 | SDC | San Diego CC Skills Center | 4343 Ocean View Blvd B, San Diego | Roof | PV | 7/8/2009 | 56.90 | 360 | | | | |
| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Crew Rate | Labor Cost | Total Cost |
| Roof top | 11.00.00 | 11.22.00 | Demolition Concrete | Electrical equipment (Transformer, inverter, etc.) pad | 7 /CY | | | | 12 /MH | \$ 140.47 | \$ 1,686 | \$ 1,686 |
| | 11.41.00 | | Electrical Equipment | | | | | | | | | |
| | | | Disconnect wiring and components at service rack | | 1 EA | | | | 13 /MH | \$ 127.80 | \$ 1,661 | \$ 1,661 |
| | | | Disconnect wiring at inverter | | 1 EA | | | | 3 /MH | \$ 127.80 | \$ 383 | \$ 383 |
| | | | Disconnect wiring at combiner boxes, remove boxes | | 3 EA | | | | 29 /MH | \$ 127.80 | \$ 3,706 | \$ 3,706 |
| | | | Pull wire from combiners to inverter | | 3 EA | | | | 21 /MH | \$ 127.80 | \$ 2,684 | \$ 2,684 |
| | | | Disconnect and remove wiring at PV panels | | 360 EA | | | | 54 /MH | \$ 127.80 | \$ 6,901 | \$ 6,901 |
| | | | Disconnect and remove grounding at PV panels and racks, | | | | | | | | | |
| | | | Remove ground rods | | 360 EA | | | | 14 /MH | \$ 127.80 | \$ 1,789 | \$ 1,789 |
| | | | Demo conduit from rack to tie point | | 1 EA | | | | 13 /MH | \$ 127.80 | \$ 1,661 | \$ 1,661 |
| | | | Demo conduit from rack to transformer | | 1 EA | | | | 10 /MH | \$ 127.80 | \$ 1,278 | \$ 1,278 |
| | | | Demo conduit from combiners to inverter | | 1 EA | | | | 52 /MH | \$ 127.80 | \$ 6,646 | \$ 6,646 |
| | | | Remove Conduits to inverters | | 1 EA | | | | 3 /MH | \$ 127.80 | \$ 383 | \$ 383 |
| | | | Remove inverters | | 1 EA | | | | 5 /MH | \$ 127.80 | \$ 639 | \$ 639 |
| | | | Remove PV panel and place in dumpster | | 360 EA | | | | 180 /MH | \$ 127.80 | \$ 23,004 | \$ 23,004 |
| | | | Remove points where panel is fixed to roof | | 360 EA | | | | 81 /MH | \$ 127.80 | \$ 10,352 | \$ 10,352 |
| | | | Remove lightning projection and other auxiliary equipment | | 1 EA | | | | 34 /MH | \$ 127.80 | \$ 4,345 | \$ 4,345 |
| | | | Remove transformer | | 1 LT | | | | 13 /MH | \$ 127.80 | \$ 1,661 | \$ 1,661 |
| | | | Demolition | | | \$ - | \$ - | \$ - | | | \$ 68,781 | \$ 68,781 |
| | 18.00.00 | | Scrap Value | | | | | | | | | |
| | 18.10.00 | | Mixed Steel | | | | | | | | | |
| | | | Steel | 1 EA, inverter 402 kW | 0.25 TN | \$ (44) | | | /MH | | \$ (44) | \$ (44) |
| | | | Steel | Service rack components | 0.09 TN | \$ (16) | | | /MH | | \$ (16) | \$ (16) |
| | | | Steel | Conduit and fittings | 0.1 TN | \$ (18) | | | /MH | | \$ (18) | \$ (18) |
| | | | Steel | Transformers | 2.93 TN | \$ (513) | | | /MH | | \$ (513) | \$ (513) |
| | | | Steel | Roof ladder, 1@ 350 lb each | 0.04 TN | \$ (7) | | | /MH | | \$ (7) | \$ (7) |
| | 18.20.00 | | Stainless Steel | | | | | | | | | |
| | | | Stainless Steel | 1788 Racks, 13.61 lbs each | 2.45 TN | \$ (2,871) | | | /MH | | \$ (2,871) | \$ (2,871) |
| | 18.30.00 | | Copper | | | | | | | | | |
| | | | Copper | 1 EA, 402 kW inverter | 0.08 TN | \$ (195) | | | /MH | | \$ (195) | \$ (195) |
| | | | Copper | Wire | 0.55 TN | \$ (1,342) | | | /MH | | \$ (1,342) | \$ (1,342) |
| | | | Copper | Transformers | 1.39 TN | \$ (3,392) | | | /MH | | \$ (3,392) | \$ (3,392) |
| | 18.50.00 | | Aluminum | | | | | | | | | |
| | | | PV Module | 1788 Modules @ 8 lbs each | 2880 LB | \$ (1,752) | | | /MH | | \$ (1,752) | \$ (1,752) |
| | | | Conduit and fittings | 100 @ 1 lb each | 20.13 LB | \$ (12) | | | /MH | | \$ (12) | \$ (12) |
| | | | Scrap Value | | | \$ - | \$ (10,162) | \$ - | | | \$ - | \$ (10,162) |
| | 21.00.00 | | Civil Work | | | | | | | | | |
| | 21.19.00 | | Disposal | | | | | | | | | |
| | | | Dumpster, 40 CY Capacity | Concrete, PV panels, rubbish (panels to recycler) | 2 EA | \$ 3,600 | | | /MH | | \$ 3,600 | \$ 3,600 |
| | | | Dumpster, 40 CY Capacity | Fix point rods | 1 EA | \$ 900 | | | /MH | | \$ 900 | \$ 900 |
| | 21.20.00 | | Backfill | | | | | | | | | |
| | | | Foundation backfill, imported material fill | Backfill concrete pads | 7 /CY | \$ 280 | | | /MH | | \$ 280 | \$ 280 |
| | | | Civil Work | | | \$ 4,780 | \$ - | \$ - | | | \$ - | \$ 4,780 |
| | 24.00.00 | | Architectural | | | | | | | | | |
| | 24.37.00 | | Roofing | | | | | | | | | |
| | | | Roof repair at fix points | Installation | 360 EA | \$ 59,400 | | | /MH | | \$ - | \$ 59,400 |
| | | | Architectural | | | \$ 59,400 | \$ - | \$ - | | | \$ - | \$ 59,400 |
| Direct Costs | | | | | | | | | | | | \$ 122,799 |
| | 61.00.00 | | Construction Indirect | | | | | | | | | |
| | 61.99.00 | | Miscellaneous | | | | | | | | | |
| | | | Downspout / Chute | | 1 LS | \$ 25,000 | | | /MH | | \$ - | \$ 25,000 |
| | | | Construction Indirect | | | \$ 25,000 | \$ - | \$ - | | | \$ - | \$ 25,000 |
| Subtotal | | | | | | \$ 89,180 | \$ (10,162) | \$ - | | | \$ 68,781 | \$ 147,799 |
| | 91.00.00 | | Other Direct & Construction Indirect Costs | | | | | | | | | |
| | | 91.09 | Contractor's General and Administration Expense | | | | | | | | | \$ 10,346 |
| | | 91.10 | Contractor's Profit | | | | | | | | | \$ 14,780 |
| | | | | | | | | | | | | \$ 25,126 |
| Direct Costs + Construction Indirect Costs | | | | | | \$ 89,180 | \$ (10,162) | \$ - | | | \$ 68,781 | \$ 172,925 |
| | 93.00.00 | | Indirect Costs | | | | | | | | | |
| | | 93.1 | Engineering, Procurement, & Project Services | | | | | | | | | \$ 10,375 |
| | | 93.2 | Construction Management Support | | | | | | | | | \$ 3,458 |
| | | 93.3 | SDG&E Internal Costs | | | | | | | | | \$ 17,292 |
| | 95.00.00 | | Contingency | | | | | | | | | |
| | | 95.1 | Contingency on Subcontractor | | | \$ 13,377 | | | | | | \$ 13,377.00 |
| | | 95.2 | Contingency on Scrap Value | | | \$ - | | | | | | \$ - |
| | | 95.3 | Contingency on Material | | | \$ - | | | | | | \$ - |
| | | 95.4 | Contingency on Labor | | | | | | | \$ 10,317 | | \$ 10,317 |
| | | 95.5 | Contingency on Indirect | | | | | | | | | \$ 4,669 |
| Total | | | | | | \$ 102,557 | \$ (10,162) | \$ - | | | \$ 79,098 | \$ 232,414 |

San Diego Gas & Electric
Decommissioning Cost Estimates
PV Sites - Roof Mounted

| Project ID | Code | Customer | Address | PV Location | Tech. | Date Energized | Facility Nameplate (kW) | Panel Qty | | | | | | |
|------------|----------|--------------------|---|--|----------|------------------|-------------------------|---------------|-----------|-----------|------------|-------------|--|--|
| 10 | GTA | Alterra Apartments | 8717 Fletcher Parkway, La Mesa | Roof | PV | 4/27/2010 | 64.70 | 368 | | | | | | |
| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Crew Rate | Labor Cost | Total Cost | | |
| Roof top | 11.00.00 | 11.22.00 | Demolition | | | | | | | | | | | |
| | | | Concrete | Electrical equipment (Transformer, inverter, etc.) pad | 7 /CY | | | | 12 /MH | \$ 140.47 | \$ 1,686 | \$ 1,686 | | |
| | | | Concrete | | | | | | | | | | | |
| | | | Electrical Equipment | | | | | | | | | | | |
| | | | Disconnect wiring and components at service rack | | 1 EA | | | | 13 /MH | \$ 127.80 | \$ 1,661 | \$ 1,661 | | |
| | | | Disconnect wiring at inverter | | 1 EA | | | | 3 /MH | \$ 127.80 | \$ 383 | \$ 383 | | |
| | | | Disconnect wiring at combiner boxes, remove boxes | | 3 EA | | | | 29 /MH | \$ 127.80 | \$ 3,706 | \$ 3,706 | | |
| | | | Pull wire from combiners to inverter | | 3 EA | | | | 21 /MH | \$ 127.80 | \$ 2,684 | \$ 2,684 | | |
| | | | Disconnect and remove wiring at PV panels | | 368 EA | | | | 55 /MH | \$ 127.80 | \$ 7,029 | \$ 7,029 | | |
| | | | Disconnect and remove grounding at PV panels and racks, | | | | | | | | | | | |
| | | | Remove ground rods | | 368 EA | | | | 15 /MH | \$ 127.80 | \$ 1,917 | \$ 1,917 | | |
| | | | Demo conduit from rack to tie point | | 1 EA | | | | 13 /MH | \$ 127.80 | \$ 1,661 | \$ 1,661 | | |
| | | | Demo conduit from rack to transformer | | 1 EA | | | | 10 /MH | \$ 127.80 | \$ 1,278 | \$ 1,278 | | |
| | | | Demo conduit from combiners to inverter | | 1 EA | | | | 53 /MH | \$ 127.80 | \$ 6,773 | \$ 6,773 | | |
| | | | Remove Conduits to inverters | | 1 EA | | | | 3 /MH | \$ 127.80 | \$ 383 | \$ 383 | | |
| | | | Remove inverters | | 1 EA | | | | 5 /MH | \$ 127.80 | \$ 639 | \$ 639 | | |
| | | | Remove PV panel and place in dumpster | | 368 EA | | | | 184 /MH | \$ 127.80 | \$ 23,515 | \$ 23,515 | | |
| | | | Remove points where panel is fixed to roof | | 368 EA | | | | 82 /MH | \$ 127.80 | \$ 10,480 | \$ 10,480 | | |
| | | | Remove lightning projection and other auxiliary equipment | | 1 EA | | | | 35 /MH | \$ 127.80 | \$ 4,473 | \$ 4,473 | | |
| | | | Remove transformer | | 1 LT | | | | 13 /MH | \$ 127.80 | \$ 1,661 | \$ 1,661 | | |
| | | | Demolition | | | \$ - | \$ - | \$ - | | | \$ 69,931 | \$ 69,931 | | |
| | | | Scrap Value | | | | | | | | | | | |
| | | | Mixed Steel | | | | | | | | | | | |
| | | | Steel | 1 EA, inverter 402 kW | 0.26 TN | \$ (46) | | | /MH | | \$ (46) | \$ (46) | | |
| | | | Steel | Service rack components | 0.1 TN | \$ (18) | | | /MH | | \$ (18) | \$ (18) | | |
| | | | Steel | Conduit and fittings | 0.1 TN | \$ (18) | | | /MH | | \$ (18) | \$ (18) | | |
| | | | Steel | Transformers | 3 TN | \$ (525) | | | /MH | | \$ (525) | \$ (525) | | |
| | | | Steel | Roof ladder, 1@ 350 lb each | 0.04 TN | \$ (7) | | | /MH | | \$ (7) | \$ (7) | | |
| | | | Stainless Steel | | | | | | | | | | | |
| | | | Stainless Steel | 1788 Racks, 13.61 lbs each | 2.5 TN | \$ (2,930) | | | /MH | | \$ (2,930) | \$ (2,930) | | |
| | | | Copper | | | | | | | | | | | |
| | | | Copper | 1 EA, 402 kW inverter | 0.08 TN | \$ (195) | | | /MH | | \$ (195) | \$ (195) | | |
| | | | Copper | Wire | 0.56 TN | \$ (1,366) | | | /MH | | \$ (1,366) | \$ (1,366) | | |
| | | | Copper | Transformers | 1.42 TN | \$ (3,465) | | | /MH | | \$ (3,465) | \$ (3,465) | | |
| | | | Aluminum | | | | | | | | | | | |
| | | | PV Module | 1788 Modules @ 8 lbs each | 2944 LB | \$ (1,791) | | | /MH | | \$ (1,791) | \$ (1,791) | | |
| | | | Conduit and fittings | 100 @ 1 lb each | 20.58 LB | \$ (13) | | | /MH | | \$ (13) | \$ (13) | | |
| | | | Scrap Value | | | \$ - | \$ (10,373) | \$ - | | | \$ - | \$ (10,373) | | |
| | | | Civil Work | | | | | | | | | | | |
| | | | Disposal | | | | | | | | | | | |
| | | | Dumpster, 40 CY Capacity | Concrete, PV panels, rubbish (panels to recycler) | 2 EA | \$ 3,600 | | | /MH | | \$ 3,600 | \$ 3,600 | | |
| | | | Dumpster, 40 CY Capacity | Fix point rods | 1 EA | \$ 900 | | | /MH | | \$ 900 | \$ 900 | | |
| | | | Backfill | | | | | | | | | | | |
| | | | Foundation backfill, imported material fill | Backfill concrete pads | 7 /CY | \$ 280 | | | /MH | | \$ 280 | \$ 280 | | |
| | | | Civil Work | | | \$ 4,780 | \$ - | \$ - | | | \$ - | \$ 4,780 | | |
| | | | Architectural | | | | | | | | | | | |
| | | | Roofing | | | | | | | | | | | |
| | | | Roof repair at fix points | Installation | 368 EA | \$ 60,720 | | | /MH | | \$ - | \$ 60,720 | | |
| | | | Architectural | | | \$ 60,720 | \$ - | \$ - | | | \$ - | \$ 60,720 | | |
| | | | Direct Costs | | | | | | | | | \$ 125,058 | | |
| | | | Construction Indirect | | | | | | | | | | | |
| | | | Miscellaneous | | | | | | | | | | | |
| | | | Downspout / Chute | | 1 LS | \$ 25,000 | | | /MH | | \$ 25,000 | \$ 25,000 | | |
| | | | Construction Indirect | | | \$ 25,000 | \$ - | \$ - | | | \$ - | \$ 25,000 | | |
| | | | Subtotal | | | \$ 90,500 | \$ (10,373) | \$ - | | | \$ 69,931 | \$ 150,058 | | |
| | | | Other Direct & Construction Indirect Costs | | | | | | | | | | | |
| | | | 91.09 Contractor's General and Administration Expense | | | | | | | | | \$ 10,504 | | |
| | | | 91.10 Contractor's Profit | | | | | | | | | \$ 15,006 | | |
| | | | | | | | | | | | | \$ 25,510 | | |
| | | | Direct Costs + Construction Indirect Costs | | | \$ 90,500 | \$ (10,373) | \$ - | | | \$ 69,931 | \$ 175,568 | | |
| | | | Indirect Costs | | | | | | | | | | | |
| | | | 93.1 Engineering, Procurement, & Project Services | | | | | | | | | \$ 10,534 | | |
| | | | 93.2 Construction Management Support | | | | | | | | | \$ 3,511 | | |
| | | | 93.3 SDG&E Internal Costs | | | | | | | | | \$ 17,557 | | |
| | | | Contingency | | | | | | | | | | | |
| | | | 95.1 Contingency on Subcontractor | | | \$ 13,575 | | | | | | \$ 13,575 | | |
| | | | 95.2 Contingency on Scrap Value | | | \$ - | | | | | | \$ - | | |
| | | | 95.3 Contingency on Material | | | \$ - | | \$ - | | | | \$ - | | |
| | | | 95.4 Contingency on Labor | | | | | | | | \$ 10,490 | \$ 10,490 | | |
| | | | 95.5 Contingency on Indirect | | | | | | | | | \$ 4,740 | | |
| | | | Total | | | \$ 104,075 | \$ (10,373) | \$ - | | | \$ 80,420 | \$ 235,975 | | |

San Diego Gas & Electric
Decommissioning Cost Estimates
PV Sites - Roof Mounted

| Project ID | Code | Customer | Address | PV Location | Tech. | Date Energized | Facility Nameplate (kW) | Panel Qty | | | | | | |
|--|----------|--------------------------------|--|---|--|---|-------------------------|---------------|--|--|---|---|------------|-----------|
| 11 | TJL | Thomas Jefferson School of Law | 1155 Island Ave., San Diego | Roof | PV | 1/13/2011 | 49.90 | 247 | | | | | | |
| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Crew Rate | Labor Cost | Total Cost | | |
| Roof top | 11.00.00 | 11.22.00 | Demolition Concrete | Electrical equipment (Transformer, inverter, etc.) pad | 7 /CY | | | | 8 /MH | \$ 140.47 | \$ 1,124 | \$ 1,124 | | |
| | 11.41.00 | | Electrical Equipment Disconnect wiring and components at service rack Disconnect wiring at inverter Disconnect wiring at combiner boxes, remove boxes Pull wire from combiners to inverter Disconnect and remove wiring at PV panels Disconnect and remove grounding at PV panels and racks, Remove ground rods Demo conduit from rack to tie point Demo conduit from rack to transformer Demo conduit from combiners to inverter Remove Conduits to inverters Remove inverters Remove PV panel and place in dumpster Remove points where panel is fixed to roof Remove lightning projection and other auxiliary equipment Remove transformer | | 1 EA 1 EA 2 EA 2 EA 247 EA 247 EA 1 EA 1 EA 1 EA 1 EA 1 EA 247 EA 247 EA 1 EA 1 LT | | | | 9 /MH 2 /MH 20 /MH 14 /MH 37 /MH 10 /MH 9 /MH 7 /MH 35 /MH 2 /MH 3 /MH 124 /MH 55 /MH 23 /MH 9 /MH | \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 | \$ 1,150 \$ 256 \$ 2,556 \$ 1,789 \$ 4,729 \$ 1,278 \$ 1,150 \$ 895 \$ 4,473 \$ 256 \$ 383 \$ 15,847 \$ 7,029 \$ 2,939 \$ 1,150 | \$ 1,150 \$ 256 \$ 2,556 \$ 1,789 \$ 4,729 \$ 1,278 \$ 1,150 \$ 895 \$ 4,473 \$ 256 \$ 383 \$ 15,847 \$ 7,029 \$ 2,939 \$ 1,150 | \$ 47,004 | \$ 47,004 |
| | 18.00.00 | | Scrap Value Mixed Steel | | | | | | | | | | | |
| | 18.10.00 | | Steel Steel Steel Steel Steel | 1 EA, inverter 402 kW Service rack components Conduit and fittings Transformers Roof ladder, 1@ 350 lb each | 0.17 TN 0.06 TN 0.07 TN 2.01 TN 0.02 TN | \$ (30) \$ (11) \$ (12) \$ (352) \$ (4) | | | /MH /MH /MH /MH /MH | | \$ (30) \$ (11) \$ (12) \$ (352) \$ (4) | | | |
| | 18.20.00 | | Stainless Steel Stainless Steel | 1788 Racks, 13.61 lbs each | 1.68 TN | \$ (1,969) | | | /MH | | \$ (1,969) | | | |
| | 18.30.00 | | Copper Copper Copper | 1 EA, 402 kW inverter Wire Transformers | 0.06 TN 0.38 TN 0.96 TN | \$ (146) \$ (927) \$ (2,342) | | | /MH /MH /MH | | \$ (146) \$ (927) \$ (2,342) | | | |
| | 18.50.00 | | Aluminum PV Module Conduit and fittings Scrap Value | 1788 Modules @ 8 lbs each 100 @ 1 lb each | 1976 LB 13.81 LB | \$ (1,202) \$ (8) | | | /MH /MH | | \$ (1,202) \$ (8) | | \$ (7,004) | |
| | 21.00.00 | | Civil Work Disposal | | | | | | | | | | | |
| | 21.19.00 | | Dumpster, 40 CY Capacity Dumpster, 40 CY Capacity | Concrete, PV panels, rubbish (panels to recycler) Fix point rods | 1 EA 1 EA | \$ 1,800 \$ 900 | | | /MH /MH | | \$ 1,800 \$ 900 | | | |
| | 21.20.00 | | Backfill Foundation backfill, imported material fill Civil Work | Backfill concrete pads | 7 /CY | \$ 280 | | | /MH | | \$ 280 | | \$ 2,980 | |
| | 24.00.00 | | Architectural Roofing Roof repair at fix points Architectural | Installation | 247 EA | \$ 40,755 | | | /MH | | \$ - | \$ 40,755 | \$ 40,755 | |
| Direct Costs | | | | | | | | | | | | | \$ 83,735 | |
| | 61.00.00 | | Construction Indirect Miscellaneous Downspout / Chute Construction Indirect | | 1 LS | \$ 25,000 | | | /MH | | \$ 25,000 | | \$ 25,000 | |
| Subtotal | | | | | | \$ 68,735 | \$ (7,004) | \$ - | | | \$ 47,004 | \$ 108,735 | | |
| | 91.00.00 | | Other Direct & Construction Indirect Costs 91.09 Contractor's General and Administration Expense 91.10 Contractor's Profit | | | | | | | | | \$ 7,611 \$ 10,874 | \$ 18,485 | |
| Direct Costs + Construction Indirect Costs | | | | | | \$ 68,735 | \$ (7,004) | \$ - | | | \$ 47,004 | \$ 127,220 | | |
| | 93.00.00 | | Indirect Costs 93.1 Engineering, Procurement, & Project Services 93.2 Construction Management Support 93.3 SDG&E Internal Costs | | | | | | | | | \$ 7,633 \$ 2,544 \$ 12,722 | | |
| | 95.00.00 | | Contingency 95.1 Contingency on Subcontractor 95.2 Contingency on Scrap Value 95.3 Contingency on Material 95.4 Contingency on Labor 95.5 Contingency on Indirect | | | \$ 10,310 | \$ - | \$ - | | | \$ 7,051 | \$ 7,051 \$ 3,435 | | |
| Total | | | | | | \$ 79,045 | \$ (7,004) | \$ - | | | \$ 54,055 | \$ 170,916 | | |

San Diego Gas & Electric
Decommissioning Cost Estimates
PV Sites - Roof Mounted

| Project ID | Code | Customer | Address | PV Location | Tech. | Date Energized | Facility Nameplate (kW) | Panel Qty | | | | |
|---|----------|------------------------------------|--|--|--|---|-------------------------|---------------------------------|---|--|--|--|
| 12 | PSD | Broadway Pier Cruise Ship Terminal | 1000 N Harbor Dr., San Diego | Roof | PV | 12/16/2010 | 30 | 156 | | | | |
| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Crew Rate | Labor Cost | Total Cost |
| Roof top | 11.00.00 | 11.22.00 | Demolition Concrete | Electrical equipment (Transformer, inverter, etc.) pad | 7 /CY | | | | 5 /MH | \$ 140.47 | \$ 702 | \$ 702 |
| | 11.41.00 | | Electrical Equipment Disconnect wiring and components at service rack Disconnect wiring at inverter Disconnect wiring at combiner boxes, remove boxes Pull wire from combiners to inverter Disconnect and remove wiring at PV panels Disconnect and remove grounding at PV panels and racks, Remove ground rods Demo conduit from rack to tie point Demo conduit from rack to transformer Demo conduit from combiners to inverter Remove Conduits to inverters Remove inverters Remove PV panel and place in dumpster Remove points where panel is fixed to roof Remove lightning projection and other auxiliary equipment Remove transformer | | 1 EA 1 EA 1 EA 1 EA 156 EA 156 EA 1 EA 1 EA 1 EA 1 EA 1 EA 156 EA 156 EA 1 EA 1 EA | | | | 6 /MH 1 /MH 12 /MH 9 /MH 23 /MH 6 /MH 6 /MH 4 /MH 22 /MH 1 /MH 2 /MH 78 /MH 35 /MH 15 /MH 6 /MH | \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 | \$ 767 \$ 128 \$ 1,534 \$ 1,150 \$ 2,939 \$ 767 \$ 767 \$ 511 \$ 2,812 \$ 128 \$ 256 \$ 9,968 \$ 4,473 \$ 1,917 \$ 767 | \$ 767 \$ 128 \$ 1,534 \$ 1,150 \$ 2,939 \$ 767 \$ 767 \$ 511 \$ 2,812 \$ 128 \$ 256 \$ 9,968 \$ 4,473 \$ 1,917 \$ 767 |
| | 18.00.00 | | Scrap Value Mixed Steel Steel Steel Steel Steel Stainless Steel Stainless Steel Copper Copper Copper Aluminum PV Module Conduit and fittings Scrap Value | 1 EA, inverter 402 kW Service rack components Conduit and fittings Transformers Roof ladder, 1@ 350 lb each 1788 Racks, 13.61 lbs each 1 EA, 402 kW inverter Wire Transformers 1788 Modules @ 8 lbs each 100 @ 1 lb each | 0.11 TN 0.04 TN 0.04 TN 1.27 TN 0.02 TN 1.06 TN 0.03 TN 0.24 TN 0.6 TN 1248 LB 8.72 LB | \$ (19) \$ (7) \$ (7) \$ (222) \$ (4) | | /MH /MH /MH /MH /MH | | \$ (19) \$ (7) \$ (7) \$ (222) \$ (4) | | |
| | 21.00.00 | 21.19.00 | Civil Work Disposal Dumpster, 40 CY Capacity Dumpster, 40 CY Capacity | Concrete, PV panels, rubbish (panels to recycler) Fix point rods | 1 EA 1 EA | \$ 1,800 \$ 900 | | | /MH /MH | | \$ 1,800 \$ 900 | |
| | | 21.20.00 | Backfill Foundation backfill, imported material fill Civil Work | Backfill concrete pads | 7 /CY | \$ 280 | | | /MH | | \$ 280 | |
| | 24.00.00 | 24.37.00 | Architectural Roofing Roof repair at fix points Architectural | Installation | 156 EA | \$ 25,740 | | | /MH | | \$ 25,740 | |
| | 61.00.00 | 61.99.00 | Construction Indirect Miscellaneous Downspout / Chute Construction Indirect | | 1 LS | \$ 25,000 | | | /MH | | \$ 25,000 | |
| Subtotal | | | | | | \$ 53,720 | \$ (4,389) | \$ - | | | \$ 29,585 | \$ 78,916 |
| | 91.00.00 | | Other Direct & Construction Indirect Costs 91.09 Contractor's General and Administration Expense 91.10 Contractor's Profit | | | | | | | | \$ 5,524 \$ 7,892 | \$ 13,416 |
| Direct Costs + Construction Indirect Costs | | | | | | \$ 53,720 | \$ (4,389) | \$ - | | | \$ 29,585 | \$ 92,332 |
| | 93.00.00 | | Indirect Costs 93.1 Engineering, Procurement, & Project Services 93.2 Construction Management Support 93.3 SDG&E Internal Costs | | | | | | | | \$ 5,540 \$ 1,847 \$ 9,233 | |
| | 95.00.00 | | Contingency 95.1 Contingency on Subcontractor 95.2 Contingency on Scrap Value 95.3 Contingency on Material 95.4 Contingency on Labor 95.5 Contingency on Indirect | | | \$ 8,058.00 | \$ - | \$ - | | | \$ 4,438 | \$ 2,493 |
| Total | | | | | | \$ 61,778 | \$ (4,389) | \$ - | | | \$ 34,023 | \$ 123,941 |

San Diego Gas & Electric
Decommissioning Cost Estimates
PV Sites - Roof Mounted

| Project ID | Code | Customer | Address | PV Location | Tech. | Date Energized | Facility Nameplate (kW) | Panel Qty | | | | | | |
|--|----------|----------|--|---|--|-----------------------|--|---------------|--|--|---|---|--|--|
| 13 | WCO | Wilco | 2633 Progress St, Vista | Roof | PV | 5/27/2010 | 384.30 | 2128 | | | | | | |
| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Crew Rate | Labor Cost | Total Cost | | |
| Roof top | 11.00.00 | 11.22.00 | Demolition Concrete | Electrical equipment (Transformer, inverter, etc.) pad | 7 /CY | | | | 71 /MH | \$ 140.47 | \$ 9,973 | \$ 9,973 | | |
| | 11.41.00 | | Electrical Equipment Disconnect wiring and components at service rack Disconnect wiring at inverter Disconnect wiring at combiner boxes, remove boxes Pull wire from combiners to inverter Disconnect and remove wiring at PV panels Disconnect and remove grounding at PV panels and racks, Remove ground rods Demo conduit from rack to tie point Demo conduit from rack to transformer Demo conduit from combiners to inverter Remove Conduits to inverters Remove inverters Remove PV panel and place in dumpster Remove points where panel is fixed to roof Remove lightning projection and other auxiliary equipment Remove transformer | | 1 EA 1 EA 15 EA 15 EA 2128 EA 2128 EA 1 EA 1 EA 1 EA 1 EA 1 EA 2128 EA 2128 EA 1 EA 1 LT | | | | 76 /MH 19 /MH 170 /MH 124 /MH 319 /MH 86 /MH 76 /MH 57 /MH 305 /MH 19 /MH 29 /MH 1064 /MH 476 /MH 200 /MH 77 /MH | \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 | \$ 9,713 \$ 2,428 \$ 21,726 \$ 15,847 \$ 40,768 \$ 10,991 \$ 9,713 \$ 7,285 \$ 38,979 \$ 2,428 \$ 3,706 \$ 135,979 \$ 60,833 \$ 25,560 \$ 9,841 | \$ 9,713 \$ 2,428 \$ 21,726 \$ 15,847 \$ 40,768 \$ 10,991 \$ 9,713 \$ 7,285 \$ 38,979 \$ 2,428 \$ 3,706 \$ 135,979 \$ 60,833 \$ 25,560 \$ 9,841 | | |
| | 18.00.00 | | Scrap Value Mixed Steel | | | | | | | | | | | |
| | 18.10.00 | | Steel Steel Steel Steel Steel | 1 EA, inverter 402 kW Service rack components Conduit and fittings Transformers Roof ladder, 1@ 350 lb each | 1.49 TN 0.56 TN 0.6 TN 17.34 TN 0.21 TN | | \$ (261) \$ (98) \$ (105) \$ (3,035) \$ (37) | | /MH /MH /MH /MH /MH | | | \$ (261) \$ (98) \$ (105) \$ (3,035) \$ (37) | | |
| | 18.20.00 | | Stainless Steel Stainless Steel | 1788 Racks, 13.61 lbs each | 14.48 TN | | \$ (16,971) | | /MH | | | \$ (16,971) | | |
| | 18.30.00 | | Copper Copper Copper | 1 EA, 402 kW inverter Wire Transformers | 0.48 TN 3.24 TN 8.24 TN | | \$ (1,171) \$ (7,906) \$ (20,106) | | /MH /MH /MH | | | \$ (1,171) \$ (7,906) \$ (20,106) | | |
| | 18.50.00 | | Aluminum PV Module Conduit and fittings Scrap Value | 1788 Modules @ 8 lbs each 100 @ 1 lb each | 17024 LB 119.02 LB | | \$ (10,359) \$ (72) | | /MH /MH | | | \$ (10,359) \$ (72) | | |
| | 21.00.00 | | Civil Work Disposal | | | | | | | | | | | |
| | 21.19.00 | | Dumpster, 40 CY Capacity Dumpster, 40 CY Capacity | Concrete, PV panels, rubbish (panels to recycler) Fix point rods | 12 EA 2 EA | \$ 21,600 \$ 1,800 | | | /MH /MH | | | \$ 21,600 \$ 1,800 | | |
| | 21.20.00 | | Backfill Foundation backfill, imported material fill Civil Work | Backfill concrete pads | 7 /CY | \$ 280 | | | /MH | | | \$ 280 | | |
| | 24.00.00 | | Architectural Roofing Roof repair at fix points Architectural | Installation | 2128 EA | \$ 351,120 | | | /MH | | | \$ 351,120 | | |
| Direct Costs | | | | | | \$ 399,800 | \$ (60,119) | \$ - | | | \$ 405,770 | \$ 745,450 | | |
| 61.00.00 | 61.99.00 | | Construction Indirect Miscellaneous Downspout / Chute Construction Indirect | | 1 LS | \$ 25,000 | | | /MH | | | \$ 25,000 | | |
| Subtotal | | | | | | \$ 399,800 | \$ (60,119) | \$ - | | | \$ 405,770 | \$ 745,450 | | |
| 91.00.00 | | | Other Direct & Construction Indirect Costs 91.09 Contractor's General and Administration Expense 91.10 Contractor's Profit | | | | | | | | | \$ 52,182 \$ 74,545 | | |
| Direct Costs + Construction Indirect Costs | | | | | | \$ 399,800 | \$ (60,119) | \$ - | | | \$ 405,770 | \$ 872,177 | | |
| 93.00.00 | | | Indirect Costs 93.1 Engineering, Procurement, & Project Services 93.2 Construction Management Support 93.3 SDG&E Internal Costs | | | | | | | | | \$ 52,331 \$ 17,444 \$ 87,218 | | |
| 95.00.00 | | | Contingency 95.1 Contingency on Subcontractor 95.2 Contingency on Scrap Value 95.3 Contingency on Material 95.4 Contingency on Labor 95.5 Contingency on Indirect | | | \$ 59,970 | \$ - | \$ - | | | \$ 60,865 | \$ 60,865 \$ 23,549 | | |
| Total | | | | | | \$ 459,770 | \$ (60,119) | \$ - | | | \$ 466,635 | \$ 1,173,553 | | |

San Diego Gas & Electric
Decommissioning Cost Estimates
PV Sites - Roof Mounted

| Project ID | Code | Customer | Address | PV Location | Tech. | Date Energized | Facility Nameplate (kW) | Panel Qty | | | | |
|--|----------|-----------------------------|---|--|----------|------------------|-------------------------|---------------|-----------|-----------|------------|------------|
| 14 | HTN | High Tech High North County | 1420 West San Marcos Blvd., San Marcos | Roof | PV | 3/11/2011 | 70.20 | 336 | | | | |
| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Crew Rate | Labor Cost | Total Cost |
| Roof top | 11.00.00 | 11.22.00 | Demolition Concrete | | | | | | | | | |
| | | | Concrete | Electrical equipment (Transformer, inverter, etc.) pad | 7 /CY | | | | 11 /MH | \$ 140.47 | \$ 1,545 | \$ 1,545 |
| | 11.41.00 | | Electrical Equipment | | | | | | | | | |
| | | | Disconnect wiring and components at service rack | | 1 EA | | | | 12 /MH | \$ 127.80 | \$ 1,534 | \$ 1,534 |
| | | | Disconnect wiring at inverter | | 1 EA | | | | 3 /MH | \$ 127.80 | \$ 383 | \$ 383 |
| | | | Disconnect wiring at combiner boxes, remove boxes | | 2 EA | | | | 27 /MH | \$ 127.80 | \$ 3,451 | \$ 3,451 |
| | | | Pull wire from combiners to inverter | | 2 EA | | | | 20 /MH | \$ 127.80 | \$ 2,556 | \$ 2,556 |
| | | | Disconnect and remove wiring at PV panels | | 336 EA | | | | 50 /MH | \$ 127.80 | \$ 6,390 | \$ 6,390 |
| | | | Disconnect and remove grounding at PV panels and racks, | | | | | | | | | |
| | | | Remove ground rods | | 336 EA | | | | 14 /MH | \$ 127.80 | \$ 1,789 | \$ 1,789 |
| | | | Demo conduit from rack to tie point | | 1 EA | | | | 12 /MH | \$ 127.80 | \$ 1,534 | \$ 1,534 |
| | | | Demo conduit from rack to transformer | | 1 EA | | | | 9 /MH | \$ 127.80 | \$ 1,150 | \$ 1,150 |
| | | | Demo conduit from combiners to inverter | | 1 EA | | | | 48 /MH | \$ 127.80 | \$ 6,134 | \$ 6,134 |
| | | | Remove Conduits to inverters | | 1 EA | | | | 3 /MH | \$ 127.80 | \$ 383 | \$ 383 |
| | | | Remove inverters | | 1 EA | | | | 5 /MH | \$ 127.80 | \$ 639 | \$ 639 |
| | | | Remove PV panel and place in dumpster | | 336 EA | | | | 168 /MH | \$ 127.80 | \$ 21,470 | \$ 21,470 |
| | | | Remove points where panel is fixed to roof | | 336 EA | | | | 75 /MH | \$ 127.80 | \$ 9,585 | \$ 9,585 |
| | | | Remove lightning projection and other auxiliary equipment | | 1 EA | | | | 32 /MH | \$ 127.80 | \$ 4,090 | \$ 4,090 |
| | | | Remove transformer | | 1 LT | | | | 12 /MH | \$ 127.80 | \$ 1,534 | \$ 1,534 |
| | | | Demolition | | | \$ - | \$ - | \$ - | | | \$ 64,167 | \$ 64,167 |
| | 18.00.00 | | Scrap Value | | | | | | | | | |
| | 18.10.00 | | Mixed Steel | | | | | | | | | |
| | | | Steel | 1 EA, inverter 402 kW | 0.23 TN | \$ (40) | | | /MH | | \$ (40) | \$ (40) |
| | | | Steel | Service rack components | 0.09 TN | \$ (16) | | | /MH | | \$ (16) | \$ (16) |
| | | | Steel | Conduit and fittings | 0.09 TN | \$ (16) | | | /MH | | \$ (16) | \$ (16) |
| | | | Steel | Transformers | 2.74 TN | \$ (480) | | | /MH | | \$ (480) | \$ (480) |
| | | | Steel | Roof ladder, 1@ 350 lb each | 0.03 TN | \$ (5) | | | /MH | | \$ (5) | \$ (5) |
| | 18.20.00 | | Stainless Steel | | | | | | | | | |
| | | | Stainless Steel | 1788 Racks, 13.61 lbs each | 2.29 TN | \$ (2,684) | | | /MH | | \$ (2,684) | \$ (2,684) |
| | 18.30.00 | | Copper | | | | | | | | | |
| | | | Copper | 1 EA, 402 kW inverter | 0.08 TN | \$ (195) | | | /MH | | \$ (195) | \$ (195) |
| | | | Copper | Wire | 0.51 TN | \$ (1,244) | | | /MH | | \$ (1,244) | \$ (1,244) |
| | | | Copper | Transformers | 1.3 TN | \$ (3,172) | | | /MH | | \$ (3,172) | \$ (3,172) |
| | 18.50.00 | | Aluminum | | | | | | | | | |
| | | | PV Module | 1788 Modules @ 8 lbs each | 2688 LB | \$ (1,636) | | | /MH | | \$ (1,636) | \$ (1,636) |
| | | | Conduit and fittings | 100 @ 1 lb each | 18.79 LB | \$ (11) | | | /MH | | \$ (11) | \$ (11) |
| | | | Scrap Value | | | \$ - | \$ (9,499) | \$ - | | | \$ - | \$ (9,499) |
| | 21.00.00 | | Civil Work | | | | | | | | | |
| | 21.19.00 | | Disposal | | | | | | | | | |
| | | | Dumpster, 40 CY Capacity | Concrete, PV panels, rubbish (panels to recycler) | 2 EA | \$ 3,600 | | | /MH | | \$ 3,600 | \$ 3,600 |
| | | | Dumpster, 40 CY Capacity | Fix point rods | 1 EA | \$ 900 | | | /MH | | \$ 900 | \$ 900 |
| | 21.20.00 | | Backfill | | | | | | | | | |
| | | | Foundation backfill, imported material fill | Backfill concrete pads | 7 /CY | \$ 280 | | | /MH | | \$ 280 | \$ 280 |
| | | | Civil Work | | | \$ 4,780 | \$ - | \$ - | | | \$ - | \$ 4,780 |
| | 24.00.00 | | Architectural | | | | | | | | | |
| | 24.37.00 | | Roofing | | | | | | | | | |
| | | | Roof repair at fix points | Installation | 336 EA | \$ 55,440 | | | /MH | | \$ - | \$ 55,440 |
| | | | Architectural | | | \$ 55,440 | \$ - | \$ - | | | \$ - | \$ 55,440 |
| Direct Costs | | | | | | | | | | | | \$ 114,888 |
| | 61.00.00 | | Construction Indirect | | | | | | | | | |
| | 61.99.00 | | Miscellaneous | | | | | | | | | |
| | | | Downspout / Chute | | 1 LS | \$ 25,000 | | | /MH | | \$ - | \$ 25,000 |
| | | | Construction Indirect | | | \$ 25,000 | \$ - | \$ - | | | \$ - | \$ 25,000 |
| Subtotal | | | | | | \$ 85,220 | \$ (9,499) | \$ - | | | \$ 64,167 | \$ 139,888 |
| | 91.00.00 | | Other Direct & Construction Indirect Costs | | | | | | | | | |
| | | 91.09 | Contractor's General and Administration Expense | | | | | | | | | \$ 9,792 |
| | | 91.10 | Contractor's Profit | | | | | | | | | \$ 13,988 |
| | | | | | | | | | | | | \$ 23,781 |
| Direct Costs + Construction Indirect Costs | | | | | | \$ 85,220 | \$ (9,499) | \$ - | | | \$ 64,167 | \$ 163,669 |
| | 93.00.00 | | Indirect Costs | | | | | | | | | |
| | | 93.1 | Engineering, Procurement, & Project Services | | | | | | | | | \$ 9,820 |
| | | 93.2 | Construction Management Support | | | | | | | | | \$ 3,273 |
| | | 93.3 | SDG&E Internal Costs | | | | | | | | | \$ 16,367 |
| | 95.00.00 | | Contingency | | | | | | | | | |
| | | 95.1 | Contingency on Subcontractor | | | \$ 12,783 | | | | | | \$ 12,783 |
| | | 95.2 | Contingency on Scrap Value | | | \$ - | | | | | | \$ - |
| | | 95.3 | Contingency on Material | | | \$ - | | | | | | \$ - |
| | | 95.4 | Contingency on Labor | | | | | | | | \$ 9,625 | \$ 9,625 |
| | | 95.5 | Contingency on Indirect | | | | | | | | | \$ 4,419 |
| Total | | | | | | \$ 98,003 | \$ (9,499) | \$ - | | | \$ 73,792 | \$ 219,957 |

San Diego Gas & Electric
Decommissioning Cost Estimates
PV Sites - Roof Mounted

| Project ID | Code | Customer | Address | PV Location | Tech. | Date Energized | Facility Nameplate (kW) | Panel Qty | | | | |
|------------|----------|-------------|--|--|----------|------------------|-------------------------|---------------|-----------|-----------|------------|------------|
| 15 | UCO | Urban Corps | 3105 Jefferson St, San Diego | Roof | PV | 6/17/2010 | 22.80 | 117 | | | | |
| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Crew Rate | Labor Cost | Total Cost |
| Roof top | 11.00.00 | | Demolition | | | | | | | | | |
| | 11.22.00 | | Concrete | Electrical equipment (Transformer, inverter, etc.) pad | 7 /CY | | | | 4 /MH | \$ 140.47 | \$ 562 | \$ 562 |
| | 11.41.00 | | Electrical Equipment | | | | | | | | | |
| | | | Disconnect wiring and components at service rack | | 1 EA | | | | 4 /MH | \$ 127.80 | \$ 511 | \$ 511 |
| | | | Disconnect wiring at inverter | | 1 EA | | | | 1 /MH | \$ 127.80 | \$ 128 | \$ 128 |
| | | | Disconnect wiring at combiner boxes, remove boxes | | 1 EA | | | | 9 /MH | \$ 127.80 | \$ 1,150 | \$ 1,150 |
| | | | Pull wire from combiners to inverter | | 1 EA | | | | 7 /MH | \$ 127.80 | \$ 895 | \$ 895 |
| | | | Disconnect and remove wiring at PV panels | | 117 EA | | | | 18 /MH | \$ 127.80 | \$ 2,300 | \$ 2,300 |
| | | | Disconnect and remove grounding at PV panels and racks, Remove ground rods | | 117 EA | | | | 5 /MH | \$ 127.80 | \$ 639 | \$ 639 |
| | | | Demo conduit from rack to tie point | | 1 EA | | | | 4 /MH | \$ 127.80 | \$ 511 | \$ 511 |
| | | | Demo conduit from rack to transformer | | 1 EA | | | | 3 /MH | \$ 127.80 | \$ 383 | \$ 383 |
| | | | Demo conduit from combiners to inverter | | 1 EA | | | | 17 /MH | \$ 127.80 | \$ 2,173 | \$ 2,173 |
| | | | Remove Conduits to inverters | | 1 EA | | | | 1 /MH | \$ 127.80 | \$ 128 | \$ 128 |
| | | | Remove inverters | | 1 EA | | | | 2 /MH | \$ 127.80 | \$ 256 | \$ 256 |
| | | | Remove PV panel and place in dumpster | | 117 EA | | | | 59 /MH | \$ 127.80 | \$ 7,540 | \$ 7,540 |
| | | | Remove points where panel is fixed to roof | | 117 EA | | | | 26 /MH | \$ 127.80 | \$ 3,323 | \$ 3,323 |
| | | | Remove lightning projection and other auxiliary equipment | | 1 EA | | | | 11 /MH | \$ 127.80 | \$ 1,406 | \$ 1,406 |
| | | | Remove transformer | | 1 LT | | | | 4 /MH | \$ 127.80 | \$ 511 | \$ 511 |
| | | | Demolition | | | \$ - | \$ - | \$ - | | | \$ 22,416 | \$ 22,416 |
| | 18.00.00 | | Scrap Value | | | | | | | | | |
| | 18.10.00 | | Mixed Steel | | | | | | | | | |
| | | | Steel | 1 EA, inverter 402 kW | 0.08 TN | \$ (14) | | | /MH | | \$ (14) | \$ (14) |
| | | | Steel | Service rack components | 0.03 TN | \$ (5) | | | /MH | | \$ (5) | \$ (5) |
| | | | Steel | Conduit and fittings | 0.03 TN | \$ (5) | | | /MH | | \$ (5) | \$ (5) |
| | | | Steel | Transformers | 0.95 TN | \$ (166) | | | /MH | | \$ (166) | \$ (166) |
| | | | Steel | Roof ladder, 1@ 350 lb each | 0.01 TN | \$ (2) | | | /MH | | \$ (2) | \$ (2) |
| | 18.20.00 | | Stainless Steel | | | | | | | | | |
| | | | Stainless Steel | 1788 Racks, 13.61 lbs each | 0.8 TN | \$ (938) | | | /MH | | \$ (938) | \$ (938) |
| | 18.30.00 | | Copper | | | | | | | | | |
| | | | Copper | 1 EA, 402 kW inverter | 0.03 TN | \$ (73) | | | /MH | | \$ (73) | \$ (73) |
| | | | Copper | Wire | 0.18 TN | \$ (439) | | | /MH | | \$ (439) | \$ (439) |
| | | | Copper | Transformers | 0.45 TN | \$ (1,098) | | | /MH | | \$ (1,098) | \$ (1,098) |
| | 18.50.00 | | Aluminum | | | | | | | | | |
| | | | PV Module | 1788 Modules @ 8 lbs each | 936 LB | \$ (570) | | | /MH | | \$ (570) | \$ (570) |
| | | | Conduit and fittings | 100 @ 1 lb each | 6.54 LB | \$ (4) | | | /MH | | \$ (4) | \$ (4) |
| | | | Scrap Value | | | \$ - | \$ (3,314) | \$ - | | | \$ - | \$ (3,314) |
| | 21.00.00 | | Civil Work | | | | | | | | | |
| | 21.19.00 | | Disposal | | | | | | | | | |
| | | | Dumpster, 40 CY Capacity | Concrete, PV panels, rubbish (panels to recycler) | 1 EA | \$ 1,800 | | | /MH | | \$ 1,800 | \$ 1,800 |
| | | | Dumpster, 40 CY Capacity | Fix point rods | 1 EA | \$ 900 | | | /MH | | \$ 900 | \$ 900 |
| | 21.20.00 | | Backfill | | | | | | | | | |
| | | | Foundation backfill, imported material fill | Backfill concrete pads | 7 /CY | \$ 280 | | | /MH | | \$ 280 | \$ 280 |
| | | | Civil Work | | | \$ 2,980 | \$ - | \$ - | | | \$ - | \$ 2,980 |
| | 24.00.00 | | Architectural | | | | | | | | | |
| | 24.37.00 | | Roofing | | | | | | | | | |
| | | | Roof repair at fix points | Installation | 117 EA | \$ 19,305 | | | /MH | | \$ - | \$ 19,305 |
| | | | Architectural | | | \$ 19,305 | \$ - | \$ - | | | \$ - | \$ 19,305 |
| | | | Direct Costs | | | | | | | | | \$ 41,387 |
| | 61.00.00 | | Construction Indirect | | | | | | | | | |
| | 61.99.00 | | Miscellaneous | | | | | | | | | |
| | | | Downspout / Chute | | 1 LS | \$ 25,000 | | | /MH | | \$ 25,000 | \$ 25,000 |
| | | | Construction Indirect | | | \$ 25,000 | \$ - | \$ - | | | \$ - | \$ 25,000 |
| | | | Subtotal | | | \$ 47,285 | \$ (3,314) | \$ - | | | \$ 22,416 | \$ 66,387 |
| | 91.00.00 | | Other Direct & Construction Indirect Costs | | | | | | | | | |
| | | | 91.09 Contractor's General and Administration Expense | | | | | | | | | \$ 4,647 |
| | | | 91.10 Contractor's Profit | | | | | | | | | \$ 6,639 |
| | | | Direct Costs + Construction Indirect Costs | | | \$ 47,285 | \$ (3,314) | \$ - | | | \$ 22,416 | \$ 77,672 |
| | 93.00.00 | | Indirect Costs | | | | | | | | | |
| | | | 93.1 Engineering, Procurement, & Project Services | | | | | | | | | \$ 4,660 |
| | | | 93.2 Construction Management Support | | | | | | | | | \$ 1,553 |
| | | | 93.3 SDG&E Internal Costs | | | | | | | | | \$ 7,767 |
| | 95.00.00 | | Contingency | | | | | | | | | |
| | | | 95.1 Contingency on Subcontractor | | | \$ 7,093 | | | | | | \$ 7,093 |
| | | | 95.2 Contingency on Scrap Value | | | \$ - | | | | | | \$ - |
| | | | 95.3 Contingency on Material | | | \$ - | | | | | | \$ - |
| | | | 95.4 Contingency on Labor | | | | | | | | \$ 3,362 | \$ 3,362 |
| | | | 95.5 Contingency on Indirect | | | | | | | | | \$ 2,097 |
| | | | Total | | | \$ 54,378 | \$ (3,314) | \$ - | | | \$ 25,778 | \$ 104,206 |

San Diego Gas & Electric
Decommissioning Cost Estimates
PV Sites - Roof Mounted

| Project ID | Code | Customer | Address | PV Location | Tech. | Date Energized | Facility Nameplate (kW) | Panel Qty | | | | | | | | | | | | | | | | |
|------------|------|----------------------|------------------------------|-------------|-------|----------------|-------------------------|-----------|------|--|-------|--|---|----------|------------------|-------------|---------------|-----------|-----------|------------|------------|-----------|------------|--|
| 16 | PRS | Pacific Ridge School | 6269 El Fuerte St., Carlsbad | Roof | PV | 1/27/2011 | 20.90 | 102 | Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Crew Rate | Labor Cost | Total Cost | | | |
| Roof top | | | | | | | | | | 11.00.00 | | Demolition | | | | | | | | | | | | |
| | | | | | | | | | | 11.22.00 | | Concrete | | | | | | | | | | | | |
| | | | | | | | | | | | | Concrete | Electrical equipment (Transformer, inverter, etc.) pad | 7 /CY | | | | | 3 /MH | \$ 140.47 | \$ 421 | \$ 421 | | |
| | | | | | | | | | | 11.41.00 | | Electrical Equipment | | | | | | | | | | | | |
| | | | | | | | | | | | | | Disconnect wiring and components at service rack | 1 EA | | | | | 4 /MH | \$ 127.80 | \$ 511 | \$ 511 | | |
| | | | | | | | | | | | | | Disconnect wiring at inverter | 1 EA | | | | | 1 /MH | \$ 127.80 | \$ 128 | \$ 128 | | |
| | | | | | | | | | | | | | Disconnect wiring at combiner boxes, remove boxes | 1 EA | | | | | 8 /MH | \$ 127.80 | \$ 1,022 | \$ 1,022 | | |
| | | | | | | | | | | | | | Pull wire from combiners to inverter | 1 EA | | | | | 6 /MH | \$ 127.80 | \$ 767 | \$ 767 | | |
| | | | | | | | | | | | | | Disconnect and remove wiring at PV panels | 102 EA | | | | | 15 /MH | \$ 127.80 | \$ 1,917 | \$ 1,917 | | |
| | | | | | | | | | | | | | Disconnect and remove grounding at PV panels and racks, | | | | | | | | | | | |
| | | | | | | | | | | | | | Remove ground rods | 102 EA | | | | | 4 /MH | \$ 127.80 | \$ 511 | \$ 511 | | |
| | | | | | | | | | | | | | Demo conduit from rack to tie point | 1 EA | | | | | 4 /MH | \$ 127.80 | \$ 511 | \$ 511 | | |
| | | | | | | | | | | | | | Demo conduit from rack to transformer | 1 EA | | | | | 3 /MH | \$ 127.80 | \$ 383 | \$ 383 | | |
| | | | | | | | | | | | | | Demo conduit from combiners to inverter | 1 EA | | | | | 15 /MH | \$ 127.80 | \$ 1,917 | \$ 1,917 | | |
| | | | | | | | | | | | | | Remove Conduits to inverters | 1 EA | | | | | 1 /MH | \$ 127.80 | \$ 128 | \$ 128 | | |
| | | | | | | | | | | | | | Remove inverters | 1 EA | | | | | 1 /MH | \$ 127.80 | \$ 128 | \$ 128 | | |
| | | | | | | | | | | | | | Remove PV panel and place in dumpster | 102 EA | | | | | 51 /MH | \$ 127.80 | \$ 6,518 | \$ 6,518 | | |
| | | | | | | | | | | | | | Remove points where panel is fixed to roof | 102 EA | | | | | 23 /MH | \$ 127.80 | \$ 2,939 | \$ 2,939 | | |
| | | | | | | | | | | | | | Remove lightning projection and other auxiliary equipment | 1 EA | | | | | 10 /MH | \$ 127.80 | \$ 1,278 | \$ 1,278 | | |
| | | | | | | | | | | | | | Remove transformer | 1 LT | | | | | 4 /MH | \$ 127.80 | \$ 511 | \$ 511 | | |
| | | | | | | | | | | | | Demolition | | | \$ - | \$ - | \$ - | | | \$ - | \$ 19,591 | \$ 19,591 | | |
| | | | | | | | | | | 18.00.00 | | Scrap Value | | | | | | | | | | | | |
| | | | | | | | | | | | | Mixed Steel | | | | | | | | | | | | |
| | | | | | | | | | | | | Steel | 1 EA, inverter 402 kW | 0.07 TN | | \$ (12) | | | | | | \$ (12) | | |
| | | | | | | | | | | | | Steel | Service rack components | 0.03 TN | | \$ (5) | | | | | | \$ (5) | | |
| | | | | | | | | | | | | Steel | Conduit and fittings | 0.03 TN | | \$ (5) | | | | | | \$ (5) | | |
| | | | | | | | | | | | | Steel | Transformers | 0.83 TN | | \$ (145) | | | | | | \$ (145) | | |
| | | | | | | | | | | | | Steel | Roof ladder, 1@ 350 lb each | 0.01 TN | | \$ (2) | | | | | | \$ (2) | | |
| | | | | | | | | | | | | Stainless Steel | | | | | | | | | | | | |
| | | | | | | | | | | | | Stainless Steel | 1788 Racks, 13.61 lbs each | 0.69 TN | | \$ (809) | | | | | | | \$ (809) | |
| | | | | | | | | | | | | Copper | | | | | | | | | | | | |
| | | | | | | | | | | | | Copper | 1 EA, 402 kW inverter | 0.02 TN | | \$ (49) | | | | | | \$ (49) | | |
| | | | | | | | | | | | | Copper | Wire | 0.16 TN | | \$ (390) | | | | | | \$ (390) | | |
| | | | | | | | | | | | | Copper | Transformers | 0.39 TN | | \$ (952) | | | | | | \$ (952) | | |
| | | | | | | | | | | | | Aluminum | | | | | | | | | | | | |
| | | | | | | | | | | | | PV Module | 1788 Modules @ 8 lbs each | 816 LB | | \$ (497) | | | | | | \$ (497) | | |
| | | | | | | | | | | | | Conduit and fittings | 100 @ 1 lb each | 5.7 LB | | \$ (3) | | | | | | \$ (3) | | |
| | | | | | | | | | | | | Scrap Value | | | \$ - | \$ (2,869) | \$ - | | | | | \$ - | \$ (2,869) | |
| | | | | | | | | | | 21.00.00 | | Civil Work | | | | | | | | | | | | |
| | | | | | | | | | | | | Disposal | | | | | | | | | | | | |
| | | | | | | | | | | | | Dumpster, 40 CY Capacity | Concrete, PV panels, rubbish (panels to recycler) | 1 EA | \$ 1,800 | | | | | | | \$ 1,800 | | |
| | | | | | | | | | | | | Dumpster, 40 CY Capacity | Fix point rods | 1 EA | \$ 900 | | | | | | | \$ 900 | | |
| | | | | | | | | | | | | Backfill | Foundation backfill, imported material fill | | | | | | | | | | | |
| | | | | | | | | | | | | Civil Work | Backfill concrete pads | 7 /CY | \$ 280 | | | | | | | \$ 280 | | |
| | | | | | | | | | | | | | | | \$ 2,980 | \$ - | \$ - | | | | \$ - | \$ 2,980 | | |
| | | | | | | | | | | 24.00.00 | | Architectural | | | | | | | | | | | | |
| | | | | | | | | | | | | Roofing | | | | | | | | | | | | |
| | | | | | | | | | | | | Roof repair at fix points | Installation | 102 EA | \$ 16,830 | | | | | | | \$ - | \$ 16,830 | |
| | | | | | | | | | | | | Architectural | | | \$ 16,830 | \$ - | \$ - | | | | \$ - | \$ 16,830 | | |
| | | | | | | | | | | Direct Costs | | | | | | | | | | | | | \$ 36,532 | |
| | | | | | | | | | | 61.00.00 | | Construction Indirect | | | | | | | | | | | | |
| | | | | | | | | | | | | Miscellaneous | | | | | | | | | | | | |
| | | | | | | | | | | | | Downspout / Chute | | 1 LS | \$ 25,000 | | | | | | | \$ 25,000 | | |
| | | | | | | | | | | | | Construction Indirect | | | \$ 25,000 | \$ - | \$ - | | | | \$ - | \$ 25,000 | | |
| | | | | | | | | | | Subtotal | | | | | \$ 44,810 | \$ (2,869) | \$ - | | | \$ 19,591 | \$ 61,532 | | | |
| | | | | | | | | | | 91.00.00 | | Other Direct & Construction Indirect Costs | | | | | | | | | | | | |
| | | | | | | | | | | | | 91.09 | Contractor's General and Administration Expense | | | | | | | | | \$ 4,307 | | |
| | | | | | | | | | | | | 91.10 | Contractor's Profit | | | | | | | | | \$ 6,153 | | |
| | | | | | | | | | | | | | | | | | | | | \$ 10,460 | | | | |
| | | | | | | | | | | Direct Costs + Construction Indirect Costs | | | | | \$ 44,810 | \$ (2,869) | \$ - | | | \$ 19,591 | \$ 71,993 | | | |
| | | | | | | | | | | 93.00.00 | | Indirect Costs | | | | | | | | | | | | |
| | | | | | | | | | | | | 93.1 | Engineering, Procurement, & Project Services | | | | | | | | | \$ 4,320 | | |
| | | | | | | | | | | | | 93.2 | Construction Management Support | | | | | | | | | \$ 1,440 | | |
| | | | | | | | | | | | | 93.3 | SDG&E Internal Costs | | | | | | | | | \$ 7,199 | | |
| | | | | | | | | | | 95.00.00 | | Contingency | | | | | | | | | | | | |
| | | | | | | | | | | | | 95.1 | Contingency on Subcontractor | | \$ 6,722 | | | | | | | \$ 6,722 | | |
| | | | | | | | | | | | | 95.2 | Contingency on Scrap Value | | | \$ - | | | | | \$ - | | | |
| | | | | | | | | | | | | 95.3 | Contingency on Material | | | \$ - | | | | \$ - | | | | |
| | | | | | | | | | | | | 95.4 | Contingency on Labor | | | | | | \$ 2,939 | \$ 2,939 | | | | |
| | | | | | | | | | | | | 95.5 | Contingency on Indirect | | | | | | | \$ 1,944 | | | | |
| | | | | | | | | | | Total | | | | | \$ 51,532 | \$ (2,869) | \$ - | | | \$ 22,530 | \$ 96,555 | | | |

San Diego Gas & Electric
Decommissioning Cost Estimates
PV Sites - Roof Mounted

| Project ID | Code | Customer | Address | PV Location | Tech. | Date Energized | Facility Nameplate (kW) | Panel Qty | | | | | | |
|--|----------|----------------------------------|--|---|--|--------------------|--|---------------|--|--|--|--|--|------------|
| 17 | SBR | Sanford Burnham Medical Research | 10905 Road to the Cure, La Jolla | Roof | PV | 1/28/2011 | 200.20 | 712 | | | | | | |
| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Crew Rate | Labor Cost | Total Cost | | |
| Roof top | 11.00.00 | 11.22.00 | Demolition Concrete | Electrical equipment (Transformer, inverter, etc.) pad | 7 /CY | | | | 24 /MH | \$ 140.47 | \$ 3,371 | \$ 3,371 | | |
| | 11.41.00 | | Electrical Equipment Disconnect wiring and components at service rack Disconnect wiring at inverter Disconnect wiring at combiner boxes, remove boxes Pull wire from combiners to inverter Disconnect and remove wiring at PV panels Disconnect and remove grounding at PV panels and racks, Remove ground rods Demo conduit from rack to tie point Demo conduit from rack to transformer Demo conduit from combiners to inverter Remove Conduits to inverters Remove inverters Remove PV panel and place in dumpster Remove points where panel is fixed to roof Remove lightning projection and other auxiliary equipment Remove transformer | | 1 EA 1 EA 5 EA 5 EA 712 EA 712 EA 1 EA 1 EA 1 EA 1 EA 1 EA 712 EA 712 EA 1 EA 1 LT | | | | 25 /MH 6 /MH 57 /MH 41 /MH 107 /MH 29 /MH 25 /MH 19 /MH 102 /MH 6 /MH 10 /MH 356 /MH 159 /MH 67 /MH 26 /MH | \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 | \$ 3,195 \$ 767 \$ 7,285 \$ 5,240 \$ 13,675 \$ 3,706 \$ 3,195 \$ 2,428 \$ 13,036 \$ 767 \$ 1,278 \$ 45,497 \$ 20,320 \$ 8,563 \$ 3,323 | \$ 3,195 \$ 767 \$ 7,285 \$ 5,240 \$ 13,675 \$ 3,706 \$ 3,195 \$ 2,428 \$ 13,036 \$ 767 \$ 1,278 \$ 45,497 \$ 20,320 \$ 8,563 \$ 3,323 | | |
| | 18.00.00 | | Scrap Value Mixed Steel | | | | | | | | | | | |
| | 18.10.00 | | Steel Steel Steel Steel Steel | 1 EA, inverter 402 kW Service rack components Conduit and fittings Transformers Roof ladder, 1@ 350 lb each | 0.5 TN 0.19 TN 0.2 TN 5.8 TN 0.07 TN | | \$ (88) \$ (33) \$ (35) \$ (1,015) \$ (12) | | /MH /MH /MH /MH /MH | | | \$ (88) \$ (33) \$ (35) \$ (1,015) \$ (12) | | |
| | 18.20.00 | | Stainless Steel Stainless Steel | 1788 Racks, 13.61 lbs each | 4.85 TN | | \$ (5,684) | | /MH | | | \$ (5,684) | | |
| | 18.30.00 | | Copper Copper Copper | 1 EA, 402 kW inverter Wire Transformers | 0.16 TN 1.08 TN 2.76 TN | | \$ (390) \$ (2,635) \$ (6,734) | | /MH /MH /MH | | | \$ (390) \$ (2,635) \$ (6,734) | | |
| | 18.50.00 | | Aluminum PV Module Conduit and fittings Scrap Value | 1788 Modules @ 8 lbs each 100 @ 1 lb each | 5696 LB 39.82 LB | | \$ (3,466) \$ (24) | | /MH /MH | | | \$ (3,466) \$ (24) | | |
| | 21.00.00 | | Civil Work Disposal | | | | | | | | | | | |
| | 21.19.00 | | Dumpster, 40 CY Capacity Dumpster, 40 CY Capacity | Concrete, PV panels, rubbish (panels to recycler) Fix point rods | 4 EA 1 EA | \$ 7,200 \$ 900 | | | /MH /MH | | | \$ 7,200 \$ 900 | | |
| | 21.20.00 | | Backfill Foundation backfill, imported material fill Civil Work | Backfill concrete pads | 7 /CY | \$ 280 | | | /MH | | | \$ 280 | | |
| | 24.00.00 | | Architectural Roofing Roof repair at fix points Architectural | Installation | 712 EA | \$ 117,480 | | | /MH | | | \$ 117,480 | | |
| Direct Costs | | | | | | \$ 117,480 | \$ - | \$ - | | | | \$ 117,480 | | \$ 241,387 |
| 61.00.00 | 61.99.00 | | Construction Indirect Miscellaneous Downspout / Chute Construction Indirect | | 1 LS | \$ 25,000 | | | /MH | | | \$ 25,000 | | \$ 25,000 |
| Subtotal | | | | | | \$ 150,860 | \$ (20,117) | \$ - | | | \$ 135,644 | \$ 266,387 | | |
| 91.00.00 | | | Other Direct & Construction Indirect Costs 91.09 Contractor's General and Administration Expense 91.10 Contractor's Profit | | | | | | | | | \$ 18,647 \$ 26,639 | | \$ 45,286 |
| Direct Costs + Construction Indirect Costs | | | | | | \$ 150,860 | \$ (20,117) | \$ - | | | \$ 135,644 | \$ 311,673 | | |
| 93.00.00 | | | Indirect Costs 93.1 Engineering, Procurement, & Project Services 93.2 Construction Management Support 93.3 SDG&E Internal Costs | | | | | | | | | \$ 18,700 \$ 6,233 \$ 31,167 | | |
| 95.00.00 | | | Contingency 95.1 Contingency on Subcontractor 95.2 Contingency on Scrap Value 95.3 Contingency on Material 95.4 Contingency on Labor 95.5 Contingency on Indirect | | | \$ 22,629 | \$ - | \$ - | | | \$ 20,347 | \$ 22,629 \$ - \$ - \$ 20,347 \$ 8,415 | | |
| Total | | | | | | \$ 173,489 | \$ (20,117) | \$ - | | | \$ 155,991 | \$ 419,164 | | |

San Diego Gas & Electric
Decommissioning Cost Estimates
PV Sites - Roof Mounted

| Project ID | Code | Customer | Address | PV Location | Tech. | Date Energized | Facility Nameplate (kW) | Panel Qty | | | | | | |
|--|--------------|--------------------------------|--|--|-----------------|-------------------------|-------------------------|----------------------|---|--|--|--|--|--|
| 18 | HCK | High Tech High Chula Vista K-8 | 1949 Discovery Falls Drive, Chula Vista | Roof | PV | 8/8/2011 | 130.10 | 644 | | | | | | |
| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Crew Rate | Labor Cost | Total Cost | | |
| Roof top | 11.00.00 | 11.22.00 | Demolition Concrete | Electrical equipment (Transformer, inverter, etc.) pad | 7 /CY | | | | 22 /MH | \$ 140.47 | \$ 3,090 | \$ 3,090 | | |
| | 11.41.00 | | Electrical Equipment Disconnect wiring and components at service rack Disconnect wiring at inverter Disconnect wiring at combiner boxes, remove boxes Pull wire from combiners to inverter Disconnect and remove wiring at PV panels Disconnect and remove grounding at PV panels and racks, Remove ground rods Demo conduit from rack to tie point Demo conduit from rack to transformer Demo conduit from combiners to inverter Remove Conduits to inverters Remove inverters Remove PV panel and place in dumpster Remove points where panel is fixed to roof Remove lightning projection and other auxiliary equipment Remove transformer | 1 EA 1 EA 5 EA 5 EA 644 EA 644 EA 1 EA 1 EA 1 EA 1 EA 1 EA 644 EA 644 EA 1 EA 1 EA | | | | | 23 /MH 6 /MH 52 /MH 37 /MH 97 /MH 26 /MH 23 /MH 17 /MH 92 /MH 6 /MH 9 /MH 322 /MH 144 /MH 61 /MH 23 /MH | \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 | \$ 2,939 \$ 767 \$ 6,646 \$ 4,729 \$ 12,397 \$ 3,323 \$ 2,939 \$ 2,173 \$ 11,758 \$ 767 \$ 1,150 \$ 41,152 \$ 18,403 \$ 7,796 \$ 2,939 | \$ 2,939 \$ 767 \$ 6,646 \$ 4,729 \$ 12,397 \$ 3,323 \$ 2,939 \$ 2,173 \$ 11,758 \$ 767 \$ 1,150 \$ 41,152 \$ 18,403 \$ 7,796 \$ 2,939 | | |
| | 18.00.00 | 18.10.00 | Scrap Value Mixed Steel | 1 EA, inverter 402 kW | 0.45 TN | | \$ (79) | | /MH | | | \$ (79) | | |
| | | | Steel | Service rack components | 0.17 TN | | \$ (30) | | /MH | | | \$ (30) | | |
| | | | Steel | Conduit and fittings | 0.18 TN | | \$ (32) | | /MH | | | \$ (32) | | |
| | | | Steel | Transformers | 5.25 TN | | \$ (919) | | /MH | | | \$ (919) | | |
| | | | Steel | Roof ladder, 1@ 350 lb each | 0.06 TN | | \$ (11) | | /MH | | | \$ (11) | | |
| | 18.20.00 | | Stainless Steel | 1788 Racks, 13.61 lbs each | 4.38 TN | | \$ (5,133) | | /MH | | | \$ (5,133) | | |
| | 18.30.00 | | Copper | 1 EA, 402 kW inverter | 0.14 TN | | \$ (342) | | /MH | | | \$ (342) | | |
| | | | Copper | Wire | 0.98 TN | | \$ (2,391) | | /MH | | | \$ (2,391) | | |
| | | | Copper | Transformers | 2.49 TN | | \$ (6,076) | | /MH | | | \$ (6,076) | | |
| | 18.50.00 | | Aluminum | 1788 Modules @ 8 lbs each | 5152 LB | | \$ (3,135) | | /MH | | | \$ (3,135) | | |
| | | | Conduit and fittings | 100 @ 1 lb each | 36.02 LB | | \$ (22) | | /MH | | | \$ (22) | | |
| | | | Scrap Value | | | \$ - | \$ (18,168) | \$ - | | | \$ - | \$ (18,168) | | |
| | 21.00.00 | 21.19.00 | Civil Work Disposal | Concrete, PV panels, rubbish (panels to recycler) | 4 EA | \$ 7,200 | | | /MH | | | \$ 7,200 | | |
| | | | Disposal | Fix point rods | 1 EA | \$ 900 | | | /MH | | | \$ 900 | | |
| | 21.20.00 | | Backfill | Foundation backfill, imported material fill | 7 /CY | \$ 280 | | | /MH | | | \$ 280 | | |
| | | | Civil Work | | | \$ 8,380 | \$ - | \$ - | | | \$ - | \$ 8,380 | | |
| | 24.00.00 | 24.37.00 | Architectural Roofing | Roof repair at fix points | 644 EA | \$ 106,260 | | | /MH | | | \$ 106,260 | | |
| | | | Architectural | | | \$ 106,260 | \$ - | \$ - | | | \$ - | \$ 106,260 | | |
| Direct Costs | | | | | | | | | | | | \$ 219,439 | | |
| | 61.00.00 | 61.99.00 | Construction Indirect Miscellaneous | Downspout / Chute | 1 LS | \$ 25,000 | | | /MH | | | \$ 25,000 | | |
| | | | Construction Indirect | | | \$ 25,000 | \$ - | \$ - | | | \$ - | \$ 25,000 | | |
| Subtotal | | | | | | \$ 139,640 | \$ (18,168) | \$ - | | | \$ 122,967 | \$ 244,439 | | |
| | 91.00.00 | | Other Direct & Construction Indirect Costs | | | | | | | | | | | |
| | | 91.09 | Contractor's General and Administration Expense | | | | | | | | | \$ 17,111 | | |
| | | 91.10 | Contractor's Profit | | | | | | | | | \$ 24,444 | | |
| | | | | | | | | | | | | \$ 41,555 | | |
| Direct Costs + Construction Indirect Costs | | | | | | \$ 139,640 | \$ (18,168) | \$ - | | | \$ 122,967 | \$ 285,993 | | |
| | 93.00.00 | | Indirect Costs | | | | | | | | | | | |
| | | 93.1 | Engineering, Procurement, & Project Services | | | | | | | | | \$ 17,160 | | |
| | | 93.2 | Construction Management Support | | | | | | | | | \$ 5,720 | | |
| | | 93.3 | SDG&E Internal Costs | | | | | | | | | \$ 28,599 | | |
| | 95.00.00 | | Contingency | | | | | | | | | | | |
| | | 95.1 | Contingency on Subcontractor | | | \$ 20,946 | | | | | | \$ 20,946 | | |
| | | 95.2 | Contingency on Scrap Value | | | \$ - | | | | | | \$ - | | |
| | | 95.3 | Contingency on Material | | | | | | | | | \$ - | | |
| | | 95.4 | Contingency on Labor | | | | | | | | \$ 18,445 | \$ 18,445 | | |
| | | 95.5 | Contingency on Indirect | | | | | | | | | \$ 7,722 | | |
| Total | | | | | | \$ 160,586 | \$ (18,168) | \$ - | | | \$ 141,412 | \$ 384,585 | | |

San Diego Gas & Electric
Decommissioning Cost Estimates
PV Sites - Roof Mounted

| Project ID | Code | Customer | Address | PV Location | Tech. | Date Energized | Facility Nameplate (kW) | Panel Qty | | | | |
|--|----------|--------------------------------|---|--|----------|------------------|-------------------------|---------------|-----------|-----------|------------|------------|
| 19 | CSM | CSUSM - Public Safety Building | Campus View Dr & La Moree Rd, San Marcos | Roof | PV | 1/19/2012 | 37.10 | 180 | | | | |
| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Crew Rate | Labor Cost | Total Cost |
| Roof top | 11.00.00 | 11.22.00 | Demolition Concrete | Electrical equipment (Transformer, inverter, etc.) pad | 7 /CY | | | | 6 /MH | \$ 140.47 | \$ 843 | \$ 843 |
| | 11.41.00 | | Electrical Equipment | | | | | | | | | |
| | | | Disconnect wiring and components at service rack | | 1 EA | | | | 6 /MH | \$ 127.80 | \$ 767 | \$ 767 |
| | | | Disconnect wiring at inverter | | 1 EA | | | | 2 /MH | \$ 127.80 | \$ 256 | \$ 256 |
| | | | Disconnect wiring at combiner boxes, remove boxes | | 1 EA | | | | 14 /MH | \$ 127.80 | \$ 1,789 | \$ 1,789 |
| | | | Pull wire from combiners to inverter | | 1 EA | | | | 10 /MH | \$ 127.80 | \$ 1,278 | \$ 1,278 |
| | | | Disconnect and remove wiring at PV panels | | 180 EA | | | | 27 /MH | \$ 127.80 | \$ 3,451 | \$ 3,451 |
| | | | Disconnect and remove grounding at PV panels and racks, | | | | | | | | | |
| | | | Remove ground rods | | 180 EA | | | | 7 /MH | \$ 127.80 | \$ 895 | \$ 895 |
| | | | Demo conduit from rack to tie point | | 1 EA | | | | 6 /MH | \$ 127.80 | \$ 767 | \$ 767 |
| | | | Demo conduit from rack to transformer | | 1 EA | | | | 5 /MH | \$ 127.80 | \$ 639 | \$ 639 |
| | | | Demo conduit from combiners to inverter | | 1 EA | | | | 26 /MH | \$ 127.80 | \$ 3,323 | \$ 3,323 |
| | | | Remove Conduits to inverters | | 1 EA | | | | 2 /MH | \$ 127.80 | \$ 256 | \$ 256 |
| | | | Remove inverters | | 1 EA | | | | 2 /MH | \$ 127.80 | \$ 256 | \$ 256 |
| | | | Remove PV panel and place in dumpster | | 180 EA | | | | 90 /MH | \$ 127.80 | \$ 11,502 | \$ 11,502 |
| | | | Remove points where panel is fixed to roof | | 180 EA | | | | 40 /MH | \$ 127.80 | \$ 5,112 | \$ 5,112 |
| | | | Remove lightning projection and other auxiliary equipment | | 1 EA | | | | 17 /MH | \$ 127.80 | \$ 2,173 | \$ 2,173 |
| | | | Remove transformer | | 1 LT | | | | 7 /MH | \$ 127.80 | \$ 895 | \$ 895 |
| | | | Demolition | | | \$ - | \$ - | \$ - | | | \$ 34,199 | \$ 34,199 |
| | 18.00.00 | | Scrap Value | | | | | | | | | |
| | 18.10.00 | | Mixed Steel | | | | | | | | | |
| | | | Steel | 1 EA, inverter 402 kW | 0.13 TN | | \$ (23) | | /MH | | \$ (23) | \$ (23) |
| | | | Steel | Service rack components | 0.05 TN | | \$ (9) | | /MH | | \$ (9) | \$ (9) |
| | | | Steel | Conduit and fittings | 0.05 TN | | \$ (9) | | /MH | | \$ (9) | \$ (9) |
| | | | Steel | Transformers | 1.47 TN | | \$ (257) | | /MH | | \$ (257) | \$ (257) |
| | | | Steel | Roof ladder, 1@ 350 lb each | 0.02 TN | | \$ (4) | | /MH | | \$ (4) | \$ (4) |
| | 18.20.00 | | Stainless Steel | | | | | | | | | |
| | | | Stainless Steel | 1788 Racks, 13.61 lbs each | 1.23 TN | | \$ (1,442) | | /MH | | \$ (1,442) | \$ (1,442) |
| | 18.30.00 | | Copper | | | | | | | | | |
| | | | Copper | 1 EA, 402 kW inverter | 0.04 TN | | \$ (98) | | /MH | | \$ (98) | \$ (98) |
| | | | Copper | Wire | 0.27 TN | | \$ (659) | | /MH | | \$ (659) | \$ (659) |
| | | | Copper | Transformers | 0.7 TN | | \$ (1,708) | | /MH | | \$ (1,708) | \$ (1,708) |
| | 18.50.00 | | Aluminum | | | | | | | | | |
| | | | PV Module | 1788 Modules @ 8 lbs each | 1440 LB | | \$ (876) | | /MH | | \$ (876) | \$ (876) |
| | | | Conduit and fittings | 100 @ 1 lb each | 10.07 LB | | \$ (6) | | /MH | | \$ (6) | \$ (6) |
| | | | Scrap Value | | | \$ - | \$ (5,089) | \$ - | | | \$ - | \$ (5,089) |
| | 21.00.00 | | Civil Work | | | | | | | | | |
| | 21.19.00 | | Disposal | | | | | | | | | |
| | | | Dumpster, 40 CY Capacity | Concrete, PV panels, rubbish (panels to recycler) | 1 EA | \$ 1,800 | | | /MH | | \$ 1,800 | \$ 1,800 |
| | | | Dumpster, 40 CY Capacity | Fix point rods | 1 EA | \$ 900 | | | /MH | | \$ 900 | \$ 900 |
| | 21.20.00 | | Backfill | | | | | | | | | |
| | | | Foundation backfill, imported material fill | Backfill concrete pads | 7 /CY | \$ 280 | | | /MH | | \$ 280 | \$ 280 |
| | | | Civil Work | | | \$ 2,980 | \$ - | \$ - | | | \$ - | \$ 2,980 |
| | 24.00.00 | | Architectural | | | | | | | | | |
| | 24.37.00 | | Roofing | | | | | | | | | |
| | | | Roof repair at fix points | Installation | 180 EA | \$ 29,700 | | | /MH | | \$ - | \$ 29,700 |
| | | | Architectural | | | \$ 29,700 | \$ - | \$ - | | | \$ - | \$ 29,700 |
| Direct Costs | | | | | | | | | | | | \$ 61,789 |
| | 61.00.00 | | Construction Indirect | | | | | | | | | |
| | 61.99.00 | | Miscellaneous | | | | | | | | | |
| | | | Downspout / Chute | | 1 LS | \$ 25,000 | | | /MH | | \$ - | \$ 25,000 |
| | | | Construction Indirect | | | \$ 25,000 | \$ - | \$ - | | | \$ - | \$ 25,000 |
| Subtotal | | | | | | \$ 57,680 | \$ (5,089) | \$ - | | | \$ 34,199 | \$ 86,789 |
| | 91.00.00 | | Other Direct & Construction Indirect Costs | | | | | | | | | |
| | | 91.09 | Contractor's General and Administration Expense | | | | | | | | | \$ 6,075 |
| | | 91.10 | Contractor's Profit | | | | | | | | | \$ 8,679 |
| | | | | | | | | | | | | \$ 14,754 |
| Direct Costs + Construction Indirect Costs | | | | | | \$ 57,680 | \$ (5,089) | \$ - | | | \$ 34,199 | \$ 101,543 |
| | 93.00.00 | | Indirect Costs | | | | | | | | | |
| | | 93.1 | Engineering, Procurement, & Project Services | | | | | | | | | \$ 6,093 |
| | | 93.2 | Construction Management Support | | | | | | | | | \$ 2,031 |
| | | 93.3 | SDG&E Internal Costs | | | | | | | | | \$ 10,154 |
| | 95.00.00 | | Contingency | | | | | | | | | |
| | | 95.1 | Contingency on Subcontractor | | | \$ 8,652 | | | | | | \$ 8,652 |
| | | 95.2 | Contingency on Scrap Value | | | | \$ - | | | | | \$ - |
| | | 95.3 | Contingency on Material | | | | \$ - | | | | | \$ - |
| | | 95.4 | Contingency on Labor | | | | | | | \$ 5,130 | | \$ 5,130 |
| | | 95.5 | Contingency on Indirect | | | | | | | | | \$ 2,742 |
| Total | | | | | | \$ 66,332 | \$ (5,089) | \$ - | | | \$ 39,328 | \$ 136,345 |

San Diego Gas & Electric
Decommissioning Cost Estimates
PV Sites - Roof Mounted

| Project ID | Code | Customer | Address | PV Location | Tech. | Date Energized | Facility Nameplate (kW) | Panel Qty | | | | |
|--|----------|------------------|---|--|----------|------------------|-------------------------|---------------|-----------|-----------|------------|------------|
| 20 | EIR | SDG&E EIC (roof) | 4760 Clairemont Mesa Blvd, San Diego | Roof | PV | 1/5/2012 | 47.33 | 234 | | | | |
| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Crew Rate | Labor Cost | Total Cost |
| Roof top | 11.00.00 | 11.22.00 | Demolition Concrete | Electrical equipment (Transformer, inverter, etc.) pad | 7 /CY | | | | 8 /MH | \$ 140.47 | \$ 1,124 | \$ 1,124 |
| | 11.41.00 | | Electrical Equipment | | | | | | | | | |
| | | | Disconnect wiring and components at service rack | | 1 EA | | | | 8 /MH | \$ 127.80 | \$ 1,022 | \$ 1,022 |
| | | | Disconnect wiring at inverter | | 1 EA | | | | 2 /MH | \$ 127.80 | \$ 256 | \$ 256 |
| | | | Disconnect wiring at combiner boxes, remove boxes | | 2 EA | | | | 19 /MH | \$ 127.80 | \$ 2,428 | \$ 2,428 |
| | | | Pull wire from combiners to inverter | | 2 EA | | | | 14 /MH | \$ 127.80 | \$ 1,789 | \$ 1,789 |
| | | | Disconnect and remove wiring at PV panels | | 234 EA | | | | 35 /MH | \$ 127.80 | \$ 4,473 | \$ 4,473 |
| | | | Disconnect and remove grounding at PV panels and racks, | | | | | | | | | |
| | | | Remove ground rods | | 234 EA | | | | 9 /MH | \$ 127.80 | \$ 1,150 | \$ 1,150 |
| | | | Demo conduit from rack to tie point | | 1 EA | | | | 8 /MH | \$ 127.80 | \$ 1,022 | \$ 1,022 |
| | | | Demo conduit from rack to transformer | | 1 EA | | | | 6 /MH | \$ 127.80 | \$ 767 | \$ 767 |
| | | | Demo conduit from combiners to inverter | | 1 EA | | | | 34 /MH | \$ 127.80 | \$ 4,345 | \$ 4,345 |
| | | | Remove Conduits to inverters | | 1 EA | | | | 2 /MH | \$ 127.80 | \$ 256 | \$ 256 |
| | | | Remove inverters | | 1 EA | | | | 3 /MH | \$ 127.80 | \$ 383 | \$ 383 |
| | | | Remove PV panel and place in dumpster | | 234 EA | | | | 117 /MH | \$ 127.80 | \$ 14,953 | \$ 14,953 |
| | | | Remove points where panel is fixed to roof | | 234 EA | | | | 52 /MH | \$ 127.80 | \$ 6,646 | \$ 6,646 |
| | | | Remove lightning projection and other auxiliary equipment | | 1 EA | | | | 22 /MH | \$ 127.80 | \$ 2,812 | \$ 2,812 |
| | | | Remove transformer | | 1 LT | | | | 9 /MH | \$ 127.80 | \$ 1,150 | \$ 1,150 |
| | | | Demolition | | | \$ - | \$ - | \$ - | | | \$ 44,576 | \$ 44,576 |
| | 18.00.00 | 18.10.00 | Scrap Value Mixed Steel | | | | | | | | | |
| | | | Steel | 1 EA, inverter 402 kW | 0.16 TN | \$ (28) | | | /MH | | \$ (28) | \$ (28) |
| | | | Steel | Service rack components | 0.06 TN | \$ (11) | | | /MH | | \$ (11) | \$ (11) |
| | | | Steel | Conduit and fittings | 0.07 TN | \$ (12) | | | /MH | | \$ (12) | \$ (12) |
| | | | Steel | Transformers | 1.91 TN | \$ (334) | | | /MH | | \$ (334) | \$ (334) |
| | | | Steel | Roof ladder, 1@ 350 lb each | 0.02 TN | \$ (4) | | | /MH | | \$ (4) | \$ (4) |
| | | 18.20.00 | Stainless Steel | 1788 Racks, 13.61 lbs each | 1.59 TN | \$ (1,863) | | | /MH | | \$ (1,863) | \$ (1,863) |
| | | 18.30.00 | Copper | | | | | | | | | |
| | | | Copper | 1 EA, 402 kW inverter | 0.05 TN | \$ (122) | | | /MH | | \$ (122) | \$ (122) |
| | | | Copper | Wire | 0.36 TN | \$ (878) | | | /MH | | \$ (878) | \$ (878) |
| | | | Copper | Transformers | 0.91 TN | \$ (2,220) | | | /MH | | \$ (2,220) | \$ (2,220) |
| | | 18.50.00 | Aluminum | | | | | | | | | |
| | | | PV Module | 1788 Modules @ 8 lbs each | 1872 LB | \$ (1,139) | | | /MH | | \$ (1,139) | \$ (1,139) |
| | | | Conduit and fittings | 100 @ 1 lb each | 13.09 LB | \$ (8) | | | /MH | | \$ (8) | \$ (8) |
| | | | Scrap Value | | | \$ - | \$ (6,620) | \$ - | | | \$ - | \$ (6,620) |
| | 21.00.00 | 21.19.00 | Civil Work Disposal | | | | | | | | | |
| | | | Dumpster, 40 CY Capacity | Concrete, PV panels, rubbish (panels to recycler) | 1 EA | \$ 1,800 | | | /MH | | \$ 1,800 | \$ 1,800 |
| | | | Dumpster, 40 CY Capacity | Fix point rods | 1 EA | \$ 900 | | | /MH | | \$ 900 | \$ 900 |
| | | 21.20.00 | Backfill | Foundation backfill, imported material fill | 7 /CY | \$ 280 | | | /MH | | \$ 280 | \$ 280 |
| | | | Civil Work | Backfill concrete pads | | \$ 2,980 | \$ - | \$ - | | | \$ - | \$ 2,980 |
| | 24.00.00 | 24.37.00 | Architectural Roofing | | | | | | | | | |
| | | | Roof repair at fix points | Installation | 234 EA | \$ 38,610 | | | /MH | | \$ - | \$ 38,610 |
| | | | Architectural | | | \$ 38,610 | \$ - | \$ - | | | \$ - | \$ 38,610 |
| Direct Costs | | | | | | | | | | | | \$ 79,546 |
| | 61.00.00 | 61.99.00 | Construction Indirect Miscellaneous | | | | | | | | | |
| | | | Downspout / Chute | | 1 LS | \$ 25,000 | | | /MH | | \$ - | \$ 25,000 |
| | | | Construction Indirect | | | \$ 25,000 | \$ - | \$ - | | | \$ - | \$ 25,000 |
| Subtotal | | | | | | \$ 66,590 | \$ (6,620) | \$ - | | | \$ 44,576 | \$ 104,546 |
| | 91.00.00 | | Other Direct & Construction Indirect Costs | | | | | | | | | |
| | | 91.09 | Contractor's General and Administration Expense | | | | | | | | | \$ 7,318 |
| | | 91.10 | Contractor's Profit | | | | | | | | | \$ 10,455 |
| | | | | | | | | | | | | \$ 17,773 |
| Direct Costs + Construction Indirect Costs | | | | | | \$ 66,590 | \$ (6,620) | \$ - | | | \$ 44,576 | \$ 122,319 |
| | 93.00.00 | | Indirect Costs | | | | | | | | | |
| | | 93.1 | Engineering, Procurement, & Project Services | | | | | | | | | \$ 7,339 |
| | | 93.2 | Construction Management Support | | | | | | | | | \$ 2,446 |
| | | 93.3 | SDG&E Internal Costs | | | | | | | | | \$ 12,232 |
| | 95.00.00 | | Contingency | | | | | | | | | |
| | | 95.1 | Contingency on Subcontractor | | | \$ 9,989 | | | | | | \$ 9,989 |
| | | 95.2 | Contingency on Scrap Value | | | \$ - | | | | | | \$ - |
| | | 95.3 | Contingency on Material | | | \$ - | | | | | | \$ - |
| | | 95.4 | Contingency on Labor | | | | | | | \$ 6,686 | | \$ 6,686 |
| | | 95.5 | Contingency on Indirect | | | | | | | | | \$ 3,303 |
| Total | | | | | | \$ 76,579 | \$ (6,620) | \$ - | | | \$ 51,262 | \$ 164,314 |

San Diego Gas & Electric
Decommissioning Cost Estimates
PV Sites - Roof Mounted

| Project ID | Code | Customer | Address | PV Location | Tech. | Date Energized | Facility Nameplate (kW) | Panel Qty | | | | |
|------------|----------|------------------------|---|--|----------|------------------|-------------------------|---------------|-----------|-----------|------------|------------|
| 21 | UCR | UCSD - Revelle College | 9500 Gilman Dr, La Jolla | Roof | PV | 10/13/2011 | 40.70 | 196 | | | | |
| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Crew Rate | Labor Cost | Total Cost |
| Roof top | 11.00.00 | | Demolition | | | | | | | | | |
| | | 11.22.00 | Concrete | | | | | | | | | |
| | | | Concrete | Electrical equipment (Transformer, inverter, etc.) pad | 7 /CY | | | | 7 /MH | \$ 140.47 | \$ 983 | \$ 983 |
| | | 11.41.00 | Electrical Equipment | | | | | | | | | |
| | | | Disconnect wiring and components at service rack | | 1 EA | | | | 7 /MH | \$ 127.80 | \$ 895 | \$ 895 |
| | | | Disconnect wiring at inverter | | 1 EA | | | | 2 /MH | \$ 127.80 | \$ 256 | \$ 256 |
| | | | Disconnect wiring at combiner boxes, remove boxes | | 1 EA | | | | 16 /MH | \$ 127.80 | \$ 2,045 | \$ 2,045 |
| | | | Pull wire from combiners to inverter | | 1 EA | | | | 11 /MH | \$ 127.80 | \$ 1,406 | \$ 1,406 |
| | | | Disconnect and remove wiring at PV panels | | 196 EA | | | | 29 /MH | \$ 127.80 | \$ 3,706 | \$ 3,706 |
| | | | Disconnect and remove grounding at PV panels and racks, | | | | | | | | | |
| | | | Remove ground rods | | 196 EA | | | | 8 /MH | \$ 127.80 | \$ 1,022 | \$ 1,022 |
| | | | Demo conduit from rack to tie point | | 1 EA | | | | 7 /MH | \$ 127.80 | \$ 895 | \$ 895 |
| | | | Demo conduit from rack to transformer | | 1 EA | | | | 5 /MH | \$ 127.80 | \$ 639 | \$ 639 |
| | | | Demo conduit from combiners to inverter | | 1 EA | | | | 28 /MH | \$ 127.80 | \$ 3,578 | \$ 3,578 |
| | | | Remove Conduits to inverters | | 1 EA | | | | 2 /MH | \$ 127.80 | \$ 256 | \$ 256 |
| | | | Remove inverters | | 1 EA | | | | 3 /MH | \$ 127.80 | \$ 383 | \$ 383 |
| | | | Remove PV panel and place in dumpster | | 196 EA | | | | 98 /MH | \$ 127.80 | \$ 12,524 | \$ 12,524 |
| | | | Remove points where panel is fixed to roof | | 196 EA | | | | 44 /MH | \$ 127.80 | \$ 5,623 | \$ 5,623 |
| | | | Remove lightning projection and other auxiliary equipment | | 1 EA | | | | 18 /MH | \$ 127.80 | \$ 2,300 | \$ 2,300 |
| | | | Remove transformer | | 1 LT | | | | 7 /MH | \$ 127.80 | \$ 895 | \$ 895 |
| | | | Demolition | | | \$ - | \$ - | \$ - | | | \$ 37,406 | \$ 37,406 |
| | 18.00.00 | | Scrap Value | | | | | | | | | |
| | | 18.10.00 | Mixed Steel | | | | | | | | | |
| | | | Steel | 1 EA, inverter 402 kW | 0.14 TN | \$ (25) | | | /MH | | \$ (25) | \$ (25) |
| | | | Steel | Service rack components | 0.05 TN | \$ (9) | | | /MH | | \$ (9) | \$ (9) |
| | | | Steel | Conduit and fittings | 0.05 TN | \$ (9) | | | /MH | | \$ (9) | \$ (9) |
| | | | Steel | Transformers | 1.6 TN | \$ (280) | | | /MH | | \$ (280) | \$ (280) |
| | | | Steel | Roof ladder, 1@ 350 lb each | 0.02 TN | \$ (4) | | | /MH | | \$ (4) | \$ (4) |
| | | 18.20.00 | Stainless Steel | | | | | | | | | |
| | | | Stainless Steel | 1788 Racks, 13.61 lbs each | 1.33 TN | \$ (1,559) | | | /MH | | \$ (1,559) | \$ (1,559) |
| | | 18.30.00 | Copper | | | | | | | | | |
| | | | Copper | 1 EA, 402 kW inverter | 0.04 TN | \$ (98) | | | /MH | | \$ (98) | \$ (98) |
| | | | Copper | Wire | 0.3 TN | \$ (732) | | | /MH | | \$ (732) | \$ (732) |
| | | | Copper | Transformers | 0.76 TN | \$ (1,854) | | | /MH | | \$ (1,854) | \$ (1,854) |
| | | 18.50.00 | Aluminum | | | | | | | | | |
| | | | PV Module | 1788 Modules @ 8 lbs each | 1568 LB | \$ (954) | | | /MH | | \$ (954) | \$ (954) |
| | | | Conduit and fittings | 100 @ 1 lb each | 10.96 LB | \$ (7) | | | /MH | | \$ (7) | \$ (7) |
| | | | Scrap Value | | | \$ - | \$ (5,529) | \$ - | | | \$ - | \$ (5,529) |
| | 21.00.00 | | Civil Work | | | | | | | | | |
| | | 21.19.00 | Disposal | | | | | | | | | |
| | | | Dumpster, 40 CY Capacity | Concrete, PV panels, rubbish (panels to recycler) | 1 EA | \$ 1,800 | | | /MH | | \$ 1,800 | \$ 1,800 |
| | | | Dumpster, 40 CY Capacity | Fix point rods | 1 EA | \$ 900 | | | /MH | | \$ 900 | \$ 900 |
| | | 21.20.00 | Backfill | | | | | | | | | |
| | | | Foundation backfill, imported material fill | Backfill concrete pads | 7 /CY | \$ 280 | | | /MH | | \$ 280 | \$ 280 |
| | | | Civil Work | | | \$ 2,980 | \$ - | \$ - | | | \$ - | \$ 2,980 |
| | 24.00.00 | | Architectural | | | | | | | | | |
| | | 24.37.00 | Roofing | | | | | | | | | |
| | | | Roof repair at fix points | Installation | 196 EA | \$ 32,340 | | | /MH | | \$ - | \$ 32,340 |
| | | | Architectural | | | \$ 32,340 | \$ - | \$ - | | | \$ - | \$ 32,340 |
| | | | Direct Costs | | | | | | | | | \$ 67,197 |
| | 61.00.00 | | Construction Indirect | | | | | | | | | |
| | | 61.99.00 | Miscellaneous | | | | | | | | | |
| | | | Downspout / Chute | | 1 LS | \$ 25,000 | | | /MH | | \$ 25,000 | \$ 25,000 |
| | | | Construction Indirect | | | \$ 25,000 | \$ - | \$ - | | | \$ - | \$ 25,000 |
| | | | Subtotal | | | \$ 60,320 | \$ (5,529) | \$ - | | | \$ 37,406 | \$ 92,197 |
| | 91.00.00 | | Other Direct & Construction Indirect Costs | | | | | | | | | |
| | | 91.09 | Contractor's General and Administration Expense | | | | | | | | | \$ 6,454 |
| | | 91.10 | Contractor's Profit | | | | | | | | | \$ 9,220 |
| | | | | | | | | | | | | \$ 15,674 |
| | | | Direct Costs + Construction Indirect Costs | | | \$ 60,320 | \$ (5,529) | \$ - | | | \$ 37,406 | \$ 107,871 |
| | 93.00.00 | | Indirect Costs | | | | | | | | | |
| | | 93.1 | Engineering, Procurement, & Project Services | | | | | | | | | \$ 6,472 |
| | | 93.2 | Construction Management Support | | | | | | | | | \$ 2,157 |
| | | 93.3 | SDG&E Internal Costs | | | | | | | | | \$ 10,787 |
| | 95.00.00 | | Contingency | | | | | | | | | |
| | | 95.1 | Contingency on Subcontractor | | | \$ 9,048 | | | | | | \$ 9,048 |
| | | 95.2 | Contingency on Scrap Value | | | \$ - | | | | | | \$ - |
| | | 95.3 | Contingency on Material | | | | \$ - | | | | | \$ - |
| | | 95.4 | Contingency on Labor | | | | | | | | \$ 5,611 | \$ 5,611 |
| | | 95.5 | Contingency on Indirect | | | | | | | | | \$ 2,913 |
| | | | Total | | | \$ 69,368 | \$ (5,529) | \$ - | | | \$ 43,017 | \$ 144,859 |

San Diego Gas & Electric
 Decommissioning Cost Estimates
 PV Sites - Roof Mounted

| Project ID | Code | Customer | Address | PV Location | Tech. | Date Energized | Facility Nameplate (kW) | Panel Qty | | | | | | |
|-------------|--------------|--------------|--|--|-----------------|-------------------------|-------------------------|----------------------|------------------|------------------|-------------------|-------------------|------------|--|
| 22 | SLD | Soledad | 6465 Nancy Ridge Rd, San Diego | Roof | PV | 1/30/2012 | 99.58 | 462 | | | | | | |
| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Crew Rate | Labor Cost | Total Cost | | |
| Roof top | 11.00.00 | 11.22.00 | Demolition | | | | | | | | | | | |
| | | | Concrete | Electrical equipment (Transformer, inverter, etc.) pad | 7 /CY | | | | 16 /MH | \$ 140.47 | \$ 2,248 | \$ 2,248 | | |
| | 11.41.00 | | Electrical Equipment | | | | | | | | | | | |
| | | | Disconnect wiring and components at service rack | | 1 EA | | | | 17 /MH | \$ 127.80 | \$ 2,173 | \$ 2,173 | | |
| | | | Disconnect wiring at inverter | | 1 EA | | | | 4 /MH | \$ 127.80 | \$ 511 | \$ 511 | | |
| | | | Disconnect wiring at combiner boxes, remove boxes | | 3 EA | | | | 37 /MH | \$ 127.80 | \$ 4,729 | \$ 4,729 | | |
| | | | Pull wire from combiners to inverter | | 3 EA | | | | 27 /MH | \$ 127.80 | \$ 3,451 | \$ 3,451 | | |
| | | | Disconnect and remove wiring at PV panels | | 462 EA | | | | 69 /MH | \$ 127.80 | \$ 8,818 | \$ 8,818 | | |
| | | | Disconnect and remove grounding at PV panels and racks, Remove ground rods | | 462 EA | | | | 19 /MH | \$ 127.80 | \$ 2,428 | \$ 2,428 | | |
| | | | Demo conduit from rack to tie point | | 1 EA | | | | 17 /MH | \$ 127.80 | \$ 2,173 | \$ 2,173 | | |
| | | | Demo conduit from rack to transformer | | 1 EA | | | | 12 /MH | \$ 127.80 | \$ 1,534 | \$ 1,534 | | |
| | | | Demo conduit from combiners to inverter | | 1 EA | | | | 66 /MH | \$ 127.80 | \$ 8,435 | \$ 8,435 | | |
| | | | Remove Conduits to inverters | | 1 EA | | | | 4 /MH | \$ 127.80 | \$ 511 | \$ 511 | | |
| | | | Remove inverters | | 1 EA | | | | 6 /MH | \$ 127.80 | \$ 767 | \$ 767 | | |
| | | | Remove PV panel and place in dumpster | | 462 EA | | | | 231 /MH | \$ 127.80 | \$ 29,522 | \$ 29,522 | | |
| | | | Remove points where panel is fixed to roof | | 462 EA | | | | 103 /MH | \$ 127.80 | \$ 13,163 | \$ 13,163 | | |
| | | | Remove lightning projection and other auxiliary equipment | | 1 EA | | | | 43 /MH | \$ 127.80 | \$ 5,495 | \$ 5,495 | | |
| | | | Remove transformer | | 1 LT | | | | 17 /MH | \$ 127.80 | \$ 2,173 | \$ 2,173 | | |
| | | | Demolition | | | \$ - | \$ - | \$ - | | | \$ 88,129 | \$ 88,129 | | |
| | 18.00.00 | | Scrap Value | | | | | | | | | | | |
| | | 18.10.00 | Mixed Steel | | | | | | | | | | | |
| | | | Steel | 1 EA, inverter 402 kW | 0.32 TN | \$ (56) | | | /MH | | \$ (56) | \$ (56) | | |
| | | | Steel | Service rack components | 0.12 TN | \$ (21) | | | /MH | | \$ (21) | \$ (21) | | |
| | | | Steel | Conduit and fittings | 0.13 TN | \$ (23) | | | /MH | | \$ (23) | \$ (23) | | |
| | | | Steel | Transformers | 3.76 TN | \$ (658) | | | /MH | | \$ (658) | \$ (658) | | |
| | | | Steel | Roof ladder, 1@ 350 lb each | 0.05 TN | \$ (9) | | | /MH | | \$ (9) | \$ (9) | | |
| | | 18.20.00 | Stainless Steel | | | | | | | | | | | |
| | | | Stainless Steel | 1788 Racks, 13.61 lbs each | 3.14 TN | \$ (3,680) | | | /MH | | \$ (3,680) | \$ (3,680) | | |
| | | 18.30.00 | Copper | | | | | | | | | | | |
| | | | Copper | 1 EA, 402 kW inverter | 0.1 TN | \$ (244) | | | /MH | | \$ (244) | \$ (244) | | |
| | | | Copper | Wire | 0.7 TN | \$ (1,708) | | | /MH | | \$ (1,708) | \$ (1,708) | | |
| | | | Copper | Transformers | 1.79 TN | \$ (4,368) | | | /MH | | \$ (4,368) | \$ (4,368) | | |
| | | 18.50.00 | Aluminum | | | | | | | | | | | |
| | | | PV Module | 1788 Modules @ 8 lbs each | 3696 LB | \$ (2,249) | | | /MH | | \$ (2,249) | \$ (2,249) | | |
| | | | Conduit and fittings | 100 @ 1 lb each | 25.84 LB | \$ (16) | | | /MH | | \$ (16) | \$ (16) | | |
| | | | Scrap Value | | | \$ - | \$ (13,031) | \$ - | | | \$ - | \$ (13,031) | | |
| | 21.00.00 | | Civil Work | | | | | | | | | | | |
| | | 21.19.00 | Disposal | | | | | | | | | | | |
| | | | Dumpster, 40 CY Capacity | Concrete, PV panels, rubbish (panels to recycler) | 3 EA | \$ 5,400 | | | /MH | | \$ 5,400 | \$ 5,400 | | |
| | | | Dumpster, 40 CY Capacity | Fix point rods | 1 EA | \$ 900 | | | /MH | | \$ 900 | \$ 900 | | |
| | | 21.20.00 | Backfill | | | | | | | | | | | |
| | | | Foundation backfill, imported material fill | Backfill concrete pads | 7 /CY | \$ 280 | | | /MH | | \$ 280 | \$ 280 | | |
| | | | Civil Work | | | \$ 6,580 | \$ - | \$ - | | | \$ - | \$ 6,580 | | |
| | 24.00.00 | | Architectural | | | | | | | | | | | |
| | | 24.37.00 | Roofing | | | | | | | | | | | |
| | | | Roof repair at fix points | Installation | 462 EA | \$ 76,230 | | | /MH | | \$ - | \$ 76,230 | | |
| | | | Architectural | | | \$ 76,230 | \$ - | \$ - | | | \$ - | \$ 76,230 | | |
| | | | Direct Costs | | | | | | | | | | \$ 157,908 | |
| | 61.00.00 | | Construction Indirect | | | | | | | | | | | |
| | | 61.99.00 | Miscellaneous | | | | | | | | | | | |
| | | | Downspout / Chute | | 1 LS | \$ 25,000 | | | /MH | | \$ 25,000 | \$ 25,000 | | |
| | | | Construction Indirect | | | \$ 25,000 | \$ - | \$ - | | | \$ - | \$ 25,000 | | |
| | | | Subtotal | | | \$ 107,810 | \$ (13,031) | \$ - | | | \$ 88,129 | \$ 182,908 | | |
| | 91.00.00 | | Other Direct & Construction Indirect Costs | | | | | | | | | | | |
| | | 91.09 | Contractor's General and Administration Expense | | | | | | | | | \$ 12,804 | \$ 12,804 | |
| | | 91.10 | Contractor's Profit | | | | | | | | | \$ 18,291 | \$ 18,291 | |
| | | | | | | | | | | | | \$ 31,094 | \$ 31,094 | |
| | | | Direct Costs + Construction Indirect Costs | | | \$ 107,810 | \$ (13,031) | \$ - | | | \$ 88,129 | \$ 214,003 | | |
| | 93.00.00 | | Indirect Costs | | | | | | | | | | | |
| | | 93.1 | Engineering, Procurement, & Project Services | | | | | | | | | \$ 12,840 | \$ 12,840 | |
| | | 93.2 | Construction Management Support | | | | | | | | | \$ 4,280 | \$ 4,280 | |
| | | 93.3 | SDG&E Internal Costs | | | | | | | | | \$ 21,400 | \$ 21,400 | |
| | 95.00.00 | | Contingency | | | | | | | | | | | |
| | | 95.1 | Contingency on Subcontractor | | | \$ 16,172 | | | | | | \$ 16,172 | \$ 16,172 | |
| | | 95.2 | Contingency on Scrap Value | | | \$ - | | | | | | \$ - | \$ - | |
| | | 95.3 | Contingency on Material | | | \$ - | | | | | | \$ - | \$ - | |
| | | 95.4 | Contingency on Labor | | | | | | | | \$ 13,219 | \$ 13,219 | \$ 13,219 | |
| | | 95.5 | Contingency on Indirect | | | | | | | | | \$ 5,778 | \$ 5,778 | |
| | | | Total | | | \$ 123,982 | \$ (13,031) | \$ - | | | \$ 101,348 | \$ 287,692 | | |

San Diego Gas & Electric
Decommissioning Cost Estimates
PV Sites - Roof Mounted

| Project ID | Code | Customer | Address | PV Location | Tech. | Date Energized | Facility Nameplate (kW) | Panel Qty | | | | |
|--|----------|-----------------|---|--|----------|------------------|-------------------------|---------------|-----------|-----------|------------|-------------|
| 23 | PST | Pacific Station | 687 South Coast Highway 101, Encinitas | Roof | PV | 5/15/2012 | 109 | 498 | | | | |
| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Crew Rate | Labor Cost | Total Cost |
| Roof top | 11.00.00 | 11.22.00 | Demolition Concrete | Electrical equipment (Transformer, inverter, etc.) pad | 7 /CY | | | | 17 /MH | \$ 140.47 | \$ 2,388 | \$ 2,388 |
| | 11.41.00 | | Electrical Equipment | | | | | | | | | |
| | | | Disconnect wiring and components at service rack | | 1 EA | | | | 18 /MH | \$ 127.80 | \$ 2,300 | \$ 2,300 |
| | | | Disconnect wiring at inverter | | 1 EA | | | | 4 /MH | \$ 127.80 | \$ 511 | \$ 511 |
| | | | Disconnect wiring at combiner boxes, remove boxes | | 4 EA | | | | 40 /MH | \$ 127.80 | \$ 5,112 | \$ 5,112 |
| | | | Pull wire from combiners to inverter | | 4 EA | | | | 29 /MH | \$ 127.80 | \$ 3,706 | \$ 3,706 |
| | | | Disconnect and remove wiring at PV panels | | 498 EA | | | | 75 /MH | \$ 127.80 | \$ 9,585 | \$ 9,585 |
| | | | Disconnect and remove grounding at PV panels and racks, | | | | | | | | | |
| | | | Remove ground rods | | 498 EA | | | | 20 /MH | \$ 127.80 | \$ 2,556 | \$ 2,556 |
| | | | Demo conduit from rack to tie point | | 1 EA | | | | 18 /MH | \$ 127.80 | \$ 2,300 | \$ 2,300 |
| | | | Demo conduit from rack to transformer | | 1 EA | | | | 13 /MH | \$ 127.80 | \$ 1,661 | \$ 1,661 |
| | | | Demo conduit from combiners to inverter | | 1 EA | | | | 71 /MH | \$ 127.80 | \$ 9,074 | \$ 9,074 |
| | | | Remove Conduits to inverters | | 1 EA | | | | 4 /MH | \$ 127.80 | \$ 511 | \$ 511 |
| | | | Remove inverters | | 1 EA | | | | 7 /MH | \$ 127.80 | \$ 895 | \$ 895 |
| | | | Remove PV panel and place in dumpster | | 498 EA | | | | 249 /MH | \$ 127.80 | \$ 31,822 | \$ 31,822 |
| | | | Remove points where panel is fixed to roof | | 498 EA | | | | 111 /MH | \$ 127.80 | \$ 14,186 | \$ 14,186 |
| | | | Remove lightning projection and other auxiliary equipment | | 1 EA | | | | 47 /MH | \$ 127.80 | \$ 6,007 | \$ 6,007 |
| | | | Remove transformer | | 1 LT | | | | 18 /MH | \$ 127.80 | \$ 2,300 | \$ 2,300 |
| | | | Demolition | | | \$ - | \$ - | \$ - | | | \$ 94,915 | \$ 94,915 |
| | 18.00.00 | | Scrap Value | | | | | | | | | |
| | 18.10.00 | | Mixed Steel | | | | | | | | | |
| | | | Steel | 1 EA, inverter 402 kW | 0.35 TN | \$ (61) | | | /MH | | \$ (61) | \$ (61) |
| | | | Steel | Service rack components | 0.13 TN | \$ (23) | | | /MH | | \$ (23) | \$ (23) |
| | | | Steel | Conduit and fittings | 0.14 TN | \$ (25) | | | /MH | | \$ (25) | \$ (25) |
| | | | Steel | Transformers | 4.06 TN | \$ (711) | | | /MH | | \$ (711) | \$ (711) |
| | | | Steel | Roof ladder, 1@ 350 lb each | 0.05 TN | \$ (9) | | | /MH | | \$ (9) | \$ (9) |
| | 18.20.00 | | Stainless Steel | | | | | | | | | |
| | | | Stainless Steel | 1788 Racks, 13.61 lbs each | 3.39 TN | \$ (3,973) | | | /MH | | \$ (3,973) | \$ (3,973) |
| | 18.30.00 | | Copper | | | | | | | | | |
| | | | Copper | 1 EA, 402 kW inverter | 0.11 TN | \$ (268) | | | /MH | | \$ (268) | \$ (268) |
| | | | Copper | Wire | 0.76 TN | \$ (1,854) | | | /MH | | \$ (1,854) | \$ (1,854) |
| | | | Copper | Transformers | 1.93 TN | \$ (4,709) | | | /MH | | \$ (4,709) | \$ (4,709) |
| | 18.50.00 | | Aluminum | | | | | | | | | |
| | | | PV Module | 1788 Modules @ 8 lbs each | 3984 LB | \$ (2,424) | | | /MH | | \$ (2,424) | \$ (2,424) |
| | | | Conduit and fittings | 100 @ 1 lb each | 27.85 LB | \$ (17) | | | /MH | | \$ (17) | \$ (17) |
| | | | Scrap Value | | | \$ - | \$ (14,074) | \$ - | | | \$ - | \$ (14,074) |
| | 21.00.00 | | Civil Work | | | | | | | | | |
| | 21.19.00 | | Disposal | | | | | | | | | |
| | | | Dumpster, 40 CY Capacity | Concrete, PV panels, rubbish (panels to recycler) | 3 EA | \$ 5,400 | | | /MH | | \$ 5,400 | \$ 5,400 |
| | | | Dumpster, 40 CY Capacity | Fix point rods | 1 EA | \$ 900 | | | /MH | | \$ 900 | \$ 900 |
| | 21.20.00 | | Backfill | | | | | | | | | |
| | | | Foundation backfill, imported material fill | Backfill concrete pads | 7 /CY | \$ 280 | | | /MH | | \$ 280 | \$ 280 |
| | | | Civil Work | | | \$ 6,580 | \$ - | \$ - | | | \$ - | \$ 6,580 |
| | 24.00.00 | | Architectural | | | | | | | | | |
| | 24.37.00 | | Roofing | | | | | | | | | |
| | | | Roof repair at fix points | Installation | 498 EA | \$ 82,170 | | | /MH | | \$ - | \$ 82,170 |
| | | | Architectural | | | \$ 82,170 | \$ - | \$ - | | | \$ - | \$ 82,170 |
| Direct Costs | | | | | | | | | | | | \$ 169,591 |
| | 61.00.00 | | Construction Indirect | | | | | | | | | |
| | 61.99.00 | | Miscellaneous | | | | | | | | | |
| | | | Downspout / Chute | | 1 LS | \$ 25,000 | | | /MH | | \$ - | \$ 25,000 |
| | | | Construction Indirect | | | \$ 25,000 | \$ - | \$ - | | | \$ - | \$ 25,000 |
| Subtotal | | | | | | \$ 113,750 | \$ (14,074) | \$ - | | | \$ 94,915 | \$ 194,591 |
| | 91.00.00 | | Other Direct & Construction Indirect Costs | | | | | | | | | |
| | | | 91.09 Contractor's General and Administration Expense | | | | | | | | | \$ 13,621 |
| | | | 91.10 Contractor's Profit | | | | | | | | | \$ 19,459 |
| | | | | | | | | | | | | \$ 33,080 |
| Direct Costs + Construction Indirect Costs | | | | | | \$ 113,750 | \$ (14,074) | \$ - | | | \$ 94,915 | \$ 227,672 |
| | 93.00.00 | | Indirect Costs | | | | | | | | | |
| | | | 93.1 Engineering, Procurement, & Project Services | | | | | | | | | \$ 13,660 |
| | | | 93.2 Construction Management Support | | | | | | | | | \$ 4,553 |
| | | | 93.3 SDG&E Internal Costs | | | | | | | | | \$ 22,767 |
| | 95.00.00 | | Contingency | | | | | | | | | |
| | | | 95.1 Contingency on Subcontractor | | | \$ 17,063 | | | | | | \$ 17,063 |
| | | | 95.2 Contingency on Scrap Value | | | \$ - | | | | | | \$ - |
| | | | 95.3 Contingency on Material | | | \$ - | | | | | | \$ - |
| | | | 95.4 Contingency on Labor | | | | | | | | \$ 14,237 | \$ 14,237 |
| | | | 95.5 Contingency on Indirect | | | | | | | | | \$ 6,147 |
| Total | | | | | | \$ 130,813 | \$ (14,074) | \$ - | | | \$ 109,152 | \$ 306,099 |

San Diego Gas & Electric
Decommissioning Cost Estimates
PV Sites - Roof Mounted

| Project ID | Code | Customer | Address | PV Location | Tech. | Date Energized | Facility Nameplate (kW) | Panel Qty | | | | | |
|------------|----------|------------------------------------|---|--|----------|------------------|-------------------------|---------------|-----------|-----------|------------|-------------|--|
| 24 | UCS | UCSD - Structural & Materials Engr | Voigt Drive and Matthews Lane | Roof | PV | 10/22/2012 | 119.93 | 566 | | | | | |
| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Crew Rate | Labor Cost | Total Cost | |
| Roof top | 11.00.00 | | Demolition | | | | | | | | | | |
| | 11.22.00 | | Concrete | Electrical equipment (Transformer, inverter, etc.) pad | 7 /CY | | | | 19 /MH | \$ 140.47 | \$ 2,669 | \$ 2,669 | |
| | 11.41.00 | | Electrical Equipment | | | | | | | | | | |
| | | | Disconnect wiring and components at service rack | | 1 EA | | | | 20 /MH | \$ 127.80 | \$ 2,556 | \$ 2,556 | |
| | | | Disconnect wiring at inverter | | 1 EA | | | | 5 /MH | \$ 127.80 | \$ 639 | \$ 639 | |
| | | | Disconnect wiring at combiner boxes, remove boxes | | 4 EA | | | | 45 /MH | \$ 127.80 | \$ 5,751 | \$ 5,751 | |
| | | | Pull wire from combiners to inverter | | 4 EA | | | | 33 /MH | \$ 127.80 | \$ 4,217 | \$ 4,217 | |
| | | | Disconnect and remove wiring at PV panels | | 566 EA | | | | 85 /MH | \$ 127.80 | \$ 10,863 | \$ 10,863 | |
| | | | Disconnect and remove grounding at PV panels and racks, | | | | | | | | | | |
| | | | Remove ground rods | | 566 EA | | | | 23 /MH | \$ 127.80 | \$ 2,939 | \$ 2,939 | |
| | | | Demo conduit from rack to tie point | | 1 EA | | | | 20 /MH | \$ 127.80 | \$ 2,556 | \$ 2,556 | |
| | | | Demo conduit from rack to transformer | | 1 EA | | | | 15 /MH | \$ 127.80 | \$ 1,917 | \$ 1,917 | |
| | | | Demo conduit from combiners to inverter | | 1 EA | | | | 81 /MH | \$ 127.80 | \$ 10,352 | \$ 10,352 | |
| | | | Remove Conduits to inverters | | 1 EA | | | | 5 /MH | \$ 127.80 | \$ 639 | \$ 639 | |
| | | | Remove inverters | | 1 EA | | | | 8 /MH | \$ 127.80 | \$ 1,022 | \$ 1,022 | |
| | | | Remove PV panel and place in dumpster | | 566 EA | | | | 283 /MH | \$ 127.80 | \$ 36,167 | \$ 36,167 | |
| | | | Remove points where panel is fixed to roof | | 566 EA | | | | 127 /MH | \$ 127.80 | \$ 16,231 | \$ 16,231 | |
| | | | Remove lightning projection and other auxiliary equipment | | 1 EA | | | | 53 /MH | \$ 127.80 | \$ 6,773 | \$ 6,773 | |
| | | | Remove transformer | | 1 LT | | | | 21 /MH | \$ 127.80 | \$ 2,684 | \$ 2,684 | |
| | | | Demolition | | | \$ - | \$ - | \$ - | | | \$ 107,976 | \$ 107,976 | |
| | 18.00.00 | | Scrap Value | | | | | | | | | | |
| | 18.10.00 | | Mixed Steel | | | | | | | | | | |
| | | | Steel | 1 EA, inverter 402 kW | 0.4 TN | \$ (70) | | | /MH | | | \$ (70) | |
| | | | Steel | Service rack components | 0.15 TN | \$ (26) | | | /MH | | | \$ (26) | |
| | | | Steel | Conduit and fittings | 0.16 TN | \$ (28) | | | /MH | | | \$ (28) | |
| | | | Steel | Transformers | 4.61 TN | \$ (807) | | | /MH | | | \$ (807) | |
| | | | Steel | Roof ladder, 1@ 350 lb each | 0.06 TN | \$ (11) | | | /MH | | | \$ (11) | |
| | 18.20.00 | | Stainless Steel | | | | | | | | | | |
| | | | Stainless Steel | 1788 Racks, 13.61 lbs each | 3.85 TN | \$ (4,512) | | | /MH | | | \$ (4,512) | |
| | 18.30.00 | | Copper | | | | | | | | | | |
| | | | Copper | 1 EA, 402 kW inverter | 0.13 TN | \$ (317) | | | /MH | | | \$ (317) | |
| | | | Copper | Wire | 0.86 TN | \$ (2,098) | | | /MH | | | \$ (2,098) | |
| | | | Copper | Transformers | 2.19 TN | \$ (5,344) | | | /MH | | | \$ (5,344) | |
| | 18.50.00 | | Aluminum | | | | | | | | | | |
| | | | PV Module | 1788 Modules @ 8 lbs each | 4528 LB | \$ (2,755) | | | /MH | | | \$ (2,755) | |
| | | | Conduit and fittings | 100 @ 1 lb each | 31.66 LB | \$ (19) | | | /MH | | | \$ (19) | |
| | | | Scrap Value | | | \$ - | \$ (15,987) | \$ - | | | \$ - | \$ (15,987) | |
| | 21.00.00 | | Civil Work | | | | | | | | | | |
| | 21.19.00 | | Disposal | | | | | | | | | | |
| | | | Dumpster, 40 CY Capacity | Concrete, PV panels, rubbish (panels to recycler) | 3 EA | \$ 5,400 | | | /MH | | | \$ 5,400 | |
| | | | Dumpster, 40 CY Capacity | Fix point rods | 1 EA | \$ 900 | | | /MH | | | \$ 900 | |
| | 21.20.00 | | Backfill | | | | | | | | | | |
| | | | Foundation backfill, imported material fill | Backfill concrete pads | 7 /CY | \$ 280 | | | /MH | | | \$ 280 | |
| | | | Civil Work | | | \$ 6,580 | \$ - | \$ - | | | \$ - | \$ 6,580 | |
| | 24.00.00 | | Architectural | | | | | | | | | | |
| | 24.37.00 | | Roofing | | | | | | | | | | |
| | | | Roof repair at fix points | Installation | 566 EA | \$ 93,390 | | | /MH | | \$ - | \$ 93,390 | |
| | | | Architectural | | | \$ 93,390 | \$ - | \$ - | | | \$ - | \$ 93,390 | |
| | | | Direct Costs | | | | | | | | | \$ 191,959 | |
| | 61.00.00 | | Construction Indirect | | | | | | | | | | |
| | 61.99.00 | | Miscellaneous | | | | | | | | | | |
| | | | Downspout / Chute | | 1 LS | \$ 25,000 | | | /MH | | | \$ 25,000 | |
| | | | Construction Indirect | | | \$ 25,000 | \$ - | \$ - | | | \$ - | \$ 25,000 | |
| | | | Subtotal | | | \$ 124,970 | \$ (15,987) | \$ - | | | \$ 107,976 | \$ 216,959 | |
| | 91.00.00 | | Other Direct & Construction Indirect Costs | | | | | | | | | | |
| | | | 91.09 Contractor's General and Administration Expense | | | | | | | | | \$ 15,187 | |
| | | | 91.10 Contractor's Profit | | | | | | | | | \$ 21,696 | |
| | | | | | | | | | | | | \$ 36,883 | |
| | | | Direct Costs + Construction Indirect Costs | | | \$ 124,970 | \$ (15,987) | \$ - | | | \$ 107,976 | \$ 253,842 | |
| | 93.00.00 | | Indirect Costs | | | | | | | | | | |
| | | | 93.1 Engineering, Procurement, & Project Services | | | | | | | | | \$ 15,230 | |
| | | | 93.2 Construction Management Support | | | | | | | | | \$ 5,077 | |
| | | | 93.3 SDG&E Internal Costs | | | | | | | | | \$ 25,384 | |
| | 95.00.00 | | Contingency | | | | | | | | | | |
| | | | 95.1 Contingency on Subcontractor | | | \$ 18,746 | | | | | | \$ 18,746 | |
| | | | 95.2 Contingency on Scrap Value | | | \$ - | | | | | | \$ - | |
| | | | 95.3 Contingency on Material | | | \$ - | \$ - | | | | \$ 16,196 | \$ 16,196 | |
| | | | 95.4 Contingency on Labor | | | | | | | | | \$ - | |
| | | | 95.5 Contingency on Indirect | | | | | | | | | \$ 6,854 | |
| | | | Total | | | \$ 143,716 | \$ (15,987) | \$ - | | | \$ 124,173 | \$ 341,329 | |

San Diego Gas & Electric
Decommissioning Cost Estimates
PV Sites - Roof Mounted

| Project ID | Code | Customer | Address | PV Location | Tech. | Date Energized | Facility Nameplate (kW) | Panel Qty | | | | | | |
|------------|----------|------------|--|--|--|---|-------------------------|---------------|---|--|---|---|--|--|
| 25 | UCM | UCSD MESOM | 8880 Biological Grade, La Jolla, CA | Roof | PV/ES | 6/14/2013 | 61.10 | 292 | | | | | | |
| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Crew Rate | Labor Cost | Total Cost | | |
| Roof top | 11.00.00 | 11.22.00 | Demolition Concrete | Electrical equipment (Transformer, inverter, etc.) pad | 7 /CY | | | | 10 /MH | \$ 140.47 | \$ 1,405 | \$ 1,405 | | |
| | 11.41.00 | | Electrical Equipment Disconnect wiring and components at service rack Disconnect wiring at inverter Disconnect wiring at combiner boxes, remove boxes Pull wire from combiners to inverter Disconnect and remove wiring at PV panels Disconnect and remove grounding at PV panels and racks, Remove ground rods Demo conduit from rack to tie point Demo conduit from rack to transformer Demo conduit from combiners to inverter Remove Conduits to inverters Remove inverters Remove PV panel and place in dumpster Remove points where panel is fixed to roof Remove lightning projection and other auxiliary equipment Remove transformer | | 1 EA 1 EA 2 EA 2 EA 292 EA 292 EA 1 EA 1 EA 1 EA 1 EA 1 EA 292 EA 292 EA 1 EA 1 LT | | | | 10 /MH 3 /MH 23 /MH 17 /MH 44 /MH 12 /MH 10 /MH 8 /MH 42 /MH 3 /MH 4 /MH 146 /MH 65 /MH 27 /MH 11 /MH | \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 \$ 127.80 | \$ 1,278 \$ 383 \$ 2,939 \$ 2,173 \$ 5,623 \$ 1,534 \$ 1,278 \$ 1,022 \$ 5,368 \$ 383 \$ 511 \$ 18,659 \$ 8,307 \$ 3,451 \$ 1,406 | \$ 1,278 \$ 383 \$ 2,939 \$ 2,173 \$ 5,623 \$ 1,534 \$ 1,278 \$ 1,022 \$ 5,368 \$ 383 \$ 511 \$ 18,659 \$ 8,307 \$ 3,451 \$ 1,406 | | |
| | 18.00.00 | | Scrap Value Mixed Steel | | | | | | | | | | | |
| | 18.10.00 | | Steel | 1 EA, inverter 402 kW | 0.2 TN | \$ (35) | | | /MH | | | \$ (35) | | |
| | | | Steel | Service rack components | 0.08 TN | \$ (14) | | | /MH | | | \$ (14) | | |
| | | | Steel | Conduit and fittings | 0.08 TN | \$ (14) | | | /MH | | | \$ (14) | | |
| | | | Steel | Transformers | 2.38 TN | \$ (417) | | | /MH | | | \$ (417) | | |
| | | | Steel | Roof ladder, 1@ 350 lb each | 0.03 TN | \$ (5) | | | /MH | | | \$ (5) | | |
| | 18.20.00 | | Stainless Steel | 1788 Racks, 13.61 lbs each | 1.99 TN | \$ (2,332) | | | /MH | | | \$ (2,332) | | |
| | 18.30.00 | | Copper | 1 EA, 402 kW inverter | 0.07 TN | \$ (171) | | | /MH | | | \$ (171) | | |
| | | | Copper | Wire | 0.44 TN | \$ (1,074) | | | /MH | | | \$ (1,074) | | |
| | | | Copper | Transformers | 1.13 TN | \$ (2,757) | | | /MH | | | \$ (2,757) | | |
| | 18.50.00 | | Aluminum | 1788 Modules @ 8 lbs each | 2336 LB | \$ (1,421) | | | /MH | | | \$ (1,421) | | |
| | | | PV Module | Conduit and fittings | 16.33 LB | \$ (10) | | | /MH | | | \$ (10) | | |
| | | | Scrap Value | | | \$ (8,250) | | | | | | \$ (8,250) | | |
| | 21.00.00 | | Civil Work Disposal | Concrete, PV panels, rubbish (panels to recycler) | 2 EA | \$ 3,600 | | | /MH | | | \$ 3,600 | | |
| | 21.19.00 | | Dumpster, 40 CY Capacity | Fix point rods | 1 EA | \$ 900 | | | /MH | | | \$ 900 | | |
| | 21.20.00 | | Backfill | Foundation backfill, imported material fill | 7 /CY | \$ 280 | | | /MH | | | \$ 280 | | |
| | | | Civil Work | Backfill concrete pads | | \$ 4,780 | | | | | | \$ 4,780 | | |
| | 24.00.00 | | Architectural Roofing | Roof repair at fix points | 292 EA | \$ 48,180 | | | /MH | | | \$ 48,180 | | |
| | 24.37.00 | | Architectural | Installation | | \$ 48,180 | | | | | | \$ 48,180 | | |
| | | | | | | \$ 48,180 | \$ - | \$ - | | | \$ - | \$ 48,180 | | |
| | | | | | | | | | | | | \$ 100,430 | | |
| | 61.00.00 | | Construction Indirect Miscellaneous | Downspout / Chute | 1 LS | \$ 25,000 | | | /MH | | | \$ 25,000 | | |
| | 61.99.00 | | Construction Indirect | | | \$ 25,000 | \$ - | \$ - | | | \$ - | \$ 25,000 | | |
| | | | | | | \$ 77,960 | \$ (8,250) | \$ - | | | \$ 55,720 | \$ 125,430 | | |
| | 91.00.00 | | Other Direct & Construction Indirect Costs 91.09 Contractor's General and Administration Expense 91.10 Contractor's Profit | | | | | | | | | \$ 8,780 \$ 12,543 \$ 21,323 | | |
| | | | | | | | | | | | | \$ 21,323 | | |
| | | | | | | \$ 77,960 | \$ (8,250) | \$ - | | | \$ 55,720 | \$ 146,753 | | |
| | 93.00.00 | | Indirect Costs 93.1 Engineering, Procurement, & Project Services 93.2 Construction Management Support 93.3 SDG&E Internal Costs | | | | | | | | | \$ 8,805 \$ 2,935 \$ 14,675 | | |
| | 95.00.00 | | Contingency 95.1 Contingency on Subcontractor 95.2 Contingency on Scrap Value 95.3 Contingency on Material 95.4 Contingency on Labor 95.5 Contingency on Indirect | | | \$ 11,694 \$ - \$ - \$ 8,358 \$ 3,962 | | | | | | \$ 11,694 \$ - \$ - \$ 8,358 \$ 3,962 | | |
| | | | | | | \$ 11,694 | \$ - | \$ - | | | \$ 8,358 | \$ 3,962 | | |
| | | | | | | \$ 89,654 | \$ (8,250) | \$ - | | | \$ 64,078 | \$ 197,182 | | |

San Diego Gas & Electric
Decommissioning Cost Estimates
PV Sites - Roof Mounted

| Project ID | Code | Customer | Address | PV Location | Tech. | Date Energized | Facility Nameplate (kW) | Panel Qty | | | | | | | |
|--------------|---|---------------------|---|--|----------|------------------|-------------------------|---------------|-----------|-----------|------------|------------|------|-----------|------------|
| 26 | SAP | Village Lindo Paseo | 5505 Lindo Paseo, San Diego, CA | Roof | PV/ES | 6/20/2013 | 36.60 | 150 | | | | | | | |
| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Crew Rate | Labor Cost | Total Cost | | | |
| Roof top | 11.00.00 | 11.22.00 | Demolition Concrete | | | | | | | | | | | | |
| | | | Concrete | Electrical equipment (Transformer, inverter, etc.) pad | 7 /CY | | | | 5 /MH | \$ 140.47 | \$ 702 | \$ 702 | | | |
| | 11.41.00 | | Electrical Equipment | | | | | | | | | | | | |
| | | | Disconnect wiring and components at service rack | | 1 EA | | | | 5 /MH | \$ 127.80 | \$ 639 | \$ 639 | | | |
| | | | Disconnect wiring at inverter | | 1 EA | | | | 1 /MH | \$ 127.80 | \$ 128 | \$ 128 | | | |
| | | | Disconnect wiring at combiner boxes, remove boxes | | 1 EA | | | | 12 /MH | \$ 127.80 | \$ 1,534 | \$ 1,534 | | | |
| | | | Pull wire from combiners to inverter | | 1 EA | | | | 9 /MH | \$ 127.80 | \$ 1,150 | \$ 1,150 | | | |
| | | | Disconnect and remove wiring at PV panels | | 150 EA | | | | 22 /MH | \$ 127.80 | \$ 2,812 | \$ 2,812 | | | |
| | | | Disconnect and remove grounding at PV panels and racks, | | | | | | | | | | | | |
| | | | Remove ground rods | | 150 EA | | | | 6 /MH | \$ 127.80 | \$ 767 | \$ 767 | | | |
| | | | Demo conduit from rack to tie point | | 1 EA | | | | 5 /MH | \$ 127.80 | \$ 639 | \$ 639 | | | |
| | | | Demo conduit from rack to transformer | | 1 EA | | | | 4 /MH | \$ 127.80 | \$ 511 | \$ 511 | | | |
| | | | Demo conduit from combiners to inverter | | 1 EA | | | | 21 /MH | \$ 127.80 | \$ 2,684 | \$ 2,684 | | | |
| | | | Remove Conduits to inverters | | 1 EA | | | | 1 /MH | \$ 127.80 | \$ 128 | \$ 128 | | | |
| | | | Remove inverters | | 1 EA | | | | 2 /MH | \$ 127.80 | \$ 256 | \$ 256 | | | |
| | | | Remove PV panel and place in dumpster | | 150 EA | | | | 75 /MH | \$ 127.80 | \$ 9,585 | \$ 9,585 | | | |
| | | | Remove points where panel is fixed to roof | | 150 EA | | | | 34 /MH | \$ 127.80 | \$ 4,345 | \$ 4,345 | | | |
| | | | Remove lightning projection and other auxiliary equipment | | 1 EA | | | | 14 /MH | \$ 127.80 | \$ 1,789 | \$ 1,789 | | | |
| | | | Remove transformer | | 1 LT | | | | 5 /MH | \$ 127.80 | \$ 639 | \$ 639 | | | |
| | | | Demolition | | | \$ - | \$ - | \$ - | | | \$ 28,307 | \$ 28,307 | | | |
| | 18.00.00 | | Scrap Value | | | | | | | | | | | | |
| | 18.10.00 | | Mixed Steel | | | | | | | | | | | | |
| | | | Steel | 1 EA, inverter 402 kW | 0.1 TN | \$ - | \$ (18) | | /MH | | \$ - | \$ (18) | | | |
| | | | Steel | Service rack components | 0.04 TN | \$ - | \$ (7) | | /MH | | \$ - | \$ (7) | | | |
| | | | Steel | Conduit and fittings | 0.04 TN | \$ - | \$ (7) | | /MH | | \$ - | \$ (7) | | | |
| | | | Steel | Transformers | 1.22 TN | \$ - | \$ (214) | | /MH | | \$ - | \$ (214) | | | |
| | | | Steel | Roof ladder, 1@ 350 lb each | 0.02 TN | \$ - | \$ (4) | | /MH | | \$ - | \$ (4) | | | |
| | 18.20.00 | | Stainless Steel | | | | | | | | | | | | |
| | | | Stainless Steel | 1788 Racks, 13.61 lbs each | 1.02 TN | \$ - | \$ (1,195) | | /MH | | \$ - | \$ (1,195) | | | |
| | 18.30.00 | | Copper | | | | | | | | | | | | |
| | | | Copper | 1 EA, 402 kW inverter | 0.03 TN | \$ - | \$ (73) | | /MH | | \$ - | \$ (73) | | | |
| | | | Copper | Wire | 0.23 TN | \$ - | \$ (561) | | /MH | | \$ - | \$ (561) | | | |
| | | | Copper | Transformers | 0.58 TN | \$ - | \$ (1,415) | | /MH | | \$ - | \$ (1,415) | | | |
| | 18.50.00 | | Aluminum | | | | | | | | | | | | |
| | | | PV Module | 1788 Modules @ 8 lbs each | 1200 LB | \$ - | \$ (730) | | /MH | | \$ - | \$ (730) | | | |
| | | | Conduit and fittings | 100 @ 1 lb each | 8.39 LB | \$ - | \$ (5) | | /MH | | \$ - | \$ (5) | | | |
| | | | Scrap Value | | | \$ - | \$ (4,229) | \$ - | | \$ - | \$ - | \$ (4,229) | | | |
| | 21.00.00 | | Civil Work | | | | | | | | | | | | |
| | 21.19.00 | | Disposal | | | | | | | | | | | | |
| | | | Dumpster, 40 CY Capacity | Concrete, PV panels, rubbish (panels to recycler) | 1 EA | \$ 1,800 | | | /MH | | \$ - | \$ 1,800 | | | |
| | | | Dumpster, 40 CY Capacity | Fix point rods | 1 EA | \$ 900 | | | /MH | | \$ - | \$ 900 | | | |
| | 21.20.00 | | Backfill | | | | | | | | | | | | |
| | | | Foundation backfill, imported material fill | Backfill concrete pads | 7 /CY | \$ 280 | | | /MH | | \$ - | \$ 280 | | | |
| | | | Civil Work | | | \$ 2,980 | \$ - | \$ - | | \$ - | \$ - | \$ 2,980 | | | |
| | 24.00.00 | | Architectural | | | | | | | | | | | | |
| | 24.37.00 | | Roofing | | | | | | | | | | | | |
| | | | Roof repair at fix points | Installation | 150 EA | \$ 24,750 | | | /MH | \$ - | \$ - | \$ 24,750 | | | |
| | | | Architectural | | | \$ 24,750 | \$ - | \$ - | | \$ - | \$ - | \$ 24,750 | | | |
| | Direct Costs | | | | | | | | | | | | | | |
| | 61.00.00 | | Construction Indirect | | | | | | | | | \$ 51,808 | | | |
| | 61.99.00 | | Miscellaneous | | | | | | | | | | | | |
| | | | Downspout / Chute | | 1 LS | \$ 25,000 | | | /MH | | \$ - | \$ 25,000 | | | |
| | | | Construction Indirect | | | \$ 25,000 | \$ - | \$ - | | \$ - | \$ - | \$ 25,000 | | | |
| | Subtotal | | | | | | | | | | | | | | |
| | 91.00.00 | | Other Direct & Construction Indirect Costs | | | | | | | | | \$ 76,808 | | | |
| | | 91.09 | Contractor's General and Administration Expense | | | | | | | | | \$ 5,377 | | | |
| | | 91.10 | Contractor's Profit | | | | | | | | | \$ 7,681 | | | |
| | | | | | | | | | | | | \$ 13,057 | | | |
| | Direct Costs + Construction Indirect Costs | | | | | | | | | | | | | | |
| | | | | | | \$ 52,730 | \$ (4,229) | \$ - | | \$ 28,307 | \$ - | \$ 89,866 | | | |
| | 93.00.00 | | Indirect Costs | | | | | | | | | | | | |
| | | 93.1 | Engineering, Procurement, & Project Services | | | | | | | | | \$ 5,392 | | | |
| | | 93.2 | Construction Management Support | | | | | | | | | \$ 1,797 | | | |
| | | 93.3 | SDG&E Internal Costs | | | | | | | | | \$ 8,987 | | | |
| | 95.00.00 | | Contingency | | | | | | | | | | | | |
| | | 95.1 | Contingency on Subcontractor | | | \$ 7,910 | | | | | | \$ 7,910 | | | |
| | | 95.2 | Contingency on Scrap Value | | | | \$ - | | | | | \$ - | | | |
| | | 95.3 | Contingency on Material | | | | \$ - | | | | \$ 4,246 | \$ 4,246 | | | |
| | | 95.4 | Contingency on Labor | | | | | | | | | \$ - | | | |
| | | 95.5 | Contingency on Indirect | | | | | | | | | \$ 2,426 | | | |
| Total | | | | | | | | | | | \$ 60,640 | \$ (4,229) | \$ - | \$ 32,553 | \$ 120,623 |

San Diego Gas & Electric
Decommissioning Cost Estimates
PV Sites - Roof Mounted

| Project ID | Code | Customer | Address | PV Location | Tech. | Date Energized | Facility Nameplate (kW) | Panel Qty | | | | |
|--|----------|------------------|---|--|----------|------------------|-------------------------|---------------|-----------|-----------|------------|-------------|
| 27 | DLA | Del Lago Academy | 1740 Scenic Trail Way, Escondido, CA | Roof | PV/ES | 12/20/2013 | 172.80 | 750 | | | | |
| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Crew Rate | Labor Cost | Total Cost |
| Roof top | 11.00.00 | 11.22.00 | Demolition Concrete | Electrical equipment (Transformer, inverter, etc.) pad | 7 /CY | | | | 25 /MH | \$ 140.47 | \$ 3,512 | \$ 3,512 |
| | 11.41.00 | | Electrical Equipment | | | | | | | | | |
| | | | Disconnect wiring and components at service rack | | 1 EA | | | | 27 /MH | \$ 127.80 | \$ 3,451 | \$ 3,451 |
| | | | Disconnect wiring at inverter | | 1 EA | | | | 7 /MH | \$ 127.80 | \$ 895 | \$ 895 |
| | | | Disconnect wiring at combiner boxes, remove boxes | | 5 EA | | | | 60 /MH | \$ 127.80 | \$ 7,668 | \$ 7,668 |
| | | | Pull wire from combiners to inverter | | 5 EA | | | | 44 /MH | \$ 127.80 | \$ 5,623 | \$ 5,623 |
| | | | Disconnect and remove wiring at PV panels | | 750 EA | | | | 112 /MH | \$ 127.80 | \$ 14,314 | \$ 14,314 |
| | | | Disconnect and remove grounding at PV panels and racks, | | | | | | | | | |
| | | | Remove ground rods | | 750 EA | | | | 30 /MH | \$ 127.80 | \$ 3,834 | \$ 3,834 |
| | | | Demo conduit from rack to tie point | | 1 EA | | | | 27 /MH | \$ 127.80 | \$ 3,451 | \$ 3,451 |
| | | | Demo conduit from rack to transformer | | 1 EA | | | | 20 /MH | \$ 127.80 | \$ 2,556 | \$ 2,556 |
| | | | Demo conduit from combiners to inverter | | 1 EA | | | | 107 /MH | \$ 127.80 | \$ 13,675 | \$ 13,675 |
| | | | Remove Conduits to inverters | | 1 EA | | | | 7 /MH | \$ 127.80 | \$ 895 | \$ 895 |
| | | | Remove inverters | | 1 EA | | | | 10 /MH | \$ 127.80 | \$ 1,278 | \$ 1,278 |
| | | | Remove PV panel and place in dumpster | | 750 EA | | | | 375 /MH | \$ 127.80 | \$ 47,925 | \$ 47,925 |
| | | | Remove points where panel is fixed to roof | | 750 EA | | | | 168 /MH | \$ 127.80 | \$ 21,470 | \$ 21,470 |
| | | | Remove lightning projection and other auxiliary equipment | | 1 EA | | | | 70 /MH | \$ 127.80 | \$ 8,946 | \$ 8,946 |
| | | | Remove transformer | | 1 LT | | | | 27 /MH | \$ 127.80 | \$ 3,451 | \$ 3,451 |
| | | | Demolition | | | \$ - | \$ - | \$ - | | | \$ 142,942 | \$ 142,942 |
| | 18.00.00 | | Scrap Value | | | | | | | | | |
| | 18.10.00 | | Mixed Steel | | | | | | | | | |
| | | | Steel | 1 EA, inverter 402 kW | 0.52 TN | \$ (91) | | | /MH | | \$ (91) | \$ (91) |
| | | | Steel | Service rack components | 0.2 TN | \$ (35) | | | /MH | | \$ (35) | \$ (35) |
| | | | Steel | Conduit and fittings | 0.21 TN | \$ (37) | | | /MH | | \$ (37) | \$ (37) |
| | | | Steel | Transformers | 6.11 TN | \$ (1,069) | | | /MH | | \$ (1,069) | \$ (1,069) |
| | | | Steel | Roof ladder, 1@ 350 lb each | 0.08 TN | \$ (14) | | | /MH | | \$ (14) | \$ (14) |
| | 18.20.00 | | Stainless Steel | | | | | | | | | |
| | | | Stainless Steel | 1788 Racks, 13.61 lbs each | 5.1 TN | \$ (5,977) | | | /MH | | \$ (5,977) | \$ (5,977) |
| | 18.30.00 | | Copper | | | | | | | | | |
| | | | Copper | 1 EA, 402 kW inverter | 0.17 TN | \$ (415) | | | /MH | | \$ (415) | \$ (415) |
| | | | Copper | Wire | 1.14 TN | \$ (2,782) | | | /MH | | \$ (2,782) | \$ (2,782) |
| | | | Copper | Transformers | 2.9 TN | \$ (7,076) | | | /MH | | \$ (7,076) | \$ (7,076) |
| | 18.50.00 | | Aluminum | | | | | | | | | |
| | | | PV Module | 1788 Modules @ 8 lbs each | 6000 LB | \$ (3,651) | | | /MH | | \$ (3,651) | \$ (3,651) |
| | | | Conduit and fittings | 100 @ 1 lb each | 41.95 LB | \$ (26) | | | /MH | | \$ (26) | \$ (26) |
| | | | Scrap Value | | | \$ - | \$ (21,172) | \$ - | | | \$ - | \$ (21,172) |
| | 21.00.00 | | Civil Work | | | | | | | | | |
| | 21.19.00 | | Disposal | | | | | | | | | |
| | | | Dumpster, 40 CY Capacity | Concrete, PV panels, rubbish (panels to recycler) | 4 EA | \$ 7,200 | | | /MH | | \$ 7,200 | \$ 7,200 |
| | | | Dumpster, 40 CY Capacity | Fix point rods | 1 EA | \$ 900 | | | /MH | | \$ 900 | \$ 900 |
| | 21.20.00 | | Backfill | | | | | | | | | |
| | | | Foundation backfill, imported material fill | Backfill concrete pads | 7 /CY | \$ 280 | | | /MH | | \$ 280 | \$ 280 |
| | | | Civil Work | | | \$ 8,380 | \$ - | \$ - | | | \$ - | \$ 8,380 |
| | 24.00.00 | | Architectural | | | | | | | | | |
| | 24.37.00 | | Roofing | | | | | | | | | |
| | | | Roof repair at fix points | Installation | 750 EA | \$ 123,750 | | | /MH | | \$ - | \$ 123,750 |
| | | | Architectural | | | \$ 123,750 | \$ - | \$ - | | | \$ - | \$ 123,750 |
| Direct Costs | | | | | | | | | | | | \$ 253,899 |
| | 61.00.00 | | Construction Indirect | | | | | | | | | |
| | 61.99.00 | | Miscellaneous | | | | | | | | | |
| | | | Downspout / Chute | | 1 LS | \$ 25,000 | | | /MH | | \$ - | \$ 25,000 |
| | | | Construction Indirect | | | \$ 25,000 | \$ - | \$ - | | | \$ - | \$ 25,000 |
| Subtotal | | | | | | \$ 157,130 | \$ (21,172) | \$ - | | | \$ 142,942 | \$ 278,899 |
| | 91.00.00 | | Other Direct & Construction Indirect Costs | | | | | | | | | |
| | | 91.09 | Contractor's General and Administration Expense | | | | | | | | | \$ 19,523 |
| | | 91.10 | Contractor's Profit | | | | | | | | | \$ 27,890 |
| | | | | | | | | | | | | \$ 47,413 |
| Direct Costs + Construction Indirect Costs | | | | | | \$ 157,130 | \$ (21,172) | \$ - | | | \$ 142,942 | \$ 326,312 |
| | 93.00.00 | | Indirect Costs | | | | | | | | | |
| | | 93.1 | Engineering, Procurement, & Project Services | | | | | | | | | \$ 19,579 |
| | | 93.2 | Construction Management Support | | | | | | | | | \$ 6,526 |
| | | 93.3 | SDG&E Internal Costs | | | | | | | | | \$ 32,631 |
| | 95.00.00 | | Contingency | | | | | | | | | |
| | | 95.1 | Contingency on Subcontractor | | | \$ 23,570 | | | | | | \$ 23,570 |
| | | 95.2 | Contingency on Scrap Value | | | \$ - | | | | | | \$ - |
| | | 95.3 | Contingency on Material | | | \$ - | | | | | | \$ - |
| | | 95.4 | Contingency on Labor | | | | | | | \$ 21,441 | | \$ 21,441 |
| | | 95.5 | Contingency on Indirect | | | | | | | | | \$ 8,810 |
| Total | | | | | | \$ 180,700 | \$ (21,172) | \$ - | | | \$ 164,383 | \$ 438,870 |

San Diego Gas & Electric
 Decommissioning Cost Estimates
 PV Sites - Canopy Mounted

| ProjID | Code | Customer | Address | PV_Location | Technology | DateEnergized | FacilityName | te_kW | PanelQty | | | |
|--|----------|---|--|---|------------|------------------|--------------|---------------|-----------|-----------|------------|--------------|
| 28 | SPS | Sony Corporation | 16590 1/3 Via Del Campo, San Diego | Carport - Cano | PV | 9/9/2009 | | 136.9 | 867 | | | |
| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Crew Rate | Labor Cost | Total Cost |
| Canopy Mount | 11.00.00 | Demolition | Concrete | Column foundations | 19 /CY | | | | 114 /MH | \$ 140.47 | \$ 16,014 | \$ 16,014 |
| | 11.22.00 | Concrete | Concrete | Electrical equipment (Transformer, Inverters) | 1 /CY | | | | 24 /MH | \$ 140.47 | \$ 3,371 | \$ 3,371 |
| | 11.24.00 | Architectural | Remove structural canopy | | 1 EA | | | | 128 /MH | \$ 140.47 | \$ 17,980 | \$ 17,980 |
| | 11.41.00 | Electrical Equipment | Disconnect wiring and components at service rack | | 1 EA | | | | 103 /MH | \$ 127.80 | \$ 13,163 | \$ 13,163 |
| | | | Demo conduit from rack to tie point | | 1 EA | | | | 26 /MH | \$ 127.80 | \$ 3,323 | \$ 3,323 |
| | | | Disconnect wiring at inverter | | 1 EA | | | | 26 /MH | \$ 127.80 | \$ 3,323 | \$ 3,323 |
| | | | Disconnect wiring at combiner boxes, remove boxes | | 3 EA | | | | 106 /MH | \$ 127.80 | \$ 13,547 | \$ 13,547 |
| | | | Pull wire from combiners to inverter | | 3 EA | | | | 77 /MH | \$ 127.80 | \$ 9,841 | \$ 9,841 |
| | | | Disconnect and remove wiring at PV panels | | 867 EA | | | | 161 /MH | \$ 127.80 | \$ 20,576 | \$ 20,576 |
| | | | Disconnect and remove grounding at PV panels and racks, Remove ground rods | | 867 EA | | | | 42 /MH | \$ 127.80 | \$ 5,368 | \$ 5,368 |
| | | | Remove PV panel and place in dumpster | | 867 EA | | | | 539 /MH | \$ 127.80 | \$ 68,884 | \$ 68,884 |
| | | | Remove Conduits to inverters | | 1 EA | | | | 13 /MH | \$ 127.80 | \$ 1,661 | \$ 1,661 |
| | | | Remove inverters | | 1 EA | | | | 13 /MH | \$ 127.80 | \$ 1,661 | \$ 1,661 |
| | | | Remove transformer | | 1 LT | | | | 51 /MH | \$ 127.80 | \$ 6,518 | \$ 6,518 |
| | | Demolition | | | | \$ - | \$ - | \$ - | | | \$ 185,230 | \$ 185,230 |
| | 18.00.00 | Scrap Value | | | | | | | | | | |
| | 18.10.00 | Mixed Steel | Steel | 1 EA, 82 KW inverter | 1.96 TN | \$ (343) | | | /MH | | | \$ (343) |
| | | | Steel | Service rack components | 1.51 TN | \$ (264) | | | /MH | | | \$ (264) |
| | | | Steel | Conduit and fittings | 1.61 TN | \$ (282) | | | /MH | | | \$ (282) |
| | | | Steel | Transformers | 17.89 TN | \$ (3,131) | | | /MH | | | \$ (3,131) |
| | | | Steel | Roof ladder, 1@ 350 lb each | 0.58 TN | \$ (102) | | | /MH | | | \$ (102) |
| | | | Steel | Canopy & steel | 64.22 TN | \$ (11,239) | | | /MH | | | \$ (11,239) |
| | 18.20.00 | Stainless Steel | Stainless Steel | 336 Racks, 13.61 lbs each | 7.35 TN | \$ (8,614) | | | /MH | | | \$ (8,614) |
| | 18.30.00 | Copper | Copper | 1 EA, 82 KW inverter | 0.64 TN | \$ (1,562) | | | /MH | | | \$ (1,562) |
| | | | Copper | Wire | 5.23 TN | \$ (12,761) | | | /MH | | | \$ (12,761) |
| | | | Copper | Transformers | 8.51 TN | \$ (20,764) | | | /MH | | | \$ (20,764) |
| | 18.50.00 | Aluminum | PV Module | 336 Modules @8 lbs each | 8631 LB | \$ (5,252) | | | /MH | | | \$ (5,252) |
| | | | Conduit and fittings | 100 @ 1 lb each | 321 LB | \$ (195) | | | /MH | | | \$ (195) |
| | | Scrap Value | | | | \$ - | \$ (64,508) | \$ - | | | \$ - | \$ (64,508) |
| | 21.00.00 | Civil Work | Disposal | Concrete, PV panels, rubbish (panels to recycler) | 10 EA | \$ 18,000 | | | /MH | | | \$ 18,000 |
| | 21.20.00 | Backfill | Foundation backfill, imported material fill | Backfill concrete pads | 19 /CY | \$ 760 | | | /MH | | | \$ 760 |
| | | Civil Work | | | | \$ 18,760 | \$ - | \$ - | | | \$ - | \$ 18,760 |
| Direct Costs | | | | | | | | | | | | \$ 139,481 |
| | 61.00.00 | Construction Indirect | | | | | | | | | | |
| | | Construction Indirect | | | | \$ - | \$ - | \$ - | | | \$ - | \$ - |
| Subtotal | | | | | | \$ 18,760 | \$ (64,508) | \$ - | | | \$ 185,230 | \$ 139,481 |
| | 91.00.00 | Other Direct & Construction Indirect Costs | | | | | | | | | | \$ 9,763.68 |
| | 91.09 | Contractor's General and Administration Expense | | | | | | | | | | \$ 13,948.12 |
| | 91.10 | Contractor's Profit | | | | | | | | | | \$ 23,712 |
| Direct Costs + Construction Indirect Costs | | | | | | \$ 18,760 | \$ (64,508) | \$ - | \$ - | \$ - | \$ 185,230 | \$ 139,481 |
| | 93.00.00 | Indirect Costs | | | | | | | | | | |
| | 93.1 | Engineering, Procurement, & Project Services | | | | | | | | | | \$ 8,368.87 |
| | 93.2 | Construction Management Support | | | | | | | | | | \$ 2,789.62 |
| | 93.3 | SDG&E Internal Costs | | | | | | | | | | \$ 13,948.12 |
| | 95.00.00 | Contingency | | | | | | | | | | |
| | 95.1 | Contingency on Subcontractor | | | | \$ 2,814 | | | | | | \$ 2,814 |
| | 95.2 | Contingency on Scrap Value | | | | \$ - | | | | | | \$ - |
| | 95.3 | Contingency on Material | | | | | | \$ - | | | | \$ - |
| | 95.4 | Contingency on Labor | | | | | | | | \$ 27,784 | | \$ 27,784 |
| | 95.5 | Contingency on Indirect | | | | | | | | | | \$ 3,766 |
| Total | | | | | | \$ 21,574 | \$ (64,508) | \$ - | | | \$ 213,014 | \$ 222,664 |

San Diego Gas & Electric
Decommissioning Cost Estimates
PV Sites - Canopy Mounted

| ProjID | Code | Customer | Address | PV_Location | Technology | DateEnergized | FacilityName | PanelQty | | | | | | | | |
|-------------|-----------------|--|--|---|-----------------|-------------------------|--------------------|----------------------|------------------|------------------|-------------------|-------------------|--|--|--|--------------|
| 29 | COP | County Operations Center Parking Structure A | 5555 Overland Ave, San Diego, CA | Carport - Canopy | PV | 2/21/2011 | 358.7000122 | 1932 | | | | | | | | |
| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Crew Rate | Labor Cost | Total Cost | | | | |
| | 11.00.00 | | Demolition | | | | | | | | | | | | | |
| | | 11.22.00 | Concrete | Column foundations | 43 /CY | | | | 258 /MH | \$ 140.47 | \$ 36,341 | \$ 36,341 | | | | |
| | | | Concrete | Electrical equipment (Transformer, inv) | 1 /CY | | | | 24 /MH | \$ 140.47 | \$ 3,371 | \$ 3,371 | | | | |
| | | 11.24.00 | Architectural | | | | | | | | | | | | | |
| | | | Remove structural canopy | | 1 EA | | | | 286 /MH | \$ 140.47 | \$ 40,174 | \$ 40,174 | | | | |
| | | 11.41.00 | Electrical Equipment | | | | | | | | | | | | | |
| | | | Disconnect wiring and components at service rack | | 1 EA | | | | 229 /MH | \$ 127.80 | \$ 29,266 | \$ 29,266 | | | | |
| | | | Demo conduit from rack to tie point | | 1 EA | | | | 57 /MH | \$ 127.80 | \$ 7,285 | \$ 7,285 | | | | |
| | | | Disconnect wiring at inverter | | 1 EA | | | | 57 /MH | \$ 127.80 | \$ 7,285 | \$ 7,285 | | | | |
| | | | Disconnect wiring at combiner boxes, remove boxes | | 3 EA | | | | 236 /MH | \$ 127.80 | \$ 30,161 | \$ 30,161 | | | | |
| | | | Pull wire from combiners to inverter | | 3 EA | | | | 172 /MH | \$ 127.80 | \$ 21,982 | \$ 21,982 | | | | |
| | | | Disconnect and remove wiring at PV panels | | 1932 EA | | | | 358 /MH | \$ 127.80 | \$ 45,752 | \$ 45,752 | | | | |
| | | | Disconnect and remove grounding at PV panels and racks, Remove ground rods | | 1932 EA | | | | 93 /MH | \$ 127.80 | \$ 11,885 | \$ 11,885 | | | | |
| | | | Remove PV panel and place in dumpster | | 1932 EA | | | | 1202 /MH | \$ 127.80 | \$ 153,616 | \$ 153,616 | | | | |
| | | | Remove Conduits to inverters | | 1 EA | | | | 29 /MH | \$ 127.80 | \$ 3,706 | \$ 3,706 | | | | |
| | | | Remove inverters | | 1 EA | | | | 29 /MH | \$ 127.80 | \$ 3,706 | \$ 3,706 | | | | |
| | | | Remove transformer | | 1 LT | | | | 114 /MH | \$ 127.80 | \$ 14,569 | \$ 14,569 | | | | |
| | | | Demolition | | | \$ - | \$ - | \$ - | | | \$ 409,000 | \$ 409,000 | | | | |
| | 18.00.00 | | Scrap Value | | | | | | | | | | | | | |
| | | 18.10.00 | Mixed Steel | | | | | | | | | | | | | |
| | | | Steel | 1 EA, 82 kW inverter | 4.36 TN | | \$ (763) | | /MH | | \$ (763) | \$ (763) | | | | |
| | | | Steel | Service rack components | 3.36 TN | | \$ (588) | | /MH | | \$ (588) | \$ (588) | | | | |
| | | | Steel | Conduit and fittings | 3.58 TN | | \$ (627) | | /MH | | \$ (627) | \$ (627) | | | | |
| | | | Steel | Transformers | 39.86 TN | | \$ (6,976) | | /MH | | \$ (6,976) | \$ (6,976) | | | | |
| | | | Steel | Roof ladder, 1 @ 350 lb each | 1.29 TN | | \$ (226) | | /MH | | \$ (226) | \$ (226) | | | | |
| | | | Steel | Canopy & steel | 143.11 TN | | \$ (25,044) | | /MH | | \$ (25,044) | \$ (25,044) | | | | |
| | | 18.20.00 | Stainless Steel | | | | | | | | | | | | | |
| | | | Stainless Steel | 336 Racks, 13.61 lbs each | 16.39 TN | | \$ (19,209) | | /MH | | \$ (19,209) | \$ (19,209) | | | | |
| | | 18.30.00 | Copper | | | | | | | | | | | | | |
| | | | Copper | 1 EA, 82 kW inverter | 1.43 TN | | \$ (3,489) | | /MH | | \$ (3,489) | \$ (3,489) | | | | |
| | | | Copper | Wire | 11.66 TN | | \$ (28,450) | | /MH | | \$ (28,450) | \$ (28,450) | | | | |
| | | | Copper | Transformers | 18.96 TN | | \$ (46,262) | | /MH | | \$ (46,262) | \$ (46,262) | | | | |
| | | 18.50.00 | Aluminum | | | | | | | | | | | | | |
| | | | PV Module | 336 Modules @8 lbs each | 19234 LB | | \$ (11,704) | | /MH | | \$ (11,704) | \$ (11,704) | | | | |
| | | | Conduit and fittings | 100 @ 1 lb each | 716 LB | | \$ (436) | | /MH | | \$ (436) | \$ (436) | | | | |
| | | | Scrap Value | | | \$ - | \$ (143,774) | \$ - | | | \$ - | \$ (143,774) | | | | |
| | 21.00.00 | | Civil Work | | | | | | | | | | | | | |
| | | 21.19.00 | Disposal | | | | | | | | | | | | | |
| | | | Dumpster, 40 CY Capacity | Concrete, PV panels, rubbish (panels to recycler) | 21 EA | | \$ 37,800 | | /MH | | \$ 37,800 | \$ 37,800 | | | | |
| | | 21.20.00 | Backfill | | | | | | | | | | | | | |
| | | | Foundation backfill, imported material fill | Backfill concrete pads | 43 /CY | | \$ 1,720 | | /MH | | \$ 1,720 | \$ 1,720 | | | | |
| | | | Civil Work | | | \$ 39,520 | \$ - | \$ - | | | \$ - | \$ 39,520 | | | | |
| | | | Direct Costs | | | | | | | | | | | | | \$ 304,746 |
| | 61.00.00 | | Construction Indirect | | | | | | | | | | | | | |
| | | | Construction Indirect | | | \$ - | \$ - | \$ - | | | \$ - | \$ - | | | | |
| | Subtotal | | | | | \$ 39,520 | \$ (143,774) | \$ - | | | \$ 409,000 | \$ 304,746 | | | | |
| | 91.00.00 | | Other Direct & Construction Indirect Costs | | | | | | | | | | | | | |
| | | 91.09 | Contractor's General and Administration Expense | | | | | | | | | | | | | \$ 21,332.23 |
| | | 91.10 | Contractor's Profit | | | | | | | | | | | | | \$ 30,474.61 |
| | | | Direct Costs + Construction Indirect Costs | | | \$ 39,520 | \$ (143,774) | \$ - | \$ - | \$ - | \$ 409,000 | \$ 304,746 | | | | |
| | 93.00.00 | | Indirect Costs | | | | | | | | | | | | | |
| | | 93.1 | Engineering, Procurement, & Project Services | | | | | | | | | | | | | \$ 18,284.77 |
| | | 93.2 | Construction Management Support | | | | | | | | | | | | | \$ 6,094.92 |
| | | 93.3 | SDG&E Internal Costs | | | | | | | | | | | | | \$ 30,474.61 |
| | 95.00.00 | | Contingency | | | | | | | | | | | | | |
| | | 95.1 | Contingency on Subcontractor | | | \$ 5,928 | | | | | | \$ 5,928 | | | | \$ 5,928 |
| | | 95.2 | Contingency on Scrap Value | | | | \$ - | | | | | \$ - | | | | \$ - |
| | | 95.3 | Contingency on Material | | | | | \$ - | | | | \$ - | | | | \$ - |
| | | 95.4 | Contingency on Labor | | | | | | | | \$ 61,350 | \$ 61,350 | | | | \$ 61,350 |
| | | 95.5 | Contingency on Indirect | | | | | | | | | | | | | \$ 8,228 |
| | Total | | | | | \$ 45,448 | \$ (143,774) | \$ - | | | \$ 470,350 | \$ 486,913 | | | | |

San Diego Gas & Electric
Decommissioning Cost Estimates
PV Sites - Canopy Mounted

| ProjID | Code | Customer | Address | PV_Location | Technology | DateEnergized | FacilityName | PanelQty | | | | | | | | |
|--|----------|---------------------|--|---|------------|------------------|--------------|---------------|-----------|-----------|------------|-------------|--|--|--|-------------|
| 30 | EIT | SDG&E EIC (parking) | 4760 Clairemont Mesa Blvd, San Diego Carport, Free-PV | | | 1/17/2012 | 59.35100174 | 286 | | | | | | | | |
| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Crew Rate | Labor Cost | Total Cost | | | | |
| Canopy Mount | 11.00.00 | | Demolition | | | | | | | | | | | | | |
| | 11.22.00 | | Concrete | Column foundations | 6 /CY | | | | 36 /MH | \$ 140.47 | \$ 5,057 | \$ 5,057 | | | | |
| | | | Concrete | Electrical equipment (Transformer, Inverters) | 1 /CY | | | | 24 /MH | \$ 140.47 | \$ 3,371 | \$ 3,371 | | | | |
| | 11.24.00 | | Architectural | | | | | | | | | | | | | |
| | | | Remove structural canopy | | 1 EA | | | | 42 /MH | \$ 140.47 | \$ 5,900 | \$ 5,900 | | | | |
| | 11.41.00 | | Electrical Equipment | | | | | | | | | | | | | |
| | | | Disconnect wiring and components at service rack | | 1 EA | | | | 34 /MH | \$ 127.80 | \$ 4,345 | \$ 4,345 | | | | |
| | | | Demo conduit from rack to tie point | | 1 EA | | | | 8 /MH | \$ 127.80 | \$ 1,022 | \$ 1,022 | | | | |
| | | | Disconnect wiring at inverter | | 1 EA | | | | 8 /MH | \$ 127.80 | \$ 1,022 | \$ 1,022 | | | | |
| | | | Disconnect wiring at combiner boxes, remove boxes | | 3 EA | | | | 35 /MH | \$ 127.80 | \$ 4,473 | \$ 4,473 | | | | |
| | | | Pull wire from combiners to inverter | | 3 EA | | | | 25 /MH | \$ 127.80 | \$ 3,195 | \$ 3,195 | | | | |
| | | | Disconnect and remove wiring at PV panels | | 286 EA | | | | 53 /MH | \$ 127.80 | \$ 6,773 | \$ 6,773 | | | | |
| | | | Disconnect and remove grounding at PV panels and racks, Remove ground rods | | 286 EA | | | | 14 /MH | \$ 127.80 | \$ 1,789 | \$ 1,789 | | | | |
| | | | Remove PV panel and place in dumpster | | 286 EA | | | | 178 /MH | \$ 127.80 | \$ 22,748 | \$ 22,748 | | | | |
| | | | Remove Conduits to inverters | | 1 EA | | | | 4 /MH | \$ 127.80 | \$ 511 | \$ 511 | | | | |
| | | | Remove inverters | | 1 EA | | | | 4 /MH | \$ 127.80 | \$ 511 | \$ 511 | | | | |
| | | | Remove transformer | | 1 LT | | | | 17 /MH | \$ 127.80 | \$ 2,173 | \$ 2,173 | | | | |
| | | | Demolition | | | \$ - | \$ - | \$ - | | | \$ 62,892 | \$ 62,892 | | | | |
| | 18.00.00 | | Scrap Value | | | | | | | | | | | | | |
| | 18.10.00 | | Mixed Steel | | | | | | | | | | | | | |
| | | | Steel | 1 EA, 82 kW inverter | 0.65 TN | \$ (114) | | | /MH | | | \$ (114) | | | | |
| | | | Steel | Service rack components | 0.5 TN | \$ (88) | | | /MH | | | \$ (88) | | | | |
| | | | Steel | Conduit and fittings | 0.53 TN | \$ (93) | | | /MH | | | \$ (93) | | | | |
| | | | Steel | Transformers | 5.9 TN | \$ (1,033) | | | /MH | | | \$ (1,033) | | | | |
| | | | Steel | Roof ladder, 1 @ 350 lb each | 0.19 TN | \$ (33) | | | /MH | | | \$ (33) | | | | |
| | | | Steel | Canopy & steel | 21.19 TN | \$ (3,708) | | | /MH | | | \$ (3,708) | | | | |
| | 18.20.00 | | Stainless Steel | | | | | | | | | | | | | |
| | | | Stainless Steel | 336 Racks, 13.61 lbs each | 2.43 TN | \$ (2,848) | | | /MH | | | \$ (2,848) | | | | |
| | 18.30.00 | | Copper | | | | | | | | | | | | | |
| | | | Copper | 1 EA, 82 kW inverter | 0.21 TN | \$ (512) | | | /MH | | | \$ (512) | | | | |
| | | | Copper | Wire | 1.73 TN | \$ (4,221) | | | /MH | | | \$ (4,221) | | | | |
| | | | Copper | Transformers | 2.81 TN | \$ (6,856) | | | /MH | | | \$ (6,856) | | | | |
| | 18.50.00 | | Aluminum | | | | | | | | | | | | | |
| | | | PV Module | 336 Modules @ 8 lbs each | 2847 LB | \$ (1,732) | | | /MH | | | \$ (1,732) | | | | |
| | | | Conduit and fittings | 100 @ 1 lb each | 106 LB | \$ (65) | | | /MH | | | \$ (65) | | | | |
| | | | Scrap Value | | | \$ - | \$ (21,303) | \$ - | | | \$ - | \$ (21,303) | | | | |
| | 21.00.00 | | Civil Work | | | | | | | | | | | | | |
| | 21.19.00 | | Disposal | | | | | | | | | | | | | |
| | | | Dumpster, 40 CY Capacity | Concrete, PV panels, rubbish (panels to recycler) | 3 EA | \$ 5,400 | | | /MH | | | \$ 5,400 | | | | |
| | 21.20.00 | | Backfill | | | | | | | | | | | | | |
| | | | Foundation backfill, imported material fill | Backfill concrete pads | 6 /CY | \$ 240 | | | /MH | | | \$ 240 | | | | |
| | | | Civil Work | | | \$ 5,640 | \$ - | \$ - | | | \$ - | \$ 5,640 | | | | |
| Direct Costs | | | | | | | | | | | | | | | | \$ 47,229 |
| | 61.00.00 | | Construction Indirect | | | | | | | | | | | | | |
| | | | Construction Indirect | | | \$ - | \$ - | \$ - | | | \$ - | \$ - | | | | |
| Subtotal | | | | | | \$ 5,640 | \$ (21,303) | \$ - | | | \$ 62,892 | \$ 47,229 | | | | |
| | 91.00.00 | | Other Direct & Construction Indirect Costs | | | | | | | | | | | | | |
| | 91.09 | | Contractor's General and Administration Expense | | | | | | | | | | | | | \$ 3,306.04 |
| | 91.10 | | Contractor's Profit | | | | | | | | | | | | | \$ 4,722.91 |
| | | | | | | \$ - | \$ - | \$ - | | | \$ - | \$ 8,029 | | | | |
| Direct Costs + Construction Indirect Costs | | | | | | \$ 5,640 | \$ (21,303) | \$ - | \$ - | \$ - | \$ 62,892 | \$ 47,229 | | | | |
| | 93.00.00 | | Indirect Costs | | | | | | | | | | | | | |
| | 93.1 | | Engineering, Procurement, & Project Services | | | | | | | | | | | | | \$ 2,833.74 |
| | 93.2 | | Construction Management Support | | | | | | | | | | | | | \$ 944.58 |
| | 93.3 | | SDG&E Internal Costs | | | | | | | | | | | | | \$ 4,722.91 |
| | 95.00.00 | | Contingency | | | | | | | | | | | | | |
| | 95.1 | | Contingency on Subcontractor | | | \$ 846 | | | | | | | | | | \$ 846 |
| | 95.2 | | Contingency on Scrap Value | | | \$ - | | | | | | | | | | \$ - |
| | 95.3 | | Contingency on Material | | | | | \$ - | | | | | | | | \$ - |
| | 95.4 | | Contingency on Labor | | | | | | | | \$ 9,434 | \$ 9,434 | | | | \$ 9,434 |
| | 95.5 | | Contingency on Indirect | | | | | | | | | | | | | \$ 1,275 |
| Total | | | | | | \$ 6,486 | \$ (21,303) | \$ - | | | \$ 72,326 | \$ 75,314 | | | | |

San Diego Gas & Electric
 Decommissioning Cost Estimates
 PV Sites - Canopy Mounted

| ProjID | Code | Customer | Address | PV_Location | Technology | DateEnergized | FacilityName | PanelQty | | | | | | | | |
|--|--------------|-----------------------------------|--|---|-----------------|-------------------------|--------------------|----------------------|------------------|------------------|-------------------|-------------------|-----------|--|--|-----------|
| 31 | SWC | Sharp Rees Stealy Wellness Center | 300 Fir Street, San Diego, CA | Carport - CanoPV | | 1/31/2013 | 74.34999847 | 333 | | | | | | | | |
| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Crew Rate | Labor Cost | Total Cost | | | | |
| Canopy Mount | 11.00.00 | | Demolition | | | | | | | | | | | | | |
| | 11.22.00 | | Concrete | Column foundations | 7 /CY | | | | 42 /MH | \$ 140.47 | \$ 5,900 | \$ 5,900 | | | | |
| | | | Concrete | Electrical equipment (Transformer, inv) | 1 /CY | | | | 24 /MH | \$ 140.47 | \$ 3,371 | \$ 3,371 | | | | |
| | 11.24.00 | | Architectural | | | | | | | | | | | | | |
| | | | Remove structural canopy | | 1 EA | | | | 49 /MH | \$ 140.47 | \$ 6,883 | \$ 6,883 | | | | |
| | 11.41.00 | | Electrical Equipment | | | | | | | | | | | | | |
| | | | Disconnect wiring and components at service rack | | 1 EA | | | | 39 /MH | \$ 127.80 | \$ 4,984 | \$ 4,984 | | | | |
| | | | Demo conduit from rack to tie point | | 1 EA | | | | 10 /MH | \$ 127.80 | \$ 1,278 | \$ 1,278 | | | | |
| | | | Disconnect wiring at inverter | | 1 EA | | | | 10 /MH | \$ 127.80 | \$ 1,278 | \$ 1,278 | | | | |
| | | | Disconnect wiring at combiner boxes, remove boxes | | 3 EA | | | | 41 /MH | \$ 127.80 | \$ 5,240 | \$ 5,240 | | | | |
| | | | Pull wire from combiners to inverter | | 3 EA | | | | 30 /MH | \$ 127.80 | \$ 3,834 | \$ 3,834 | | | | |
| | | | Disconnect and remove wiring at PV panels | | 333 EA | | | | 62 /MH | \$ 127.80 | \$ 7,924 | \$ 7,924 | | | | |
| | | | Disconnect and remove grounding at PV panels and racks, Remove ground rods | | 333 EA | | | | 16 /MH | \$ 127.80 | \$ 2,045 | \$ 2,045 | | | | |
| | | | Remove PV panel and place in dumpster | | 333 EA | | | | 207 /MH | \$ 127.80 | \$ 26,455 | \$ 26,455 | | | | |
| | | | Remove Conduits to inverters | | 1 EA | | | | 5 /MH | \$ 127.80 | \$ 639 | \$ 639 | | | | |
| | | | Remove inverters | | 1 EA | | | | 5 /MH | \$ 127.80 | \$ 639 | \$ 639 | | | | |
| | | | Remove transformer | | 1 LT | | | | 20 /MH | \$ 127.80 | \$ 2,556 | \$ 2,556 | | | | |
| | | | Demolition | | | \$ - | \$ - | \$ - | | | \$ 73,025 | \$ 73,025 | | | | |
| | 18.00.00 | | Scrap Value | | | | | | | | | | | | | |
| | 18.10.00 | | Mixed Steel | | | | | | | | | | | | | |
| | | | Steel | 1 EA, 82 kW inverter | 0.75 TN | | \$ (131) | | /MH | | | \$ (131) | | | | |
| | | | Steel | Service rack components | 0.58 TN | | \$ (102) | | /MH | | | \$ (102) | | | | |
| | | | Steel | Conduit and fittings | 0.62 TN | | \$ (109) | | /MH | | | \$ (109) | | | | |
| | | | Steel | Transformers | 6.87 TN | | \$ (1,202) | | /MH | | | \$ (1,202) | | | | |
| | | | Steel | Roof ladder, 1 @ 350 lb each | 0.22 TN | | \$ (39) | | /MH | | | \$ (39) | | | | |
| | | | Steel | Canopy & steel | 24.67 TN | | \$ (4,317) | | /MH | | | \$ (4,317) | | | | |
| | 18.20.00 | | Stainless Steel | | | | | | | | | | | | | |
| | | | Stainless Steel | 336 Racks, 13.61 lbs each | 2.82 TN | | \$ (3,305) | | /MH | | | \$ (3,305) | | | | |
| | 18.30.00 | | Copper | | | | | | | | | | | | | |
| | | | Copper | 1 EA, 82 kW inverter | 0.25 TN | | \$ (610) | | /MH | | | \$ (610) | | | | |
| | | | Copper | Wire | 2.01 TN | | \$ (4,904) | | /MH | | | \$ (4,904) | | | | |
| | | | Copper | Transformers | 3.27 TN | | \$ (7,979) | | /MH | | | \$ (7,979) | | | | |
| | 18.50.00 | | Aluminum | | | | | | | | | | | | | |
| | | | PV Module | 336 Modules @8 lbs each | 3315 LB | | \$ (2,017) | | /MH | | | \$ (2,017) | | | | |
| | | | Conduit and fittings | 100 @ 1 lb each | 123 LB | | \$ (75) | | /MH | | | \$ (75) | | | | |
| | | | Scrap Value | | | \$ - | \$ (24,790) | \$ - | | | \$ - | \$ (24,790) | | | | |
| | 21.00.00 | | Civil Work | | | | | | | | | | | | | |
| | 21.19.00 | | Disposal | | | | | | | | | | | | | |
| | | | Dumpster, 40 CY Capacity | Concrete, PV panels, rubbish (panels to recycler) | 4 EA | \$ 7,200 | | | /MH | | | \$ 7,200 | | | | |
| | 21.20.00 | | Backfill | | | | | | | | | | | | | |
| | | | Foundation backfill, imported material fill | Backfill concrete pads | 7 /CY | \$ 280 | | | /MH | | | \$ 280 | | | | |
| | | | Civil Work | | | \$ 7,480 | \$ - | \$ - | | | \$ - | \$ 7,480 | | | | |
| Direct Costs | | | | | | | | | | | | | | | | \$ 55,716 |
| | 61.00.00 | | Construction Indirect | | | | | | | | | | | | | |
| | | | Construction Indirect | | | \$ - | \$ - | \$ - | | | \$ - | \$ - | | | | |
| Subtotal | | | | | | \$ 7,480 | \$ (24,790) | \$ - | | | \$ 73,025 | \$ 55,716 | | | | |
| | 91.00.00 | | Other Direct & Construction Indirect Costs | | | | | | | | | | | | | |
| | 91.09 | | Contractor's General and Administration Expense | | | | | | | | | \$ 3,900.09 | | | | |
| | 91.10 | | Contractor's Profit | | | | | | | | | \$ 5,571.55 | | | | |
| | | | | | | | | | | | | \$ 9,472 | | | | |
| Direct Costs + Construction Indirect Costs | | | | | | \$ 7,480 | \$ (24,790) | \$ - | \$ - | \$ - | \$ - | \$ 73,025 | \$ 55,716 | | | |
| | 93.00.00 | | Indirect Costs | | | | | | | | | | | | | |
| | 93.1 | | Engineering, Procurement, & Project Services | | | | | | | | | \$ 3,342.93 | | | | |
| | 93.2 | | Construction Management Support | | | | | | | | | \$ 1,114.31 | | | | |
| | 93.3 | | SDG&E Internal Costs | | | | | | | | | \$ 5,571.55 | | | | |
| | 95.00.00 | | Contingency | | | | | | | | | | | | | |
| | 95.1 | | Contingency on Subcontractor | | | \$ 1,122 | | | | | | \$ 1,122 | | | | |
| | 95.2 | | Contingency on Scrap Value | | | \$ - | | | | | | \$ - | | | | |
| | 95.3 | | Contingency on Material | | | \$ - | | \$ - | | | | \$ - | | | | |
| | 95.4 | | Contingency on Labor | | | | | | | | \$ 10,954 | \$ 10,954 | | | | |
| | 95.5 | | Contingency on Indirect | | | | | | | | | \$ 1,504 | | | | |
| Total | | | | | | \$ 8,602 | \$ (24,790) | \$ - | | | \$ 83,979 | \$ 88,796 | | | | |

San Diego Gas & Electric
Decommissioning Cost Estimates
PV Sites - Canopy Mounted

| ProjID | Code | Customer | Address | PV_Location | Technology | DateEnergized | FacilityName | PanelQty | 60 | | | | |
|---|----------|--|---|--|------------------------------|------------------|--------------|---------------|-----------|-----------|------------|-------------|-----------|
| 33 | DLP | Fast EV Suncharge/Del Lago Park N Ride | 3310 Del Lago Blvd D, Escondido, CA | Carport - Cano | PV/ES | 3/6/2014 | 13-10000038 | | | | | | |
| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Crew Rate | Labor Cost | Total Cost | |
| Canopy Mount | 11.00.00 | | Demolition | | | | | | | | | | |
| | 11.22.00 | | Concrete | Column foundations | 1 /CY | | | | 6 /MH | \$ 140.47 | \$ 843 | \$ 843 | |
| | | | Concrete | Electrical equipment (Transformer, inv) | 1 /CY | | | | 24 /MH | \$ 140.47 | \$ 3,371 | \$ 3,371 | |
| | 11.24.00 | | Architectural | | | | | | | | | | |
| | | | | Remove structural canopy | | 1 EA | | | | 9 /MH | \$ 140.47 | \$ 1,264 | \$ 1,264 |
| | 11.41.00 | | Electrical Equipment | | | | | | | | | | |
| | | | | Disconnect wiring and components at service rack | | 1 EA | | | | 7 /MH | \$ 127.80 | \$ 895 | \$ 895 |
| | | | | Demo conduit from rack to tie point | | 1 EA | | | | 2 /MH | \$ 127.80 | \$ 256 | \$ 256 |
| | | | | Disconnect wiring at inverter | | 1 EA | | | | 2 /MH | \$ 127.80 | \$ 256 | \$ 256 |
| | | | | Disconnect wiring at combiner boxes, remove boxes | | 3 EA | | | | 7 /MH | \$ 127.80 | \$ 895 | \$ 895 |
| | | | | Pull wire from combiners to inverter | | 3 EA | | | | 5 /MH | \$ 127.80 | \$ 639 | \$ 639 |
| | | | | Disconnect and remove wiring at PV panels | | 60 EA | | | | 11 /MH | \$ 127.80 | \$ 1,406 | \$ 1,406 |
| | | | | Disconnect and remove grounding at PV panels and racks, Remove ground rods | | 60 EA | | | | 3 /MH | \$ 127.80 | \$ 383 | \$ 383 |
| | | | | Remove PV panel and place in dumpster | | 60 EA | | | | 37 /MH | \$ 127.80 | \$ 4,729 | \$ 4,729 |
| | | | | Remove Conduits to inverters | | 1 EA | | | | 1 /MH | \$ 127.80 | \$ 128 | \$ 128 |
| | | | | Remove inverters | | 1 EA | | | | 1 /MH | \$ 127.80 | \$ 128 | \$ 128 |
| | | | | Remove transformer | | 1 LT | | | | 4 /MH | \$ 127.80 | \$ 511 | \$ 511 |
| | | | | Demolition | | | \$ - | \$ - | \$ - | | | \$ 15,702 | \$ 15,702 |
| | 18.00.00 | | | Scrap Value | | | | | | | | | |
| | 18.10.00 | | | Mixed Steel | | | | | | | | | |
| | | | | Steel | 1 EA, 82 kW inverter | 0.14 TN | | \$ (25) | | /MH | | | \$ (25) |
| | | | | Steel | Service rack components | 0.11 TN | | \$ (18) | | /MH | | | \$ (18) |
| | | | | Steel | Conduit and fittings | 0.11 TN | | \$ (19) | | /MH | | | \$ (19) |
| | | | | Steel | Transformers | 1.24 TN | | \$ (217) | | /MH | | | \$ (217) |
| | | | | Steel | Roof ladder, 1 @ 350 lb each | 0.04 TN | | \$ (7) | | /MH | | | \$ (7) |
| | | | Steel | Canopy & steel | 4.44 TN | | \$ (777) | | /MH | | | \$ (777) | |
| 18.20.00 | | | Stainless Steel | | | | | | | | | | |
| | | | Stainless Steel | 336 Racks, 13.61 lbs each | 0.51 TN | | \$ (598) | | /MH | | | \$ (598) | |
| 18.30.00 | | | Copper | | | | | | | | | | |
| | | | Copper | 1 EA, 82 kW inverter | 0.04 TN | | \$ (98) | | /MH | | | \$ (98) | |
| | | | Copper | Wire | 0.36 TN | | \$ (878) | | /MH | | | \$ (878) | |
| | | | Copper | Transformers | 0.59 TN | | \$ (1,440) | | /MH | | | \$ (1,440) | |
| 18.50.00 | | | Aluminum | | | | | | | | | | |
| | | | PV Module | 336 Modules @8 lbs each | 597 LB | | \$ (363) | | /MH | | | \$ (363) | |
| | | | Conduit and fittings | 100 @ 1 lb each | 22 LB | | \$ (13) | | /MH | | | \$ (13) | |
| | | | Scrap Value | | | \$ - | \$ (4,452) | \$ - | | | \$ - | \$ (4,452) | |
| 21.00.00 | | | Civil Work | | | | | | | | | | |
| 21.19.00 | | | Disposal | | | | | | | | | | |
| | | | Dumpster, 40 CY Capacity | Concrete, PV panels, rubbish (panels to recycler) | 1 EA | \$ 1,800 | | | /MH | | | \$ 1,800 | |
| 21.20.00 | | | Backfill | | | | | | | | | | |
| | | | Foundation backfill, imported material fill | Backfill concrete pads | 2 /CY | \$ 80 | | | /MH | | | \$ 80 | |
| | | | Civil Work | | | \$ 1,880 | \$ - | \$ - | | | \$ - | \$ 1,880 | |
| Direct Costs | | | | | | | | | | | | \$ 13,130 | |
| 61.00.00 | | | Construction Indirect | | | | | | | | | | |
| | | | Construction Indirect | | | \$ - | \$ - | \$ - | | | \$ - | \$ - | |
| Subtotal | | | | | | | | | | | | \$ 1,880 | |
| 91.00.00 | | | Other Direct & Construction Indirect Costs | | | | | | | | | | |
| | | | 91.09 Contractor's General and Administration Expense | | | | | | | | | \$ 919.11 | |
| | | | 91.10 Contractor's Profit | | | | | | | | | \$ 1,313.01 | |
| | | | | | | | | | | | | \$ 2,232 | |
| Direct Costs + Construction Indirect Costs | | | | | | | | | | | | \$ 15,702 | |
| 93.00.00 | | | Indirect Costs | | | | | | | | | | |
| | | | 93.1 Engineering, Procurement, & Project Services | | | | | | | | | \$ 787.81 | |
| | | | 93.2 Construction Management Support | | | | | | | | | \$ 262.60 | |
| | | | 93.3 SDG&E Internal Costs | | | | | | | | | \$ 1,313.01 | |
| 95.00.00 | | | Contingency | | | | | | | | | | |
| | | | 95.1 Contingency on Subcontractor | | | \$ 282 | | | | | | \$ 282 | |
| | | | 95.2 Contingency on Scrap Value | | | | \$ - | | | | | \$ - | |
| | | | 95.3 Contingency on Material | | | | | \$ - | | | | \$ - | |
| | | | 95.4 Contingency on Labor | | | | | | | | \$ 2,355 | \$ 2,355 | |
| | | | 95.5 Contingency on Indirect | | | | | | | | | \$ 355 | |
| Total | | | | | | | | | | | | \$ 2,162 | |
| | | | | | | | | | | | | \$ (4,452) | |
| | | | | | | | | | | | | \$ - | |
| | | | | | | | | | | | | \$ 18,058 | |
| | | | | | | | | | | | | \$ 20,717 | |

San Diego Gas & Electric
 Decommissioning Cost Estimates
 PV Sites - Canopy Mounted

| ProjID | Code | Customer | Address | PV_Location | Technology | DateEnergized | FacilityName | PanelQty | | | | | |
|---|----------|---------------|---|--|------------------------------|------------------|--------------|---------------|-----------|-----------|------------|------------|---------|
| 34 | AHL | Agua Hedionda | 1580 Cannon Rd, Carlsbad, CA | Carport - CanoPV | | 3/28/2014 | S.300000191 | 24 | | | | | |
| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Crew Rate | Labor Cost | Total Cost | |
| Canopy Mount | 11.00.00 | | Demolition | | | | | | | | | | |
| | 11.22.00 | | Concrete | Column foundations | 1 /CY | | | | 6 /MH | \$ 140.47 | \$ 843 | \$ 843 | |
| | | | Concrete | Electrical equipment (Transformer, inv) | 1 /CY | | | | 24 /MH | \$ 140.47 | \$ 3,371 | \$ 3,371 | |
| | 11.24.00 | | Architectural | | | | | | | | | | |
| | | | | Remove structural canopy | | 1 EA | | | 4 /MH | \$ 140.47 | \$ 562 | \$ 562 | |
| | 11.41.00 | | Electrical Equipment | | | | | | | | | | |
| | | | | Disconnect wiring and components at service rack | | 1 EA | | | 3 /MH | \$ 127.80 | \$ 383 | \$ 383 | |
| | | | | Demo conduit from rack to tie point | | 1 EA | | | 1 /MH | \$ 127.80 | \$ 128 | \$ 128 | |
| | | | | Disconnect wiring at inverter | | 1 EA | | | 1 /MH | \$ 127.80 | \$ 128 | \$ 128 | |
| | | | | Disconnect wiring at combiner boxes, remove boxes | | 3 EA | | | 3 /MH | \$ 127.80 | \$ 383 | \$ 383 | |
| | | | | Pull wire from combiners to inverter | | 3 EA | | | 2 /MH | \$ 127.80 | \$ 256 | \$ 256 | |
| | | | | Disconnect and remove wiring at PV panels | | 24 EA | | | 4 /MH | \$ 127.80 | \$ 511 | \$ 511 | |
| | | | | Disconnect and remove grounding at PV panels and racks, Remove ground rods | | 24 EA | | | 1 /MH | \$ 127.80 | \$ 128 | \$ 128 | |
| | | | | Remove PV panel and place in dumpster | | 24 EA | | | 15 /MH | \$ 127.80 | \$ 1,917 | \$ 1,917 | |
| | | | | Remove Conduits to inverters | | 1 EA | | | 0 /MH | \$ 127.80 | \$ - | \$ - | |
| | | | | Remove inverters | | 1 EA | | | 0 /MH | \$ 127.80 | \$ - | \$ - | |
| | | | | Remove transformer | | 1 LT | | | 1 /MH | \$ 127.80 | \$ 128 | \$ 128 | |
| | | | | Demolition | | | \$ - | \$ - | \$ - | | \$ 8,738 | \$ 8,738 | |
| | 18.00.00 | | | Scrap Value | | | | | | | | | |
| | 18.10.00 | | | Mixed Steel | | | | | | | | | |
| | | | | Steel | 1 EA, 82 kW inverter | 0.05 TN | | \$ (9) | | /MH | | \$ (9) | \$ (9) |
| | | | | Steel | Service rack components | 0.04 TN | | \$ (7) | | /MH | | \$ (7) | \$ (7) |
| | | | | Steel | Conduit and fittings | 0.04 TN | | \$ (7) | | /MH | | \$ (7) | \$ (7) |
| | | | | Steel | Transformers | 0.5 TN | | \$ (88) | | /MH | | \$ (88) | \$ (88) |
| | | | | Steel | Roof ladder, 1 @ 350 lb each | 0.02 TN | | \$ (4) | | /MH | | \$ (4) | \$ (4) |
| | | | Steel | Canopy & steel | 1.78 TN | | \$ (312) | | /MH | | \$ (312) | \$ (312) | |
| 18.20.00 | | | Stainless Steel | | | | | | | | | | |
| | | | Stainless Steel | 336 Racks, 13.61 lbs each | 0.2 TN | | \$ (234) | | /MH | | \$ (234) | \$ (234) | |
| 18.30.00 | | | Copper | | | | | | | | | | |
| | | | Copper | 1 EA, 82 kW inverter | 0.02 TN | | \$ (49) | | /MH | | \$ (49) | \$ (49) | |
| | | | Copper | Wire | 0.14 TN | | \$ (342) | | /MH | | \$ (342) | \$ (342) | |
| | | | Copper | Transformers | 0.24 TN | | \$ (586) | | /MH | | \$ (586) | \$ (586) | |
| 18.50.00 | | | Aluminum | | | | | | | | | | |
| | | | PV Module | 336 Modules @8 lbs each | 239 LB | | \$ (145) | | /MH | | \$ (145) | \$ (145) | |
| | | | Conduit and fittings | 100 @ 1 lb each | 9 LB | | \$ (5) | | /MH | | \$ (5) | \$ (5) | |
| | | | Scrap Value | | | \$ - | \$ (1,787) | \$ - | | \$ - | \$ (1,787) | \$ (1,787) | |
| 21.00.00 | | | Civil Work | | | | | | | | | | |
| 21.19.00 | | | Disposal | | | | | | | | | | |
| | | | Dumpster, 40 CY Capacity | Concrete, PV panels, rubbish (panels to recycler) | 1 EA | \$ 1,800 | | | /MH | | \$ 1,800 | \$ 1,800 | |
| 21.20.00 | | | Backfill | | | | | | | | | | |
| | | | Foundation backfill, imported material fill | Backfill concrete pads | 1 /CY | \$ 40 | | | /MH | | \$ 40 | \$ 40 | |
| | | | Civil Work | | | \$ 1,840 | \$ - | \$ - | | \$ - | \$ 1,840 | \$ 1,840 | |
| Direct Costs | | | | | | | | | | | | \$ 8,791 | |
| 61.00.00 | | | Construction Indirect | | | | | | | | | | |
| | | | Construction Indirect | | | \$ - | \$ - | \$ - | | \$ - | \$ - | \$ - | |
| Subtotal | | | | | | | | | | | | \$ 8,791 | |
| 91.00.00 | | | Other Direct & Construction Indirect Costs | | | \$ 1,840 | \$ (1,787) | \$ - | | \$ 8,738 | \$ 8,791 | \$ 8,791 | |
| | | | 91.09 Contractor's General and Administration Expense | | | | | | | | \$ 615.39 | \$ 615.39 | |
| | | | 91.10 Contractor's Profit | | | | | | | | \$ 879.12 | \$ 879.12 | |
| | | | | | | | | | | | \$ 1,495 | \$ 1,495 | |
| Direct Costs + Construction Indirect Costs | | | | | | | | | | | | \$ 8,791 | |
| 93.00.00 | | | Indirect Costs | | | | | | | | | | |
| | | | 93.1 Engineering, Procurement, & Project Services | | | | | | | | \$ 527.47 | \$ 527.47 | |
| | | | 93.2 Construction Management Support | | | | | | | | \$ 175.82 | \$ 175.82 | |
| | | | 93.3 SDG&E Internal Costs | | | | | | | | \$ 879.12 | \$ 879.12 | |
| 95.00.00 | | | Contingency | | | | | | | | | | |
| | | | 95.1 Contingency on Subcontractor | | | \$ 276 | | | | | \$ 276 | \$ 276 | |
| | | | 95.2 Contingency on Scrap Value | | | \$ - | | | | | \$ - | \$ - | |
| | | | 95.3 Contingency on Material | | | \$ - | | \$ - | | | \$ - | \$ - | |
| | | | 95.4 Contingency on Labor | | | | | | | \$ 1,311 | \$ 1,311 | \$ 1,311 | |
| | | | 95.5 Contingency on Indirect | | | | | | | | \$ 237 | \$ 237 | |
| Total | | | | | | | | | | | | \$ 10,048 | |
| | | | | | | \$ 2,116 | \$ (1,787) | \$ - | | \$ 8,738 | \$ 13,692 | \$ 13,692 | |

San Diego Gas & Electric
 Decommissioning Cost Estimates
 PV Sites - Canopy Mounted

| ProjID | Code | Customer | Address | PV_Location | Technology | DateEnergized | FacilityName | te_kW | PanelQty | | | |
|---|--------------|----------------------------|--|---|------------|------------------|--------------|---------------|-----------|-----------|------------|-------------|
| 35 | CWP | Civita Westpark Apartments | 7777 Westside Dr, San Diego CA | Carport | PV/ES | 4/4/2016 | | 87 | 352 | | | |
| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Crew Rate | Labor Cost | Total Cost |
| 11.00.00 | Canopy Mount | | Demolition | | | | | | | | | |
| 11.22.00 | | | Concrete | Column foundations | 8 /CY | | | | 48 /MH | \$ 140.47 | \$ 6,743 | \$ 6,743 |
| | | | Concrete | Electrical equipment (Transformer, inw) | 1 /CY | | | | 24 /MH | \$ 140.47 | \$ 3,371 | \$ 3,371 |
| 11.24.00 | | | Architectural | | | | | | | | | |
| | | | Remove structural canopy | | 1 EA | | | | 52 /MH | \$ 140.47 | \$ 7,304 | \$ 7,304 |
| 11.41.00 | | | Electrical Equipment | | | | | | | | | |
| | | | Disconnect wiring and components at service rack | | 1 EA | | | | 42 /MH | \$ 127.80 | \$ 5,368 | \$ 5,368 |
| | | | Demo conduit from rack to tie point | | 1 EA | | | | 10 /MH | \$ 127.80 | \$ 1,278 | \$ 1,278 |
| | | | Disconnect wiring at inverter | | 1 EA | | | | 10 /MH | \$ 127.80 | \$ 1,278 | \$ 1,278 |
| | | | Disconnect wiring at combiner boxes, remove boxes | | 3 EA | | | | 43 /MH | \$ 127.80 | \$ 5,495 | \$ 5,495 |
| | | | Pull wire from combiners to inverter | | 3 EA | | | | 31 /MH | \$ 127.80 | \$ 3,962 | \$ 3,962 |
| | | | Disconnect and remove wiring at PV panels | | 352 EA | | | | 65 /MH | \$ 127.80 | \$ 8,307 | \$ 8,307 |
| | | | Disconnect and remove grounding at PV panels and racks, Remove ground rods | | 352 EA | | | | 17 /MH | \$ 127.80 | \$ 2,173 | \$ 2,173 |
| | | | Remove PV panel and place in dumpster | | 352 EA | | | | 219 /MH | \$ 127.80 | \$ 27,988 | \$ 27,988 |
| | | | Remove Conduits to inverters | | 1 EA | | | | 5 /MH | \$ 127.80 | \$ 639 | \$ 639 |
| | | | Remove inverters | | 1 EA | | | | 5 /MH | \$ 127.80 | \$ 639 | \$ 639 |
| | | | Remove transformer | | 1 LT | | | | 21 /MH | \$ 127.80 | \$ 2,684 | \$ 2,684 |
| | | | Demolition | | | \$ - | \$ - | \$ - | | | \$ 77,229 | \$ 77,229 |
| 18.00.00 | | | Scrap Value | | | | | | | | | |
| 18.10.00 | | | Mixed Steel | | | | | | | | | |
| | | | Steel | 1 EA, 82 kW inverter | 0.8 TN | | \$ (140) | | /MH | | | \$ (140) |
| | | | Steel | Service rack components | 0.61 TN | | \$ (107) | | /MH | | | \$ (107) |
| | | | Steel | Conduit and fittings | 0.65 TN | | \$ (114) | | /MH | | | \$ (114) |
| | | | Steel | Transformers | 7.26 TN | | \$ (1,271) | | /MH | | | \$ (1,271) |
| | | | Steel | Roof ladder, 1@ 350 lb each | 0.23 TN | | \$ (40) | | /MH | | | \$ (40) |
| | | | Steel | Canopy & steel | 26.07 TN | | \$ (4,562) | | /MH | | | \$ (4,562) |
| 18.20.00 | | | Stainless Steel | | | | | | | | | |
| | | | Stainless Steel | 336 Racks, 13.61 lbs each | 2.99 TN | | \$ (3,504) | | /MH | | | \$ (3,504) |
| 18.30.00 | | | Copper | | | | | | | | | |
| | | | Copper | 1 EA, 82 kW inverter | 0.26 TN | | \$ (634) | | /MH | | | \$ (634) |
| | | | Copper | Wire | 2.13 TN | | \$ (5,197) | | /MH | | | \$ (5,197) |
| | | | Copper | Transformers | 3.45 TN | | \$ (8,418) | | /MH | | | \$ (8,418) |
| 18.50.00 | | | Aluminum | | | | | | | | | |
| | | | PV Module | 336 Modules @8 lbs each | 3504 LB | | \$ (2,132) | | /MH | | | \$ (2,132) |
| | | | Conduit and fittings | 100 @ 1 lb each | 130 LB | | \$ (79) | | /MH | | | \$ (79) |
| | | | Scrap Value | | | \$ - | \$ (26,199) | \$ - | | | \$ - | \$ (26,199) |
| 21.00.00 | | | Civil Work | | | | | | | | | |
| 21.19.00 | | | Disposal | Concrete, PV panels, rubbish (panels to recycler) | 4 EA | \$ 7,200 | | | /MH | | | \$ 7,200 |
| 21.20.00 | | | Backfill | Foundation backfill, imported material fill | 8 /CY | \$ 320 | | | /MH | | | \$ 320 |
| | | | Civil Work | | | \$ 7,520 | \$ - | \$ - | | | \$ - | \$ 7,520 |
| Direct Costs | | | | | | | | | | | | |
| 61.00.00 | | | Construction Indirect | | | | | | | | | |
| | | | Construction Indirect | | | \$ - | \$ - | \$ - | | | \$ - | \$ - |
| Subtotal | | | | | | \$ 7,520 | \$ (26,199) | \$ - | | | \$ 77,229 | \$ 58,550 |
| 91.00.00 | | | Other Direct & Construction Indirect Costs | | | | | | | | | |
| | | | 91.09 | Contractor's General and Administration Expense | | | | | | | | \$ 4,098.50 |
| | | | 91.10 | Contractor's Profit | | | | | | | | \$ 5,855.00 |
| Direct Costs + Construction Indirect Costs | | | | | | \$ 7,520 | \$ (26,199) | \$ - | \$ - | \$ - | \$ 77,229 | \$ 58,550 |
| 93.00.00 | | | Indirect Costs | | | | | | | | | |
| | | | 93.1 | Engineering, Procurement, & Project Services | | | | | | | | \$ 3,513.00 |
| | | | 93.2 | Construction Management Support | | | | | | | | \$ 1,171.00 |
| | | | 93.3 | SDG&E Internal Costs | | | | | | | | \$ 5,855.00 |
| 95.00.00 | | | Contingency | | | | | | | | | |
| | | | 95.1 | Contingency on Subcontractor | | \$ 1,128 | | | | | | \$ 1,128 |
| | | | 95.2 | Contingency on Scrap Value | | | \$ - | | | | | \$ - |
| | | | 95.3 | Contingency on Material | | | | \$ - | | | | \$ - |
| | | | 95.4 | Contingency on Labor | | | | | | | \$ 11,584 | \$ 11,584 |
| | | | 95.5 | Contingency on Indirect | | | | | | | | \$ 1,581 |
| Total | | | | | | \$ 8,648 | \$ (26,199) | \$ - | | | \$ 88,813 | \$ 93,336 |

SL-016628.F_SDGE Decom(Ramona)

Decommissioning Study

**Prepared for
San Diego Gas & Electric Company
Ramona Solar Energy Plant**

Prepared by Sargent & Lundy

LEGAL NOTICE

This deliverable was prepared by Sargent & Lundy, L.L.C. (S&L) expressly for the sole use of San Diego Gas & Electric Company (Client) in accordance with the contract agreement between S&L and Client. This deliverable was prepared using the degree of skill and care ordinarily exercised by engineers practicing under similar circumstances. Client acknowledges: (1) S&L prepared this deliverable subject to the particular scope limitations, budgetary and time constraints, and business objectives of Client; (2) information and data provided by others, including Client, may not have been independently verified by S&L; and (3) the information and data contained in this deliverable are time-sensitive and changes in the data, applicable codes, standards, and acceptable engineering practices may invalidate the findings of this deliverable. Any use or reliance upon this deliverable by third parties shall be at their sole risk.

Sargent & Lundy is one of the oldest and most experienced full-service architect engineering firms in the world. Founded in 1891, the firm is a global leader in power and energy with expertise in grid modernization, renewable energy, energy storage, nuclear power, and fossil fuels. Sargent & Lundy delivers comprehensive project services—from consulting, design, and implementation to construction management, commissioning, and operations/maintenance—with an emphasis on quality and safety. The firm serves public and private sector clients in the power and energy, gas distribution, industrial, and government sectors.

55 East Monroe Street • Chicago, IL 60603-5780 USA • 312-269-2000

VERSION LOG

| Version | Issue Date | Sections Modified |
|----------|-------------------|---------------------|
| Draft v0 | December 15, 2021 | Initial Issue |
| Final | March 30, 2022 | ES, 2.2, Appendix A |

ISSUE SUMMARY AND APPROVAL PAGE

This is to certify that this document has been prepared, reviewed, and approved in accordance with Sargent & Lundy's Standard Operating Procedure SOP-0405, which is based on ANSI/ISO/ASSQC Q9001 Quality Management Systems.

Contributors

Prepared by:

| Name | Title | Section(s) Prepared | Signature | Date |
|--------------|---------------------------|--------------------------|-----------|-----------|
| Ikbal Lebbi | Manager Consultant | ES, Section 1, Section 2 | | 3/30/2022 |
| Gregory Amen | Cost Information Division | Section 3, Appendix A | | 3/30/2022 |

Reviewed by:

| Name | Title | Section(s) Reviewed | Signature | Date |
|--------------------|---|-----------------------|-----------|-----------|
| Borko Andric | Manager | Section 3, Appendix A | | 3/30/2022 |
| Craig Gitchell | Senior Energy Consultant | All | | 3/30/2022 |
| Robert. P. Charles | Senior Principal Consultant & Project Manager | All | | 3/30/2022 |

Approved by:

| | |
|--|----------------|
| | March 30, 2022 |
| Kevin C. Hopkins | Date |
| Principal Consultant & Project Manager | |

CONTENTS

| | |
|--------------------------------------|----------|
| EXECUTIVE SUMMARY | I |
| METHODOLOGY | I |
| CONCEPTUAL COST ESTIMATE | I |
| 1. INTRODUCTION..... | 1 |
| 1.1. RAMONA SOLAR ENERGY PLANT | 1 |
| 2. COST ESTIMATE | 4 |
| 2.1. METHODOLOGY | 4 |
| 2.2. COST ESTIMATE SUMMARY | 4 |
| 3. BASIS OF ESTIMATE | 6 |
| 4. REFERENCES..... | 9 |

TABLES

| | |
|---|----|
| TABLE ES-1 — RAMONA COST ESTIMATE SUMMARY..... | I |
| TABLE ES-2 — RAMONA COST ESTIMATE SUMMARY BY FERC ACCOUNT | II |
| TABLE 1-1 — RAMONA COMPONENTS TO BE DECOMMISSIONED | 2 |
| TABLE 2-1 — RAMONA COST ESTIMATE SUMMARY | 5 |
| TABLE 2-2 — RAMONA COST ESTIMATE SUMMARY BY FERC ACCOUNT | 5 |
| TABLE 3-1 — SCRAP VALUE..... | 7 |
| TABLE 3-2 — SDG&E INTERNAL COSTS IN SUPPORT OF DECOMMISSIONING..... | 7 |

APPENDIXES

APPENDIX A. CONCEPTUAL COST ESTIMATE TO DECOMMISSION RAMONA SOLAR

ACRONYMS AND ABBREVIATIONS

| Acronym/Abbreviation | Definition/Clarification |
|----------------------|--------------------------------------|
| CEC | California Energy Commission |
| FERC | Federal Energy Regulatory Commission |
| Owner | San Diego Gas & Electric Company |
| PTC | PVUSA Test Conditions |
| PV | photovoltaic |
| Ramona | Ramona Solar Energy Plant |
| S&L | Sargent & Lundy |
| SDG&E | San Diego Gas & Electric Company |
| STC | Standard Test Conditions |

EXECUTIVE SUMMARY

Sargent & Lundy (S&L) was contracted by San Diego Gas & Electric Company (“SDG&E” or the “Owner”) to perform an independent conceptual dismantling cost estimate and average service life estimate for the Ramona Solar Energy Plant (Ramona) near San Diego, California. The work scope included a review of drawings and documents of the facility.

METHODOLOGY

The S&L methodology for developing the cost estimate consists of three elements: (i) S&L experience in developing plant demolition costs and S&L’s existing database for numerous other projects; (ii) use of the unit cost factor methodology; and (iii) quotes from previous projects for similar activities. The cost estimate was developed based on the drawings, documents, and data provided by the Owner [5]. These drawings and documents were used to estimate the foundation sizes, steel quantities, solar array material quantities, and other equipment quantities. This information was used with unit cost factors developed by S&L based on industry data and experience. Unit cost factors for concrete removal, steel removal, cutting costs, etc. were developed from labor and material cost information. S&L also estimated the quantities of metals that could be recovered and sold for scrap. The estimate includes the value of scrap metals; however, equipment is assumed to have no resale or other salvage value besides the value of scrap metal at the end of its life.

CONCEPTUAL COST ESTIMATE

The summary of the cost estimate for decommissioning Ramona is shown in Table ES-1. The FERC account for the estimate is E344.1 for solar generators, as shown in Table ES-2. All costs are in 2021 U.S. dollars. The decommissioning costs are expected to increase by the end of the service life of the asset due to escalation and other factors.

Table ES-1 — Ramona Cost Estimate Summary

| Description | Total Cost | Subtotal |
|--|--------------------|-------------|
| Demolition Direct Costs | \$1,962,188 | – |
| Labor | – | \$1,256,264 |
| Subcontracts | – | \$469,529 |
| Equipment | – | \$193,695 |
| Material | – | \$15,700 |
| General Condition (Decommissioning Contractor Indirect) Costs | \$669,052 | – |

| Description | Total Cost | Subtotal |
|---|--------------------|-----------|
| Scrap Value | (\$156,059) | – |
| Subtotal Demolition Contractor Costs | \$2,475,181 | – |
| Project Indirect Costs | \$270,000 | – |
| Engineering | – | \$30,000 |
| SDG&E Internal Costs | – | \$240,000 |
| Contingency Costs | \$435,185 | – |
| Total Demolition Costs | \$3,180,366 | – |

Table ES-2 — Ramona Cost Estimate Summary by FERC Account

| FERC No. | Description | Total Cost |
|----------|--------------------|----------------|
| E344.1 | Generators - Solar | \$3,180,366 |
| – | General Conditions | Included Above |
| – | Engineering | Included Above |
| – | Contingency | Included Above |
| – | Total Project Cost | \$3,180,366 |

1. INTRODUCTION

Sargent & Lundy (S&L) was contracted by San Diego Gas & Electric Company (“SDG&E” or the “Owner”) to perform an independent conceptual cost estimate for the Ramona Solar Energy Plant (Ramona) near San Diego, California. The work scope included a review of drawings and documents of the facility.

Sargent & Lundy has been dedicated to providing complete engineering and environmental services exclusively to the power industry since 1891. Through our work with various utilities, lending institutions, and developers over the years, Sargent & Lundy Consulting has become one of the premier power project consultants in the power industry. This commitment to quality is proven by the successful completion of our ISO 9001 certification audit. Our experience encompasses independent engineer services, including decommissioning cost estimation and average service life evaluation for both global and domestic electric power assets.

Sargent & Lundy has engineered over 958 power plant units. We have both the benefit of extensive design experience with feedback from operating plants, as well as individuals with extensive plant operations experience, to support our consulting services. S&L has extensive decommissioning and related services experience, including power plant dismantling, demolition, and layout for fossil fuel, renewable energy, and nuclear plants. This includes decommissioning cost estimates, decommissioning studies, and related services for 18 clients at more than 70 stations. S&L also has extensive experience providing clients with testimony services.

1.1. RAMONA SOLAR ENERGY PLANT

Ramona is located within the rural community of Ramona in San Diego County. The site is located on SDG&E land at the corner of Creelman Lane and Ashley Road, approximately one-half mile west of San Vicente Road. The solar plant utilizes 18.3 acres of land and is designed to produce power for 25 years.

Ramona consists of a total of 15,012 330-W solar photovoltaic (PV) modules, which equates to a system size of 4.95 MW_{DC} (STC), 4.41 MW_{DC} (PTC), and 4.32 MW_{AC} (CEC). Output is limited to the 4.4-MW combined inverter nameplate ratings. The PV system exports power to the utility power grid.

The 4-MW_{AC} system uses Hyundai silicon crystalline modules (Model No. HIS-S330TI) and fixed racking. The current generated by module strings is collected in several combiner boxes, then routed to the DC fuse box, inverters, and transformers. The system uses two Sunny Central 2200-US 4-MW inverters (2200 kVA for 1000 V_{DC}) and two EATON transformers (COOPER POWER SERIES 00020A65XEPA).

The solar cells are connected in series to make up a module. The modules are placed in series called module strings; the system has 18 such strings. The module strings are wired and routed underground to a collection point at the disconnect combiner box. The system has 48 SOLARBOS combiner boxes (1000 V_{DC}, 250-A disconnect switch, 18 input circuits). The combiner box collects the DC circuits from multiple module strings and combines them into one circuit that is then routed to the inverter.

The solar PV array is installed on a ground-mounted racking structure and surrounded by a perimeter fence. The PV arrays are supported on galvanized steel posts that are driven into the ground. The inverters, transformers, switchgear, and water tank are supported on concrete pad foundations. The security camera, fencing, and shade structures are supported on posts with concrete pier foundations.

For the purposes of this report, the solar system and supporting foundations, racks, solar modules, inverters, transformers, combiners, and cables will be removed at decommissioning. The fencing, security camera, duct banks (for communication and the security camera), and access roads—including all foundations—will also be completely removed upon decommissioning. The 4000-gallon water tank and pump, switchgear station, and shade structures—including all foundations—will be removed at decommissioning. Buried conduits, cables, or other buried commodities installed in support of the project may be abandoned in place at the discretion of the landowner and in accordance with agreements with the state and the federal regulating entities. Access roads or other existing facilities that are likely to be impacted or modified during the decommissioning and reclamation process will be repaired after completion of the decommissioning phase.

The quantities of materials for the main foundations and components to be removed, salvaged, or disposed are included herein. Several materials for removed components may have salvage or resale values; however, there are some components that may have no salvage or resale values at the time of decommissioning. The disposal of waste materials will be in accordance with state and federal laws in an approved, licensed solid waste facility. Solar panels may have a resale value in the market depending on usage and working condition at the time of decommissioning. Table 1-1 summarizes the main structures and components of the solar plant included in this decommissioning report:

Table 1-1 — Ramona Components to Be Decommissioned

| Component | Quantity | Unit of Measure |
|------------------------------------|----------|-----------------|
| Solar Modules | 15,012 | Each |
| Racks | 1,280 | Each |
| Steel Posts | 1,324 | Each |
| Inverter Stations with Foundations | 2 | Each |

| Component | Quantity | Unit of Measure |
|--|----------|-----------------|
| Transformers with Foundations | 2 | Each |
| Combiner Boxes | 48 | Each |
| Electrical Cables and Conduits (estimated) | 61,780 | Linear Foot |
| Perimeter Fencing | 3,907 | Linear Foot |
| Access Roads | 3,907 | Linear Foot |
| Gravel | 1,447 | Cubic Feet |
| Water Tank | 1 | Each |
| Switchgear | 1 | Each |
| Camera | 1 | Each |

2. COST ESTIMATE

2.1. METHODOLOGY

The methodology used for developing the cost estimate is based on deterministic methods. Deterministic methods were used based on the quantity and size of equipment (e.g., the number of foundations, linear feet of duct banks, equipment, etc.).

The cost estimate was developed based on drawings, documents, and data provided by the Owner. These drawings and documents were used to estimate the number of solar panels, foundation sizes, steel quantities, and other equipment quantities.

The S&L methodology for developing the cost estimate consist of three elements: (i) S&L experience in developing plant demolition cost and S&L's existing database for numerous other projects; (ii) use of the unit cost factor methodology; and (iii) quotes for previous projects for similar activities.

Cost estimates were created using the S&L cost model format and the S&L cost database. The estimates developed include both summaries and details for each type of work performed, indirect costs, and contingencies. The cost estimate database report lists costs by buildings, plant systems, and other categories.

An inventory of solar panels, equipment, concrete, duct banks, wiring, and other equipment was developed based on a review of the drawings. This information was used with unit cost factors developed by S&L based on industry data and experience. Unit cost factors for concrete removal, steel removal, cutting costs, and other tasks were developed from labor and material cost information. S&L also estimated the quantities of recoverable metals that could be recovered and sold for scrap. The estimate includes the value of scrap metals; however, equipment is assumed to have no resale or other salvage value besides the value of scrap metal at the end of its life. Solar panels were assumed to be recycled by a company such as We Recycle Solar at a cost to SDG&E of \$20/panel based on a publication by the National Renewable Energy Laboratory and verbal information from We Recycle Solar

2.2. COST ESTIMATE SUMMARY

The summary of the cost estimate for decommissioning the Ramona Solar Energy Plant is shown in Table 2-1. The commercial and technical basis for the estimate is included in Section 3. The detailed estimate is included in Appendix A.

The estimate is represented by the FERC account for solar generators, as shown in Table 2-2.

All costs are in 2021 U.S. dollars. The decommissioning costs are expected to increase by the end of service life of the asset due to escalation and other factors.

Table 2-1 — Ramona Cost Estimate Summary

| Description | Total Cost | Subtotal |
|--|--------------------|-------------|
| Demolition Direct Costs | \$1,962,188 | – |
| Labor | – | \$1,256,264 |
| Subcontracts | – | \$469,529 |
| Equipment | – | \$193,695 |
| Material | – | \$15,700 |
| General Condition (Decommissioning Contractor Indirect) Costs | \$669,052 | – |
| Scrap Value | (\$156,059) | – |
| Subtotal Demolition Contractor Costs | \$2,475,181 | – |
| Project Indirect Costs | \$270,000 | – |
| Engineering | – | \$30,000 |
| SDG&E Internal Costs | – | \$240,000 |
| Contingency Costs | \$435,185 | – |
| Total Demolition Costs | \$3,180,366 | – |

Table 2-2 — Ramona Cost Estimate Summary by FERC Account

| FERC No. | Description | Total Cost |
|----------|--------------------|----------------|
| E344.1 | Generators - Solar | \$3,180,366 |
| – | General Conditions | Included Above |
| – | Engineering | Included Above |
| – | Contingency | Included Above |
| – | Total Project Cost | \$3,180,366 |

3. BASIS OF ESTIMATE

The basis for the cost estimate is as follows:

1. Construction Labor Wages

Craft labor rates (or craft hourly rates) for the cost estimate are based on the prevailing wages for San Diego, California as published in *R.S. Means Labor Rates for the Construction Industry* (2021). These prevailing rates are representative of union or non-union rates, whichever is prevailing in the area. Costs have been added to cover social security, workmen's compensation, and federal and state unemployment insurance. The resulting burdened craft rates were then used to develop typical crew rates applicable to the task being performed.

2. Labor Work Schedule and Incentives

The labor estimate is based on a 40-hour workweek with no per diem or other labor incentives.

3. Quantity Sources

Quantities of pieces of equipment and/or bulk material commodities used in this cost estimate were developed from engineering-supplied information from the sites and the S&L database.

4. General Conditions Cost

Allowances were included for the decommissioning contractor indirect costs in the cost estimate as direct costs, as noted for the following:

- Labor Supervision
- Construction Management
- Field Office Expenses
- Safety
- Temporary Facilities
- Mobilization/Demobilization
- Legal Expenses/Claims
- Small Tools and Consumables
- General Liability Insurance
- Construction Equipment Mobilization/Demobilization
- Freight on Material
- Contractor's General and Administrative Costs
- Contractor's Profit

5. Scrap

Scrap metals are a globally traded commodity and are part of the larger metals industry. The value of scrap metal is subject to constantly changing economic conditions; as such, the price of mixed steel, stainless steel, copper, and aluminum can vary greatly over time as a result of global supply and demand. The value of scrap for this study was determined by a 12-month average from *Scrap Metals MarketWatch*¹ (November 2020–October 2021) for the West Coast (Zone 1) of the United States. The values obtained are delivered prices to the recycler. Transportation cost to the recycler is assumed to be \$30/ton, resulting in the values below:

Table 3-1 — Scrap Value

| Commodity | Scrap Value (\$/ton) |
|--------------------------|----------------------|
| Carbon Steel | 175 |
| #2 Copper | 6,145 |
| #2 Insulated Copper Wire | 2,440 |

Note: 1 ton = 2000 lbs.

6. PV Panel Recycle

At the end of their useful life, many PV panels are currently sent to landfills that may release substances harmful to the environment. SDG&E has elected to recycle the PV panels in lieu of landfill disposal. In this scenario, SDG&E will pay a company such as We Recycle Solar and other specialized recyclers to recycle the panels for \$20/panel. This cost is on the low end of current pricing and is based on a publication by the National Renewable Energy Laboratory and a conversation with We Recycle Solar.

7. Project Schedule

Ramona has a 12-month construction schedule.

8. Indirect Expenses

- Engineering is included to cover preparation of the decommissioning work specification, the engineering required to place the plant in safe shutdown, and any unique engineering required during demolition.
- SDG&E internal costs are included to cover costs in support of decommissioning the facility. These costs are summarized in Table 3-2.

Table 3-2 — SDG&E Internal Costs in Support of Decommissioning

| Activity | Estimated Cost |
|--|----------------|
| Labor to prepare the site for demolition, including drain oils, drain reagents, de-energization of the power buses, etc. | \$90,000 |

¹ www.americanrecycler.com

| Activity | Estimated Cost |
|--|------------------|
| Site security | \$60,000 |
| Subcontracts to remove chemicals, oils, and reagents from the site | \$40,000 |
| SDG&E project management, permitting, and procurement | \$80,000 |
| Total | \$270,000 |

9. Escalation Rates

No escalation rates are included.

10. Sales and Use Taxes

Sales and use taxes are not included.

11. Contingency

- A 15% contingency is applied for material, labor, and indirect expenses.
- There is no contingency on scrap value.

12. Contract Basis for Estimate

The contracting strategy will be a multiple lump sum.

13. Assumptions

- The facility will be in safe-shutdown mode and ready for a decommissioning contractor to start work.
- All chemicals and lubricating oils will be removed from the facilities to be demolished by the utility before demolition.
- No extraordinary environmental costs for demolition will be needed.
- Switchyards within the plant boundaries are not part of the scope, nor are access roads to these facilities.
- All items above grade and to a depth of four feet will be demolished. All foundations will be removed. Any other items buried more than 4 feet deep will remain in place.
- All demolished materials are considered debris, except for organic combustibles and non-embedded metals with scrap value.
- The basis for salvage estimating is for scrap value only. No resale of equipment or material is included.
- Handling onsite and offsite disposal of hazardous materials will be performed in compliance with methods approved by SDG&E's Environmental Services Department.\
- All borrow (fill) material is assumed to be from offsite sources.

4. REFERENCES

1. Sargent & Lundy Cost Database.
2. R.S. Means Cost Data, 2021.
3. Engineering drawings, equipment lists, operations and maintenance records, and other information provided by San Diego Gas & Electric.
4. *Scrap Metals MarketWatch*, West Coast (Zone 1), www.americanrecycler.com.
5. Ramona decommissioning data provided by SDG&E in response to an information request.

**APPENDIX A. CONCEPTUAL COST ESTIMATE TO
DECOMMISSION RAMONA SOLAR**

**SAN DIEGO GAS & ELECTRIC
RAMONA SOLAR ENERGY PLANT
DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS**

| | |
|-------------------------|------------|
| Estimator | GA |
| Labor rate table | 21CASAN |
| Project No. | A14520.001 |
| Estimate Date | 12/8/21 |
| Reviewed By | BA |
| Approved By | BA |
| Estimate No. | 35767A |

SAN DIEGO GAS & ELECTRIC
 RAMONA SOLAR ENERGY PLANT
 DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS



| Area | Description | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|--------|--------------------------------|------------------|-------------|---------------|-----------|------------|--------------|------------|
| E344.1 | GENERATORS - SOLAR | 198,175 | (90,570) | | 8,004 | 1,296,551 | 268,082 | 1,672,238 |
| E345.1 | ACCESSORY ELECTRICAL EQUIPMENT | 431,426 | (65,488) | 24,457 | 7,409 | 1,086,175 | 31,558 | 1,508,128 |

**SAN DIEGO GAS & ELECTRIC
 RAMONA SOLAR ENERGY PLANT
 DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS**



Estimate Totals

| Description | Amount | Totals | Hours |
|-------------------------------------|------------------|------------------|--------|
| Labor | 2,382,727 | | 15,413 |
| Material | 24,457 | | |
| Subcontract | 629,601 | | |
| Construction Equipment | 299,640 | | |
| Process Equipment | <u>(156,059)</u> | | |
| | 3,180,366 | 3,180,366 | |
| General Conditions | | | |
| Additional Labor Costs | | | |
| Site Overheads | | | |
| Other Construction Indirects | | | |
| | | 3,180,366 | |
| Project Indirect Costs | | | |
| | | 3,180,366 | |
| Contingency | | | |
| | | 3,180,366 | |
| Escalation | | | |
| | | 3,180,366 | |
| Total | | 3,180,366 | |

General Condition Costs, Indirect Costs and Contingency are allocated in the line items above.

SAN DIEGO GAS & ELECTRIC
 RAMONA SOLAR ENERGY PLANT
 DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS



| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|---------------|----------|----------|--|-----------------------------------|--------------|------------------|-------------|---------------|-----------|------------|--------------|------------|
| E344.1 | | | GENERATORS - SOLAR | | | | | | | | | |
| | 10.00.00 | | WHOLE PLANT DEMOLITION | | | | | | | | | |
| | | 10.21.00 | CIVIL WORK | | | | | | | | | |
| | | | REMOVE FENCE | | 3,907.00 LF | - | - | | 156 | 26,336 | 11,164 | 37,501 |
| | | | CIVIL WORK | | | | | | 156 | 26,336 | 11,164 | 37,501 |
| | | 10.22.00 | CONCRETE | | | | | | | | | |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | INVERTERS, SWITCHGEAR FOUNDATIONS | 28.00 CY | - | - | | 47 | 7,998 | 1,607 | 9,605 |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | WATER TANK AND PUMP PAD | 13.00 CY | - | - | | 22 | 3,713 | 746 | 4,459 |
| | | | BUILDING/EQUIPMENT FOUNDATION/PAD | PANEL BOARD FOUNDATIONS (8 EACH) | 2.00 CY | - | - | | 6 | 1,016 | 204 | 1,220 |
| | | | REMOVE CONCRETE PIER | SECURITY CAMERA POST PIER | 4.00 EA | - | - | | 1 | 203 | 41 | 244 |
| | | | REMOVE CONCRETE PIER | INVERTER SHADE STRUCTURE | 12.00 EA | - | - | | 12 | 2,031 | 408 | 2,439 |
| | | | REMOVE CONCRETE PIER | SWITCHGEAR SHADE STRUCTURE | 4.00 EA | - | - | | 4 | 677 | 136 | 813 |
| | | | REMOVE CONCRETE PIER | FENCE POST PIER | 500.00 EA | - | - | | 150 | 25,389 | 5,103 | 30,492 |
| | | | REMOVE AND LOADOUT CONCRETE DUCTBANK | AC DUCTBANK | 560.00 LF | - | - | | 280 | 47,393 | 9,525 | 56,918 |
| | | | INCLUDING EMBEDDED PVC CONDUIT AND MANHOLE. | | | | | | | | | |
| | | | EXCAVATE AND BACKFILL WITH NATIVE SOIL INCLUDED. | | | | | | | | | |
| | | | REMOVE AND LOADOUT CONCRETE DUCTBANK | DC DUCTBANK | 2,212.00 LF | - | - | | 1,770 | 299,522 | 60,198 | 359,720 |
| | | | INCLUDING EMBEDDED PVC CONDUIT AND PULLBOXES. | | | | | | | | | |
| | | | EXCAVATE AND BACKFILL WITH NATIVE SOIL INCLUDED. | | | | | | | | | |
| | | | REMOVE AND LOADOUT CONCRETE DUCTBANK | SITE PERIMETER DUCTBANK FOR | 2,772.00 LF | - | - | | 1,386 | 234,594 | 47,149 | 281,742 |
| | | | INCLUDING EMBEDDED PVC CONDUIT AND PULLBOXES. | COMMUNICATION AND SECURITY | | | | | | | | |
| | | | EXCAVATE AND BACKFILL WITH NATIVE SOIL INCLUDED. | CAMERAS | | | | | | | | |
| | | | CONCRETE | | | | | | 3,678 | 622,534 | 125,117 | 747,651 |
| | | 10.23.00 | STEEL | | | | | | | | | |
| | | | REMOVE AND LOAD STEEL RACKING POST | | 1,324.00 EA | - | - | | 794 | 128,915 | 20,719 | 149,634 |
| | | | REMOVE AND LOAD STEEL | INVERTER SHADE STRUCTURES | 2.00 EA | - | - | | 64 | 10,386 | 1,669 | 12,055 |
| | | | REMOVE AND LOAD STEEL | SWITCHGEAR SHADE STRUCTURE | 1.00 EA | - | - | | 32 | 5,193 | 835 | 6,028 |
| | | | REMOVE AND LOAD SECURITY CAMERA 10 FT POLE | | 4.00 EA | - | - | | 12 | 1,947 | 313 | 2,260 |
| | | | STEEL | | | | | | 902 | 146,441 | 23,536 | 169,978 |
| | | 10.31.00 | MECHANICAL EQUIPMENT | | | | | | | | | |
| | | | 4,000 GAL WATER TANK AND PUMP | | 1.00 LT | - | - | | 60 | 9,097 | 2,113 | 11,211 |
| | | | MECHANICAL EQUIPMENT | | | | | | 60 | 9,097 | 2,113 | 11,211 |
| | | 10.43.00 | CABLE | | | | | | | | | |
| | | | #4 1/C BARE CU WIRE IN CONDUIT | DC WIRE | 20,370.00 LF | - | - | | 204 | 30,163 | 5,051 | 35,214 |
| | | | #4/0 3/C CU INSULATED WIRE IN CONDUIT | AC WIRE | 610.00 LF | - | - | | 43 | 6,323 | 1,059 | 7,382 |
| | | | #250 KCMIL 1/C CU INSULATED WIRE IN CONDUIT | DC WIRE | 40,800.00 LF | - | - | | 2,040 | 302,070 | 50,588 | 352,658 |
| | | | CABLE | | | | | | 2,286 | 338,555 | 56,698 | 395,253 |
| | | | WHOLE PLANT DEMOLITION | | | | | | 7,083 | 1,142,964 | 218,629 | 1,361,594 |
| | 18.00.00 | | SCRAP VALUE | | | | | | | | | |
| | | 18.10.00 | MIXED STEEL | | | | | | | | | |
| | | | STEEL | FENCING | -16.00 TN | - | (3,472) | - | | | | (3,472) |
| | | | STEEL | INVERTER SHADE STRUCTURES | -1.42 TN | - | (308) | - | | | | (308) |
| | | | STEEL | SWITCHGEAR SHADE STRUCTURE | -0.90 TN | - | (195) | - | | | | (195) |
| | | | STEEL | WATER TANK AND PUMP | -2.00 TN | - | (434) | - | | | | (434) |
| | | | MIXED STEEL | | | | (4,409) | | | | | (4,409) |
| | | 18.30.00 | COPPER | | | | | | | | | |
| | | | #2 INSULATED COPPER WIRE | | -35.40 TN | - | (78,234) | - | 0 | | | (78,234) |
| | | | BARE COPPER WIRE | | -1.29 TN | - | (7,927) | - | 0 | | | (7,927) |
| | | | COPPER | | | | (86,161) | | 0 | | | (86,161) |
| | | | SCRAP VALUE | | | | (90,570) | | 0 | | | (90,570) |
| | 21.00.00 | | CIVIL WORK | | | | | | | | | |
| | | 21.17.00 | EXCAVATION | | | | | | | | | |
| | | | EXCAVATION, 4 INCHES DEEP | GRAVEL ACCESS ROAD, 4 INCHES DEEP | 1,447.00 CY | - | - | | 203 | 35,011 | 30,079 | 65,090 |
| | | | EXCAVATION | | | | | | 203 | 35,011 | 30,079 | 65,090 |
| | | 21.18.00 | HAULING | | | | | | | | | |
| | | | HAULING, 40 MILE ROUNDTRIP, 50 MPH | ACCESS ROAD GRAVEL | 1,447.00 CY | | | 30,091 | | | | 30,091 |
| | | | HAULING | | | | | 30,091 | | | | 30,091 |
| | | 21.19.00 | DISPOSAL | | | | | | | | | |
| | | | DUMPSTER, 40 CY CAPACITY | CONCRETE, RUBBISH, PVC CONDUIT | 120.00 EA | 124,772 | - | | | | | 124,772 |
| | | | NO DISPOSAL FEE FOR ACCESS ROAD GRAVEL. | | EA | | - | | | | | |
| | | | ASSUME IT IS REUSED | | | | | | | | | |

**SAN DIEGO GAS & ELECTRIC
 RAMONA SOLAR ENERGY PLANT
 DECOMMISSIONING STUDY - SORTED BY FERC ACCOUNTS**



| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|---------------|----------|----------|--|--|--------------|------------------|-----------------|---------------|--------------|------------------|----------------|------------------|
| | | | DISPOSAL | | | 124,772 | | | | | | 124,772 |
| | 21.45.00 | | GRADING FINISH GRADING | DUCTBANK TRENCHES AND ROADWAY - FILL IN AND BLEND/LEVEL INTO SURROUNDING AREA | 71,851.00 SY | | | | 719 | 118,576 | 19,374 | 137,949 |
| | | | GRADING | | | | | | 719 | 118,576 | 19,374 | 137,949 |
| | 21.47.00 | | LANDSCAPING HYDRO SEEDING | | 14.80 AC | 43,313 | | | | | | 43,313 |
| | | | LANDSCAPING | | | 43,313 | | | | | | 43,313 |
| | | | CIVIL WORK | | | 198,175 | | | 921 | 153,587 | 49,452 | 401,214 |
| | | | E344.1 GENERATORS - SOLAR | | | 198,175 | (90,570) | | 8,004 | 1,296,551 | 268,082 | 1,672,238 |
| E345.1 | | | ACCESSORY ELECTRICAL EQUIPMENT | | | | | | | | | |
| | 10.00.00 | | WHOLE PLANT DEMOLITION | | | | | | | | | |
| | | 10.41.00 | ELECTRICAL EQUIPMENT | | | | | | | | | |
| | | | DISCONNECT/REMOVE FREE STANDING PANEL BOARD RACK | | 8.00 EA | | | | 64 | 9,704 | 2,254 | 11,958 |
| | | | DISCONNECT/REMOVE INVERTERS | | 2.00 EA | | | | 48 | 7,278 | 1,691 | 8,969 |
| | | | DISCONNECT / REMOVE "DISCONNECT COMBINER" | | 48.00 EA | | | | 96 | 14,053 | 275 | 14,328 |
| | | | DISCONNECT/REMOVE DC WIRING (PANEL TO COMBINER) | | 15,012.00 EA | | | | 751 | 109,877 | 2,148 | 112,025 |
| | | | DISCONNECT/REMOVE GROUNDING WIRING AT PANELS AND RACKS, REMOVE GROUND RODS | | 15,012.00 EA | | | | 600 | 87,902 | 1,719 | 89,620 |
| | | | REMOVE PV PANEL FROM RACK | | 15,012.00 EA | | | | 1,501 | 219,754 | 4,296 | 224,050 |
| | | | LOAD AND BAND PV PANELS ON PALLET | | 15,012.00 EA | | | | 300 | 43,951 | 859 | 44,810 |
| | | | 4' X 8' WOOD PALLET, HANDLE AND LOAD IN TRUCK | 30 PANELS PER PALLET | 500.00 EA | | | 23,367 | 100 | 15,162 | 3,522 | 42,051 |
| | | | STEEL STRAP BANDING MATERIAL COST | | 1.00 LT | | | 1,090 | | | | 1,090 |
| | | | REMOVE "RBI" SOLAR RACKS | | 1,280.00 EA | | | | 3,840 | 562,121 | 10,990 | 573,110 |
| | | | TRANSFORMERS 2200 KVA, 34.5 KV OUTPUT | | 2.00 EA | | | | 48 | 7,278 | 1,691 | 8,969 |
| | | | REMOVE SWITCHGEAR AND SCADA CABINET | | 1.00 EA | | | | 60 | 9,097 | 2,113 | 11,211 |
| | | | ELECTRICAL EQUIPMENT | | | | | 24,457 | 7,409 | 1,086,175 | 31,558 | 1,142,191 |
| | | | WHOLE PLANT DEMOLITION | | | | | 24,457 | 7,409 | 1,086,175 | 31,558 | 1,142,191 |
| | 18.00.00 | | SCRAP VALUE | | | | | | | | | |
| | | 18.10.00 | MIXED STEEL | | | | | | | | | |
| | | | STEEL | "RBI" SOLAR RACKS AND POSTS | -261.00 TN | | (56,637) | | | | | (56,637) |
| | | | STEEL | CONDUIT, FITTINGS AND DISCONNECTS | -0.50 TN | | (108) | | | | | (108) |
| | | | STEEL | SERVICE RACK COMPONENTS | -0.47 TN | | (102) | | | | | (102) |
| | | | STEEL | INVERTERS | -8.82 TN | | (1,914) | | | | | (1,914) |
| | | | STEEL / COPPER MIX - LARGE TRANSFORMER > 100 KVA | MEDIUM VOLTAGE BLOCK WHICH INCLUDES TRANSFORMERS 2200 KVA, 34.5 KV OUTPUT | -15.50 TN | | (6,727) | | 0 | | | (6,727) |
| | | | MIXED STEEL | | | | (65,488) | | | | | (65,488) |
| | | | SCRAP VALUE | | | | (65,488) | | 0 | | | (65,488) |
| | 21.00.00 | | CIVIL WORK | | | | | | | | | |
| | | 21.18.00 | HAULING | | | | | | | | | |
| | | | HAULING, 170 MILES TO YUMA, ARIZONA | 20 PALLETS / TRUCK LOAD. TRANSPORT PV PANELS TO "WE RECYCLE SOLAR" FACILITY IN YUMA, ARIZONA | 25.00 EA | 50,720 | | | | | | 50,720 |
| | | | HAULING | | | 50,720 | | | | | | 50,720 |
| | | 21.19.00 | DISPOSAL | | | | | | | | | |
| | | | PV PANEL DISPOSAL FEE. | "WE RECYCLE SOLAR", YUMA, ARIZONA | 15,012.00 EA | 380,706 | | | | | | 380,706 |
| | | | DISPOSAL | | | 380,706 | | | | | | 380,706 |
| | | | CIVIL WORK | | | 431,426 | | | | | | 431,426 |
| | | | E345.1 ACCESSORY ELECTRICAL EQUIPMENT | | | 431,426 | (65,488) | 24,457 | 7,409 | 1,086,175 | 31,558 | 1,508,128 |

**SAN DIEGO GAS & ELECTRIC
RAMONA SOLAR ENERGY PLANT
DECOMMISSIONING STUDY**

| | |
|-------------------------|------------|
| Estimator | GA |
| Labor rate table | 21CASAN |
| Project No. | A14520.001 |
| Estimate Date | 12/8/21 |
| Reviewed By | BA |
| Approved By | BA |
| Estimate No. | 35767A |

SAN DIEGO GAS & ELECTRIC
 RAMONA SOLAR ENERGY PLANT
 DECOMMISSIONING STUDY



| Group | Description | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|----------|------------------------|------------------|------------------|---------------|---------------|------------------|----------------|------------------|
| 10.00.00 | WHOLE PLANT DEMOLITION | | | 15,700 | 14,492 | 1,175,287 | 161,728 | 1,352,715 |
| 18.00.00 | SCRAP VALUE | | (156,059) | | 0 | | | (156,059) |
| 21.00.00 | CIVIL WORK | 496,529 | | | 921 | 80,977 | 31,967 | 609,473 |
| | TOTAL DIRECT | 496,529 | (156,059) | 15,700 | 15,413 | 1,256,264 | 193,695 | 1,806,129 |

**SAN DIEGO GAS & ELECTRIC
 RAMONA SOLAR ENERGY PLANT
 DECOMMISSIONING STUDY**



Estimate Totals

| Description | Amount | Totals | Hours |
|-------------------------------------|------------------|------------------|--------|
| Labor | 1,256,264 | | 15,413 |
| Material | 15,700 | | |
| Subcontract | 496,529 | | |
| Construction Equipment | 193,695 | | |
| Process Equipment | <u>(156,059)</u> | | |
| | 1,806,129 | 1,806,129 | |
| General Conditions | | | |
| Additional Labor Costs | | | |
| 90-1 Labor Supervision | 75,376 | | |
| 90-2 Show-up Time | 25,125 | | |
| 90-3 Cost Due To OT 5-10's | | | |
| 90-4 Cost Due To OT 6-10's | | | |
| 90-5 Per Diem | | | |
| Site Overheads | | | |
| 91-1 Construction Management | 135,676 | | |
| 91-2 Field Office Expenses | 29,849 | | |
| 91-3 Material&Quality Control | | | |
| 91-4 Site Services | | | |
| 91-5 Safety | 13,568 | | |
| 91-6 Temporary Facilities | 20,392 | | |
| 91-7 Temporary Utilities | | | |
| 91-8 Mobilization/Demob. | 21,491 | | |
| 91-9 Legal Expenses/Claims | 3,175 | | |
| Other Construction Indirects | | | |
| 92-1 Small Tools & Consumables | 13,568 | | |
| 92-2 Scaffolding | | | |
| 92-3 General Liability Insur. | 13,568 | | |
| 92-4 Constr. Equip. Mob/Demob | 9,685 | | |
| 92-5 Freight on Material | 785 | | |
| 92-6 Freight on Process Equip | | | |
| 92-7 Sales Tax | | | |
| 92-8 Contractors G&A | 126,327 | | |
| 92-9 Contractors Profit | <u>180,467</u> | | |
| | 669,052 | 2,475,181 | |
| Project Indirect Costs | | | |
| 93-1 Engineering Services | 30,000 | | |
| 93-2 CM Support | | | |
| 93-3 Start-Up/Commissioning | | | |
| 93-4 Start-Up/Spare Parts | | | |
| 93-5 Excess Liability Insur. | | | |
| 93-6 Sales Tax On Indirects | | | |
| 93-7 SDG&E Internal Costs | 240,000 | | |
| 93-8 EPC Fee | <u></u> | | |
| | 270,000 | 2,745,181 | |
| Contingency | | | |
| 94-1 Contingency on Const Eq | 35,446 | | |
| 94-3 Contingency on Material | 2,893 | | |
| 94-4 Contingency on Labor | 281,867 | | |
| 94-5 Contingency on Subcontr. | 74,479 | | |
| 94-6 Contingency on Process Eq | | | |
| 94-7 Contingency on Indirect | <u>40,500</u> | | |
| | 435,185 | 3,180,366 | |
| Escalation | | | |
| 96-1 Escalation on Const Equip | | | |
| 96-3 Escalation on Material | | | |
| 96-4 Escalation on Labor | | | |
| 96-5 Escalation on Subcontract | | | |
| 96-6 Escalation on Process Eqp | | | |
| 96-7 Escalation on Indirects | | | |
| | | 3,180,366 | |
| 98 Interest During Constr | | 3,180,366 | |
| Total | | 3,180,366 | |

**SAN DIEGO GAS & ELECTRIC
 RAMONA SOLAR ENERGY PLANT
 DECOMMISSIONING STUDY**



| Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|-----------------|-----------------|--|--|--------------|------------------|-------------|---------------|---------------|------------------|----------------|------------------|
| 10.00.00 | | WHOLE PLANT DEMOLITION | | | | | | | | | |
| | 10.21.00 | CIVIL WORK | | | | | | | | | |
| | | REMOVE FENCE | | 3,907.00 LF | - | - | | 156 | 13,885 | 7,217 | 21,102 |
| | | CIVIL WORK | | | | | | 156 | 13,885 | 7,217 | 21,102 |
| | 10.22.00 | CONCRETE | | | | | | | | | |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | INVERTERS, SWITCHGEAR FOUNDATIONS | 28.00 CY | - | - | | 47 | 4,217 | 1,039 | 5,256 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | WATER TANK AND PUMP PAD | 13.00 CY | - | - | | 22 | 1,958 | 482 | 2,440 |
| | | BUILDING/EQUIPMENT FOUNDATION/PAD | PANEL BOARD FOUNDATIONS (8 EACH) | 2.00 CY | - | - | | 6 | 535 | 132 | 667 |
| | | REMOVE CONCRETE PIER | SECURITY CAMERA POST PIER | 4.00 EA | - | - | | 1 | 107 | 26 | 133 |
| | | REMOVE CONCRETE PIER | INVERTER SHADE STRUCTURE | 12.00 EA | - | - | | 12 | 1,071 | 264 | 1,335 |
| | | REMOVE CONCRETE PIER | SWITCHGEAR SHADE STRUCTURE | 4.00 EA | - | - | | 4 | 357 | 88 | 445 |
| | | REMOVE CONCRETE PIER | FENCE POST PIER | 500.00 EA | - | - | | 150 | 13,386 | 3,299 | 16,685 |
| | | REMOVE AND LOADOUT CONCRETE DUCTBANK INCLUDING EMBEDDED PVC CONDUIT AND MANHOLE. | AC DUCTBANK | 560.00 LF | - | - | | 280 | 24,987 | 6,157 | 31,144 |
| | | EXCAVATE AND BACKFILL WITH NATIVE SOIL INCLUDED. | | | | | | | | | |
| | | REMOVE AND LOADOUT CONCRETE DUCTBANK INCLUDING EMBEDDED PVC CONDUIT AND PULLBOXES. | DC DUCTBANK | 2,212.00 LF | - | - | | 1,770 | 157,919 | 38,914 | 196,833 |
| | | EXCAVATE AND BACKFILL WITH NATIVE SOIL INCLUDED. | | | | | | | | | |
| | | REMOVE AND LOADOUT CONCRETE DUCTBANK INCLUDING EMBEDDED PVC CONDUIT AND PULLBOXES. | SITE PERIMETER DUCTBANK FOR COMMUNICATION AND SECURITY CAMERAS | 2,772.00 LF | - | - | | 1,386 | 123,687 | 30,478 | 154,165 |
| | | EXCAVATE AND BACKFILL WITH NATIVE SOIL INCLUDED. | | | | | | | | | |
| | | CONCRETE | | | | | | 3,678 | 328,224 | 80,879 | 409,103 |
| | 10.23.00 | STEEL | | | | | | | | | |
| | | REMOVE AND LOAD STEEL RACKING POST | | 1,324.00 EA | - | - | | 794 | 67,969 | 13,394 | 81,362 |
| | | REMOVE AND LOAD STEEL | INVERTER SHADE STRUCTURES | 2.00 EA | - | - | | 64 | 5,476 | 1,079 | 6,555 |
| | | REMOVE AND LOAD STEEL | SWITCHGEAR SHADE STRUCTURE | 1.00 EA | - | - | | 32 | 2,738 | 540 | 3,277 |
| | | REMOVE AND LOAD SECURITY CAMERA 10 FT POLE | | 4.00 EA | - | - | | 12 | 1,027 | 202 | 1,229 |
| | | STEEL | | | | | | 902 | 77,209 | 15,214 | 92,424 |
| | 10.31.00 | MECHANICAL EQUIPMENT | | | | | | | | | |
| | | 4,000 GAL WATER TANK AND PUMP | | 1.00 LT | - | - | | 60 | 4,796 | 1,366 | 6,163 |
| | | MECHANICAL EQUIPMENT | | | | | | 60 | 4,796 | 1,366 | 6,163 |
| | 10.41.00 | ELECTRICAL EQUIPMENT | | | | | | | | | |
| | | DISCONNECT/REMOVE FREE STANDING PANEL BOARD RACK | | 8.00 EA | - | - | | 64 | 5,116 | 1,457 | 6,573 |
| | | DISCONNECT/REMOVE INVERTERS | | 2.00 EA | - | - | | 48 | 3,837 | 1,093 | 4,930 |
| | | DISCONNECT / REMOVE "DISCONNECT COMBINER" | | 48.00 EA | - | - | | 96 | 7,409 | 178 | 7,587 |
| | | DISCONNECT/REMOVE DC WIRING (PANEL TO COMBINER) | | 15,012.00 EA | - | - | | 751 | 57,931 | 1,389 | 59,320 |
| | | DISCONNECT/REMOVE GROUNDING WIRING AT PANELS AND RACKS, REMOVE GROUND RODS | | 15,012.00 EA | - | - | | 600 | 46,345 | 1,111 | 47,456 |
| | | REMOVE PV PANEL FROM RACK | | 15,012.00 EA | - | - | | 1,501 | 115,863 | 2,777 | 118,640 |
| | | LOAD AND BAND PV PANELS ON PALLET | | 15,012.00 EA | - | - | | 300 | 23,173 | 555 | 23,728 |
| | | 4' X 8' WOOD PALLET, HANDLE AND LOAD IN TRUCK | 30 PANELS PER PALLET | 500.00 EA | - | - | 15,000 | 100 | 7,994 | 2,277 | 25,271 |
| | | STEEL STRAP BANDING MATERIAL COST | | 1.00 LT | - | - | 700 | | | | 700 |
| | | REMOVE "RBI" SOLAR RACKS | | 1,280.00 EA | - | - | | 3,840 | 296,371 | 7,104 | 303,475 |
| | | TRANSFORMERS 2200 KVA, 34.5 KV OUTPUT | | 2.00 EA | - | - | | 48 | 3,837 | 1,093 | 4,930 |
| | | REMOVE SWITCHGEAR AND SCADA CABINET | | 1.00 EA | - | - | | 60 | 4,796 | 1,366 | 6,163 |
| | | ELECTRICAL EQUIPMENT | | | | | 15,700 | 7,409 | 572,673 | 20,400 | 608,773 |
| | 10.43.00 | CABLE | | | | | | | | | |
| | | #4 1/C BARE CU WIRE IN CONDUIT | DC WIRE | 20,370.00 LF | - | - | | 204 | 15,903 | 3,265 | 19,168 |
| | | #4/0 3/C CU INSULATED WIRE IN CONDUIT | AC WIRE | 610.00 LF | - | - | | 43 | 3,334 | 684 | 4,018 |
| | | #250 KCMIL 1/C CU INSULATED WIRE IN CONDUIT | DC WIRE | 40,800.00 LF | - | - | | 2,040 | 159,263 | 32,701 | 191,964 |
| | | CABLE | | | | | | 2,286 | 178,499 | 36,651 | 215,150 |
| | | WHOLE PLANT DEMOLITION | | | | | 15,700 | 14,492 | 1,175,287 | 161,728 | 1,352,715 |

18.00.00 **SCRAP VALUE**
 18.10.00 **MIXED STEEL**

**SAN DIEGO GAS & ELECTRIC
 RAMONA SOLAR ENERGY PLANT
 DECOMMISSIONING STUDY**



| Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Labor Cost | Equip Amount | Total Cost |
|-----------------|-----------------|---|--|--------------|------------------|------------------|---------------|------------|---------------|---------------|------------------|
| | 18.10.00 | MIXED STEEL | | | | | | | | | |
| | | STEEL | "RBI" SOLAR RACKS AND POSTS | -261.00 TN | - | (56,637) | - | | | - | (56,637) |
| | | STEEL | CONDUIT, FITTINGS AND DISCONNECTS | -0.50 TN | - | (108) | - | | | - | (108) |
| | | STEEL | SERVICE RACK COMPONENTS | -0.47 TN | - | (102) | - | | | - | (102) |
| | | STEEL | FENCING | -16.00 TN | - | (3,472) | - | | | - | (3,472) |
| | | STEEL | INVERTER SHADE STRUCTURES | -1.42 TN | - | (308) | - | | | - | (308) |
| | | STEEL | SWITCHGEAR SHADE STRUCTURE | -0.90 TN | - | (195) | - | | | - | (195) |
| | | STEEL | WATER TANK AND PUMP | -2.00 TN | - | (434) | - | | | - | (434) |
| | | STEEL | INVERTERS | -8.82 TN | - | (1,914) | - | | | - | (1,914) |
| | | STEEL / COPPER MIX - LARGE TRANSFORMER > 100 KVA | MEDIUM VOLTAGE BLOCK WHICH INCLUDES TRANSFORMERS 2200 KVA, 34.5 KV OUTPUT | -15.50 TN | - | (6,727) | - | 0 | | - | (6,727) |
| | | MIXED STEEL | | | | (69,898) | | 0 | | | (69,898) |
| | 18.30.00 | COPPER | | | | | | | | | |
| | | #2 INSULATED COPPER WIRE | | -35.40 TN | - | (78,234) | - | 0 | | | (78,234) |
| | | BARE COPPER WIRE | | -1.29 TN | - | (7,927) | - | 0 | | | (7,927) |
| | | COPPER | | | | (86,161) | | 0 | | | (86,161) |
| | | SCRAP VALUE | | | | (156,059) | | 0 | | | (156,059) |
| 21.00.00 | | CIVIL WORK | | | | | | | | | |
| | 21.17.00 | EXCAVATION | | | | | | | | | |
| | | EXCAVATION, 4 INCHES DEEP | GRAVEL ACCESS ROAD, 4 INCHES DEEP | 1,447.00 CY | - | - | - | 203 | 18,459 | 19,444 | 37,903 |
| | | EXCAVATION | | | | | | 203 | 18,459 | 19,444 | 37,903 |
| | 21.18.00 | HAULING | | | | | | | | | |
| | | HAULING, 40 MILE ROUNDTRIP, 50 MPH | ACCESS ROAD GRAVEL | 1,447.00 CY | 23,731 | - | - | | | | 23,731 |
| | | HAULING, 170 MILES TO YUMA, ARIZONA | 20 PALLETS / TRUCK LOAD. TRANSPORT PV PANELS TO "WE RECYCLE SOLAR" FACILITY IN YUMA, ARIZONA | 25.00 EA | 40,000 | - | - | | | | 40,000 |
| | | HAULING | | | 63,731 | | | | | | 63,731 |
| | 21.19.00 | DISPOSAL | | | | | | | | | |
| | | DUMPSTER, 40 CY CAPACITY | CONCRETE, RUBBISH, PVC CONDUIT | 120.00 EA | 98,400 | - | - | | | | 98,400 |
| | | NO DISPOSAL FEE FOR ACCESS ROAD GRAVEL. ASSUME IT IS REUSED | | | | - | - | | | | |
| | | PV PANEL DISPOSAL FEE. | "WE RECYCLE SOLAR", YUMA, ARIZONA | 15,012.00 EA | 300,240 | - | - | | | | 300,240 |
| | | DISPOSAL | | | 398,640 | | | | | | 398,640 |
| | 21.45.00 | GRADING | | | | | | | | | |
| | | FINISH GRADING | DUCTBANK TRENCHES AND ROADWAY - FILL IN AND BLEND/LEVEL INTO SURROUNDING AREA | 71,851.00 SY | - | - | - | 719 | 62,518 | 12,524 | 75,041 |
| | | GRADING | | | | | | 719 | 62,518 | 12,524 | 75,041 |
| | 21.47.00 | LANDSCAPING | | | | | | | | | |
| | | HYDRO SEEDING | | 14.80 AC | 34,158 | - | - | | | | 34,158 |
| | | LANDSCAPING | | | 34,158 | | | | | | 34,158 |
| | | CIVIL WORK | | | 496,529 | | | 921 | 80,977 | 31,967 | 609,473 |

SL-016628.G_SDGE Decom(EV)

Decommissioning Study

Prepared for
San Diego Gas & Electric Company
Electric Vehicle (EV) Charging Stations

Prepared by Sargent & Lundy

LEGAL NOTICE

This deliverable was prepared by Sargent & Lundy, L.L.C. (S&L) expressly for the sole use of San Diego Gas & Electric Company (Client) in accordance with the contract agreement between S&L and Client. This deliverable was prepared using the degree of skill and care ordinarily exercised by engineers practicing under similar circumstances. Client acknowledges: (1) S&L prepared this deliverable subject to the particular scope limitations, budgetary and time constraints, and business objectives of Client; (2) information and data provided by others, including Client, may not have been independently verified by S&L; and (3) the information and data contained in this deliverable are time-sensitive and changes in the data, applicable codes, standards, and acceptable engineering practices may invalidate the findings of this deliverable. Any use or reliance upon this deliverable by third parties shall be at their sole risk.

Sargent & Lundy is one of the oldest and most experienced full-service architect engineering firms in the world. Founded in 1891, the firm is a global leader in power and energy with expertise in grid modernization, renewable energy, energy storage, nuclear power, and fossil fuels. Sargent & Lundy delivers comprehensive project services—from consulting, design, and implementation to construction management, commissioning, and operations/maintenance—with an emphasis on quality and safety. The firm serves public and private sector clients in the power and energy, gas distribution, industrial, and government sectors.

55 East Monroe Street • Chicago, IL 60603-5780 USA • 312-269-2000

VERSION LOG

| Version | Issue Date | Sections Modified |
|----------|------------------|-------------------|
| Draft v0 | December 9, 2021 | Initial Issue |
| Final | March 30, 2021 | N/A |

ISSUE SUMMARY AND APPROVAL PAGE

This is to certify that this document has been prepared, reviewed, and approved in accordance with Sargent & Lundy's Standard Operating Procedure SOP-0405, which is based on ANSI/ISO/ASSQC Q9001 Quality Management Systems.

Contributors

Prepared by:

| Name | Title | Section(s) Prepared | Signature | Date |
|----------------|--------------------------|----------------------|-----------|-----------|
| Craig Gitchell | Senior Energy Consultant | Section 3 | | 3/30/2022 |
| Kyle Folken | Management Consultant | Section 1, Section 2 | | 3/30/2022 |

Reviewed by:

| Name | Title | Section(s) Reviewed | Signature | Date |
|--------------------|---|---------------------|-----------|-----------|
| Kevin C. Hopkins | Principal Consultant & Project Manager | All | | 3/30/2022 |
| Robert. P. Charles | Senior Principal Consultant & Project Manager | All | | 3/30/2022 |

Approved by:

Kevin C. Hopkins
Principal Consultant & Project
Manager

March 30, 2022

Date

TABLE OF CONTENTS

| | |
|--|-----------|
| EXECUTIVE SUMMARY | I |
| METHODOLOGY | I |
| CONCEPTUAL COST ESTIMATE | I |
| 1. INTRODUCTION | 1 |
| 1.1. SCOPE OF WORK | 1 |
| 1.2. SARGENT & LUNDY BACKGROUND | 1 |
| 1.3. EV CHARGING STATION DESCRIPTIONS | 2 |
| 2. COST ESTIMATE | 5 |
| 2.1. METHODOLOGY | 5 |
| 2.2. COST ESTIMATE SUMMARY | 5 |
| 2.2.1. <i>EV CHARGING STATIONS</i> | 5 |
| 2.2.2. <i>VARIANCE FROM 2016 STUDY</i> | 6 |
| 3. BASIS OF ESTIMATE | 7 |
| 3.1. PROCEDURE | 7 |
| 3.2. PRICING AND QUANTITIES | 8 |
| 4. REFERENCES | 11 |

FIGURES AND TABLES

| | |
|---|----|
| FIGURE 1-1 — EXAMPLE GE WATTSTATION EV CHARGING STATION | 3 |
| FIGURE 1-2 — EXAMPLE CLIPPER CREEK EV CHARGING STATION..... | 3 |
| FIGURE 1-3 — EXAMPLE CHARGEPOINT EV CHARGING STATION | 4 |
| | |
| TABLE ES-1 — COST ESTIMATE SUMMARY FOR EV CHARGING STATIONS | II |
| TABLE 2-1 — COST ESTIMATE SUMMARY FOR ELECTRIC VEHICLE CHARGING STATIONS..... | 6 |

APPENDIXES

| |
|--|
| APPENDIX A. CONCEPTUAL ESTIMATE OF COST TO DECOMMISSION EV CHARGING STATIONS |
|--|

ACRONYMS AND ABBREVIATIONS

| Acronym/Abbreviation | Definition/Clarification |
|----------------------|--------------------------------------|
| EV | Electric vehicle |
| FERC | Federal Energy Regulatory Commission |
| GE | General Electric |
| Owner | San Diego Gas & Electric Company |
| S&L | Sargent & Lundy LLC |
| SDG&E | San Diego Gas & Electric Company |

EXECUTIVE SUMMARY

Sargent & Lundy (S&L) was contracted by San Diego Gas & Electric Company (“SDG&E” or the “Owner”) to perform an independent conceptual decommissioning cost estimate for the SDG&E portfolio of electric vehicle (EV) charging stations. SDG&E indicated that the cost estimate should assume that all the charging stations are pedestal-mounted and are one of the three typical models found in SDG&E’s portfolio of charging stations: General Electric (GE) WattStation, Clipper Creek, or ChargePoint. The charging stations are located throughout the SDG&E service area. The work scope included updating the 2016 conceptual demolition cost estimate and report.

METHODOLOGY

The methodology for developing the cost estimate consisted of S&L experience in developing demolition costs, the existing S&L database from numerous other projects, and use of the unit cost factor methodology. The cost estimate was developed based on information provided by SDG&E and publicly available information about the EV charging stations. This information was used to estimate the foundation sizes, quantity of steel, and other components. S&L performed a site walkdown at the SDG&E headquarters to review typical charging stations. The site walkdown was performed in 2016; however, recent discussions with the Owner and facility management confirmed that the only significant change since that time is a large increase in the number of installed stations. This information was used with cost factors developed by S&L based on industry data and experience.

S&L also estimated the quantities of metals that could be recovered and sold for scrap. The estimate herein includes the value of scrap metals; however, equipment is assumed to have no resale or other salvage value besides the value of scrap metal at the end of its life.

CONCEPTUAL COST ESTIMATE

The estimate assumes that EV charging stations are decommissioned in batches of 25 stations at a time. The total number of stations is 2463. The summary of the cost estimate for decommissioning the SDG&E EV charging stations is shown in Table ES-1. The FERC account for these costs is E371.1 according to guidance SDG&E received from FERC. All costs are in 2021 U.S. dollars. Decommissioning costs are expected to increase by the end of service life due to escalation.

Table ES-1 — Cost Estimate Summary for EV Charging Stations

| | Includes Contingency | | | | | Scrap Value | G&A and Profit | Total Cost |
|---|----------------------|---------------|--------------|-----------------------------|----------------------|--------------|----------------|---------------|
| | Subcontract Cost | Material Cost | Labor Cost | Subcontractor Indirect Cost | SDG&E Internal Costs | | | |
| <i>Number of EV Charging Stations Decommissioned at a Time:</i> 25 | \$ 1,035 | \$ 4,157 | \$ 87,353 | \$ 8,531 | \$ 10,664 | \$ (1,217) | \$ 13,474 | \$ 123,997 |
| <i>Current Number of EV Charging Stations in the SDG&E Portfolio:</i> 2463 | \$ 101,968 | \$ 409,572 | \$ 8,606,025 | \$ 840,497 | \$ 1,050,624 | \$ (119,899) | \$ 1,327,431 | \$ 12,216,219 |

The total estimated cost to decommission the 2463 existing EV charging stations is \$12,216,219; therefore, the average or blended cost is approximately \$4,960 per unit. The actual decommission cost will vary with respect to the type of EV charging station, type of foundation, number of units at a single location, and other factors listed in the cost estimate.

1. INTRODUCTION

1.1. SCOPE OF WORK

Sargent & Lundy (S&L) was contracted by San Diego Gas & Electric Company (“SDG&E” or the “Owner”) to perform a conceptual decommissioning cost estimate for the SDG&E portfolio of electric vehicle (EV) charging stations. The work scope included updating the 2016 conceptual demolition cost estimate report. SDG&E indicated that the cost estimate should assume that all the charging stations are pedestal-mounted and are one of the three typical models found in SDG&E’s portfolio of charging stations: General Electric (GE) WattStation, Clipper Creek, or ChargePoint. The charging stations are located throughout the SDG&E service area.

1.2. SARGENT & LUNDY BACKGROUND

S&L has been dedicated to providing complete engineering and environmental services exclusively to the power industry since 1891. Through work with various utilities, lending institutions, and developers over the years, the Sargent & Lundy Consulting Group has become one of the premier power project consultants in the power industry. This commitment to quality is proven by the successful completion of the ISO 9001 certification audit. S&L’s experience encompasses independent engineer services—including decommissioning cost estimation and average service life evaluation—for both global and domestic electric power assets.

S&L has extensive decommissioning and related services experience, including power plant dismantling, demolition, and layup for fossil fuel, renewable energy, and nuclear plants. This includes decommissioning cost estimates, decommissioning studies, and related services for 18 clients at more than 70 stations. S&L also has extensive experience providing clients with testimony services.

Having engineered over 958 power plant units, S&L has both the benefit of extensive design experience—supported with feedback from operating plants—and individuals with extensive plant operations experience to support consulting services such as those performed for SDG&E’s EV fleet.

1.3. EV CHARGING STATION DESCRIPTIONS

EVs were first widely introduced in the United States in the early 1900s (4% of the 4192 cars manufactured at that time were electric). This was short-lived with the rise and consequent mass production of gasoline-powered cars; however, EVs are now becoming more prevalent. Several car manufacturers have increased EV production over the past few years. This development has resulted in growth in the number of EV charging stations, which has already reached approximately one million public and six million private units globally.

EV charging stations supply and meter electric power to individual EVs. The main components of an EV charging stations are noted below:

- **Power Source:** The power source supplies the electricity needed for the charging station.
- **Charging Device:** Inside the charging station is a charging device responsible for converting and transferring the electricity from the power source to the EV. Some systems include electronics that integrate payment systems with the metering of power. The charging device can be standing (i.e., a pedestal) or wall-mounted.
- **Cabling and Plugs:** Cablings and plugs connect EVs to charging stations. Charging stations that swap banks of batteries or charge wirelessly are not widespread and are not part of the SDG&E portfolio.
- **Controls:** Controls include the electric equipment and software necessary to control, monitor, and optimize the flow of electricity to rapidly charge/recharge EVs.

SDG&E's portfolio is comprised of 2463 EV charging stations. There are three main pedestal chargers:

- **GE WattStation Pedestal:** These charging stations are manufactured by GE and come with retractable cords. It includes "advanced network management" software tools to help the user monitor and manage the charging station remotely. The GE WattStation comes with a three-year parts warranty. Its standby power is typically 5 W, while its alternating current charging power output is 7200 W. The stand is powder-coated stainless steel. In 2017, the GE charging network was acquired by ChargePoint, whose chargers are also utilized by SDG&E. The 2017 announcement stated that the warranties would continue to be honored.

Figure 1-1 — Example GE WattStation EV Charging Station



- **ClipperCreek Pedestal:** These charging stations are manufactured by ClipperCreek in the United States. They feature a slim profile with a powder-coated stainless steel enclosure for environmental durability. ClipperCreek pedestal charging stations come with a three-year parts warranty.

Figure 1-2 — Example Clipper Creek EV Charging Station



- **ChargePoint Pedestal:** ChargePoint pedestal stations come with extended parts and labor warranty coverage for up to five additional years. Its standby power is typically 8 W, while its alternating current charging power output is up to 7200 W.

Figure 1-3 — Example ChargePoint EV Charging Station



2. COST ESTIMATE

2.1. METHODOLOGY

The methodology used for developing the cost estimate includes a combination of stochastic and deterministic methods. Deterministic methods were used based on the quantity and size of equipment (e.g., the number of foundations, equipment, etc.). Stochastic methods were also used if quantitative information (e.g., miscellaneous electrical equipment) was unavailable.

The cost estimate was developed based on drawings, documents, and data provided by the Owner and publicly available information. These drawings and documents were used to estimate the foundation sizes, unit volumes, equipment, and metal quantities.

The methodology for developing the cost estimate considered S&L's experience in developing demolition costs, the existing S&L database for numerous other projects, and the use of the unit cost factor methodology. The estimate was created using the S&L cost model format and the S&L cost database. The estimate includes details for each type of work performed, indirect costs, and contingencies.

S&L visited representative charging stations at the SDG&E headquarters in 2016 to review typical charging stations and determine any unique site-specific requirements. Recent discussions with the Owner and facility management confirmed that no significant modifications have occurred since that time other than a large increase in installed stations. This information was used with cost factors developed by S&L based on industry data and experience. Cost factors for concrete removal and other tasks were developed from labor and material cost information.

S&L also estimated the quantities of metals that could be recovered and sold for scrap. The estimate herein includes the value of scrap metals; however, equipment is assumed to have no resale or other salvage value besides the value of scrap metal at the end of its life.

2.2. COST ESTIMATE SUMMARY

2.2.1. EV Charging Stations

The estimate assumes that EV charging stations are decommissioned by 25 stations at a time. The total number of stations is 2463. The summary of the cost estimate for decommissioning the SDG&E EV stations is shown in Table 2-1. The FERC account for these costs is E371.1 according to guidance SDG&E received from FERC. All costs are in 2021 U.S. dollars. Decommissioning costs are expected to increase by the end of service life due to escalation.

The commercial and technical basis for the estimate is included in Section 2. The detailed estimate is included in Appendix A.

Table 2-1 — Cost Estimate Summary for Electric Vehicle Charging Stations

| | Includes Contingency | | | | | | | |
|---|-------------------------|----------------------|-------------------|------------------------------------|---------------------------------|--------------------|---------------------------|-------------------|
| | <i>Subcontract Cost</i> | <i>Material Cost</i> | <i>Labor Cost</i> | <i>Subcontractor Indirect Cost</i> | <i>SDG&E Internal Costs</i> | <i>Scrap Value</i> | <i>G&A and Profit</i> | <i>Total Cost</i> |
| <i>Number of EV Charging Stations Decommissioned at a Time:</i> 25 | \$ 1,035 | \$ 4,157 | \$ 87,353 | \$ 8,531 | \$ 10,664 | \$ (1,217) | \$ 13,474 | \$ 123,997 |
| <i>Current Number of EV Charging Stations in the SDG&E Portfolio:</i> 2463 | \$ 101,968 | \$ 409,572 | \$ 8,606,025 | \$ 840,497 | \$ 1,050,624 | \$ (119,899) | \$ 1,327,431 | \$ 12,216,219 |

The total cost to decommission the 2463 existing EV charging stations is estimated to be \$12,216,219; therefore, the average or blended cost is approximately \$4,960 per unit. The actual decommission cost will vary with respect to the type of EV charging station, type of foundation, number of units at a single location, and other factors listed in the cost estimate.

2.2.2. Variance from 2016 Study

The following list summarizes the changes from the S&L 2016 report. Note that material quantities and labor hours in the estimate were unchanged from 2016 (per 25 charging stations).

- The number of charging stations increased tenfold. In 2016, there were 206 stations compared to 2463 in 2021.
- The current estimate utilizes updated labor rates, material costs, and scrap value to current 2021 values.
- The depth of foundation to be removed was revised from 3 feet to 1 foot.
- The contractor general and administrative costs and profit were increased from 5% and 8%, respectively, to 7% and 10% based on the S&L database.
- SDG&E internal costs were added to the estimate. These were excluded from the 2016 estimate. The internal costs include disconnecting the units from the grid and securing and managing the contractor.

3. BASIS OF ESTIMATE

The basis for the cost estimate is as follows:

The decommissioning cost estimates in Section 2 and Appendix A are for the dismantlement and removal of 2463 pedestal-type, EV charging stations. SDG&E indicated that all charging stations are assumed to be the pedestal type, of which there are three models: GE WattStation, ClipperCreek, and ChargePoint.

The cost estimate is based primarily on data provided by SDG&E and S&L's experience with similar equipment.

3.1. PROCEDURE

In general, the methodology to decommission an EV charging station fixed to existing pavement or concrete considers the following:

- The charging station will be de-energized and disconnected by SDG&E.
- The charging station pedestal will be unbolted or otherwise removed from the base.
- The in-ground conduit and cable will be cut, capped, and abandoned in place.
- Internal electronics, cables, conduits, wires, controls, and other related items will be separated from the station metal pedestal and disposed.
- The pedestal will be demolished for stainless steel recycling.
- Bolts or other connections left in existing pavement or concrete will be cut and removed.
- Damage to existing pavement or concrete will be repaired using appropriate patch repair material.
- Any bollards will be completely cut out, removed from the site, and disposed.
- Holes left from bollard removal will be filled with concrete.

In general, the procedure to decommission an EV charging station fixed to a free-standing foundation is as follows:

- The charging station will be de-energized and disconnected by SDG&E.
- The charging station pedestal will be unbolted or otherwise removed from the base.
- The concrete foundation will be removed down to one foot.
- The in-ground conduit and cable will be cut, capped, and abandoned in place.
- Internal electronics, cables, conduits, wires, controls, and other related items will be separated from the station metal pedestal and disposed.
- The pedestal will be demolished for stainless steel recycling.

- Any bollards will be completely cut out, removed from the site, and disposed.
- Holes left from bollard removal will be filled with concrete.

3.2. PRICING AND QUANTITIES

1. Construction Labor Wages

Craft labor rates (or craft hourly rates) for the cost estimate are based on the prevailing wages for San Diego, California as published in *R.S. Means Labor Rates for the Construction Industry* (2021). These prevailing rates are representative of union or non-union rates, whichever is prevailing in the area. Costs have been added to cover social security, workmen's compensation, and federal and state unemployment insurance. The resulting burdened craft rates were then used to develop typical crew rates applicable to the task being performed.

2. Labor Work Schedule and Incentives

- The labor estimate is based on a 40-hour workweek with no per diem or other labor incentives.
- An allowance for show-up time is included if workers arrive and are then sent home.

3. Quantity Sources

Quantities of pieces of equipment and/or bulk material commodities used in this cost estimate were developed from supplied engineering information from the sites and the S&L database.

4. General Conditions Cost

Allowances were included in the cost estimate for the decommissioning contractor indirect costs for the following:

- Labor supervision and safety
- Small tools and consumables
- General liability insurance
- Contractor general and administrative costs (7% of labor [direct labor, additional labor cost, site overheads, and other construction indirect cost], material [direct material cost and freight cost], and equipment)
- Contractor's profit (10% of labor [direct labor, additional labor cost, site overheads, and other construction indirect cost], material [direct material cost and freight cost], and equipment)

5. Scrap

Scrap metals are a globally traded commodity and part of the larger metals industry. The value of scrap metal is subject to constantly changing economic conditions, as such the price of mixed steel, stainless steel, copper, and aluminum can vary greatly over time as a result of global supply and demand. Stainless steel is assumed to be the only scrap metal from the charging stations worth salvaging.

The value of scrap for this study was determined by a 12-month average from *Scrap Metals MarketWatch*¹ (November 2020–October 2021) for the West Coast (Zone 1) of the United States. The value obtained is the delivered price to the recycler. Transportation cost to the recycler is estimated at \$30/ton (2000 lbs.), resulting in a stainless steel scrap value of \$1217/ton.

6. Indirect Expenses

- Engineering is included to cover preparation of the decommissioning work specification, engineering required to place the charging stations in safe shutdown, and any unique engineering required during demolition.
- SDG&E internal costs are included to cover costs in support of decommissioning the stations such as disconnecting the units from the grid and securing and managing the contractor.

7. Escalation Rates

Escalation rates were excluded from the estimate.

8. Sales and Use Taxes

Sales and use taxes were excluded from the estimate.

9. Contingency

- A 15% contingency is applied for material, labor, and indirect expenses.
- There is no contingency on scrap value.

10. Contract Basis for Estimate

The contracting strategy is a multiple lump sum for the estimate.

11. Assumptions

- The cost estimate is based on 25 EV charging stations being decommissioned at a time.
- All stations are pedestal-mounted type, as was assumed per SDG&E in 2016.
- Most EV charging stations are in series of 2–10 pedestals in parking lots and garages. Some individual pedestals have two protective bollards while others have none or are protected by curbs; consequently, to account for the removal of bollards, one bollard for each pedestal is included with the estimate.
- SDG&E has indicated that conduits in rights of way to pedestals will be abandoned in place.
- Underground facilities, such as conduits, will be included through other accounts per SDG&E. These are not included in this decommissioning cost estimate.
- Pedestal foundations and bollards shall be removed to three feet below grade.
- Bollard weight and dimensions are for a typical unit and are based on a manufacturer drawing (1700 lbs.; 2-ft diameter by 3-ft height and 7.5-in. diameter by 4.33 ft; 10.75 ft³ of concrete per bollard).²

¹ www.americanrecycler.com

² "Vaughn Concrete Products," www.vaughnconcreteproducts.com/bollards

- Based on observations during the site visit, a review of charging station installation manuals, and street views of SDG&E stations on Google Maps, the EV charging stations were found to be installed on sidewalks, pavement, curbs, and other structures. Some stations were fixed to freestanding foundations surrounded by soil. Half of the pedestals are assumed to be fixed to 2-ft x 2-ft x 3-ft deep foundations, and the remaining half are assumed to be fixed to existing concrete or pavement.
- The estimate considers that freestanding pedestal foundations will be removed, demolished for scrap, and backfilled (with a volume of 12 ft³ per foundation).
- All borrow (fill) material is assumed to be from offsite sources.
- The estimate assumes that the process of removing bolts from existing concrete will result in some damage to existing surfaces. A material allowance of 5 yd³ of concrete repair per station is assumed for the project.
- The pedestal weight is based on the GE WattStation. The weight of salvageable stainless steel is estimated to be 80 lbs. based on GE specifications. This weight is typical for pedestal-type EV charging stations.
- The amount of mixed steel, aluminum, copper, and other valuable metals is considered too small to salvage. All demolished materials are considered debris except for stainless steel.
- The basis for salvage estimating is for scrap value only. No resale of equipment or material is included.
- No extraordinary environmental costs for demolition will be needed.

4. REFERENCES

12. Sargent & Lundy Cost Database.
13. RSMeans Cost Data, 2021.
14. Engineering drawings, equipment lists, operations and maintenance records, and other information provided by San Diego Gas & Electric.
15. *Scrap Metals MarketWatch* – West Coast (Zone 1), www.americanrecycler.com.
16. Bollard Dimensions – Vaugh Concrete Products, www.vaughnconcreteproducts.com/bollards.

**APPENDIX A. CONCEPTUAL ESTIMATE OF COST
TO DECOMMISSION EV CHARGING STATIONS**

San Diego Gas & Electric
 Decommissioning Cost Estimates
 Electric Vehicle Charging Stations

Total Number of EV Charging Stations 2463
 Number of EV Charging Stations Decommissioned at one time 25

| Area | Group | Phase | Description | Notes | Quantity | Subcontract Cost | Scrap Value | Material Cost | Man Hours | Crew Rate | Labor Cost | Total Cost |
|--|----------------------------------|----------|--|--|----------|------------------|--------------|---------------|-----------|-----------|--------------|---------------|
| | 11.00.00 | | Demolition | | | | | | | | | |
| | | 11.22.00 | Concrete | Foundations 2'x2'x1' Protective Bollards, 103 @ 0.39 cu yd each | 2.0 CY | | | | 103 /MH | \$ 140.47 | \$ 14,448 | \$ 14,448 |
| | | | Concrete | | 5.0 CY | | | | 257 /MH | \$ 140.47 | \$ 36,121 | \$ 36,121 |
| | | 11.41.00 | Electrical Equipment | | | | | | | | | |
| | | | Remove pedestal from base | | 25 EA | | | | 50 /MH | \$ 127.80 | \$ 6,390 | \$ 6,390 |
| | | | Remove control units, conduit, wiring, other electronics, etc. | | 25 EA | | | | 125 /MH | \$ 127.80 | \$ 15,975 | \$ 15,975 |
| | | | Demolition | | | \$ - | \$ - | \$ - | | | \$ 72,934 | \$ 72,934 |
| | 18.00.00 | | Scrap Value | | | | | | | | | |
| | | 18.20.00 | Stainless Steel | Pedestals @ 80 lbs. each | 1 TN | | \$ (1,217) | | /MH | | | \$ (1,217) |
| | | | Scrap Value | | | \$ - | \$ (1,217) | \$ - | | | \$ - | \$ (1,217) |
| | 21.00.00 | | Civil Work | | | | | | | | | |
| | | 21.19.00 | Disposal | | 7.0 CY | | | | | | | |
| | | | Dumpster, 40 CY Capacity | For concrete, electronics, rubbish | 1 EA | \$ 900 | | | /MH | | | \$ 900 |
| | | 21.20.00 | Backfill | | | | | | | | | |
| | | | Foundation backfill, imported material fill | | 1.0 CY | | | \$ 40 | | | | \$ 40 |
| | | | Civil Work | | | \$ 900 | \$ - | \$ 40 | | | \$ - | \$ 940 |
| | 24.00.00 | | Architectural | | | | | | | | | |
| | | | Concrete | | | | | | | | | |
| | | | Repair of concrete from removed pedestal base. | | 5.0 CY | | | \$ 2,750 | 5.0 CY | \$ 275.00 | \$ 1,375 | \$ 4,125 |
| | | | Foundation backfill, pedestals on concrete/asphalt surfaces | | 1.0 CY | | | \$ 138 | 1.0 CY | \$ 275.00 | \$ 275 | \$ 413 |
| | | | Foundation backfill, bollards | Installation | 5.0 CY | | | \$ 688 | 5.0 CY | \$ 275.00 | \$ 1,375 | \$ 2,063 |
| | | | Architectural | | | \$ - | \$ - | \$ 3,575 | | | \$ 3,025 | \$ 6,600 |
| Subtotal | | | | | | \$ 900 | \$ (1,217) | \$ 3,615 | | | \$ 75,959 | \$ 79,257 |
| | 91.00.00 | | Other Direct & Construction Indirect Costs | | | | | | | | | |
| | | 91.09 | Contractor's General and Administration Expense | | | | | | | | | \$ 5,548 |
| | | 91.10 | Contractor's Profit | | | | | | | | | \$ 7,926 |
| | | | | | | | | | | | | \$ 13,474 |
| Direct Costs + Construction Indirect Costs | | | | | | \$ 900 | \$ (1,217) | \$ 3,615 | | | \$ 75,959 | \$ 92,731 |
| | 93.00.00 | | Indirect Costs | | | | | | | | | |
| | | 93.1 | Engineering, Procurement, & Project Services | | | | | | | | | \$ 5,564 |
| | | 93.2 | Construction Management Support | | | | | | | | | \$ 1,855 |
| | | 93.3 | SDG&E Internal Costs | | | | | | | | | \$ 9,273 |
| | 95.00.00 | | Contingency | | | | | | | | | |
| | | 95.1 | Contingency on Subcontractor | | | \$ 135 | | | | | | \$ 135 |
| | | 95.2 | Contingency on Scrap Value | | | | \$ - | | | | | \$ - |
| | | 95.3 | Contingency on Material | | | | | \$ 542 | | | | \$ 542 |
| | | 95.4 | Contingency on Labor | | | | | | | | \$ 11,394 | \$ 11,394 |
| | | 95.5 | Contingency on Indirect | | | | | | | | | \$ 2,504 |
| Subtotal for | 25 EV Charging Stations | | | | | \$ 1,035 | \$ (1,217) | \$ 4,157 | | | \$ 87,353 | \$ 123,997 |
| Total for | 2463 EV Charging Stations | | | | | \$ 101,968 | \$ (119,899) | \$ 409,572 | | | \$ 8,606,025 | \$ 12,216,219 |